13. 11. 95

THE FINNISH FOREST RESEARCH INSTITUTE
RESEARCH PAPERS 567

Northern Silviculture and Management



Edited by
Aulis Ritari, Hannu Saarenmaa,
Marja Saarela and Helena Poikajärvi

METSÄNTUTKIMUSLAITOS
Kirjasto

ROVANIEMI RESEARCH STATION 1995

13. 11. 95

METSÄNTUTKIMUSLAITOS
Kirjasto

ABSTRACT

Ritari, A, Saarenmaa, H., Saarela, M. and Poikajärvi H., editors 1995. Northern Silviculture and Management. Proc. IUFRO Working Party S1.05–12 Symposium, Lapland, Finland, 16–22 Aug. 1987. The Finnish Forest Research Institute, Research Papers 567. 290 p.

The ninth Meeting and Symposium of the IUFRO Northern Forest Silviculture and Management Working Party (S1.05–12) met in Finnish Lapland on 16–22 August 1987. 57 delegates from 9 countries met to discuss the three themes of the Symposium:
1) Site Preparation in Northern Boreal Forests,
2) Larix in Northern Boreal Forests, and
3) Forest Management in Protection Forests Close to the Timberline.

24 scientific papers, 13 posters and 13 excursion abstracts were presented. The Symposium in Rovaniemi was followed by an excursion to Central and Northern Finnish Lapland. Visits to numerous places of scientific and cultural interest gave an insight to forestry and human environment of the area.

Keywords: boreal forests, timberline, forest regeneration, Larix, IUFRO S1.05–12.

Publisher:
The Finnish Forest Research Institute

Copies of this report are available from:
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O. Box 16
96301 Rovaniemi, Finland

Tel. int. +358-60-336 411
Fax int. +358-60-336 4640

Cover:
Pyhätunturi-fell in Central Lapland
Photo by Tapani Vartiainen

ISBN 951-40-1466-9
ISSN 0358-4283


Printing:
Gummerus Kirjapaino Oy
Saarijärvi 1995

Northern Silviculture and Management

Edited by
Aulis Ritari, Hannu Saarenmaa,
Marja Saarela and Helena Poikajärvi

The Finnish Forest Research Institute
Rovaniemi Research Station
1995

Research Papers 567



IUFRO Working Party S1.05–12
Northern Forest Silviculture and Management
Symposium in Lapland, Finland
August 16–22, 1987.
Participants on Ounasvaara fell in Rovaniemi.

Proceedings of the Symposium on

Northern Silviculture and Management

August 16 - 22, 1987 in Lapland, Finland

PREFACE 5

CONTENTS

Opening Address:

Opening remarks from the Finnish Forest Research Institute
Aarne Nyyssönen 7
Northern Boreal Forest Resources, their Utilization and Ecology
Kullervo Kuusela 11

Site Preparation in Northern Boreal Forests

Effects of Site Preparation on the Development of Planted Seedlings in Northern Sweden
Göran Örlander 39
Effect of Site Preparation on Seedling Performance in a Hylocomium Myrtillus-Stand
Aulis Ritari 47
Site Preparation and Leaching of Nutrients
Eero Kubin 55
Site Preparation, Stock Selection and White Spruce Seedling Performance in Western Canada
R. G. McMinn, M. Grismer and L. J. Herring 63
Some Aspects on Site Preparation and Natural Regeneration in Sweden
Evert Jeansson 69
Spot Scarification in a Mountainous Scots Pine Forest in Norway
Sverre Skoklefald 85
Techniques and Technologies of Using Containerized Planting Stock on Clearant Areas with Waterlogged Soil in the Northwest.USSR
D. V. Ogievsky 91
Guidelines of the National Board of Forestry for Site Preparation in Lapland
Kari Pelkonen 101
Effect of Site Preparation on Regeneration Results in Lapland
Eljas Pohtila 105

Larix in Northern Boreal Forests

Experiences with Larix Species in Northern Finland
Max Hagman 111
Research on Larix Laricina in Sweden
Milan Simak and Evert Jeansson 125
The Distribution and Regeneration of Larix Forests in Northeast China
Chou Yi-Liang and Wu Hong-gi 139
Larix in the USSR
A.I. Iroshnikov 151
Larch in North America
Edmond C. Packee 161

Forest Management in Protection Forests Close to Timberline

Structure and Dynamics of Natural Conifer Forests Near the Upper Forest Limit
Helmut Schmidt-Vogt 175
Monitoring Timberline Dynamics at the Kevo Subarctic Research Institute in Northern Finland
Paavo Kallio 181
Seed Production of Scots Pine close the Timberline in Finland
Erkki Numminen 195
The Effects of Elevation on Sitka Spruce Productivity in Scotland
R. Worrell and D.C. Malcolm 201
Nature and Rational Use of Pretundra Pine Forests in the European Part of the USSR
A.A. Listov and B.A. Semyonov 211
Forest Research in Areas close to the Timberline in Sweden
Mats Hagner 217

Restrictions on Forest Management close to the Timberline in North America
J. Peter Hall 227
Restrictions on Forest Management close to the Timberline in Norway
Oddvar Haveraaen 237
Restrictions on Forest Management close to the Timberline in Finland
Matti Leikola 243
Reforestation Experiments at the Pine Timberline in Northernmost Finland
Custaf Sirén 249

POSTERS

Competition Control with Pronone (Granular Hexazinone) Applied in Winter
F.W. von Althen, J.E. Wood and R.a. Campbell 261
Field Guide to Forest Ecosystems of West-Central Alberta
I.G.W. Corns 261
The Larch and the Others — a Comparison
Max. Hagman 262
The Influence from Scarification upon the Inwintering Process in Pine
Mats Hagner 262
Establishment of Pinus Contorta with Four Site Preparation Treatments on Four Sites in Jämtland
James Hunt 263
Properties of Larix in Finnish Sawmilling Industry
R. Juvonen 265
Introduction to Korean Pine Forest in the Northeast China
Li Jing-wen 266
Field Experiments on Site Preparation of the Department of Soil Science, Finnish Forest Research Institute
Kaarina Niska 267
Site Preparation, Fertilization and Draining of Forest Land in Finland
Aulis Ritari 268
Long-Term Effects of Prescribed Burning on Soil Chemistry
Aulis Ritari 269
Raivola Larch Stand
Aili Tuimala 270
Effect of Size of Clear-Cutting Area on the Development of Scots Pine Cultivation
Jukka Valtanen 270
Height Growth of Larix Laricina (Du ROI) K Koch) on Variety of Sites in Interior Alaska
Trudy T. Heffernan 271

EXCURSION ABSTRACTS

Rovaniemi Research Station of the Forest Research Institute
Hannu Saarenmaa 273
Kivalo Experimental Forest
Aulis Ritari 274
Tree Species Trial in Höpöttäjä
Martti Varmola 274
Stand Establishment Plots in Kemijärvi Common Forest
E. Pohtila et al. 275
Forestry Board Of Lapland
Jukka Ylimartimo 276
Management of Private Forests
Mikko Hyppönen 277
State Support for Owners of Private Forests
Mikko Hyppönen 277
Reforestation Experiments in Poksaselkä
Aulis Ritari 279
Geological Features and interglacial Larch Subfossils in Finnish Lapland
Peter Johansson 280
Reforestation in the Palkisoja Forest Fire Area
Kari Pelkonen 281
The Goal of Forest Regeneration of a Young Forest Stand in Kaitavaara
Arno Uusvaara 282
Epirrita Autumnata Defoliation of Mountain Birch
Hannu Saarenmaa 283
The Green Gold of the Northern countries
Markus Lassheikki 284

PROGRAM 285

PARTICIPANTS 287

PREFACE

This volume contains the proceedings from the ninth annual gathering of those interested in the Northern Forests and the third meeting of the IUFRO Working Party S1.05-12 held in the Finnish Lapland in August 16 - 22, 1987.

The theme of the meeting fitted well under the title of the Working Party "Northern Forest Silviculture and Management". It included three main themes:
1. Site Preparation in Northern Boreal Forests,
2. Larix in Northern Boreal Forests, and
3. Forest Management in Protection Forests Close to the Timberline.

The papers and posters were presented in Rovaniemi, the Capital of the Province of Lapland. The excursion went through the province all the way up to the Norwegian border in the north. The programme consisted of a number of stops where specific problems in the area and research findings were introduced.

The meeting attracted 57 participants from nine countries the farthest guests coming from Northern China and Alaska. Publishing was first inteded to be done in the USA. Due to problems in financing and editing the proceedings could not be printed until now. We believe, however, that the content of papers is still highly relevant and you find it interesting and useful reading. The variations in the printing quality and formats of papers made rewriting necessary, partially using OCR-technique and language checking. We hope that the minor corrections in the text have improved the readability of the papers.

The symposium required the efforts of more than one hundred people. For their co-operation we wish to thank all the practitioners of forestry in Lapland, especially Chairman Paavo Onnela, Director Jukka Ylimartimo, District Foresters Alpo Eeronheimo, Mikko Hyppönen and Pertti Veijola, and Forest Technicians Risto Junttila and Tarmo Mattila. The role of the 'organizing group' was decisive. We acknowledge and thank our collegues at the Finnish Forest Reseach Institute, especially Sven-Erik Appelroth, Kaarina Niska and Mauri Timonen from the Finnish Forest Research Institute. Special thanks is given to Prof. Edmond C. Packee, the Chairman of the Working Party at the time of the meeting, from the University of Alaska, Fairbanks, for his knowledgeable enthusiasm and support. The proceedings were technically edited by Marja Saarela and Helena Poikajärvi, the latter also acted as the treasurer. The symposium was financially supported by the FFRI and the Ministry of Agriculture and Forestry of Finland.

Aulis Ritari
Chairman IUFRO S1.05-12
Member of the Organizing Committee

Hannu Saarenmaa
Chairman of the Organizing Committee

OPENING REMARKS

Aarne Nyyssönen

It is a great pleasure for me to welcome you, the participants in the symposium, on behalf of IUFRO and the Finnish Forest Research Institute. Since I may be the only participant in this symposium who was present on the first occasion of this series of the gatherings of the people interested in northern forests, I wish also to greet you in that capacity. The symposium was held in Fairbanks, Alaska, 10 years ago in September 1977. "North American Forest Lands at Latitudes North of 60 Degrees" and "High-Latitude Forestry" were used as titles at that time.

Among some 200 participants at the first symposium there were only four persons from outside of the United States and Canada. In the appendix of the proceedings of the symposium was included a report on "Forestry Potential in Interior Alaska", prepared by a Scandinavian group of forest scientists (Braathe, Holmen and Nyyssönen). The group had been invited by the United States Forest Service to undertake a tour in Alaska in the previous July. The purpose of our report was to provide the State of Alaska and the U.S. Forest Service with an analysis of the Interior Alaska forest lands as compared with Fennoskandia. The emphasis was in various problems of productivity, utility and management concerning current and future demands of forest commodities, but attention was also given to the total environmental aspects of those northern lands, including wildlife and recreation.

The sponsors of the first symposium were the University of Alaska, the Alaska Humanities Forum, the U.S. Forest Service and the Bureau of Land Management, with the cooperation of the folloning: Alaska Federation of Natives, Joint Federal-State Land Use Planning Commission for Alaska, Society of American Foresters and the Forestry Section of the Department of Natural Resources of the State of Alaska.

It may be of interest to notice that the list given above does not include the IUFRO, our present parent organization. But, due to a strong need to continue the cooperation on northern forestry problems and to extend it to the other continents, the IUFRO soon came into the picture. We are proud that we now can celebrate the 9th symposium.

I have been asked by the Chairman of the Working Party to provide some information about the IUFRO and its goals. The main aim of this union, which will soon be 100 years old, is to promote international cooperation in scientific studies embracing the whole field of research related to forestry, including forestry operations and forest products. In particular, its functions are exercised by:

- facilitating the exchange of ideas among individual research workers throughout the world,
- creating and maintaining contacts between Member Organizations and by encouraging the establishment of common programmes of research and co-operation in their execution,
- promoting the dissemination and application of research results,
- co-operating with national and international organizations of a scientific, technical or cultural nature and more specifically with the Food and Agriculture Organization of the United Nations (FAO),

Professor Aarne Nyyssönen, Director The Finnish Forest Research Institute SF-00170 Helsinki

- working towards the introduction of a uniformity of nomenclature and for standardization in matters such as information storage and retrieval, and

- arranging periodical meetings, often combined with excursions.

Members of the IUFRO are the research organizations, not countries nor individual research workers. There are about 600 member organizations in about 100 countries, among them 12 from Finland. The most conspicuous form of IUFRO activities are the World Congresses held normally at five-year intervals. However, the activity proper takes place in about 250 groups — subject, project and working groups. The supreme authority responsible for regulating the affairs of the Union is the International Council; I have represented Finnish member organizations in the Council since 1967. The Executive Board of about forty members meets annually.

Since 1981 the orientation of co-operation took a new dimension when the World Bank and FAO came to the Kyoto Congress asking: would it be a time for reappraisal of forestry research priorities in developing countries? A review of research needs had indicated that traditional forestry research was not making a sufficient contribution to rural development, existing institutional arrangements were inadequate to meet the needs for promotion of research and that the resources allocated to research in developing countries were inadequate.

As a follow-up to the recommendations given by the Congress, the IUFRO Executive Board hired a special coordinator for developing countries to assist in planning practical measures. The special program has succeeded in organizing workshops, disseminating information, stimulating research activities, and gaining acceptance and support among forestry professionals, research institutions, and governments in developing and developed countries, as well as among bilateral aid agencies and international organizations.

At the Yugoslavia Congress last year the International Council of IUFRO took an important step to institutionalize the special programme. The council authorized and directed the executive board to take all necessary measures, consistent with the IUFRO's statutes, to establish an International Council for Forestry Research and Extension (INCOFORE) whose task shall be to promote and foster forestry research and extension in developing countries. The proposed budget for INCOFORE for this five-year-period is USP 8 million. It is likely also that Finnish financial support will be available for the implementation of the program.

After these references to IUFRO and its goals I should like to give you brief information about existing research institutions in the field of forestry and wood science in Finland (see Table).

FOREST RESEARCH INSTITUTIONS IN FINLAND

Forestry Finnish Forest Research Institute Universities (Helsinki, Joensuu)
Research Council for Agriculture and Forestry
Work Efficiency Association
Foundation for Forest Tree Breeding
Metsäteho (Work Efficiency in Forestry)

Wood Science Helsinki University of Technology
Technical Research Centre of Finland
Finnish Pulp and Paper Research Institute

Society of Forestry in Finland

We may notice that in addition to two groups of research institutions there is the Society of Forestry which is a kind of contact organization for all the forest research in this country.

It can be roughly estimated that the total number of research workers in these orgsnizations is around 400, and in forestry research alone some 300 with an annual research budget of some FIM 130 Million. About two thirds of the total budget and manpower in forest research accounted for by the Forest Research Institute which was established in 1917. The number of scientists at this institute is almost 200. Total personal is about 700, but including temporary assistants the annual input is in the order of about 1 000 man-years. About one half of the people work at the central unit in the Helsinki area and the other half elsewhere. There are 8 research stations in different parts of the country. The surface area of research forests and nature conservation areas administered by the Institute is 140 000 hectares.

The main activity of these institutions, forest research, involves publishing and extension activities. In addition, the Forest Research Institute is charged with official duties in the fields of forest statistics, forest taxation, inspection of pesticides and registration of regeneration materials. The Institute also needs to prepare reports requested especially by government agencies. Another important activity is international co-operation.

A large group of the participants at this symposium work at our Forest Research Institute. We are here in order to implement one of the Institutes tasks mentioned above, international co-operation. But I think this is a common goal to all of us. At the same time, I think this symposium also fills all the prerequisites to meet the goals of IUFRO. There is a comprehensive programme with several sessions and field tours ahead of us, thanks to the preparations done by many persons. I wish every success to the symposium.

NORTHERN BOREAL FOREST RESOURCES, THEIR UTILIZATION AND ECOLOGY "THE EVERGREEN CROWN OF THE GLOBE"

An introductory paper

Kullervo Kuusela

1. FOREST AND MAN

Forests, the largest and most diverse single terrestrial ecosystem, and man have a common destiny. The first human beings and numerous successive generations have been part of the forest in a way that the largest mammals are considered to be today. Man gathered and hunted for his food in the forest and other nearby ecosystems, he sheltered himself with grasses, leaves and timber, he warmed himself and cooked his food by burning wood, and from wood he crafted his tools, utensils and weapons.

For thousands of years man was a true member of the forest ecosystem. He changed it little, probably less than the biggest animals such as elephant and mammoth. What he took he gave back as consumption residues to the nutrient cycle of the nature. He may have set destructive fires for chasing animals or accidentally from his primitive hearths, but lightning did the same. Whatever the origin of an ancient wild fire it was the beginning of a new round of successive plant and animal communities and a source of renewed diversity.

Of the principal forest zones: boreal coniferous, temperate mixed and broad-leaved, evergreen mixed, tropical dry, and tropical moist; primeval man favoured those in the warmer climates where life was less arduous. In these forests there were also plenty of edible seeds and fruits, and the fauna was rich.

Prof. Dr. Kullervo Kuusela
Forest Research Institute Unioninkatu 40 A
SF-00170 Helsinki

The relations between man and forest changed profoundly when man learned to cultivate crops and raise cattle on cleaned land. Selective breeding increased the productivity of the crop species. Man became independent of the capricious gifts of the nature. Thanks to clothes, houses, utensils and weapons he could endure more extreme climates. His numbers increased, he felt himself the master of the plants and animals and commenced to invade more and rigorous environments.

However, even in these early stages of development man favoured the temperate and warm zones more than the two extremes, Boreal coniferous and tropical rain forests. The Boreal climate was too cold and the soil too infertile and the tropical ecosystem too profuse to surrender to the first agriculturists except in isolated niches.

New skills to prepare metals and tools from them further increased man's domains. Still the northern podzolic soils and jungles were stronger than man with his axe and primitive plow in the time of muscular power. The growing human population concentrated in the warm temperate zones and in those dry subtropical and tropical areas where soils were fertile and the shortage of water could be compensated for by irrigation. In this stage of development the temperate forests were severely destroyed and reduced by agriculturists and cattle raisers.

The exploitation and destruction of the temperate forests reached its peak during the early stages of the industrial revolution when machine power replaced muscular power in production and transport. During this period two thirds of the European forests were cleared into fields, pastures and dwelling sites. Almost

all of the natural forests vanished from the Mediterranean region and in large areas of South and south-east Asia as well as the bulk of them in North and Latin America between the Tropical Rain and the Boreal coniferous zones.

In over-populated Europe, even in time of muscular power man had colonized large areas of the Boreal zone. The first colonizers lived on hunting, fishing and scanty crops of shift-cultivation and raising cattle. Trade with furs and other crops from nature was of great value. During good periods the population increased but in bad periods crops often failed and the population was reduced by hunger and diseases. For several hundred years industries such as tar extracting and charcoal burning, small scale mining, boat and shipbuilding improved the standard of living in the Boreal region of North Europe.

In the 20th century scientific technology, cheap energy, machines, and improved health services created a geometrical rate of growth of the population. Consumers increased, living standard rose and basic needs had to be satisfied by more fields and pastures, constructional timber, sawn wood, pulp and paper. The destructive exploitation of the forests swept over the continents. Boreal forests also became the prey of the unsuitable human race.

Man succeeded to establish permanent and growing settlements adjacent to the Boreal coniferous belt by using machine power; scientific agriculture with drainage, fertilizers, insectes and pesticides, cultivated pastures, and plant and animal breeding. Only under European conditions of land-shortage, with regard to the increasing number of people, were large parts of the Boreal zone colonized. In Alaska, Canada, the bulk of the European Soviet Union and Asia the principal parts of the Boreal belt are outside of the inhabited areas proper. But the forests of these areas became an important timber source for mankind.

In the industrialized countries with high living standards there is at least a temporary balance between the remaining forests and other land uses. Efficient agriculture and cattle raising have produced surplus food in many of these countries. Large areas of marginal fields and pastures have been afforested, and the forest area is increasing in many countries and in Europe as a whole.

The forest area of the Boreal zone is stabilized or increasing. Exploitive logging without proper regeneration measures and wild fires, however, decrease the area of coniferous tree stands and change them into the first stages of successions forested by broad-leaved pioneer trees. Parts of the original coniferous forests may change after logging into paludified peat sites. Only in Nordic Countries Norway, Sweden and Finland, and in limited areas in the other Boreal countries forestry is based on sustained-yield silviculture and regeneration of tree stands after final cutting.

The forest situation is quite different in subtropical and tropical zones of the developing world than in the Boreal zone. There the population is increasing. There is a desperate need for more fields and pastures and for more fuel wood and other household timber. The severe shortage of fuelwood is expected to be approximately 1 000 mill. m^3 per year around 2 000. The destruction of forests by shifting cultivation and reckless logging for industrial timber is continuous. The annual decrease of forests is 10 to 15 mill. ha. The destruction of forests leads to erosion, floads, silting water tables and to other hazards to the environment.

In the 20th century mankind has reached an explosive stage of technological development. Man has become a force of geological magnitude capable of destroying his ecological environment by combining science and technology in the industrialized production of commodities and energy, including electronics and nuclear power. Mankind has a potential to multiply the worlds sweeping ecological changes that he has brought about so far.

The increase of carbon dioxide in the atmosphere and of airborn pollutants are feared to lead to fundamental changes in climates and ecosystems. The sagacious and industrious human being has reached a stage where he has the capability to degenerate the very roots of his life.

2. BOREAL FOREST RECOURCES AND THEIR UTILIZATION

The Boreal coniferous zone is a homogeneous vegetation belt around the North Pole. There is no precise estimate of its area because it belongs to various states and administrational units which also include other forest zones. An approximate estimate of forest in the zone proper is 850 mill. ha, which is 29 % of all forests and 73 % of the coniferous forests of the world. Its share of industrial wood removal is 33 % and of industrial coniferous removal 35 %.

The high economic value of the Boreal forest stems from its good quality coniferous sawnwood and fibre and from the homogeneous structure of the tree stands. The climax stages of tree stands comprise of often only up to 3 more or less similar conifers. The harvestable crop per hectare is great in spite of the small annual increment of stem volume.

Frozen ground and snow cover in winter and floatable waterways in summer favoured logging and transport of timber in the time of muscular power. Except in mountains, the terrain and soils are easily operable from the point of view of constructing forest roads and using tractors. Soft peat lands restrict logging in the summer but can carry vehicles and equipment in the frozen season.

In Boreal regions the forest resources per capita have been, and are still, much greater than the world average. The area of exploitable closed forest per capita varies from 2 to 9 ha and annual removals from 1.4 to 8.9 m^3, timber assortment volume under bark. The world averages are 0.44 ha and 0.66 m^3. Boreal countries have much more harvestable wood per capita than they need for their own consumption. For example, in Europe, excluding the Soviet Union, the consumption of forest products corresponds to 0.75 m^3 of roundwood per capita while the removals are 6.4 m^3 /capita in Canada and 5.9 m^3/capita in Nordic countries.

Men capable of living in the rigorous climate have had to possess considerable physical qualities to over-come the hard living and working conditions. They have attained the knowledge and skills to harvest and process wood into a great variety of commodities. The boreal zone has become and remains one of the most important global suppliers of timber and processes products.

Forest resources

The Boreal forests cover much of Alaska, Canada and the Soviet Union as well as Nordic countries. Resource information compiled in the late 1970's and around 1980 are presented in Table 1.

The total area of forest and other wooded land of these regions is 1 474 mill. ha. of which closed forest is about 1 120 mill. ha. and exploitable closed forest 802 mill. ha. Large areas of these regions belong to the temperate zone, however. About 20 % of the Soviet forests, coastal Alaska and British Columbia, although these latter two areas are dominated by conifers, are outside the Boreal zone proper. The southernmost parts of Canada, Norway, Sweden and a narrow strip of south-western coast of Finland also belong to the temperate mixed forest zone.

Shares of the forest resources from the world total (Fig. 1) compared with the share of population demonstrate how rich the boreal countries are in forests. Shares within the Boreal regions and growing stock and net annual increment per hectare of exploitable forest are as follows (Page 14).

It should be noted that even though the growing stock volume per hectare is smallest in Nordic countries the net annual increment of this region is by far greatest. In the case of the Soviet Union the area of exploitable closed forest obviously consists only of forested land. If about 120 mill. ha. of land capable of growing closed forest, but at the moment treeless or under scrub forest following final fellings and wild fires, were included in exploitable closed forest, the net annual increment per hectare would be 1.15 m^3 in the Soviet Union. The Canadian exploitable closed forest land includes 22 mill. ha. of land more or less treeless, following final cutting, forest fires and other calamities.

	Alaska	Canada	Nordic	USSR	Total
		per cent			
Population	-	8	6	86	100
Forest and other wooded land	3	30	4	63	100
Expl. closed forest	1	24	6	66	100
Growing stock	1	24	5	70	100
Coniferous	1	24	5	70	100
Net annual increment	-				
Coniferous	-	27	13	60	100
Growing stock m^3/ha	287	107	91	125	119
Net annual increment"	0.79	1.68	3.27	1.40	1.58

	Alaska	Canada	Nordic	USSR	Total
		percent of world totals			
Removals	0.1	5.2	3.5	12.2	21.0
Coniferous	0.3	11.9	7.3	25.4	44.9
Industrial timber	0.2	10.4	6.6	19.7	36.9
		percent of Boreal totals			
Removals	0.5	24.8	16.6	58.1	100.0
Coniferous	0.5	26.5	16.4	56.6	100.0
Industrial timber	0.5	28.3	17.9	53.3	100.0
Removals m^3/ha	0.69	0.71	2.11	0.67	0.76

Removals of timber

Removals of timber in under bark volumes of harvested timber assortments are presented in Table 1. The shares of the world removals, the shares of the Boreal totals, and removals per hectare of exploitable closed forest are as shown above.

Nordic removals per hectare are about three times greater than in other Boreal areas.

Annual removals were increased from the beginning of the 1960's to the first half of the 1980's, if removals at 1980 equal 100, by 30 percentage units in the world as a whole and by 35 units in Canada (Fig. 2a). In Nordic countries removal increased up to 1975 but then decreased to the level of the beginning of the 1960's. In the Soviet Union the removals decreased by about 8 percentage units around 1975 and have since remained on the 100 percent level.

The world removals of coniferous assortments and industrial wood have increased less than the total removals and removal of industrial wood. This is explained by the growing need for fuelwood and increasing removals of non-coniferous assortments in the developing countries. In the industrialized Boreal countries the consumption of fuelwood and removals of non-coniferous assortments have decreased.

Increases in the removals of industrial wood stagnated around 1980. This is partly explained by the increasing consumption of saw- and ve-

neer-milling residues and the use of waste paper for pulp, particle and fibre boards.

There is some evidence, that the timber resources within reasonable distances of the forest industries in Canada and the Soviet Union are exhausted and there are increasing difficulties to economically satisfy the need for timber from forests farther away. In Nordic countries the removals are 15 to 20 percent smaller than removals on the basis of sustained yield. The bulk of the forests there are in private ownership and the owners are not willing to utilize them fully. Nordic forest industries have for about 15 years been dependent on timber imports which have covered 10 to 15 percent of their needs.

Production of forest industries

Production of forest industries in the Boreal regions of Canada, Nordic countries and the Soviet Union around 1980 and the share of totals of the world production are presented in Table 2 and the country shares of the world production in Table 3. These countries produced 53 percent of mechanical pulp and newsprint, 38 percent of sawnwood and 35 percent of the products of basic forest industries.

Proportional shares of countries are:

	C	N	S	F	NC	USSR	Total
				percent			
Sawnwood	26	1	7	5	13	61	100.0
Wood-based panels	25	3	10	8	21	54	100.0
Mechanical pulp	52	6	13	16	35	13	100.0
Chemical and other pulp	38	2	21	15	38	24	100.0
Total basic industry	31	2	12	9	23	46	100.0
Newsprint	64	4	11	11	26	10	100.0
Writing and printing paper	24	5	17	34	56	20	100.0
Other paper and p.broad	20	3	23	14	40	40	100.0
Total paper and p.broad	38	4	17	16	37	25	100.0

Canada is a great producer of sawnwood, mechanical pulp and newsprint, the Soviet Union produces much sawnwood and wood based panels, and Nordic countries produce much paper and paper board, especially writing and printing paper in Finland.

Production per capita figures (Table 4) demonstrate that forestry and the forest industries are of greatest importance to Finland, Sweden and Canada. In proportion to population, the production of paper and paper board is much smaller in the Soviet Union than in other Boreal countries.

Value of forest exports and imports

The total values of forest exports and imports and the values per capita, and the shares of totals in world trade are presented in Table 5 and the shares by products in Table 3. Boreal countries account for 47 percent. Of the world exports and 5 percent of imports. The share of sawnwood exports is 55 percent, wood pulp 66 percent and paper and paper board 53 percent.

The export of forest products is of the greatest importance to Finland, 942 U.S.$ per capita. The corresponding value for Sweden is 596 U.S.$ and for Canada 403 U.S.$.

Efficiency of forestry

In spite of the international attempts to standardize the units of measurements and methods in surveying forest resources there are still many inaccuracies which make it difficult to compare the figures of one country with another. Some conclusions are, however, obvious.

In the following review the recorded net annual increment and removals per hectare around 1980 in Alaska are marked as 100. The corresponding estimates for other areas in proportion to the Alaskan values are:

	Net annual increment	Removals	Percent of removals from net annual increment	
			total	coniferous
Alaska	100	100	86	158
Canada	209	103	74	68
Nordic countries	409	306	81	85
Norway	328	200	65	76
Sweden	442	329	80	83
Finland	396	316	86	90
USSR	175	97	62	64
Total	198	112	63	68

The net annual increment and removals per hectare are far greatest in Nordic countries. Possible reasons for this are discussed in the part of this paper concerning forest ecology.

In the Boreal region of European Soviet Union (Fig. 1) the proportional value of removals was 197 at the end of 1970's. In this region the removals are reported to exceed the net increment by 26 percent. The overcut has been greatest in the administrational regions in the Boreal zone proper. For some time, the aim of Soviet forestry policy has been to move logging to Siberia and the Far East where there are large virgin forests. However, even in Siberia the forests near railways and floatable and navigable rivers have been heavily exploited.

In Canada the removals can be increased if the net increment of the total area of exploitable closed forest is taken as the ceiling of the allowable cut. The forests in use so far have been heavily exploited, and there are difficulties in moving logging to the remaining virgin forests far away from the forest industries and populated areas. If the current level of production is continued, the mill prices of wood can be expected to rise and the quality of wood to decrease.

In Nordic countries the removals, though much greater than in other Boreal areas (Fig. 1), have been smaller than the net increment by 35 percent in Norway, by 20 percent in Sweden and by 14 percent in Finland. These countries have lost, at least temporarily, their ability to fully utilize their timber resources.

In all Boreal countries, the coniferous tree stands are exploited proportionally more than the non-coniferous ones. The obvious reason for this is the small size, higher logging costs and lower value of non-coniferous trees. If the unexploitable non-coniferous trees are not cleared away as a silvicultural measure in the regeneration areas, and if large parts of the overcut areas are left to regenerate naturally by pioneer tree species, the productive value of forests will decrease.

3. ECOLOGY

Ecological conditions

The boreal coniferous forest is a homogeneous vegetation belt around the North Pole. Temperature is the most influential environmental factor determining its geographical location. The northern boundary of the zone is approximately on the July 13° C isotherm. Marked departures, however, are caused by mountains and oceans, and maritime and continental climatic influences. The southern boundary coincides with the July 18° C isotherm. Conditions drier than average push the zone northwards.

The Boreal zone can be divided into continental, high-continental and maritime parts. The continental climate dominates most of it. Winter is long and cold. Abundant snow lasts 5 to 7 months. Considerable variations in the monthly mean temperature is a marked feature. Desiccating winds and temperature of -20 to -40° C, or even colder, can be lethal for trees in the northern parts of the belt.

Warming in the spring is rapid but there is a great variation in the time when photosynthesis begins. Summer weather is comparatively warm but it can be very changeable. The vegetation period lasts 100 to 150 days, 90 to 160 days in most extreme conditions. The mean temperature of the warmest month is +10 to +20° C.

The annual precipitation varies from 400 to 600 mm, with the maximum of it falling during the summer months. The relative humidity is 50 to 70 percent in July and August. Climate is humid and water moves generally downwards in the soil.

During a year the range of the mean temperature is 20 to 40° C and the maximum range can be 60 to 70° C.

In the high-continental climate the winter is very long, extremely cold and dry. The mean annual temperature is -7 to -10° C. The range of the mean monthly temperature can be more than 40° C. The maximum range of temperature is 80 to 100° C and the lowest temperatures can be -50 to -60° C. The mean temperature of the coldest month can be colder than -25° C. Summer is short and comparatively warm. Mean temperature of the warmest month is +10 to +20° C. However, frost is possible every night even in summer.

Precipitation is generally smaller than in the other parts of the zone. Because of cold winter and thin snowcover there is permafrost in large areas. As an example of the capricious weather, in the Western Sibiria the annual presipitation varies from 350 to 600 mm of which 80 mm can fall in one storm.

In the maritime part of the zone the range of climatic extremes is smaller. There is more snow. Winter is comparatively mild and summer often cool. The temperature of the warmest month is +10 to +15° C and of the coldest +2 to -3° C. The annual precipitation ranges from 400 to 800 mm or more in some coastal areas and much of it falls during the winter.

Because of glacial action the parent soil material is generally less fertile than in the temperate zone. Glacial and alluvial sands and gravel's dominate with moraines. Podzols are the most common soil profile in the cold and humid climate and the podzolization process is fastest in sandy glacial outwashes. In the more fertile sites podzolization proceeds at a slower rate. These profiles are nearer to brown forest soils than podzols proper and are often referred to as brown podzols.

Sites are inclined to paludify and change into peat-forming mires in conditions where drainage is impeded.

Coniferous trees are well adapted to Boreal conditions. They can reduce their transpirational water-loss to a very low level during the winter when water is unobtainable from the frozen soil.

In the spring, when temperature allows photosynthesis, the conifers are able to profit from it earlier than deciduous trees which have to grow leaves before photosynthesis can commence. Thus deciduous trees waste a part of the short growing season.

The deciduous trees have also to use a greater part of their net primary production to maintain foliage than the conifers. They renew their foliage once every year while the ever-

green conifers renew their needlemass during 4 to 7 years.

Because of these competitive advantages the taller growing and longer living conifers can over-top and, with their greater biomass, outcompete the broad-leaved trees. This also explains the greater timber production of conifers compared with broad-leaved trees on similar sites.

In rigorous weather conditions near the northernmost boundary of the zone and in forest tundra, however, the coniferous evergreens can not endure the desiccating winds and bitter cold. Under such conditions some broad-leaved deciduous trees and shrubs such as birch, aspen and willows are more competitive than conifers. Growing slow and low, leafless in winter and partly inside the snow and regenerating by vegetative sprouts, they can overcome the cold weather and desiccating winds and form sparse stands.

In the most rigorous conditions of the Eastern Siberia and the Far East, two conifers, Dahurian larch (*Larix dahurica*) and its associate, dwarf Siberian pine (*Pinus pumila*) can survive and form the forest boundary against the tundra. They are shallow-rooted, low-growing, and often creep along the ground. The Dahurian larch combines the competitive qualities of both coniferous and deciduous trees.

In addition to the climatic and edaphic factors, the location, height and orientation of the mountain ranges and the location of seas have effected the composition of the plant species which have had to retreat and re-advance during the glacial and inter-glacial periods.

Plant-species compositions are comparatively similar in the North American, European and Asian formations of the Boreal formation-type. As a rule, the same plant genera occur and prevail in environmentally corresponding areas throughout the Boreal belt. However, there is a marked difference in the number of dominating tree species in North America, in Nordic countries, in the European Soviet Union and in Asia. The number of tree species is greatest in North America, and greater in Asia than in Europe. The location of the mountain ranges and seas in Europe have been a barrier for advancing tree species during the interglacial periods.

In North America, including the coast of Alaska and British Columbia, there are six principal coniferous tree genera and the number of species is 24. In the Boreal North America proper the corresponding numbers are 5 and 11.

In Nordic countries there are only 2 coniferous genera and 2 species and in the European Soviet Union 4 and 4. The corresponding numbers in Asia are 4 and 16; the number of species increasing from west to east.

The genera *Betula*, *Populus* and *Alnus* are pioneers in the Boreal tree stand successions. They belong to climax stages on water sides, wet lands and some mire types, and are associate species in stands dominated by conifers.

Natural and human dynamics in forests

The current state and future development of Boreal forestry are results of both natural and human dynamics. Principles guiding the dynamics of forest ecosystems are also the basis for studying and understanding the disturbances in forest ecosystems caused by human activities. Forest ecosystems attempt to adjust to these disturbances by definite natural reactions and when disturbances cease the ecosystems revert to their natural development.

The natural and human dynamics are illustrated by selected features of the forests of Finland with few references to other Boreal areas.

Plant-community successions and climatic climaxes

Boreal plant-communities are very young when compared with the tropical rain forests which have changed little over the last million years. During the glacial period, ice advancing from the north swept away all plants, animals and soils. After the ice retreated there appeared a completely inorganic surface of the parent soil material: bare rock, smooth boulders, glacial

and fluvial sands and gravels, moraines and fluvial loam and clay plains. The pre-glacial drainage system was destroyed and the new terrain was poorly drained, studded with ponds and lakes. Large areas were from the beginning susceptible to development into peat forming mires.

Plant and animal life started to invade the land rising from water after the retreating ice. Colonization and further development are usually described by a succession of plant communities, although the description could equally be focused on the characteristics of animal communities, microclimates or soil, processes (Fig. 3).

Colonization stages on inorganic bare sites are called primary seres. The first pioneering community comprises algae and lichens which can anchor themselves on the rock and boulders, take water when it is available and withstand desiccating periods. Pioneering communities create primitive soil from inorganic and organic particles, and prepare the site for more demanding plant and animal communities.

The secondary community also consists of mosses able to store water. This accelerates soil-forming processes with water-retaining layers, thus making the habitat less susceptible to drought. Microbes and animals co-operate with plants in soil-forming processes.

In the third stage turf-forming annual and ephemeral grasses (e.g. *Festuca ovina*) and in the fourth stage low- growing shrubs invade the site and create a thick soil layer.

In the subsequent stages trees dominate. At first, broad-leaved pioneer species with light-weight seeds transported by wind. Shrubs and trees create an ameliorated micro-climate. Climatic extremes are reduced, the number of plant and animal species increase and forest soil profiles start to develop.

In the final stage, the deep-rooted, long-living climax tree species and the ground vegetation tolerating the shade of trees dominate the site. Species from earlier stages rarely survive under climax conditions. This is because the most competitive trees have shade tolerating seedlings which nevertheless outgrow shade-intolerant pioneer trees. The result is a climatic climax where, at least in theory, the plant and animal community is in balance with all environmental factors.

However, the climatic climax may not be permanent in the sense that it is an unchanging system where there is a balanced mixture of regenerating, growing and dying trees and other plants. Left undisturbed by wild fires and other calamities the climax tree-stand may finally give way to smaller and greater openings in the crown canopy thus giving a chance for a new serial development. Another interference to a climax tree-stand may be caused by degenerating nutrient cycle, paludification and the change of a poorly-drained site into mire.

Arresting factors, e.g., temporarily impeded drainage, may change the direction of a serial development into a sub-climax community. When the arresting factor is removed, the subsere continues towards the true climax.

In natural Boreal conditions without effects caused by man, wild fire and some other calamities destroy climatic climaxes and start new serial successions towards climaxes. A very heavy fire may cause more or less bare site conditions where the successions restart from smaller plants than trees.

Plagioseres and plagioclimaxes are additional developments of plant-communities caused by the protracted actions of man and his domestic animals. Shifting cultivation with regular rotations and forest pasturing have maintained plagioseres. A heavy stock of reindeers, for example, and silviculture maintain forest structures different from natural forests.

Natural tree-stand successions

On lands exposed by the retreating ice cap some 10 000 - 12 000 years ago there developed two basically different types of soils, a mixture of mineral particles and humus on mineral sites and pure organic soils on peat lands. On lands where topography, impeded drainage and precipitation exceeding evaporation favoured paludification and peat-forming, mires were abundant.

About a third of land in Finland is now covered by peat. The proportion of mires increases towards the north. In Northern Ostrobothnia 60 to 70 percent of land is under mires. Moss and shrub vegetation dominates and tree stands are composed in most cases by small, stunted and bushlike scattered trees.

Before man, wild fire was the iniciator of treestand successions and the rejuvenator of forest ecosystems. On driest glacial sands and gravels the rotation of wild fire was 40 to 60 years and only on fresh moraines, loams and clays the plant-communities could develop undisturbed for more than about hundred years.

A simplified scheme of the tree-stand successions on mineral sites is presented in Fig. 4. Some additional and partly hypothetical comments are needed to supplement the sheme.

As stated earlier, temperature during the growing season restricts most the gross primary production of tree stands. Cold weather retards the decomposition of the plant residues. On poor podzol soils, insufficient nutrients restrict the gross primary production more than the insufficiency of solar radiation, temperature and water.

The more assorted the soil parent material is and the less it includes clay particles, the greater is the susceptibility of sites and tree stands on them to fire. In natural conditions the rotation of wild fire is so short that on most of these sites there has been never a true climatic climax-stand. Because spruce is much more susceptible to fire damage than pine, pine is generally considered as the climax tree on alluvial sands and gravels.

On the poorest sites pine is also a pioneer tree. Birch, aspen and alder as pioneers invade open sites after fire or any other calamity. On moraines and more fertile sites spruce is the climax tree.

Mixed forests and stands dominated by broad-leaved trees can form climax stands on watersides and wet lands.

Without wild fire and human disturbances tree stands would developed into climaxes. Spruce would dominate on almost all sites except possibly the poorest sands and gravels. Spruce undergrowth together with spruce dominated crown-layers would shade-out all other tree species from the site until a calamity or the death of overmature large trees created openings and open land for other tree species to form pioneer stands.

There is evidence that under climax conditions the site begins to degenerate: mosses increase in the ground vegetation; the raw humus layer becomes thicker; nutrients available for trees, especially nitrogen, decrease; the site looses its fertility; paludification increases in conditions of poor drainage and the site may change into mire.

On the most barren sites and especially near the northern forest boundary heavy fires can damage the thin humus layer to such extent that the site looses its fertility and becomes, for a period of time, unable to carry closed tree stands. During historical dry periods fire has moved the northern forest boundary long distances to the south.

Climatic climaxes of spruce may represent a degenerated nutrient cycle and lower site quality compared with conditions where repeated wild fire interrupts the advancing degeneration. Burning rejuvenates the soil and increases also the active nitrogen resources because of the symbiotic fixation by alder and some pioneer shrubs.

As an extreme example, in a black spruce stand the total storage of nitrogen in the humus and soil can be 1 722 kg/ha. of which there is only 37 kg or 2 percent available for trees which take up annually 15 kg and return to the soil in the form of litter an equal amount.

Tree stand successions under human disturbances

Most of the Boreal forest belt has been and remains outside the main zones of human settlement. Only in Nordic countries has man extensively settled in the Boreal zone and developed there a modern industrialized society. Virgin forests outside silviculture and timber production consist of smaller and smaller areas. Soon virgin forests will exist only in national parks, other reserves and limited areas outside

profitable logging. Even these may no longer be inately virgin, as they are protected from wild fires, and also suffer from airborn pollutants.

Human activities can be studied and analyzed inside the frames of the scheme presented in Fig. 5. During several hundreds of years the Boreal forests have been under the influence of the developing types of economics with corresponding functions of forests and dimensions of timber production.

The first human settlements and their economies a and b, Fig. 5, did not significantly change the natural forest conditions. There is some evidence that nomadic pasturalists with their reindeer stocks introduced deliberate forest fires to improve the pastures and thus modified to some extent the northernmost forests. The first colonizers increased rather than restricted forest fires and corresponding tree-stand successions.

The era of shifting cultivation, pasturing in forests, extracting tar and charcoal, the growing consumption of wood for houses, fuel and many other household purposes, and boats and ships (2c, Fig. 5), flourished up to 19th century and thoroughly changed the virgin forests within the reach of muscular power and floatways into plagio seres dependent on human activities.

Although the number of people was much smaller than now, man penetrated everywhere, except the most barren watersheds and eastern and northern wilderness. In the north, permanent settlements extended along river valleys to beyond the Arctic Circle.

It has been estimated that shifting cultivation has covered 4 mill. ha. of forest land. Human activities increased forest fires. The bulk of the spruce forests were pushed away from the most fertile sites. The rotation period of shifting cultivation was from 20 to 40 years. Between agricultural cropping of 2 to 4 years, the sites grew mostly alder, birch and aspen. In large areas of Southern Finland and along the Gulf of Bothnia large-size construction timber was a rare commodity.

This stage of economic evaluation supported a population of only about 1.5 mill. When crops failed, tens of thousands of people died of hunger and diseases. However small the population, men exhausted the timber resources, which reached a minimum in the second half of 19th century.

Mining, extracting metals from the ore and shipbuilding industries were great consumers of wood. Because of an imminent shortage of exploitable timber, laws were enacted to restrict the cutting of forests. Initially, sawmills driven by water-power were suspected to be a cause of the destruction of the forests. The establishment of steam sawmills was permitted in 1857.

Steam-power, produced by burning wood, was introduced to increase production. It overcame the distances of timber transport. Steam and waterways became the means to transport timber from inland to factories and coast and timber and processed products to export markets. Exports made possible imports of raw-materials, machines and foodstuff which enabled the population to grow and to increase more diversified production.

The green gold of Finland was discovered. The sawmilling expanded strongly in the 1880's. The value of forests increased by another large step after wood-fibres started to be used as the raw-material for paper. The first pulp-grinding machine was started up in 1860, the first kraft pulp mill in 1880 and the first sulphite mill in 1885. The economy switched through type 2d to 2e (Fig. 5).

During the time of sawmilling dominance there was market demand only for large-dimensioned trees which were felled by selection cutting. This finally led to poorly productive residual tree stands, many of them of spruce on barren sites. The growth of pulp and paper industry resulted in demand for all timber assortments and permitted the carrying out of silvicultural thinnings, regeneration cuttings and the rational growing of timber.

Although the consumption of timber by the forest industries increased strongly, industrialization brought about a start on the improvement, regeneration and increase of forest resources. At the same time, the wasteful practices of shifting cultivation and tar burning

were discontinued. Forest fires became effectively controlled. Fuelwood was replaced by coal, oil and electricity. The use of wood as building material declined.

Industrialization resulted in a major structural change in wood consumption. The proportion of wood used by industry out of the total stemwood drain was about 2 percent in the 1850's, 20 percent in 1900, 50 percent in 1950 and 82 percent in 1980.

Without the great increase in the comsumption of industrial wood removals would have been much smaller than they have been during this century. Drain of stemwood smaller than its increment would have resulted in overdensity, over-ageing and partial deterioration of the growing stock, and a mature tree crop much larger than has happened so far.

From the point of view of forest ecology, shifting cultivation, large forest fires, and heavy utilization of timber prevented overmaturing of the tree stands and the widespread development of climatic climaxes dominated by spruce. During the stage of expanding industrialization there were still large virgin forests in the eastern and northern parts of Finland. In Southern Finland young and middle-aged tree stands, many of them in seral stages, dominated and produced most the timber for growing industries.

Tree stands in the stages of highest net primary production have dominated the age-class structure of forests in the principal timber producing regions. In addition to this, the intensive human disturbances also activated the nutrient stores in soils and increased the flow of the nutrient cycle between soil, trees and ground vegetation.

The aim of the first forest laws was to guarantee timber for shipbuilding and mining. The laws to promote silviculture and sustained-yield management were not enacted until the beginning of the 20th century when the demand for timber grew in the export oriented forest industries. The main objective of the current forest laws is to prevent the destructive exploitation of the immature tree stands, and to guarantee regeneration after final cutting.

Silviculture has been intensive since the beginning of the 1950's when the markets for all timber assortments improved. Thinning yield was about 60 percent, or even more, from the total removals until the 1970's and are 20 to 30 percent at the moment. During the past 20 years final harvesting with regeneration has totalled about 160 000 ha. per annum of which about 125 000 ha. have been planted or artificially seeded. Scarification and ploughing has totalled about 120 000 per annum.

Silvicultural and forest improvement achievements on the 19.6 mill. ha. of forest land in timber production between 1947 and 1986 are as follows:

- artificially planted and seeded stands	3.6 mill. ha.
- seedling stand improvements about	9.0 "
- drainage (61 percent of the area of mires and other wet lands)	5.5 "
- fertilization	2.8 "
- increase of forest land capable of growing closed forest: from 17.4 to 20.1 mill. ha. in 1952-1981	2.7 "
- increase of tree stands younger than 40 years	3.2 "
- increase of tree stands dominated by pine	3.8 "
- construction of forest roads	76 000 km

The area of spruce stands on poor sites has considerably decreased, especially in Northern Finland. On the other hand spruce has invaded most of those areas which had grown pioneer tree stands after the period of shifting cultivation. Non- coniferous tree stands decreased during the period 1950 - 75 but have started to increase since then, especially on drained peatlands and abandoned fields. The bulk of the current broad-leaved stock grows as a mixture in tree stands dominated by conifers.

Logging and regeneration cuttings have reached the coniferous forests near the northern forest boundary. In the coldest climate and on the barren sites artificial stand establishment

often fails and is at least unprofitable in comparison with the natural seeding.

Natural regeneration of coniferous tree stands succeeds on cleared and prepared ground, even near the northern forest boundary, although the time required there for seedling stand to become established can be from 10 to 30 years. If the northern forest boundary has changed during the 20th century, it has moved northwards. There is evidence that the historical movements of the forest boundary have only been caused by changes in the macro-climate. Cold and dry periods with large forest fires have shifted the forest boundary southwards; warmer and more moist periods move it northwards.

From the point of view of ecological productivity, the heavy utilization of the forest via silvicultural harvesting and regeneration after final felling has resulted in an age-structure where all age-classes of tree stands are represented. Most of the stands are in the stage of greatest net primary production.

Tree-species composition have been constantly changing. Silvicultural measures have stopped the degrading development of soils under old climax coniferous stands or the stand development towards climax. On all regeneration areas there is at least a short time stage of pioneer vegetation even if the new stand is dominated by conifers in the later stages.

The silvicultural disturbances can be considered as a substitute for wild fires rejuvenating the tree stand and soil ecology. The current silvicultural measures may not counterbalance the degrading tendencies in the Finnish conditions where the total area of forest fires was only 4 360 ha. during the period 1976 - 86.

In Boreal Canada and the Soviet Union, most of the forests have been outside human settlements and the bulk of the current exploitable tree stands are at ages and seral stages where the net primary production is small or even negative. This explains the great mortality and small net increment of the stem volume. Possibly the site quality has also degenerated under the stands dominated by spruces and firs.

In those countries, almost all timber is harvested by final cuttings from old and over-aged virgin stands. The large overcut areas are frequently left without silvicultural measures to natural regeneration. Forest fires and other calamities destroy huge amounts of timber. Millions of hectares of the original coniferous forests have changed to seral successions dominated by broad-leaved trees.

In the northern European Soviet Union and West Siberia, where the rivers flow into the Arctic Ocean and where the spring melting of snow and ice starts at the fountainheads, the flat terrain is inclined to floods and paludification. Large clear-cuttings without immediate regeneration may lead to reduced evaporation to an extent that former dry lands change into mires.

As stated earlier, the Nordic countries have reached a post-industrial stage of economic development (2f, Fig. 5). Future timber removals will be, at least for the time being, about 20 percent smaller than the net increment of growing stock volume. The share of thinnings will be 20 to 30 percent of the total removals which is too little to maintain the good silvicultural conditions of the growing stock. The density and age of the growing stock will increase and many of the spruce and pine stands will develop towards plagioclimaxes.

Side by side with the technological, economic and social development the function of forests has changed from a commodity function to a protective, social and cultural function (3a-d, Fig. 5). As a consequence, effective and profitable timber production measures are often considered to be harmful and undesirable. Further, the great share of private non-industrial forests composed of numerous small holdings seriously restrict effective timber production.

Both the increasing density and age of the growing stock and the share of the overmature climax stands will increase the mortality and losses of the timber crop and degrade the forest as a productive element and a good environment. Long term consequences are most serious if this development also leads to a degrading nutrient cycle and a deterioration of the site qualities.

The latest human disturbance and menace to the Boreal forest are the airborne pollutants and the increase of the carbon dioxide in the atmosphere. There is some evidence that the precipitation of nitrogen and the increase of carbon dioxide have temporarily increased the growth of the trees. Damages caused by direct fume effects and the precipitation of sulphur and other pollutants in the neighbourhood of industrial centres are obvious. The accumulation of pollutants in large forest areas is considered great enough to cause changes in the ecosystems.

Several industrial compounds and high-level jet exhaust may damage the earth's protective ozone layer. The reduced ozone layer causes an increase of harmful ultraviolet radiation. The phenomenon may be most severe in the Boreal latitudes.

The continuing increase of atmospheric carbon dioxide is considered to result in an increase in the mean air temperature which in turn may change the precipitation and wind conditions. Although the process is slow and its consequences may, at least at the moment, be hypothetical, the subject matter is of utmost importance for the future of the Boreal forests. Even seemingly small increases in the mean temperature increase the competitiveness of broad-leaved trees with regard to the conifers. This results in areal changes in the tree-species composition and pushes the Boreal belt northwards.

4. FINDINGS AND DISCUSSION

The Boreal countries posses rich forest resources. The area of exploitable closed forest varies from 1.6 to 9.0 ha. per capita and removals around 1980 from 1.4 to 8.9 m^3 per capita while the world averages are only 0.44 and 0.66 respectively.

In all Boreal countries and Alaska timber is an important raw material. Processed by forest industries into commodities it is a valuable export asset. These regions account for 21 percent of the world removals, 45 percent of the coniferous removals and 31 percent of the removals of industrial timber.

Canada, the Nordic countries and the Soviet Union account for 35 percent of the world production of the basic forest industries, 21 percent of paper and paper board and 53 percent of both mechanical pulp and newsprint. Their share of the export value of the forest products is 47 percent, 55 percent of the value of sawnwood exports, 66 percent of woodpulp and 53 percent of paper and paper board.

In order to maintain their share of world production and trade, Boreal countries have to intensify their forestry and move logging deeper and deeper into the remaining wilderness.

Net annual increment of stem wood per hectare is 2 to 3 times and removals about 3 times greater in Nordic countries than in other Boreal areas. In regard to the climate they are greatest in Finland and second greatest in Sweden. There are obvious reasons for this:

During past centuries the Nordic people have lived inside the forests and utilized them heavily. The consumption of wood was so great during the time of the muscular power that the growing stock volume was very small in the l9th century and at the beginning of the 20th century. At that time virgin forests existed only outside the reach of man, horse and waterways.

The heavy utilization of timber continued for the growing forest industries later in the 20th century. This maintained conditions where the mature tree stands were cut and new young stands were regenerated after the final cuttings. Therefore the bulk of the current tree stands are in the ages of great 'net primary production'.

Silviculture has been at a high level during the last 50 years. Forest owners have been responsible for establishing a new tree stand after harvesting the mature stock and applying silvicultural thinnings to immature stands. Thinning yield was about 60 percent of the total removals around the middle of this century and is still 20 to 30 percent now. Mortality and the decays of stemwood in the forest has been comparatively small.

Human disturbances, earlier combined with large wild fires, have maintained the rejuvenating seral successions of the tree species and activated the free nutrients in the soils. Large scale drainage of mires in Finland has restricted the paludification and peat-forming processes and increased productive tree stands on drained and fertilized peat lands.

In Canada and in the Soviet Union almost all timber is harvested by final cuttings, mostly without proper regeneration measures, from mature and overmature tree stands away from human settlements. Mature and immature climax stands are in the stages of small, zero or negative net primary production and the site under them is susceptible to degenerative processes.

Mortality and fire damages are huge. Large areas of earlier coniferous forests have changed into shrub forests and successive sub-seral stages dominated by low-value non-coniferous trees.

Paludification and mires may increase on flat lands, especially along rivers flowing to the arctic ocean. Harvesting of timber is moving to far-away virgin forests which increases logging and transport costs and may lead to decreasing quality of timber.

In post-industrial Nordic countries repeating wild fires have been effectively eliminated. Removals are about 20 percent smaller that the increment of growing stock. The bulk of the tree stands are becoming denser and older. If this continues long enough mortality will increase and the value of timber stock will decrease. Over-dense and over-mature tree stands are not the best environment for the multiple-use purposes.

In large areas, old spruce stands and the risk of degenerating soil fertility will increase. In neglected degeneration areas, seedling and young stands on peat lands and abandoned fields, the low-quality non-coniferous trees are also increasing in Nordic countries.

The environmental turmoils in Boreal forestry call forth many topics for further research:

Logging is moving farther and farther away from the settled areas and mill sites to the remaining virgin forests. How much will this increase the costs of production and transport? What will be the quality of timber? E.g: if the quality of coniferous sawlogs decreases, what are the consequences in the sawnwood markets?

An important item is the extent, and tree-species composition, of the pioneer stands established by natural reproduction on the over-cut areas and how long a time will the seral development take from non-coniferous stands to harvestable coniferous under different site conditions.

The process from broad-leaved stands to spruce stands lasted about 100 years without silvicultural measures in Southern Finland following the cessation of shifting cultivation. The time was reduced to 50 to 70 years by silvicultural cuttings, and to 30 to 50 years using planting and other silvicultural measures.

A minor but locally important topic for investigation is the rate of tree-stand successions on drained peat lands and abandoned fields.

It would be interesting to find out whether economically possible means exist to release the inactive storage of soil nitrogen for trees and thus increase the productivity of the Boreal sites.

There is evidence that in large areas in Boreal regions where flat land with poor drainage conditions dominates paludification and development of mineral sites into mires increases after harvesting old coniferous stands. What is the geographical distribution of this process and what are the consequences?

The benefits and value of site preparation, herbicides, drainage, etc., require further studies. For example, in Finland there are large over-cut areas in stages of regeneration near the northern forest boundary. Although there will be new tree stands, what is their species composition and how long a time is needed to grow harvestable timber in these rigorous conditions?

And finally, too little is known what are the consequences in Boreal forests of the air-borne pollutants and the changing composition of the atmosphere.

LITERATURE

An analysis of the timber situation in the United States, 1952-2030. 1980. Washington, D.C. USDA Forest Service. Forest Resource Report No. 23.

Canada's Forest Inventory 1981. 1982. Canadian Forest Service.

Eyre, S.R. 1963. Vegetation and soils. A world picture. London.

Forest Management Expenditures in Canada, 1977-1983. 1986. Joint Report No. 9. Canadian Forestry Service.

The forest resources of the ECE region (Europe, the USSR, North America). 1985. FAO/ECE. Geneva.

Holowacz, J. 1985. Forest of the USSR. The Forestry Chronicle. October 1985, pp. 366-373.

Kauppi, P. & Posch, M. 1985. Sensitivity of Boreal forests to possible climatic warming. Climatic Change 7, pp. 45-54. D. Reidel Publishing Company.

Kuusela, K. 1984. Euroopan metsävarat ja niiden käyttö. Suomen itsenäisyyden juhlavuoden 1967 rahasto (SITRA). sarja B, Nro 75. Helsinki.

— 1985. Euroopan puuntuotanto ja teollisuuden ulkomaankauppa 1950-2000. Suomen itsenäisyyden juhlavuoden 1967 rahasto (SITRA). Sarja B, Nro 79. Helsinki.

— 1986. Development of Nordic forest resources in the results of the European Timber Trend Studies. Reports of Norwegian Forest Research Institute 39.15, pp. 265-281.

— 1987. Forest products — world situation. AMBIO, Vol. 16 No. 2-3, pp. 80-85.

Kuusipalo, J. 1985. An ecological study of upland forest site classification in Southern Finland. Seloste: Ekologinen tutkimus Etelä-Suomen kangasmetsien kasvupaikkaluokituksesta. Acta For. Fennica 192.

Larsen, J.A. 1980. The boreal ecosystem. Academic Press. New York, London, Toronto, Sydney, San Francisco.

Nizon, V. 1985. Forstwirtschaft in der Sovjetunion — ein Überblick. Schweiz. Z. Forstwes., 136. 9: 763-771.

Paterson, S.S. 1956. The forest area of the world and its potential productivity. Meddelande från Göteborgs Universitets Geografiska Institution 51.

Raumolin, J. 1985. The impact of forest sector on economic development in Finland and Eastern Canada. Fennia 163:2, pp. 395-431.

Resources and Man. 1969. A Study and Recommendations by the Committee on Resources and Man, the National Academy of Sciences. San Francisco. 259 p.

Ronge, E.W. 1928. Kort redogörelse för vissa skogliga försök, verkställda under åren 1914-1928 å Kramfors Aktiebolags skogar, och resultatens praktiska tillämpning i skogsbruket. Norrlands Skogsvårdsförbunds Tidskrift, s. 308-356.

Selected Forestry Statistics. Canada 1984. Information Report E-X-34. Economic Branch, Canadian Forestry Service Headquarters.

Tseplyaev, V.P. 1961. The Forests of the U.S.S.R. Translation. Jerusalem.

Weck, J. & Wiebecke, C. 1961. Weltforstwirtschaft und Deutschlands. Forst- und Holzwirtshaft. München-Bonn-Wien.

Windhorst, H.-W. 1978. Geographia der Wald- und Forstwirtschaft. B.G. Teubner. Stuttgart.

A World Geography of forest Resources. 1956. The Ronald Press Company. New York.

Yearbook of forest products 1962-1973. 1973. FAO.

Yearbook of forest products 1973-1984. 1984. FAO.

Zackrisson, O. 1977. Influence of forest fires on the North Swedish boreal forest. Oikos. 29: 22-32. Copenhagen.

Table 1. Forest resources of the Boreal regions and their share of the world totals.

		Alaska	Canada	Norway	Sweden	Finland	Nordic countries	USSR	Total	Per cent of world
Population	mill.	0.40	23.94	4.09	8.31	4.78	17.18	265.54	307.06	7
Land	1000 ha	146 698	916 700	30 754	41 148	30 547	102 449	2 227 500	3 393 347	26
Forest and other wooded land	"	48 218	436 400	8 701	27 842	23 225	59 768	929 600	1 473 986	36
Closed forest	"	..	264 100	7 635	24 400	19 885	51 920	791 600	1 107 620	2) 38
Exploitable closed forest	"	4 512	214 780	6 600	22 230	19 445	48 275	534 500	802 067	2) 41
- coniferous	"	..	137 910	5 280	21 103	17 884	44 267	405 900	588 077	2) 59
Growing stock	mill.m^3,o.b.	1 294	22 958	575	2 264	1 568	4 407	66 996	95 655	45
- coniferous	"	1 222	18 310	459	1 934	1 290	3 683	54 669	77 884	53
Net annual increment	1000 m^3,o.b.	3 583	356 000	17 310	78 500	61 930	157 740	750 300	1 267 623	31
- coniferous	"	1 863	267 000	13 710	65 155	48 119	126 984	601 500	997 347	45
1) Removals, per annum	1000 m^3,u.b.	3 132	152 048	9 103	50 404	42 460	101 967	357 220	614 367	21
- coniferous	"	2 999	139 459	8 339	43 251	34 464	86 054	297 680	526 192	45
- industrial timber	"	2 900	147 182	8 461	46 278	38 376	93 115	277 420	520 617	37

1) Annual averages of 1978-82

2) Approximately

Table 2. Production of forest industries in Canada, Nordic countries and the Soviet Union in equivalent tons per annum, 1978-82 averages.

	Canada	Norway	Sweden	Finland	Nordic	USSR	Total	Per cent of world
Basic industry								
Sawn wood	18 174	1 001	4 742	3 714	9 457	42 948	70 579	38
Wood-based panels	2 254	267	846	745	1 858	4 926	9 039	19
Mechanical pulp	7 386	886	1 870	2 276	5 032	1 773	14 191	53
Chemical and other pulp	11 614	628	6 645	4 612	11 885	7 274	30 773	32
Total	39 428	2 782	14 103	11 347	28 232	56 921	124 581	35
Paper and paper board								
Newsprint	8 641	600	1 441	1 482	3 523	1 384	13 548	53
Writing and printing	1 453	301	978	2 015	3 294	1 166	5 913	15
Other	3 187	437	3 624	2 268	6 329	6 376	15 892	16
Total	13 281	1 338	6 043	5 765	13 146	8 926	35 353	21

Table 3. Percentage share of the Boreal countries from the world totals.

	Canada	Norway	Sweden	Finland	Nordic	USSR	Total
Production of timber	5.2	0.3	1.7	1.5	3.5	12.1	20.8
Production of sawn wood	9.7	0.5	2.5	2.0	5.0	22.9	37.6
-"- wood based panels	4.8	0.5	1.8	1.6	3.9	10.4	19.1
-"- mechanical pulp	27.5	3.3	6.9	8.5	18.7	6.6	52.8
-"- chemical and other pulp	12.1	0.6	6.9	4.8	12.3	7.6	32.0
Production of total basic industry	11.0	0.8	3.9	3.2	7.9	15.9	34.8
Production of newspring	33.7	2.3	5.6	5.8	13.7	5.4	52.8
-"- writing and printing paper	3.6	0.7	2.4	5.0	8.1	2.9	14.6
-"- other paper products	3.1	0.4	3.6	2.3	6.3	6.3	15.7
Production of total paper and paper board	7.9	0.8	3.6	3.5	7.9	5.3	21.1
Value of exports							
roundwood	2.0	0.4	0.7	1.5	2.6	10.6	15.2
sawn wood	26.3	0.5	10.5	8.4	19.4	9.1	54.8
wood based panels	5.6	0.4	3.3	7.7	11.4	3.9	20.9
wood pulp	34.6	2.5	15.8	8.9	27.2	3.8	65.6
paper and paper board	20.8	2.8	13.3	13.6	29.7	2.0	52.5
total	20.0	1.7	10.3	9.3	21.3	5.3	46.6
Value of imports							
roundwood	0.9	0.6	1.9	1.2	3.7	0.3	4.9
sawn wood	1.8	0.9	0.5	0.1	3.3	0.6	3.9
wood based panels	1.9	1.4	1.9	0.2	3.5	0.8	6.2
wood pulp	0.8	1.1	0.3	0.2	1.6	1.4	3.8
paper and paper board	1.2	0.6	0.9	0.3	1.8	2.8	5.8
total	1.3	0.8	1.0	0.4	2.2	1.5	5.0
Population	0.5	0.1	0.2	0.1	0.4	6.0	6.9

Table 4. Forest production per hectare of expl. cl. forest and per capita in Boreal countries.

		C	N	S	F	NC	USSR	W	C	N	S	F	NC	USSR	W
		per ha of expl. cl. forest							per capita						
Expl. closed forest	ha								9.0	1.6	2.7	4.1	2.8	2.0	0.44
Removals	m^3,u.b.	0.71	1.38	2.27	2.18	1.96	0.67	1.50	6.4	2.2	6.1	8.9	5.9	1.4	0.66
Sawnwood	kg	85	152	213	191	182	80	96	759	245	571	777	550	162	43
Wood-based panels	"	10	40	38	38	36	9	24	94	65	102	156	108	19	11
Mechanical pulp	"	34	134	84	117	97	3	14	309	217	225	476	293	7	6
Chemical and other pulp	"	54	95	299	237	229	14	49	485	154	800	965	692	27	22
Total basic industry	"	184	422	634	583	544	106	184	1647	680	1697	2374	1643	214	81
Newsprint	"	40	91	65	76	68	3	13	361	147	173	310	205	5	6
Writing and printing	"	7	46	44	104	63	2	21	61	74	118	422	192	4	9
Other	"	15	66	163	117	122	12	52	133	107	436	474	368	24	23
Total paper and paper board	kg	62	203	272	296	253	17	86	555	327	727	1206	765	34	38

Table 5. Value of forest products exports and imports, annual averages of 1978-82.

	Exports			Imports		
	mill. $ U.S.	per cent	$ U.S. per cap.	mill. $ U.S.	per cent	$ U.S. per cap.
World	48 144	100.0	11	54 040	100.0	12
Canada	9 650	20.0	403	701	1.3	29
Norway	802	1.7	196	438	0.8	107
Sweden	4 949	10.3	596	527	1.0	63
Finland	4 502	9.3	942	221	0.4	46
Nordic countries	10 253	21.3	597	1 186	2.2	69
USSR	2 548	5.3	10	789	1.5	3
Total Boreal	22 451	46.6	73	2 676	5.0	9

FIG. 1. ANNUAL REMOVALS, M^3, U.B. PER HA OF EXPLOITABLE CLOSED FOREST.

AVERAGES OF 1978-82; ANNUAL OF 1977 IN REGIONS OF THE USSR





FIG. 2A. PRODUCTION OF FORESTRY AND FOREST INDUSTRIES 1962-84.



W = WORLD NC = NORDIC COUNTRIES USSR = THE SOVIET UNION C = CANADA

PRODUCTION IN 1980 = 100; ROUNDWOOD, SAWNWOOD AND WOOD-BASED PANELS IN MILL. OF M^3; PULP, PAPER AND PAPER BOARD IN MILL. OF TONS

FIG. 2B. PRODUCTION OF FORESTRY AND FOREST INDUSTRIES 1962-84.




FIG. 2c. PRODUCTION OF FORESTRY AND FOREST INDUSTRIES 1962-84.





FIG. 3. SUCCESSIONS OF PLANT COMMUNITIES.



PHASES IN THE PROCESS OF SUCCESSION:

1. NUDATION, BARE SITE AS A RESULT
2. MIGRATION OF PIONEER SPECIES TO THE SITE
3. ADJUSTMENT OF SPECIES TO THE ENVIRONMENT
4. COMPETITION AND PATRONIZING BETWEEN SPECIES AND INDIVIDUALS
5. REACTION OF PLANTS AND ANIMALS TO THE SITE
6. STABILIZED CLIMAX IN EQUILIBRIUM WITH THE ENVIRONMENT

FIG. 4. TREE-STAND SUCCESSIONS IN BOREAL FINLAND





FIG. 5. SCHEME OF ANALYSIS OF THE NATURE, ROLE AND DEVELOPMENT OF BOREAL CONIFEROUS FORESTS.



EFFECTS OF SITE PREPARATION ON THE DEVELOPMENT OF PLANTED SEEDLINGS IN NORTHERN SWEDEN

Göran Örlander

ABSTRACT: The choice of site preparation method is important for the performance of planted seedlings. In an analysis of a scarification experiment in Lycksele, mounding and tilt-plowing was found to be favourable for survival and growth of the seedling. It was also found that difficult spots (mostly moist) were more effectively regenerated using mounding or tilt-plowing due to the positive effects on soil temperature, aeration, drainage and nutrient supply. Some of the negative effects of mounding discussed in this paper are as follows: The risk of low soil moisture during dry periods and low soil temperatures in the winter as well as the increased risk of frost heaving and spring frost.

INTRODUCTION

Site preparation as a means of improving the performance of planted seedlings has been known by foresters for hundreds of years. As an example, Gayer describes mounding methods in a German textbook of 1880.

The biological reasons for site preparation are many and those considered to be most important are discussed here. Special emphasis will be put on mounding.

Systematic research concerning mounding was started in the early seventies by professor Söderström in Sweden (e.g. Söderström et al., 1978). Field experiments were established in both southern and northern Sweden. Two of the experiments in northern Sweden were inventoried in 1985 and the results from these experiments will be presented in this paper.

THE IDEAL MICROSITE FOR THE PLANTED SEEDLING

It is well known that seedlings suffer from a transplanting shock after planting, which often results in mortality and poor growth of the seedlings. Such seedlings often suffer from water stress after planting (e.g. Örlander 1984, 1986). As the water-absorbing capacity of newly planted seedling is often poor, efforts must be made to enhance the capacity. One way of doing it is to choose the proper scarification method.

Soil temperature

Low soil temperatures negatively affect the water-absorbing capacity of the seedlings (Fig. 1) mainly due to the facts that the viscosity of water increases and the permeability of root membranes decreases at low soil temperatures. A rise in soil temperature up to an optimum of 20-30° C increases root growth and accordingly speeds up the recovery from water stress.




Figure 1. Effects of soil temperature on the transpiration of 1-year-old Scots pine and Norway spruce seedlings.

GÖRAN ÖRLANDER is a doctor of Forestry at the Swedish University of Agricultural Sciences, Dept of Silviculture, S-901 83 UMEÅ.

The soil temperature is usually low below the unbroken humus layer (Fig. 2). The good insulation capacity of the humus layer decreases both absorption and emittance of heat from the soil and the soil temperature will be low even during the summer with low amplitude in daily maximum and minimum temperature (Fig. 2). Patch scarification raises the soil temperature during amplitude between day and night increases compared to that below the unbroken humus layer. The highest soil temperatures and temperature amplitudes are found after mounding, especially if the mound is placed on an inverted humus layer (Fig. 2). The temperature sum (daily mean temperature -5 degrees) is higher in mounds than in scarified patches or below the unbroken humus layer (Fig. 3) in spring and summer. In the autumn the situation is the opposite and the mounds freeze relatively early. We have measured rather low minimum temperatures in mounds, especially those placed in inverted humus (cf. Fig. 2). Although negative effects of low soil temperatures are reported from nurseries (Lindström 1987), no harmful effects of low soil temperatures in mounds have been reported, so far.

In the spring the mounds thaw earlier than the soil in scarified patches or below the humus layer. Occasionally, depending on the weather conditions the mounds will be repeatedly thaw and frozen, which increases the risk of frost heaving.




Figure 2. Effects of some methods of soil treatment on daily maximum and minimum temperatures 10 cm below soil surface. Field Research Station, Vindeln (64°15'N, 19°45'E, alt. 225 m) 1982.




Figure 3. Temperature sum (>5° C), 10 cm below soil surface in soil treated in different ways. Vindeln 1982.

Soil moisture and aeration

Soil moisture is of course an important factor affecting transpiration. Normally, at a clear-felled area there is an abundance of soil water since the transpiring stand has been removed.

Planted seedlings seem to be more sensitive to low soil water potentials than established ones (Örlander 1986). However, detrimental soil water potentials are seldom found if the soil is patch scarified (e.g. Söderström 1976). In mounds, especially in mounds placed on the humus layer, low soil water potentials have been found during dry periods (Örlander 1984, 1986; Mälkönen 1987). Below the humus layer the soil water potential seems to be constantly high (Örlander 1984).

Poor soil aeration, which is a common occurrence on clearfelled areas, is a big problem for the water uptake. Local drainage of the planting spots is provided by choosing high elevated planting spots.

Aeration is also improved by loosening up the soil, which increases root growth both as a result of better oxygen supply and less mechanical resistance for the root growth.

Nutrients

Adding of nutrients at the time of planting may drastically decrease the root growth and the water uptake of the seedlings (cf. Örlander 1987).

Results reported from fertilization experiments do not speak in favour of using this method. If, however, nutrients could be added to the planted seedlings in low concentration continuously it is possible that fertilization might be more positive. In some previous field experiments (Örlander 1987), where nutrients were added to planted seedlings with drip irrigation, the period of stagnation in growth after planting was avoided even for spruce.

The mineralization of nutrients can be controlled by the choice of scarification method. The fastest mineralization is achieved if mineral soil and humus are mixed whereas the mineralization in an inverted humus layer is somewhat lower (e.g. Mälkönen 1987). On an optimal planting spot the mineralization of nutrients should be so fast as to cover the needs of the seedling. However, too fast mineralization (total mixing of humus/mineral soil or heavy plowing) could endanger the long-term productivity of the stand because mineralized nutrients which are not utilized by the plants may leach out (cf. Mälkönen 1987; Bäcke et al., 1986).

Frost and frost heaving

The risk of frost is supposed to decrease on scarified areas. However, after patch scarification the rise in temperature is relatively small compared to undisturbed soil. Lundmark (1985) reports the air temperature increase at 5 cm height to be 0.5° C in a scarified patch and 2° C in a mound (20 l) compared to undisturbed soil. Plowing increases the minimum temperatures even more than do the mounds.

Frost heaving might be more serious in mounds than in patches and unscarified spots. The temperature in a mound is relatively instable and freezing/thawing may occur several times during a short period in spring or autumn. The soil is more loose in the mound than in the scarified patch, which might also increase the risk of frost heaving. The risk of frost heaving seems to be less in mounds placed on the humus layer than in those placed on mineral soil, probably due to the lower soil water potential in the mound on humus.

SCARIFICATION EXPERIMENT IN LYCKSELE — AN EXAMPLE

Background

In 1973 and 1974 experiments were established in northern and southern Sweden in order to test planting in mineral mounds placed either on mineral soil or on humus. The first results of the experiments presented by Söderström et al., 1978. The plots were remeasured in 1979 and 1985. In 1985 the trees on the plots in southern Sweden were so high (about 5 m) that severe competition had occurred among the seedlings. Since the experimental design was 5-tree plots, no further measurement was made.

In the following, results from two of the experiments in northern Sweden, Lycksele 1 and 3, will be briefly described. These experiments will be referred to as Expts 1 and 3.

Expt. 1 includes the treatments: No scarification, patch scarification, mound on mineral soil and mound on humus (the size of mound about 15 l). In Expt. 3 disc trenching and plowing (terrace- and tiltplowing) were also added as treatments. Four of the treatments, disc trenching, mound on humus, terrace- and tilt-plowing were measured and will be presented here.

In both experiments the experimental design was 5-tree plots with 40 replications.

Survival and growth of the seedlings

Generally, mounding was favourable in both experiments (Table 1). In Expt. 1 the mean survival for no scarification of all species and types of seedlings was 65 %, 67 % for patch scarification and 85 % for the mounds. In Expt. 3 the survival for disc trenching was 78 %, for mounds 89 %, for terrace-plowing 81 % and for tilt-plowing 88 %.

Table 1. Effects of some methods of soil treatment on survival, mean height and stem volume of Scots pine and Norway spruce seedlings. Experiments 1 and 3. Values followed by the same letter do not differ significantly ($p < 0.05$).

	Soil treatment	Survival %	Mean height, cm	Mean stem vol. dm^3
Expt. 1				
Scots	Not scarified	55.7 a	225.8 a	3.05
pine	Patch	61.6 ab	234.8 a	2.89
2/0	Mound on			
	mineral soil	67.2 ab	284.1 b	5.69
	Mound on humus	73.5 b	278.6 b	5.05
Scots pine	Not scarified	67.9 a	224.3 a	2.45
paperpot	Patch	61.7 a	214.3 a	2.88
	Mound on			
	mineral soil	85.2 b	266.8 b	4.28
	Mound on humus	88.3 b	262.5 b	3.29
Norway	Not scarified	72.0 a	149.3 a	0.66
spruce	Patch	77.3 a	144.9 a	0.66
2/1	Mound on			
	mineral soil	97.9 b	159.9 a	0.83
	Mound on humus	96.8 b	161.2 a	0.85
Expt. 3				
Scots pine	Disc trenching	68.5 a	220.7 a	2.72
2/0	Mound on humus	82.7 b	236.8 ab	3.17
	Plow, terrace	71.2 a	225.4 a	2.45
	" , tilt	81.9 b	259.7 b	4.60
Norway	Disc trenching	87.4 a	123.1 a	0.44
spruce	Mound on humus	96.0 b	130.5 a	0.54
2/2	Plow, terrace	89.9 ab	157.8 b	1.13
	" , tilt	93.8 ab	174.4 b	1.28

Mounding was almost equally favourable irrespective of species and type of seedling. The growth of the seedlings was also positively affected by mounding. The effect was roughly the same for mounds placed on mineral soil and those placed on humus. In Expt. 3 the best growth was found on the plowed tilt. This was especially evident for the spruce.




Figure 4. Relation between mean height and survival for seedlings of Scots pine and Norway spruce. Planting year 1973. Inventoried in 1974, 1976, 1979 and 1985. Expt.. 1 • = Not scarified ▲ = Patch scarification * = Mound on mineral soil ▪ = Mound on humus.

The relatively small differences in survival and height development measured the first years after planting increased with time (Fig. 4 & 5). Especially for seedlings planted in mounds or plowed tilts, the mortality was low after the first years.




Figure 5. Relation between mean height and survival for seedlings of Scots pine and Norway spruce. Planting year 1974. Inventoried in 1976, 1979 and 1985. Expt.. 3. Δ = Disc trenching ▪ = Mound on humus o = Plow, terrace ▫ = Plow, tilt.

The experiment was mainly planted on mesic dwarf-shrub type. However, some of the plots were planted on moist spots. In table 2 growth and survival of the seedlings is shown after dividing them into two soil moisture classes. On blocks that were classified as moist both survival and growth was lower for seedlings planted in scarified patches than on mesic ones (Table 2, Expt. 1). This was not found for the other soil treatments. In Expt. 3 the survival on moist sites was considerably lower for seedling planted after disc trenching. For seedlings planted on plowed tilt both survival and growth was somewhat better on the blocks that were moist.

Table 2. Effects of some methods of soil treatment on height and survival (within brackets) of Scots pine and Norway spruce seedlings. The blocks were grouped according to mesic and moist soil conditions. Expt. 1 and 3.

Soil treatment	Scots pine Soil moisture		Norway spruce Soil moisture	
	Mesic	Moist	Mesic	Moist
Expt. 1				
Not scarified	227.7	228.1	142.0	159.3
	(60.4)	(66.4)	(66.2)	(86.5)
Patch	234.2	229.6	150.7	133.2
	(64.4)	(52.8)	(82.1)	(64.7)
Mound on mineral soil	275.0	278.5	159.5	164.0
	(77.9)	(70.6)	(97.0)	(100.0)
Mound on humus	271.5	265.5	160.3	168.3
	(81.6)	(79.2)	(96.2)	(98.1)
Expt. 3				
Disc trenching	218.9	232.0	122.5	125.7
	(67.9)	(71.4)	(90.0)	(75.6)
Mound on humus	233.4	242.1	128.6	141.4
	(85.2)	(71.4)	(94.8)	(100.0)
Plow, terrace	221.0	238.2	160.9	157.2
	(70.1)	(74.3)	(91.3)	(85.4)
Plow, tilt	253.4	275.0	172.4	184.0
	(81.1)	(85.7)	(93.3)	(95.3)

An analysis was made to study whether the size of gaps decreased with increasing survival. The 5-tree plots were therefore divided into 6 classes; 0, 1, 2, 3, 4 or 5 surviving seedlings/plot. Some of the results are shown in table 3.

Table 3. Effects of some methods of soil treatment on the number of surviving seedlings per plot. 5-tree pots. Expt.. 3.

Soil treatment	Survival, %	Number of plots with ≥ 2 surviving seedlings	≥ 3 surviving seedlings
Disc trenching	68.5	80.0	50.0
Mound on humus	82.7	92.5	77.5
Plow, terrace	71.2	85.0	65.0
" , tilt	81.9	92.5	72.5

Soil treatments that were favourable for survival, such as mounding and plowing, also decreased the number of plots with few surviving seedlings (Table 3). Thus an increased survival also resulted in a decreased frequency of large gaps.

CONCLUSIONS

Mounding as a means of soil treatment has a lot of advantages compared to disc trenching and patch scarification. Positive biological effects are increased soil temperature, sufficient local drainage of the planting spot, good aeration and decreased frost risk. If the mounds are placed on humus, or on an inverted humus layer, the nutrient supply will also be beneficial. Positive effects of mounding are reported in the present study and in several other reports (e.g. Söderstrom et al., 1978; Mc Minn 1985; Edlund & Jönsson 1987).

However, as shown in the present report, there are also some disadvantages that are especially pronounced if the mounds are placed on a humus layer. The temperature amplitude between night and day is very high in a mound and low temperatures are to be expected in autumn before the snow falls. Low soil water potentials could be expected during dry periods, especially if the mounds are placed on the humus layer (Örlander 1984, 1986; cf. Mälkönen 1976, 1987; Sutton 1984). Frost heaving and frost damage in the spring (Söderstrom 1978) may also increase in mounds.

In my opinion, the problems with drought risk, insufficient nutrient supply, the risk of frost heaving and insect attacks by *Hylobius abietis* are not yet satisfactorily solved for areas with low humidity (cf. Bäcke et al., 1986). Some field studies are now started to further investigate the problem. The experiments include for example effects of planting depth and choice of planting spot within a mound. Results from the experiments will be presented in the near future.

In the present study the positive effects of soil treatment seem to increase with seedling age/size. On parts of the experimental area where for example patch scarification is not a good method (particularly on moist spots) both survival and growth were improved by mounding or plowing and planting in the tilt.

Mounding is today assumed to be the most suitable method of soil treatment in Sweden (cf. Bäcke et al., 1986). However, no scarification principle is universal. On cold soils with an inactive humus layer mounding might not be sufficient with regard to soil temperature increase, drainage and nutrient mineralization. On such sites plowing or mounding with excavator is recommended. In areas with low summer precipitation no ideal scarification method is available today. The problem is pronounced on dry soils.

LITERATURE CITED

Bäcke, J., Larsson, M., Lundmark, J-E & Örlander, G. 1986. Site adapted scarification. A theoretical analysis of some scarification principles. Skogsarbeten, redogörelse 3.

Edlund, L. & Jönsson, F. 1987. Swedish experience with ten years of mounding site preparation. IUFRO Working Party S1.05-12, Grand Praire and Dawson Creek, Canada, 1986 (in prep).

Lundmark, T. 1985. Temperaturens påverkan på plantor. Skogsfakta, konferens 7, 1985.

Mälkönen, E. 1976. Markberedningens ekologi och inverkan på planteringsresultatet. Skogsarbeten, redogörelse 6, 11-15.

— 1987. A review of soil preparation in Finland. IUFRO Working Party S1.05-12, Grand Praire and Dawson Creek Canada 1986 (in prep).

—, Niska, K. & Levula, T. 1987. Preliminary results on the development of Scots pine and Norway spruce plantations in soil tilling experiments in Finland. IUFRO Working Party S1.05-12, Grand Praire and Dawson Creek, Canada, 1986 (in prep.)

Mc Minn, R.G. 1985. Mechanical site preparation and spruce performance. Presented at Northern Silviculture Committee Seminar, Prince George B.C., 1985.

Sutton, R.F. 1984. Mounding site preparation. Evaluation of jack pine outplantings in a boreal Ontario study. COJFRC, Jack Pine Symposium, Sault Ste. Marie, Canada 1984.

Söderström, V. 1976. Markvärme — en minimifaktor vid plantering. Skogsarbeten, redogörelse 6, 16-22.

—, Bäcke, J., Byfalk, R & Jonsson C. 1978. Comparison between planting in mineral soil heeps and after some other soil treatment methods. Dept. of Silviculture, Umeå, Sweden Res. note 11.

Örlander, G. 1984. Some aspects of water relations in planted seedlings of Pinus sylvestris L. Dept. of Silviculture, Umeå, Dissertation.

— 1986. Effect of planting and scarification on the water relations in planted seedlings of Scots pine. Studia Forestalia Suecica 173.

— 1987. Water and untreat uptake in relation to regeneration success. IUFRO Working Party S1.05-12, Grand Parire and Dawson Creek, Canada 1986.

EFFECT OF SITE PREPARATION ON SEEDLING PERFORMANCE IN A HYLOCOMIUM MYRTILLUS-STAND

Aulis Ritari

ABSTRACT: In a comparative study conducted on a northern *Hylocomium Myrtillus* -site the best group of planted Scots pine, Norway spruce, Siberian larch and natural Norway spruce seedlings with respect to the previous summer's height and length of shoot was found where the soil was prepared using tilt ploughing or rotary tilling. After eight growing seasons the behaviour of larch differed from the other species in that its best seedling group with respect to survival was also located on elevated microreliefs.

Proper drainage and a rise in temperature of the substrate were found to be important for the growth of seedlings. The findings support the idea that the reason for the low survival of planted pine and spruce seedlings on elevated microreliefs lies in their poorer resistance to late winter low temperatures and frost desiccation. This situation is aggravated by the short growing season and a gradual depletion of nutrients from the substrate. The larch, which grows fast and sheds its needles, would seem to succeed better on a tilt than planted pine and spruce seedlings.

INTRODUCTION

The regeneration of spruce forests became topical in Finnish Lapland in the 1930's. It was at this time that studies were begun in the form of soil preparation and cultivation experiments (Heikinheimo 1939).

Previously, Renvall (1919) had called attention to poor seed crops and coil conditions and the seedling damage attributed to reindeer as obstacles to regenerating pine forests at the timberline.

Results of regeneration on areas burned in wild fires indicated that prescribed burning could provide necessary improvement in soil conditions at least on drier sites (Sarvas 1937). In the 1950's and even later it was generally held that spruce stands grow on degenerated raw humus sites whose original fertility could be restored through prescribed burning (Sirén 1955). Production considerations spoke in favor of a change in species from spruce to pine (Ilvessalo 1937). The burned area to be reforested was first prepared through manual scalpin, mechanical 1950's. In the 1960's the main means of soil preparation on moist upland sites became ploughing when extensive failures were observed in earlier pine cultures on burned and scalped sites (Etholén 1972). At present an attempt is being made to employ lighter methods whenever drainage conditions permit.

The ideas — or at least the relative weight thereof — concerning the environmental factors which limit the germination and growth of seedlings have thus varied and research findings have been available only years after the introduction of a new method. For these reasons as well as owing to technical and economical considerations involved in soil preparation and cultivation, equipment development has often been guided by concerns other than the goal of creating the optimum environment for tree seedlings.

The environment of a seedling can be roughly divided into the soil and the ambient air, whereby examination thereof takes place in terms of edaphic and climatic factors. Disadvantageous soil factors such as excessive moisture and the concomitant poor aeration as well as the coldness of the soil have been found by Leikola (1974), Mutka and Lähde (1977)

Aulis Ritari is a researcher in forest soil science at the Rovaniemi Research Station of Finnish Forest Research Institute

and Söderström et al. (1978) to be connected with the poor performance of seedlings in a northern climate. The significance of growth rhythm and cell-level changes for the frost resistance of trees is currently the object of active research (Kallio 1978, Koski and Sievänen 1985). The theory germane to the present study is that described by Tranquillini (1979), which deals with frost damage and desiccation of tree seedlings caused by incomplete development of shoot and frost resistance at the alpine timberline. More recently increasing attention has focused on the nutrient status of prepared soil and explanation for the development of seedlings has been sought in the chemistry of the substrate (Lundmark 1984, Ritari 1985, Mälkönen et al. 1986, Tikkanen 1986).

The present study deals with the results of a soil preparation and cultivation experiment in Central Lapland, its goal being to estimate the dependency of seedling characteristics on environmental factors in light of current theories and hypotheses. The study is part of the reforestation investigations in the area.

MATERIAL AND METHODS

The study area is located approx. 130 km north of the Arctic Circle (67° 52' N, 26° 12' E) and is about 340 m asl. The native forest consists of sparse mixed spruce-birch forest classified as HMT (*Hylocomium myrtillus* -type) (Cajander 1949). Due to its northern location, elevation and successional stage the site evinces such characteristics as a short growing stock (approx. 10 m) and a thick humus layer (approx. 6 cm).

The glacial till soil exhibits diverse layered formations. A dense silty layer under the thin surficial moraine decreases soil permeability and makes the soil itself moist (Pernu and Ritari 1978). The soil type is humic podzol. Geological studies indicate that ultramaphic rocks are common in the area (Lestinen 1980).

The experimental area, strip-felled in the winter of 1971 - 72, was divided into 60 x 180 m blocks (4 replications) for which the mechanical soil preparation was chosen at random. The treatments in the present material are: 1) scalping, 2) shoulder ploughing, 3) tilt ploughing, 4) rotary tilling, 5) untreated, clear-cut and 6) untreated, forest — these last two constituting the control material. Each experimental block had 7 systematically placed cultivation points (8 seedlings/species/point) which formed a circular plot with a radius of approximately 5 m (Fig. 1). The plots were cultivated in the summer of 1976 with bare-rooted 1+1 Scots pine (*Pinus sylvestris* L., local) and Siberian larch (*Larix sibirica* Ledeb., Raivola), and 1+2 Norway spruce (*Picea abies* (L.) Karst., local) seedlings. The reference to species also means the provenance and seedling type used and the physiological condition of seedlings at the time of planting.

The seedling inventory data is from the summer of 1983. At the same time control material consisting of natural spruce seedlings (the 8 highest per plot) was gathered. The characteristics under study were: height and shoot length of living seedlings and survival (for natural seedlings only height and shoot length).




Figure 1. The location of cultivation points within the experimental blocks.

The physical soil properties are those obtained at the beginning of the period of study (soil temperature in 1983) and the chemical properties those from 1984. The observations and samples represent the uppermost 10 cm of the cultivation point. In addition to exchangeable cations and easily extractable phosphorus the reserve fractions of the same elements were studied. The details of the methods can be found in Ritari (1985).

The relationships between soil and seedling characteristics were examined by extracting the

seedling material (168 plots in all) two samples, one representing the most and the other the least successful group of seedlings in the whole population. More precisely, each group represents observations located at least one standard deviation from the mean (Fig. 2).




Figure 2. The studied groups (shaded) with respect to the population mean in case of a normal distribution.

This procedure yielded the largest possible contrast between the seedling populations and made it possible to keep the material undivided in the analysis.

RESULTS

Table 1 presents the mean values for the environmental variables of the largest and smallest group of seedling properties.

As far as height and shoot length are concerned the relationship of the different species with regard to the environmental properties measured was very similar. Pine and spruce behaved in the opposite fashion to larch with regard to survival, a finding also established as a negative correlation between survival and other seedling characteristics for the two first mentioned.

Distinct differences among the values of the environmental variables appeared in the chemical data gathered during the end of the measurement period. The findings indicate that the nutrient content of the environment of seedlings showing good growth was lower than that in the environment of seedlings exhibiting poor growth.

There are at least three possible explanations for such a development which seems odd at first sight: first, the bulk densities differ between samples from different treatments — the figures in the table are expressed per a weight unit (cf. also L.I. ~ humus content); second, the sample layer does not represent the root zone of the seedlings owing to growth of roots; third, the properties examined are simply not minimal factors determining growth. The applicability of these explanations will be evaluated in later research. On the other hand, the iron and magnesium reserves as well as the content of easily soluble aluminium were greater in the group which grew well decreasing the probability of toxic effects. The opposite situation obtained for survival of pine and spruce, i.e. high nutrient content in the environment of a seedling group exhibiting good growth, could be indicative of the role of a fertility regime in the process of frost hardening of seedlings.

Soil moisture was lower and air space greater for seedling groups exhibiting good growth. Survival of pine and spruce showed deviation, however, from this general rule. A similar situation prevailed for the monthly mean temperature of the soil: in seedling groups exhibiting good growth it was clearly higher than in those showing poor growth. Pine and spruce again behaved in the opposite fashion with regard to survival. In case of pine and spruce the vigorous growth made possible by well-aerated and warm soil can prove detrimental in that it may retard frost hardening, which, in turn, means a low survival rate.

The best seedling group with respect to height and shoot length for different species was most often located where tilt ploughing had been done and the worst in untreated forest (Fig. 3). The environmental variables presented thus represent in the main these two treatment types. For spruce and pine, survival was best in untreated forest. Larch, on the other hand, would seem to benefit from a strong soil treatment in this regard.

DISCUSSION

The material offered an opportunity to test the applicability of some hypotheses and theories related to seedling performance under conditions prevailing in a northern HMT forest. As it deals with various forms of mechanical soil

preparation and both cultivated and natural seedlings, the study material is quite extensive; nevertheless the multiplicity of growth factors and the nature of living material impose their own limitations on the interpretations (cf. Mueller-Dombois and Ellenberg 1974). It is not always even possible to measure the growth factors directly, whereby the collection of ecological observations must be based on known or assumed causal mechanisms (Kuusipalo 1985). The examination of the seedling groups exhibiting the best and poorest performance aimed at bringing out a contrast which is often obscured in comparisons of population means. Use of soil preparation broadened the range of the environmental variables, which was thought to be reflected when the dependence is strong, in the values of criterion variables.

Table 1. The mean values and the statistical significance of the differences (t-test) of the environmental variables for the groups of seedling properties. The explanation for the variables is in Appendix 1.

VARIABLE	GROUP	HEIGHT Pine	SHOOT LENGTH Pine	SURVIVAL Pine	HEIGHT Spruce	SHOOT LENGTH Spruce	SURVIVAL Spruce	HEIGHT Larch	SHOOT LENGTH Larch	SURVIVAL Larch	HEIGHT Spruce,nat.	SHOOT LENGTH Spruce,nat.
Ks	means	5.6AA	4.9A	3.9	5.6	4.9	4.5	4.4	4.9	4.3	4.0	4.5
	means	3.8	3.6	4.7	4.5	4.7	5.2	3.8	4.5	4.6	4.8	4.5
Cas	means	13.5AAA	9.2	5.2AAA	14.8AAA	13.1AAA	6.7	10.9AAA	11.7AA	15.6AA	19.2	17.6AA
	means	4.2	7.1	12.6	4.3	4.5	12.7	4.9	4.3	6.6	7.3	4.3
Mgs	means	1.3AAA	2.2A	3.5AAA	0.9AAA	1.2AAA	3.5AAA	1.7AAA	1.2AAA	1.5AAA	0.9AAA	1.1AAA
	means	3.2	3.0	1.4	3.9	3.9	1.7	3.7	4.2	3.3	3.5	4.1
Fes	means	0.8AAA	1.4A	2.2AAA	0.6AAA	0.8AAA	2.1AAA	1.0AAA	0.9AAA	1.0AAA	0.7AAA	0.7AAA
	means	2.0	2.0	1.0	2.2	2.1	1.1	2.2	2.3	2.0	1.9	2.3
Als	means	2.3AAA	1.9AA	1.4A	2.3AAA	1.8	1.5A	2.2AA	2.5AAA	2.1A	1.5	1.8
	means	1.2	1.4	2.0	1.4	1.4	2.4	1.4	1.4	1.6	1.8	1.5
Ps	means	2.9AAA	2.3A	1.5AAA	3.0AAA	2.6AAA	1.7AAA	2.4AA	2.6AAA	2.5AA	2.3	2.3AA
	means	1.5	1.7	2.5	1.5	1.5	2.9	1.6	1.5	1.7	1.8	1.5
Pa	means	66.6AAA	42.4A	7.8AAA	87.0AAA	75.1AAA	11.3AA	47.5AAA	50.3AAA	54.9AA	54.5	50.8AAA
	means	3.3	15.7	64.4	4.3	5.2	59.4	4.3	1.9	15.1	18.8	2.9
Ka	means	45.9AAA	30.2AA	4.8AAA	51.7AAA	41.9AAA	5.5AAA	31.9AAA	40.9AAA	32.3AAA	33.2A	37.1AAA
	means	2.7	8.1	37.5	3.2	4.2	40.9	3.4	1.7	11.0	12.7	2.9
Caa	means	78.6AAA	43.0	11.1AAA	89.3AAA	73.9AAA	11.4AAA	60.7AAA	71.2AAA	76.9AAA	73.6A	78.0AAA
	means	5.8	27.2	76.4	6.8	7.6	68.9	10.2	5.1	22.3	25.4	6.2
Mga	means	82.1AAA	48.7	7.1AAA	95.4AAA	90.7AAA	4.3AAA	92.5AAA	65.1AAA	70.2AAA	78.4AA	87.3AAA
	means	2.0	16.6	56.4	7.7	10.4	64.8	2.2	0.9	16.9	5.3	1.7
Fea	means	1.5	2.4	3.0A	0.9A	1.4	3.4A	2.1	1.7	1.6A	1.9	1.2A
	means	2.4	2.8	1.7	2.3	2.5	1.7	2.5	2.5	2.7	2.9	3.1
Ala	means	3.3AAA	7.3	11.2AAA	2.6AAA	3.2AAA	10.8AA	3.8AAA	3.7AAA	3.8AAA	3.2AA	3.5AAA
	means	8.7	9.6	4.4	10.3	9.8	5.9	10.7	10.9	10.0	10.2	9.9
TOT-N	means	8.1AAA	5.1A	1.2AAA	8.7AAA	7.9AAA	1.8AAA	6.7AAA	7.5AAA	6.6AAA	6.7A	7.2AAA
	means	1.3	2.3	6.9	1.0	1.1	7.0	1.1	0.7	2.3	2.5	0.9
E. COND.	means	3.3AAA	2.7AA	1.3AAA	4.0AAA	3.4AAA	1.4AAA	3.1AAA	2.6AAA	2.4A	2.2	2.5AAA
	means	1.3	1.3	2.9	1.2	1.2	2.7	1.2	1.2	1.7	2.1	1.3
cHH2O	means	0.9A	0.7	0.6	1.0A	0.8	0.7	1.0AA	0.9AA	1.0A	1.0	1.0A
	means	0.6	0.5	0.8	0.6	0.6	1.0	0.5	0.4	0.6	0.6	0.5
cHKCL	means	0.9	0.8	0.6A	1.0	0.8	0.8	1.0A	0.8	1.2AA	0.9	0.8
	means	0.7	0.7	0.9	0.7	0.8	0.9	0.6	0.5	0.6	0.7	0.6
L.I.	means	3.4AAA	2.2AA	0.5AAA	3.7AAA	3.3AAA	0.7AAA	2.8AAA	3.3AAA	2.5AAA	2.7	3.0AAA
	means	0.5	0.8	2.9	0.4	0.5	3.1	0.5	0.3	1.0	1.1	0.4
MOISTURE	means	38.7AAA	35.6AA	25.4AAA	36.8AAA	37.0AAA	29.7	38.3AAA	42.2AAA	39.5AAA	38.3AA	38.8AAA
	means	26.9	27.8	37.1	24.5	24.6	32.1	25.7	23.0	28.4	27.1	27.6
AIR	means	12.3AA	14.0AA	28.9AAA	16.5AA	16.6A	23.7	14.6AA	7.6AAA	11.0AAA	15.0	13.4A
	means	24.4	25.7	11.8	28.3	27.8	20.7	27.6	29.1	24.3	22.9	21.7
JUNE, TEMP	means	8.0AAA	8.2AAA	10.1AA	8.2AAA	7.8AAA	9.0	8.3AAA	8.0AAA	8.3A	8.2	8.2
	means	10.2	10.7	9.1	10.8	10.4	8.8	10.8	11.0	9.7	9.3	9.6
JULY, '	means	10.8AAA	11.3AAA	14.0AAA	11.1AAA	10.7AAA	12.5	11.1AAA	11.0AAA	11.1AA	11.1	11.1A
	means	14.2	14.7	11.0	15.1	14.4	11.9	15.0	15.3	13.4	12.8	13.3
AUGUST, '	means	8.8AA	9.3AA	11.4AAA	9.7A	8.4AA	10.1	8.4AAA	8.1AAA	9.3A	8.3	8.8
	means	11.3	11.6	8.8	11.8	11.3	10.0	12.0	12.1	11.1	10.7	10.8
SEPTEMBER	means	6.6	6.5AA	7.1	6.9	6.3	6.5	6.6A	6.4A	6.7	6.5	6.6
	means	7.1	7.5	6.5	7.3	7.1	7.0	7.4	7.4	7.0	6.8	6.7
Seedling	means	32.0AAA	2.3AAA	26.0AAA	19.8AAA	1.1AAA	31.7AAA	18.0AAA	1.2AAA	15.2AAA	127.9AAA	18.7AAA
property	means	81.9	12.4	100.0	69.5	10.3	100.0	107.3	24.0	91.1	335.6	91.4

A knowledge of the environmental factors affecting seedling growth is a goal which will, when realized, provide a basis for understanding their interdependence and for regulating them appropriately. To date, the analysis of various means of soil preparation has generally confined itself to a mere statement of their effects without a closer understanding or study of growth factors. In addition, not enough attention has been paid to the choice of the criterion variables. The development of soil preparation methods has, moreover, often been dependent upon certain predilections or upon technical considerations. On the other hand, studying the effects of soil preparation on the level of growth factors is difficult because several factors are changed in the process simultaneously; interpretation of the results becomes more demanding than in the case of fertilization experiments, for example, in which the effect of an individual nutrient element is examined.

Clear evidence for the positive effect of elevated microreliefs on the height and length of the seedlings was noted for all species studied. In operating in the harsh growth conditions which prevail near the timberline it is important to be familiar with the potential and limitations of the soil. If the level of growth is mainly dependent on climatic conditions during the winter, perennial trees may not benefit much from soil preparation the positive effect of which is restricted to the growing season.

The lower survival on elevated microreliefs of pine in particular but also of planted spruce

seedlings as compared with other reliefs seems to be consonant with the description and explanation of winter damages by Tranquillini (1979). Observations in the area of needle losses, mechanical damage and of Scleroderris -canker on pine seedlings support the theory (Ritari, A., unpublished data; cf. Eiche 1966). It is also known that the microclimate of the elevated microreliefs exhibits extreme fluctuation causing serious stress to root systems sensitive to high and low temperatures (Vaartaja 1954, Sutinen 1986), Late winter is a critical time if the winter dormancy ends too early (Havas 1978). Although various types of damage were in evidence on all species, larch, which adopts more xeromorphic form for winter, seems to survive better on elevated microreliefs than pine and spruce.




Figure 3. Distribution of observations by different treatments for seedling groups studied.

It proved problematical to determine the significance of the soil fertility regime and of the humus in as much as the extracted high content of nutrients was not found to have any direct effect on the height and growth of the seedlings. On the other hand, the survival of pine and spruce was highest on experimental plots of untreated forest comparatively rich in nutrients, i.e. those plots covered with undisturbed humus. As stated earlier, this result might be due to the fact that for the largest seedlings the samples analyzed no longer represented the principal layer, where the nutrients are extracted by the root tips. For the largest larches this is most evident. However, on ploughed tilt the bulk density of the inverted humus layer is lower than that of the soil layer above, which would lower the nutrient content when calculated per volume. It is likely that the reduced nutrient contents in the surface of the elevated microreliefs, a result of leaching, contribute to the poor frost resistance of the seedlings (cf. Ritari 1985) although it is known that the amount of nutrients available to plants in undisturbed raw humus is also low (Tamm 1953). According to Pellet and Carter (1981) the improvement of cold hardiness in plants by nutritional factors is not restricted to potassium and phosphorus but a nutrient regime which promotes optimum growth also means good frost resistance.

A better survival of pine and spruce seedlings in untreated forest as compared with ploughed tilt must be seen as an outcome of the protection by larger trees and by the snow-cover (cf. Koskela 1970). A high survival rate at an age of 8 years still provides no guarantee that reforestation will succeed if the seedlings became stunted, as was the case with the seedlings planted in untreated forest. As untreated forest and untreated clear-cut did not differ from one another much in respect of extracted soil nutrients (Ritari 1985), poor seedling growth in the forest must be explained by factors including inadequate light for photosynthesis and root competition.

LITERATURE CITED

Cajander, A. K. 1949. Forest types and their significance. Acta For. Fenn. 56: 1-69.

Eiche, V. 1966. Cold Damage and Plant Mortality in Experimental Provenance Plantations with Scots pine in Northern Sweden. Stud. For. Suecica 36: 1-219.

Havas, P. 1978. Kasvien talvi. Summary: Plants in winter. Acta Lapponica Fenn. 10: 108-116.

Heikinheimo, O. 1939. Kokemuksla paksusammaltyypin metsien käsittelystä: Erfahrungen betreffend die Behandlung der Wälder wom Dickmosstyp. Silva Fenn. 52: 121-139, 292.

Ilvessalo, Y. 1937. Peräpohjolan luonnonnormaalien metsiköiden kasvu ja kehitys. Summary: Growth of natural normal stands in central North-Suomi (Finland). Commun. Inst. For. Fenn. 24(2): 1-168.

Kallio, P. 1978. Kasvien sopeutuminen pohjoiseen. Summary: The adaptation of plants to northern conditions. Acta Lapponica Fenn. 10: 101-107.

Koskela, V. 1970. Havaintoja kuusen, männyn, rauduskoivun ja siperialaisen lehtikuusen halla- ja pakkaskuivumisvaurioista Kivisuon metsälannoituskoekentällä. Summary: On the occurrence of various frost damages on norway pines, Scots pine, Silver birch and Siberian larch in the forest fertilization experimental area at Kivisuo. Folia For. 78: 1-25.

Koski, V. & Sievänen, R. 1985. Timing and growth cessation in relation to the variations in the growing season. In: P. Tigerstedt, P. Puttonen and V. Koski (eds.) Crop Physiology of Forest Trees. Yliopistokirjapaino, Helsinki. 1985: 167-193.

Kuusipalo, J. 1985. An ecological study of upland forest site classification in Southern Finland. Seloste. Ekolo-ginen tutkimus Etelä-Suomen kangasmetsien kasvupaikkaluokituksesta. Acta For. Fenn. 192: 1-77.

Leikola, M. 1974. Muokkauksen vaikutus metsämaan lämpösuhteisiin Pohjois-Suomessa. Summary: Effect of soil preparation on soil temperature conditions of forest regeneration areas in Northern Finland. Commun. Inst. For. Fenn. 84(2): 1-64.

Lestinen, P. 1980. Peurasuvannon karttalehtialueen geokemiallisen kartoituksen tulokset. Summary: The results of the geochemical survey in the Peurasuvanto map-sheet area: Geologinen tutkimuslaitos, Geokemiallisten karttojen selitykset, lehti 3723, 1980. 101 p.

Lundmark, J-E. 1984. Markberedning i allmänhet och inom kyliga klimat lägen i synnerhet. In: Fjällnara skogsbruk. Exkursions-underlag för Skogsvårdsförbrundets exkursion om fjällnära skogsbruk, augusti 1984. 32 p.

Mueller-Dombois, D. & Ellenberg, H. 1974. Aims and Methods of Vegetation Ecology. John Wiley & Sons, New York. 1974. 547 p.

Mutka, K. & Lähde, E. 1977. Effect of soil treatment, liming and phosphate fertilization on initial development of bare-rooted Scots pine transplants. Commun. Inst. For. Fenn. 91(3): 1-43.

Mälkönen, E., Niska, K. & Levula, T. 1986. Preliminary results on the development of Scots pine and Norway spruce plantations in soil tilling experiments in Finland. A paper presented at the 8th Annual Workshop of IUFRO Working Party S1.05.-12, Grand Prairie and Dawson Creek, Canada, August 22-26, 1986; 12 p.

Pellet, H. & Carter. J. 1981. Effect of nutritional factors on cold hardiness of plants. Horticultural Reviews 3: 144-171.

Pernu, T. & Ritari, A. 1978. Vastusluotauksia Sodankylän Poksaselässä pohjaveden esiintymisen selvittämiseksi. Groundwater prospecting in North-Finland by means of resestivity soundings. Univ. of Oulu, Dept. of Geophysics, Contrib. 96: 1-15.

Renwall, A. 1919. Metsänhoidon perusteet varsinaisella mäntymetsänrajavyöhykkeellä. The priciples of silviculture at the true timberline of pine (in Finnish). Suojametsäkysymyksestä 5. Acta For. Fenn. 11: 1-112.

Ritari, A. 1985. Muokkauksen vaikutus paksusammalkuusikon maan ominaisuuksiin. Effect of site preparation on soil properties in a Hylocomium myrtillusstand (in Finnish). Licentiate thesis. Univ. of Helsinki, Dept. of Silviculture: 1985. 104 p.

Sarvas, R. 1937. Kuloalojen luontaisesta metsittymisestä Pohjois-Suomen kuivilla kankailla suoritettu metsäbiologinen tutkielma. Referat: Über die natürliche Bewaldung der Waldbrandflächen, Acta For. Fenn. 46(1): 1-146.

Sirén, G. 1955. The development of spruce forest on raw humus sites in Northern Finland and its ecology. Seloste: Pohjois-Suomen paksusammalkankaiden kuusimetsien kehityksestä ja sen ekologiasta. Acta Forestalia Fennica 62(4): 1-408.

Sutinen, M-L. 1986. Kennotaimien juurten pakkasvaurioista. Frost damages of roots in containerized seedlings (in Finnish). Metsäntutkimuslaitoksen tiedonantoja 249: 67-71.

Söderström, V., Bäcke, J., Byfalk, R. & Jonsson, C. 1978. Jämförelse mellan plantering i jordrabatter och efter andra markberedningsmetoder. Summary: Comparison between planting in mineral soil heaps and after some other soil treatment methods. Institutionen for skogsskötsel, Res. Notes 1: 1-177.

Tamm, C-0. 1953. Growth, yield and nutrition in carpets of a forest moss (Hylocomium splendens). Medd. från statens skogsforskningsinstitut 43(1): 1-140.

Tikkanen, E. 1986. A hypothesis on the cause of abnormal development in Scots pine saplings on ploughed sites in Northern Finland. A paper presented at the 8th Annual Workshop of IUFRO Working Party SI.05-12, Grand Prairie and Dawson Creek Canada, August 22-26, 1986; 22 p.

Tranquillini, W. 1979. Physiological Ecology of the Alpine Timberline. Ecological Studies 31. Springer-Verlag, Berlin. 1979; 137 p.

Vaartaja, 0. 1954. Temperature and evaporation at and near ground level on a certain forest sites. Can. J. For. 32: 760-783.

Appendix 1.

VARIABLE	UNITS
Ks HCl extr.	$(*10^{-2})$, %
Cas "	$(*10^{-2})$, %
Mgs "	$(*10^{-1})$, %
Fes "	%
Als "	%
Ps "	$(*10^{-2})$, %
Pa NH4OAc extr.	$(*10^{-4})$, %
Ka "	$(*10^{-3})$, %
Caa "	$(*10^{-3})$, %
Mga	$(*10^{-3})$, %
Fea "	$(*10^{-2})$, %
Ala "	$(*10^{-2})$, %
TOT-N	$(*10^{-1})$, %
E. COND.	μScm^{-1} (*10)
cHH2O	$(*10^{2})$
cHKCl	$(*10^{2})$
L.I.	(*10), %
MOISTURE soil	%
AIR "	%
JUNE soil temp.	^{o}C
JULY " "	^{o}C
AUGUST " "	^{o}C
SEPTEMBER " "	^{o}C
Seedling height	cm
" shoot length	cm
" survival	%

SITE PREPARATION AND LEACHING OF NUTRIENTS

Eero Kubin

ABSTRACT: Several experimental fields were founded in northern Finland from the 1960's onwards in order to research into the ecological problems attached to artificial forest regeneration. On one of these was also examined the leaching of nutrients. Determinations were done from runoff water in the spring between 1979 and 1986. The results show that clear cutting and soil preparation increase the leaching of nutrients in surface waters. The amount of leaching, however, depends on the element. Of all the elements that were examined (NO_3-N, NH_4-N, P, K, Ca, Mg, Na and Fe) the leaching of nitrate was the greatest during about two years after site preparation. As a whole the increase in leaching lasted about 5 years.

INTRODUCTION

The ecological problems attached to artificial forest regeneration were started to be examined intensively in Finland at the end of the 1960's. The reason for this was above all the failures in forest regeneration in northern Finland. The research was started expressly in Lapland when the Department of Silviculture of the Forest Research Institute started a series of field experiments in order to measure site factors in connection with different methods of site preparation and also partly with different methods of regeneration.

A series of experiments measuring several different ecological site factors was started in 1973. As a part of this, with the leadership of the head of Muhos Forest Research Station, Jukka Valtanen, was founded the experimental field of Kivesvaara to the south of Lapland. The work concerning the nutrient value of the soil and runoff water was started in collaboration with the Botanical Department of Oulu University, where the research group of Dr. Heikki Haapala with experience in hydrochemical research took part in the research. The analyses were at first done in the laboratory of the Botanical Department and from 1979 onwards in Muhos when the laboratories in the research station had been completed.

Eero Kubin is a Researcher Silviculture, specializing in ecological site factors in the Finnish Forest Research Institute at Muhos Research Station.

The experimental area of Kivesvaara is the first place in Finland where the effect of site preparation on the quality of runoff water is examined. In Nurmes-research, started in 1978, there is corresponding research into site preparation, but these treatments were not done there until in 1986 (Nurmes-research 1979). On the other hand preliminary results have already been presented about the effect of clear cutting in Nurmes-research (Ahtiainen and Kenttämies 1935). There are also results from increased leaching of nitrogen after clear cutting in Swedish research (Tamm et al. 1974, Wiklander 1974, 1983) and in Sweden there is also extensive research going on into coniferous forest watersheds (Rosén 1982).

As the main weight of the work on the experimental field of Kivesvaara lies on measuring ecological site factors it was from the very beginning not planned for examining the leaching in individual watersheds. The leaching of nutrients has been measured in the surface water that runs from separate prepared areas. At the same time has also been followed the total effect of the clear cutting and soil treatment of separate areas by examining also the nutrient contents of the water that runs away from the whole experimental area. The results presented now from this study represent the most prolonged series of measurements of this kind in Finland.

MATERIAL AND METHODS

The geographical location of the experimental field is 64°N 27°E (Fig. 1). The topographical height varies between 198 - 215 m above the sea level. The site is of fresh mineral soil forest site (*Vaccinium-Myrtillus* -type) and the soil is fine sandy till. The stand consists mainly of spruce with a little pine and birch. After clear cutting the artificial regeneration was done for Scots pine.

The field was clear-cut in the winter of 1974 and the soil was prepared in the autumn of the same year. Between the experimental plots there were dug ditches 50 that the surface waters from every strip gathered at the lower end into one point. The ditches were dug already before clear cutting. The methods of soil preparation were (1) unprepared or planting on a hand made scalp, (2) machine made scalp, (3) ploughing with a shoulder plough and (4) full tilling with shoulder plough.

The follow-up of leaching was started in the spring of 1974. It was noticed during the first years that runoff water did not gather into all ditches. When the snow melted there was water in all of them but this period was short and the water that melted from snow and stayed partly still did not represent surface runoff. Because of this the basic idea about a runoff that could be obtained from different experimental plots did not succeed, but the runoff had to be measured from certain points. Even from these the water ran out in May, so the leaching of nutrients was measured mainly during the spring runoff. There are from some years determinations from early autumn, too, but in this connection only results from the spring runoff are presented. Only some cation values are presented from the midsummer of 1974, because there were no observations in the spring.

Water samples were taken from running water into plastic bottles and the chemical analyse was started either on the same or immediately following day. Nutrients were determined with the methods commonly in use in hydrochemistry. Spectrophotometrically NO_3-N, NH_4-N and PO_4-P, were measured the latter as total phosphorus after reduction in an autoclave. By using a flameatomabsorbtion spectrophotometre K, Ca, Mg, Fe, Mn, Na and Fe were measured. In addition to that the pH-value and conductivity were also studied.




Figure 1. The experimental field of Kivesvaara and the sample points of the research of the leaching of nutrients.

The formation of runoff water has varied yearly, because of which the number of sample takings also varies yearly from one or two to more than ten. As the conditions in the spring also vary both as for rains and for the way the snow melts this, too, causes a deviation in the results. So the annual mean values, which are presented in the following, also describe for a great part the conditions in different years. Because of the above reasons temporal trends of development do not necessarily come forth about all the elements which were examined.

RESULTS

Total effect of clear cutting and of different site preparations

The clear-cut was done in the winter of 1973 - 74 and the soil of certain strips was prepared a little before snowfall in the autumn of 1974. The total effect of these treatments on the quality of the runoff is examined in sample points 1 and in upper comparison point 17 (Fig. 1). The water in sample point 17 partly flows to the sample point 1. Into sample point 1 come also waters from the sides that are outside the experimental area.

By comparing the water above the experimental area (sample point 17) and the water that runs away from the whole area with each other we find out partly the effects of clear cutting and the soil preparation of different separate areas. The bigger the part of the water that runs through, the smaller the effect of the treatments.

The results show (Fig. 2) that the contents of the elements in point 1 grow compared with both the values before preparation and with the above comparison point. The increase in contents is neither sharp, nor of long duration. Magnesium, iron and natrium have similar trends with those of nitrate, phosphorus and potassium shown in Figure 2. On the other hand, the content of ammonium, nitrogen and manganese varied yearly more randomly. The pH-value of water showed light increase in point 1 during the first years, but otherwise there was no long-term trend in that, either. According to the annual mean values the pH-value varied between 4.25 - 4.91, and correspondingly, in comparison, point 17 between 4.36 - 4.74.

Sample points 7 and 8 represent a corresponding composition to sample points 1 and 17. In point 8, however is shown only the effect of clear cutting because the soil above it is not prepared, nor do any waters from outside the experimental area run into it. All the water that comes into sample point 7 has thus formed in the upper area inside the experimental field.

The general picture of the changes in nutrient contents in sample point 7 is similar to that




Figure 2. Nutrient contents of the runoff water in sample point 1 and in upper comparison point 17. Determinations were done in the springs of 1974 - 1986. Clear cutting was done in the winter of 1973 - 74, site preparation in the autumn of 1974. The locations of the sample points are presented in Fig. 1.




Figure 3. Nitrate contents and the pH values of the runoff water in sample point 7 and in upper comparison point 8. Site preparation was done in 1974. The locations of the sample points are in Fig. 1.

in point 1, but the increase in content values is greater. In particular the nitrate content (Fig 3) increases sharply in the second summer after preparation. The maximum value was 1280 ug/l. The sharp increase was, however followed by a considerably quick decrease. As a whole the increase in the content of the elements due to cutting and soil preparation lasted about five years. The increase in the leaching of other elements was relatively small compared to that of nitrate nitrogen. Eq. potassium values were nearly equal in point 8, above all soil treatments, with the values of point 7.

Compared to sample points 1 and 17, the pH-value of the runoff water is higher, about pH 5. In sample point 7 there was a temporal development towards an increasing and decreasing direction, but the values measured in point 8 showed for many years after clear cutting a decrease, and then turned to an increasing direction. However, there are a few yearly observations and this, as well as the small amount of water in point 8, may have an effect on the results of pH and also on the elements.

The runoff that gathers into point 8 comes from the upper parts of the experimental field from a relatively small area. The amount of runoff is small and it lasts a short time compared to the lowest point 7. The number of observations is considerably smaller than in the lower points because of lack of water. From that point of view the effect of only clear cutting cannot be detected very reliably, although the trend of the contents can be said to show at some extent exactly the effect of clear cutting. In spite of these insufficiencies we can consider the comparison of waters that gather into sample points 7 and 8 to show clearly that the leaching of nutrients increases because of clear cutting and soil preparation, expecially for the part of nitrate nitrogen.

Effect of site preparation

The runoff into sample points 13 and 14 comes only from the ploughed plots (See Fig. 1). There are no measurements from the time before the soil preparation from these points, but the effect of ploughing is clear and the trend is similar with its duration when one takes the former observations into consideration (Fig. 4).

From sample points 11, 18 and 20 comes runoff that runs from the fully tilled experimental plots. In points 11 and 18 the runoff flows into the ditches, but point 20 differs from these so that the surface runoff is apparently borne in a fully tilled area inside the experimental plot, but its runoff is relatively small.

When comparing the trends of the nutrient contents of these three points they were between each other similar with their general features, with the exception of ammonium nitrogen. Its content was in point 20 in 1977, when the measurements were only started there, the biggest of all three. The lowest mean content of ammonium was in point 11. In point 18 the mean value of the spring was almost ten times bigger compared with the value before ploughing.




Figure 4. Nutrient contents of the runoff water from the ploughed plots (Mean values from sample points 13 and 14. Their locations can be seen in Fig. 1.). Site preparation was done in 1974. Observe that there are no measurements in these sample points in 1974.

In Figure 5 there are the combined results of the above mentioned three points for the part of some nutrients. The effect of full tilling is fairly similar with that of ploughing and so the results reinforce each other. The content of potassium is interesting, its descending trend continued for almost 10 years after the peak values following soil preparation.




Figure 5. Nutrient contents of the runoff water from the fully tilled plots (Mean values from sample points 11, 18 and 20. Their locations can be seen in Fig. 1.) Observe that there is only potassium value from the year 1974.

DISCUSSION

Surface runoff is formed either directly from rain or when snow melts into water. The melting of snow has a decisive significance for the formation of surface runoff in the experimental area in the spring. Surface runoff is also born so that rain falling may infiltrate and travel along subsurface pathways and slowly seep from the soil into runoff water.

Evaporation and the transpiration of the plant cover have a significance to the formation of the runoff, as well as the texture and the structure of the soil. In fine soil, where the portion of clay is as a rule great, water does

not filter quickly into ground water, but fills the pores in the soil and soil moisture remains great. On these kind of places are also developed a thick layer of raw humus, which can store great quantities of water and also nutrients. The soil type of the experimental area is a fine sandy till, which lets water through relatively slowly. Soil frost too, which is formed in the clear-cut and in the prepared areas of the experimental field (Kubin and Poikolainen 1932) has an effect on how water filters into the soil.

The chemical composition of runoff water depends greatly on the way in which the runoff water is born. There are several more nutrients in through fall than in free precipitation (Päivänen 1974) and when the snow melts the nutrients that have been accumulated into it fall into soil or directly into surface runoff.

The chemical weathering and the mineral composition of the soil have a decisive significance for the water that comes from inside the ground into surface runoff. In the research area 73 % of the bedrock was composed of granitic rocks, 6 % of quartzites and 21 % of basic rocks and schists (Kubin 1977). The great portion of the basic type of stones indicates relatively high productivity.

Besides the weathering of minerals, the nutrients that are released when organic matter decomposes have a central significance in the runoff. The nutrients that get into soil water drift with the water, dissolved in it, and are bound to soil particles or plants take them up with their roots for constructing new organic matter. Positively reserved cations are usually bound to soil particles and many negatively reserved anions can form chemical combinations. This means that they are not leached easily, although for example clear increase in the content of some elements could be observed in this research.

There is plenty of nitrogen in organic matter and special consideration must be paid on it. When organic matter decomposes the compounds of nitrogen are released and positive ammonium nitrogen is formed. Ammonium nitrogen may get bound to the negative parts of soil particles and thus it has not been considered very liable for leaching (Tamm et al. 1974). The results of this research show perhaps a little surprisingly that during the years after site preparation the contents of ammonium nitrogen in the runoff water also increased.

Released ammonium nitrogen may oxidize through nitrification to nitrite and nitrate. The only way in which nitrate nitrogen is bound in the biological cycle is by the uptake of vegetation. Nitrate nitrogen is also easily soluble and it is leached in a very short time; e.g. the preliminary phases of snow melting cause a decrease in the nitrate content in melt water (Kubin and Lippo 1987).

In the situation which prevails after clear cutting vegetation binds very little nitrogen, because of which its content in surface and in ground waters has been observed to increase (Tamm et al. 1974, Wiklander 1974, 1983). If the site quality is high, the leaching is greater than if the site quality is low. The results of this research, about the effect of clear cutting and site preparation on the leaching of nitrate are similar to those observed in Sweden about clear cutting. We, too, have measured high nitrate concentration in the raw humus under the tilts some years after ploughing, and so a great amount of leaching is possible. In the Nurmes-research, that is going on in Finland, it has also been observed that clear cutting increases the leaching of nutrients (Ahtiainen and Kenttämies 1985).

For the part of site preparation the results presented now are new and no corresponding researches have been accomplished elsewhere. The amount of the leaching of nutrients and also its duration vary as for the element. In general lines we can state that leaching is greatest 2 - 3 years after site preparation, after which the values are nearer the level before preparation. It seems that potassium, a lot of which is also removed with through fall (Päivänen 1974), is leached for a considerably long time compared, e.g. with nitrate nitrogen. At a very early stage of decomposition after clear cutting a lot of potassium is also released from the needles (Kubin 1977). In addition to nitrate it is also worth noting the quite strong

leaching of ammonium nitrogen in the years after soil preparation.

The total significance of leaching for the nutrients of the regeneration area is not presented in this connection. That would require an accurate knowledge of precipitation and also of measurements of the quantity of the runoff. There are annual observations about the quantity of the runoff from the whole area and also of rain water but there are only a few measurements of the nutrients from it. The analysis of these results and of the observations that are not included in this study will be done later.

In conclusion there is reason to state that the undertaken treatments increase the leaching of nutrients but the duration of their peak values is relatively short. The amount of the loss of nutrients depends on the site and on the quantity of the runoff. When one considers the environmental effects and also the loss of nutrients of the site there is reason to pay more attention to what kind of areas are selected for site preparation and what kind of methods are used. It is also necessary to avoid conducting surface water into open waters.

Besides, we must emphasize the importance of ground vegetation. As the nutrient requirement of a stand is small when the trees are still seedlings, the ground vegetation grows luxuriant and binds nutrients to the biological cycle, and thus prevents them from getting leached into both surface and ground waters.

ACKNOWLEDGEMENT

In the preliminary phases the laboratory analyses were undertaken by several members of a group working in the Botanical Department of Oulu University besides myself. Similarly several people from the Research Station of Muhos have participated in the work in its different phases from 1979 onwards. The practical site preparations concerning the founding of the experimental field were performed by the owner of the area, Kajaani Oy, whose positive attitude has greatly contributed the study. I acknowledge to all those who have taken part in the research, and extend my gratitude to them.

LITERATURE CITED

Ahtiainen, M. & Kenttämies, K. 1985. Water quality effects of clear-cutting and forestry drainage. Preliminary results from Nurmes-research. National Board of Waters, Finland. 3 p.

Kubin, E. 1977. The effect of clear cutting upon the nutrient status of a spruce forest in northern Finland (64 28'N). Seloste: Paljaaksihakkuun vaikutus kuusimetsän ravinnetilaan Pohjois-Suomessa (64° 28'N). Acta For. Fenn. 155: 1-40.

— & Poikolainen, J. 1982. Hakkaamattoman metsän sekä eri tavoin muokatun avohakkuualan routa- ja lumisuhteista. Summary: Snow and frost conditions in an uncut forest and open clear-cut areas prepared in various ways. Folia For. 518: 1-24.,

— & Lippo, H. 1987. Determining acid deposition in snow in northern Finland. International symposium an acidification and water pathways in Bolkesjø, Norway 4-8 May 1987. Vol II: 239-248.

Nurmes-research 1979. Nurmes research. On hydrological effects of silvicultural treatments. National Board of Waters, Finland 1979. 11 p.

Päivänen, J. 1974. Nutrient removal from Scots pine canopy on drained peatland by rain. Seloste: Ravinteiden siirtyminen sadeveden mukana latvustosta maahan turvemaan männikössä. Acta For. Fenn. 139: 1-18.

Rosén, K. 1982. Supply, loss and distribution of nutrients in three coniferous forest watersheds in central Sweden. Rapp. Uppsats. Avd. Skogsekol. 41: 1-70.

Tamm, C.O., Holmen, H., Popovic, B. & Wiklander, G. 1974. Leaching of plant nutrients from Soils as a concequence of forestry operations. Ambio III(6): 211-221.

Wiklander, G. 1974. Hyggesupptagningens inverkan på växtnärings innehåll i yt och grundvatten. Summary: Effect of clear felling on the content of nutrients in surface and ground water Sv. SkogsvFörb. Tidskr. 1: 86-90.

— 1983. Kväveutlakning från bördig skogsmark i södra Sverige. Summary: Loss of nitrogen by leaching from fertile forest soils in southern Sweden Skogs- o. Lantbr. - akad. Tidskr. 122: 311-317.

SITE PREPARATION, STOCK SELECTION AND WHITE SPRUCE SEEDLING PERFORMANCE IN WESTERN CANADA

R.G. McMinn, M. Grismer and L.J. Herring

ABSTRACT: Trial results are presented to indicate that appropriate site preparation and stock type selection can be significant factors for regeneration success in the boreal forests of northern Alberta and British Columbia where climatic and site differences are great over relatively short distances. Regeneration prescriptions should be site specific for optimum seedling performance.

INTRODUCTION

While increasing soil temperature is a universally important objective of site preparation for reforestation of northern forests, the forests of northern Alberta and British Columbia grow in a wide range of climates and sites. Consequently, site preparation and stock type prescriptions must be site specific to achieve optimum results. For example, soil moisture on some sites may be excessive and on others deficient; competing vegetation may be dense enough to smother seedlings, reduce light intensity and compete for moisture and nutrients or it may be inconsequential; and the presence of fine-textured soil may impose particular constraints on site preparation.

Ecological Classifications developed in both provinces provide a framework for regeneration prescriptions (Corns and Annis 1986, McLeod and Meidinger 1985, Pojar et al. 1984). This paper gives examples to show the benefits that can accrue from site preparation treatments specific to particular ecological conditions. Appropriate planting stock can also be an important ingredient of success with or without site preparation. Some of the trials reported have been ongoing long enough to indicate that the benefits of favourable regeneration practices extend beyond the establishment period.

R.G.McMINN is a consultant in Victoria, B.C., Canada; M.GRISMER is a technician at the Pacific Forestry Centre, Victoria, B.C., Canada and L.J.HERRING is Regional Research Officer, British Columbia Ministry of Forests and Lands, Prince George, B.C., Canada.

SITE PREPARATION BY SCALPING

Removal of shading vegetation and surface organic matter (humus or L, F, H horizons) insulating the mineral soil from the heating effects of the sun increase soil temperature (Table 1). Such increases are likely to be a significant factor benefitting seedling performance because even with site preparation, the temperature levels indicated as optimum by growth chamber experiments (Dobbs and McMinn 1977) are only infrequently reached.

Table 1. Soil temperature 5 cm below the soil surface during a warm July afternoon and vegetation cover during the second growing season following site preparation.

Treatment	Temperature °C	Vegetation cover %
Untreated	14	59
Scalping	20	22

Exposure of mineral soil and removal of shading vegetation by scalping off surface layers above medium-textured soil can provide a

favorable seedling response for at least 10 years after planting (Table 2).

Table 2. Performance of container grown white spruce 10 years following outplanting in a site with a sandy soil and dense competing vegetation.

Treatment	Survival %	Height cm	Volume[1] cm^3
Untreated	40a[2]	136a	370a
Scalping	89b	222b	1590b

[1]/Stem volume equals height times one third stem area at ground level.

[2]/Values in each column followed by a different letter differ significantly (p = 0.05).

The increased root growth promoted by increased soil temperature more than compensates for the initial unavailability of the nutrients in the surface layers pushed aside by scalping to expose mineral soil. Where scalped patches are small or seedlings are planted toward the edge of bulldozer scarified strips, enhanced root growth resulting from increased soil temperature can relatively quickly enable seedlings to reach the nutrients of adjacent undisturbed soil.

Unlike medium-textured soils, fine-textured soils, which make up a significant proportion of the forest soils of northern Alberta and British Columbia, constitute a poor medium for the growth of planted seedlings following scalping. Inhibition of root extension in compact, fine-textured subsurface soil may result in roots being confined to the planting hole for an extended period. Without access to the nitrogen of surface layers seedlings become chlorotic and they may suffer moisture deficits when soils are dry.

Site preparation of fine-textured soils should allow seedlings immediate access to surface organic matter as well as exposing mineral soil (to increase soil temperature) and control competing vegetation. Favorable results have been obtained using mixing and inverting methods which provide a mineral soil surface above the inverted humus.

SITE PREPARATION BY MIXING

Mixing the surface organic matter with the underlying mineral soil results in a soil surface which is essentially mineral in characteristics as well as making the nutrients of upper layers immediately available to planted seedlings. Soil temperature is enhanced by the new mineral soil surface. When mixing is complete enough to control competing vegetation, planted seedling receive an initial benefit and a continued advantage compared with scalping and no treatment (Table 3).

Table 3. Performance of 2+0 bare root white spruce 13 years following outplanting in a site with fine-textured soil and dense competing vegetation.

Treatment	Survival %	Height cm	Volume[1] cm^3
Untreated	75a[2]	297a	3121a
Skalping	87b	320b	3580b
Mixing	90b	403c	5830c

[1]/Stem volume equals height times one third stem area at ground level.

[2]/Values in each column followed by a different letter differ significantly (p = 0.05).

High speed or repeated mixing controls competing vegetation. Incomplete, low speed mixing, however, may exacerbate the negative effects of competing vegetation because weeds also benefit from the availability of nutrients and from soil warming.

The high speed (300 rpm) of the Rotoclear has provided effective vegetation control in experimental plots without the use of herbicides, presumably by comminuting vegetation sufficiently to suppress resprouting. The Rotoclear, however, was developed for agricultural use and in its present form is rather cumber-

some and expensive for forest operations. A scaled down version is reported to be under development.

The rotors of farm rotovators do not seem to turn fast enough to adequately comminute and control aggressively competitive vegetation unless repeated passes are made an impractical procedure for forest use. High rotor speed, on the other hand, is likely to cause excessive implement wear.

Consequently, even though mixing can be a biologically effective method of retaining the fertility of upper soil horizons immediately available to planted seedlings the constraints on mixing (high speed necessary for adequate vegetation control and excessive implement wear in stony ground) limit its usefulness as a method of forest site preparation.

SITE PREPARATION BY INVERTING

Planting spots consisting of an inverted layer of surface organic matter covered by mineral soil provide planted seedlings with the benefits of enhanced soil temperature (resulting from mineral soil exposure) and immediate access to the nitrogen of the inverted organic matter. Competing vegetation is also controlled if the mineral soil covering is deep enough. Both inverted humus mounds and plowing provide mineral soil covered inverted surface organic matter planting spots which can result in more favorable seedling performance than scalping fine-textured soils (Tables 4 and 5).

Table 4. Performance of 2+0 bare root whit spruce seedlings 5 years following outplanting in a site with relatively fine-textured soil and dense competing vegetation.

Treatment	Survival %	Height cm	Volume[1] cm^3
Untreated	64a[2]	45a	7a
Scalping	89b	45a	11b
Mound+ 2cm cap[3]	85b	71b	27c
Mound+ 6cm cap	92b	70b	30cd
Mound+12cm cap	88b	72b	32d

[1]/Stem volume equals height times one third stem area at ground level.

[2]/Values in each column followed be a different letter differ significantly (p = 0.05)

[3]/Inverted humus mound with 2 cm depth of mineral soil capping.

Table 5. Performance of white spruce seedlings 2 years after outplanting in a fine-textured soil following plowing and no treatment.

Treatment	Stem volume[1] cm^3
Untreated	1.2a[2]
Plowing	2.7b

[1]/Stem volume equals height times one third stem area at ground level.

[2]/Values followed by a different letter differ significantly (p = 0.05).

Inverted humus mounds are advantageous on wet sites because seedlings are in raised planting spots. However, where rainfall is low during the growing season, the mineral soil capping of mounds may dry out subjecting seedlings to moisture stress. Although deep mineral soil cappings may produce better results than shallow cappings (Table 4), deep cappings may accentuate drying out problems. Deep planting has been found to alleviate the problem of cappings drying out. The roots of deep planted seedlings are in contact with the soil beneath the mound which, although cool, remains moist. Evaporation and transpiration losses from the soil beneath mounds is limited when competing vegetation is controlled by adequate depth of mineral soil capping. Deep planted seedlings can utilize the warm upper layers for root growth and nutrient uptake when they are moist and the moist lower layers to sustain adequate seedling moisture when the upper layers are dry.

The possible advantages of long rooted (23 cm) container grown seedlings are being investigated. The use of long rooted seedlings should obviate the need and possible disadvantages of partially burying the foliage of seedlings with standard root lengths in order that roots reach the constant supply of moisture beneath mounds.

On dry sites, plowing, which places the inverted organic matter of the furrow slice directly onto mineral soil exposed by removal of the preceding furrow slice, may provide more favourable moisture relations than inverted humus mounds. Inverted humus mounds have a double layer of organic matter because the inverted surface organic matter is placed on top of undisturbed surface organic matter. The single layer of organic matter above the mineral soil resulting from plowing is likely to be less disruptive of capillary recharge of moisture than the double layer of mounds. Transpiration of tree seedlings may also be less than on mounds because plowing provides a surface which is essentially flush with the general ground level.

The development of equipment for intermittentplowing or in situ inverted patches could be beneficial for the treatment of fine-textured soils in relatively dry climates.

SIZE AND CONDITION OF PLANTING STOCK

While it might seem economical to use the smallest planting stock that will survive, it is possible that improved performance from large stock may more than pay for the difference in initial cost. Trials with various sizes of container-grown stock planted in unprepared ground have shown that the largest stock had the best performance (Table 6). If trends over the first 5 years continue, the large stock would reach stand closure and possibly harvestable size well before the small stock. Shortening rotation age should increase allowable cut and therefore provide immediate return on the higher cost of using large stock.

Table 6. Performance of white spruce seedlings grown in containers of various sizes 5 years after outplanting in an untreated, brushy, backlog site.

Treatment	Survival %	Height cm	Volume[2] cm^3
Small[1]	70a[3]	43a	7a
Medium	82b	50b	10b
Large	89b	59c	16c

[1]/PSB 211 styroblocks with cavity volumes of 26 cm^3 (2 in^3): medium size PSB 313 styroblocks with cavity volumes of 65 cm^3 (4 in^3): large size PSB 415 styroblocks with cavity volumes of 130 cm^3 (8 in^3).

[2]/Stem volume equals height times one third stem area at ground level.

Similar differences have been demonstrated with different stock sizes in prepared planting spots. Large stock planted in biologically favorable spots prepared by mixing grew better than small stock in mixed, scalped and unprepared planting spots (Table 7). Definitive information should be sought to determine under what conditions a return on investment can be obtained with the use of large stock plus biologically superior site preparation. Under appropriate site conditions, large stock may compensate for lack of site preparation (Table 8).

In the Boreal Zone near Dawson Creek, British Columbia, considerable losses have been experienced through winter damage. Affected seedlings turn red and lose all or part of their foliage as the new growing season begins. Severely affected seedlings die. Incidence of winter damage has been highest with 1+0 container-grown stock exposed to fluctuating winter temperatures by lack of snow cover. Naturally regenerated white spruce are unaffected and two seasons after outplanting planted stock withstands this kind of stress. This contrast suggests that differences in climatic adaptation may be involved.

Table 7. Size at time of planting and performance of white spruce seedlings grown in large and small containers 10 years after outplanting in a moist, fertile site with fine-textured soil following mixing, blade scarification and no treatment.

At planting				
Stock type	Height	Mass		
		Top	Root	Total
	cm	g	g	g
Large[1]	15a[3]	1.6a	1.6a	3.2a
Small[2]	13b	1.0b	0.7b	1.7b

At 10 years			
Treatment	Survival %	Height cm	Volume[4] cm^3
Large			
Mixing	99a	279a	1817a
Untreated	96a	234b	1288b
Scalping	98a	211c	803c
Small			
Mixing	99a	235b	1077bc
Untreated	93a	204c	722cd
Scalping	97a	189c	515d

[1]/PSB 415: container stock grown in styroblocks with cavity volumes of 130 cm^3 (8 in^3).
[2]/PSB 211: container stock grown in styroblocks with cavity volumes of 26 cm^3 (2 in^3).
[3]/Values in each column followed by different letter differ significantly (p = 0.05)
[4]/Stem volume equals height times one third stem area at ground level.

Table 8. Size at time of planting and performance of white spruce seedlings grown in large and small containers 10 years after outplanting following blade scarification and no treatment.

At planting			
Stock size	Height cm	Diameter cm	Mass g
Large[1]	18.3a[3]	0.26a	2.0a
Small[2]	17.8b	0.23b	1.6b

At 10 years			
Stock/Treatment	Surv. %	Height cm	Vol.[4] cm^3
Small/Scalping	97a	156a	353a
Large/Untreated	95a	228b	1104b

[1]/PSB 313: container stock grown in styroblocks with cavity volumes of 65 cm^3 (4in^3)

[2]/PSB 211: container stock grown in styroblocks with cavity volumes of 26 cm^3 (2 in^3)

[3]/Values in each column followed by different letters differ significantly (p = 0.05)

[4]/Stem volume equals height times one third stem area at ground level.

In order that 1+0 container-grown stock reaches adequate size for outplanting, extended photo period may be used to extend the growth period. Even when the supplemental lighting is terminated in time to obtain budset and hardening off before seedlings are lifted, the use of extended photoperiod may interfere with the conditioning needed for seedlings to withstand fluctuating winter temperatures when unprotected by snow cover. Rowe (1964) suggests that environmental conditions during the previous season of growth can exert a strong influence on the expression of certain tree characteristics. Preliminary observations near Dawson Creek suggest that bareroot or two-year old container-grown stock which has not been subjected to artificial photoperiod extension is less susceptible to winter damage than 1+0 stock (Herring 1987). The importance of appropriately conditioning stock for regeneration success merits further investigation.

LITERATURE CITED

Corns, I.G.W. & Annas, R.M.1986. Field guide to forest ecosystems of west-central Alberta. Northern Forestry Centre, Canadian Forestry Service, Edmonton. 1986. 251 p.

Dobbs, R.C. & McMinn, R.G. 1977. Effect of scalping on soil temperature and growth of white spruce seedlings. In: Black, T.A. et al eds. Energy, water and the physical environment of the soil. 6th. B.C. Soil Sci. Workshop Rept. B.C. Min. Agric., Victoria, B.C. 1977. pp 66-73.

Herring, L.J. E.P. 986. 1987. Unpublished results. B.C. Min, Forests and Lands, Prince George. B.C. 1987.

McLeod, A & Meidinger, D. 1985. Biogeoclimatic Region. 1:60,000 map. B.C. Min. Forests Victoria and Prince George. 1985.

Pojar, J, Trowbridge, R & Coates, D. 1984. Ecosystem classification and interpretation of the Sub-Boreal Spruce Zone. Land Management Report No. 17. B.C. Min. of Forests, Victoria, B.C.

Rowe, J.S. 1964. Environmental preconditioning, with special reference to forestry. Ecology. 45(2): 399-402.

SOME ASPECTS ON SITE PREPARATION AND NATURAL REGENERATION IN SWEDEN

Evert Jeansson

ABSTRACT: The first part of the paper deals with mechanical soil preparation for natural regeneration. The extent of natural regeneration and soil preparation in Sweden is reviewed and some principal aspects on the topic are discussed. In the second part a presentation is given of an experiment with natural regeneration and seeding in scarified patches of increasing age in five seed tree stands of different densities.

INTRODUCTION

The concept of site preparation for natural regeneration (NR) includes several silvicultural measures such as clearing of undesired growth, draining, prescribed burning with or without seed trees and mechanical or chemical site preparation. This paper only discusses mechanical site preparation or soil scarification. The two terms are used synonymously.

Scarification with natural regeneration has been subject to increasing interest in Swedish forestry. Introduction of new implements such as power driven disc trenchers has considerably improved the possibilities for effective soil treatment in seed tree stands. Hereby the prospects for successful application of NR-methods have increased. However, for a good result adaption to local edaphic and biotic conditions is essential. Some aspects on this theme are discussed in the first part of the paper.

Natural regeneration is sometimes called in question on harsher areas and in higher elevations. An experiment has been established on lat. 54 deg. 55 min. N, altitude 365 to 470 m. with the aim to study natural regeneration on a relatively harsh site. In the trial NR is compared with seeding in scarified patches of different ages. Two plots are laid out in sparse seed tree stands and three plots have been established in denser, mature stands. The experiment and some of the results are presented in the second part of this paper.

Evert Jeansson, Dept. of Silviculture Swedish University of Agricultural Sciences, Umeå, Sweden. Main field of research: Natural regenerat.

PRESENT EXTENT OF SITE PREPARATION (SOIL SCARIFICATION) IN SWEDEN FOR ARTIFICIAL (AR) AND FOR NATURAL REGENERATION (NR)

In recent years the area of final fellings in Sweden has varied between 200 000 and 230 000 hectares, Figure 1. The major part of this area is reforested by planting or by seeding. Natural regeneration is applied to 25 % or about 50 000 hectares. (Skogsstyrelsen 1986). According to Figure 1, the area of seed tree stands amounts to about 15 % of the total regeneration area.

This Figure refers to occurrence of seed tree stands established in the year previous to the inventory, whereas the value 25 % represents regeneration's randomly sampled from objects subjected to final felling 5 years before the inventory (for Northern Sweden 7 years before).

Soil scarification has in later years been applied on over 80 % of the artificial and on about 50 % of the natural regeneration, Figure 2. The proportion of scarification for planting and seeding has risen from about 50 % in 1975 to 88 % in 1985. For natural regeneration the increase is from 15 % to about 50 % during the same period.

Final cuttings and reforestation measures




Figure 1: Final cuttings, soil scarification, artificial regenerations and seed tree stands in 1000:s of hectares. Consecutive 3-year means 1975-1985, according to the National Forest Survey.

Percentage of scarification for AR and for NR




Figure 2: Soil scarification by artificial and by natural regeneration. Mean values for the whole country. National Board of Forestry 1986.

From 1965 to the present there has also been a pronounced development in the type of machinery used for scarification. In the 60's and early 70's patch-scarifiers were in common use. This type of implement is still frequently used but they have been increasingly replaced by disc trenchers performing a more continous soil preparation and treating a higher percentage of the area. The development has also led to heavier equipment capable of a deeper and more thorough soil treatment.

PRINCIPAL ASPECTS ON MECHANICAL SITE PREPARATION FOR NATURAL REGENERATION

1. Appropriate sites where mechanical site preparation can be advantageous
2. Suitable time for a scarification operation.
3. Area coverage of and degree of disturbance of the ground by a scarification operation.
4. Aspects on dispersal and accumulation of seeds by wind and water, and predation of seeds by animals.
5. Climatic and edaphic considerations of scarification in a seed tree stand.
6. Scarification and utilization of under storey second growth.
7. Forest hygiene, risks for damaging or unstabilizing the seed trees.

1. Appropriate sites

In the case of natural regeneration soil scarification is in general advantageous on fresh and moist forest sites with relatively thick humus layer i.e. *Myrtillus*, *Hylocomium* and *Polytrichum* types. On drier sites such as pine heaths with bottom vegetation of lichens or lichen-*Vaccinium vitis-idaea*, a scarification operation can be guestionable. On these types of forest sites the success of natural regeneration is sometimes better outside scarified plots than inside. Wet sites and sites with frostheaving mineral soils require special considerations. The draining of the ground is essential here. A dense seed tree stand has a good draining effect, but ditching or other measures could be justified. Soil scarification on wet sites should

preferably aim at disturbing or upturning of the humus layer without exposing the mineral soil. It is important to consider the air permeability of the soil, especially for fine textured and water retentive soils (Black 1968). Concerning the influence of altitude Teikmanis (1956) states: "The dependence on the altitude is obvious for natural regeneration but not as noticeable on scarified areas as on localities with no soil preparation."

2. Suitable time for a scarification operation

A general recommendation for the most suitable time of application of a site preparation treatment with natural regeneration is just before an expected good seedfall. This raises the question of good seed prognosis. A great deal of work has been carried out in this field (eg. Leikola et al. 1981, Leikola 1892). At best it should be possible to foresee a good seed crop about a year in advance.

However, the local conditions are crucial concerning the seedfall at a specific site. Before a final cut the seed production in a mature stand can be considerable. Following harvest of the old stand, the seed production drops considerably depending on the change to a new environment for the seed trees and often due to insect attacks. This is especially the case on more northern and harsher localities and with seed trees with small and elevated crowns. After some years the seed trees will recover and their seed production increases. Meanwhile, various vegetation invades the site including scarified patches. The patpatches or strips are most effective for germination and plant establishment during the first years. Their effectiveness declines fairly soon though, and after 5 to 6 years their quality is not much better than the surrounding forest ground (Hagner 1962). However, on harsher sites and in denser shelter tree stands the patches can be effective up to 10 years (Bergan 1981).

If recently established seedlings in scarified patches are to be able to effectively compete with existing understorey growth, the scarification ought to be performed as early as possible. Thus, it would be beneficial to scarify prior to final felling in order to take advantage of the good seed supply in mature stands as well as utilizing the seed dispersal at the logging operation (cf. Kinnunen 1985b). This could, however present difficulties with currently available site preparation equipment. Thus development of scarifiers capable of operation in denser stands is required.

In the case of an unsuccessful regeneration result, the scarification could be repeated after some years. Retreatment should preferably be carried out in tracks or strips crossing the earlier tracks. Good results have been reported after such repeated treatment (Swedish National Forest Service pers. comm.)

3. Area coverage of and degree of disturance of the ground by a scarification operation

The proportion of scarified area and exposed mineral soil should be considered. In difficult terrain the technical accessability can set limitations. Concerning already established second growth some comments are presented in section 6. Adaption of site preparation measures to varying edaphic conditions over an area should be considered. On drier sand- and gravel-dominated areas of lichen type it may not be advisable to scarify where losses of existing advanced growth could be high. Thicker raw humus layers mostly indicates that a site preparation treatment should have a high degree of coverage. If a special distribution pattern for the new regrowth is desired (e.g. row formation), such a distribution could be obtained by scarification in strips, with the desired spacing. Disc trenching in two directions with crossing tracks increases the area coverage.

The degree of disturbance by site preparation can vary considerably. A light treatment may be obtained by the logging operation. A patch scarifier gives a more intense treatment and even more so a disc trencher. Ploughing gives the highest impact on the forest ground. The principal aims of site preparation with natural regeneration is to create favourable

mircrosites for seed germination and plant establishment, to alleviate competition for water and nutrients and to provide protection from predators and unfavourable weather conditions. Large open scarified patches or tracks with exposed mineral soil are less favourable in many cases as also are tracks with steep, exposed sides formed by disc trenching or by ploughing (cf Kinnunen 1982, Pohtila 1977, Yli-Vakkuri 1961). The risks for seed displacement and predation, surface desiccation, soil erosion and frost heaving are more pronounced here than with smaller patches and lighter soil treatment. Patch scarification is not to be recommended on moist or wet sites where the scarified depressions can fill with water for long periods. On these types of sites it may be desireable to affect the water table with drainage or a denser shelter tree stand. Scarification could preferably aim at a light disturbance or upturning of the humus layer, not exposing the mineral soil.

4. Aspects on dispersal and accumulation of seeds by wind and water, and predation of seeds by animals

The success of natural regeneration depends primarily on the availability of sufficient amounts of viable seeds that can germinate and develop on suitable growing spots. Seeds on the ground are exposed to many risks and usually only a low fraction of the initial amount will emerge into seedlings. Dispersal and accumulation of seeds by wind and water onto unsuitable growing places along with predation by birds and animals impairs seed germination and establishment. These factors should be considered in the design of soil preparation implements, planning of operations, and instruction of operators.

Predation by birds and rodents accounts for a large part of seed losses especially in the late winter and in the early spring (Bergsten 1985, Hansson 1975, Heikkilä 1977, Wiklund 1986). Rodent predation can be extreme during years of high population cycles. Exposure of seeds on snow-crusts or scarified patches with open mineral soil implies increased risk for predation.

Protected hideouts where the seeds are sheltered for predators, direct sunlight and waterlogging, are to be preferred when performing a scarification operation. At the Dept. of Silviculture, Umeå, experiments have been carried out involving microtopographies in scarified patches for reducing the risk of predation and improving the establishment conditions for germinating seeds (Bergman and Bergsten 1984).

5. Climatic and edaphic considerations of scarification in a seed tree stand

The climatic and edaphic conditions are different in a seed tree stand compared with those in an open clear-cut area. Site preparation will modify the conditions in the topmost soil layers.

The main difference is that the climate in a seed tree stand is more moderate in several respects (Odin et al. 1987). The temperature regime is more even and relatively milder and the wind velocity is lower. The interception of rain or snow in the tree crowns and the consumption of water and nutrients by the seed trees reduces the run-off and the leaching of nutrients. However, this also implies that less water and nutrients are available for new seedlings. This can be unfavourable at drier and poorer sites or in general under dry weather conditions. On a clear-cut area the snowmelt can come one week or more earlier than in a dense stand. In a seed tree stand the conditions are intermediate. A sparse stand doesn't differ much from an open area. Yet the trees can reduce the surface run-off of meltwater partly by providing shade, thus reducing incoming radiation, and partly by consuming water themselves. The latter lowers the ground water Table and increases the water storage capacity in the ground. On sites exposed to summer frosts partial shading by the seed trees can prevent solar radiation damage to the seedlings after a frost night Hagner 1962, Lundmark et al. 1987).

Germinating seedlings in a moss, lichen, or thick humus cover have difficulties to reach the mineral soil where the moisture conditions are more favourable. Scarifying will improve the situation and also for some time reduce the competition for water and nutrients. Effects of reduced root competition has been demonstrated by numerous investigations (Tatarinov 1971, Yli-Vakkuri 1961).

The drying out of the topmost soil layer in scarified areas will not be so accentuated in a seed or shelter tree stand as in open areas. The total amount of available water is yet less in a stand and the risk for water-logging of scarified patches is reduced compared with that on a regeneration area without trees.

In the autumn and winter problems with frost-heaving are common for young seedlings growing in certain types of fine-textured, mineral soils. The more even climatic conditions and the reduced amount of free water in the upper soil layers in a seed tree stand reduces the risk for frost-heaving, even on scarified areas, compared to the situation on a clear-cut area. Open exposure of mineral soil should though be avoided on this type of soils.

6. Scarification and of understorey second growth

Older stands approaching harvest can contain considerable amounts of advanced growth seedlings. This regrowth has developed during a long period of time and is well established in the actual environment. Often these seedlings can contribute considerably to the stocking of the new stand. Utilization of understorey second growth of this kind entails several advantages, not the least giving a "flying start" to the new tree generation (Kalinichenko et al. 1973). However, early, preparatory measures are mostly required for a good establishment of advanced second growth (Wretlind 1934, Olsson 1965). Conventional felling methods, together with site preparation, tend to eradicate most of the existing, understorey regeneration. The increase in light and radiation by the release to a more open environment, can be as disasterous to such seedlings, especially in the case of spruce. Kinnunen (1985) reports an example of the reduction in existing, understorey regeneration due to final felling and site preparation. From an initial stocking of 2 900 seedlings per hectare before felling, 1 800 stems capable of development remained after the cutting, out of which 1 150 could be considered as main crop stems. After disc trenching 760 seedlings were left, out of which 550 were main crop stems. Forest ploughing reduced the total number to 410 and the remaining main crop plants to 280 per ha. The total number of seedlings was thus reduced by 74 % for logging and disc trenching and by 86 % for logging followed by ploughing. However, Table 1 (after Cilimov 1965, see Kalinichenko et al. 1973) indicates that in a considerable amount of the existing understorey, advanced growth can be preserved by adaption of suitable logging methods.

Table 1. Undamaged portion of existing understorey regrowth after felling according to the Kostroma-method compared with conventional felling. (After Chilimov, 1965, referred by Kalinichenko et al. 1973).

Plant hight	Felling meth.	Felling season	Before, seedl. per ha	after felling, seedl. per ha	pct undam.pl.
< 1 m	Conv.	summer	6 284	1 646	26.2
-"-	-"-	winter	4 663	2 522	54.1
< 1 m	Kost.	summer	5 867	3 602	61.4
-"-	-"-	winter	6 129	4 801	78.5
> 1 m	Conv.	summer	3 986	849	21.3
-"-	-"-	winter	3 658	648	18.3
> 1 m	Kost.	summer	3 471	985	28.4
-"-	-"-	winter	4 582	1 154	25.2

This aspect is also valid for site preparation operations. The choosing of treatment routes so as to leave seedlings growing between the patches or strips undamaged and avoiding treatment of areas with clusters of advanced undergrowth are simple ways to preserve already established seedlings. The sooner in the

regeneration period scarification is undertaken, the more the advanced undergrowth will be preserved. These seedlings are smaller by then and can better survive damage by the operation. Scarification before harvest of the old stand could be a way to level the competitive situation between advanced and new regrowth. Besides, this timing would take advantage of the better seed supply in the old stand and of the seeds dispersed by the logging operation.

7. Forest hygiene, risks for damaging or unstabilizing the seed trees

Hygienic aspects are essential in every forest operation. By scarification in a seed tree stand a sufficiently large area around the trees has to be left untreated so as not to damage the stems or the root systems, and for stability reasons. Wounds to the roots are potential points of entry for pathogens.

Damaged root systems increase the risk of stormfelling. Windthrown trees are the given brood material for bark beetles and pine-shoot borers. The multiplication of these insects in windthrown seed trees can be very high, up to 40 000 new individuals per stem have been reported. Though numbers below 6 000 are more normal (Långström 1984). The prime target for the new insect generation is the annual shoots of the seed trees. Heavy attacks can destroy several years of seed production and growth. The release of the seed trees to a new stand environment by the harvest of the old stand also causes extra stress, especially in the case of spruce, increasing the sensitivity to insect attacks. Early removal of windthrown and unhealthy trees is essential for good forest hygiene and is also prescribed by the Swedish Act of Forestry. The reduction of hazards of this kind by careful forest management comes foremost.

In a broader sense the concept of forest hygiene also includes efforts to avoid risks endangering forest seedlings and juvenile growth. One point here is the unfavourable clustering of seedlings often occurring in scarified patches. Such clusters favour the growth and spread of the snow blight fungus, *Phacidium infestans* for pine and *Lophophacidium hyperboreum* for spruce. One of the few possible steps against a major drain of seedlings by these fungi is to create a more uniform distribution of the seedlings over the area, thus increasing the distance for the mycelium to cover before being able to infect the next individual (Björkman 1948). This implies that a scarification operation should be designed to create small microsites suiTable for germination and seedling establishment and distributed as uniformly as possible over the regeneration area.


Good forest hygiene also involves good care of the forest ground. In the case of site preparation this implies that the operation should be carried out as to avoid macro- and micro-erosion, leaching of nutrients, excessive drainage, exposure of frostheaving soils, as well as other consequences endangering the site's long-term productivity (cf. Burschel et al. 1977).

AN EXPERIMENT WITH NATURAL REGENERATION AND SEEDING COMBINED WITH SITE PREPARATION IN SEED TREE STANDS OF DIFFERENT DENSITIES

The aim of the experiment is to study the establishment and development of natural regeneration compared to seeding in scarified patches of different ages located in seed tree stands of different densities.

LOCALITY


The trial was laid out in 1983 in five stands, A to E, on Joranliden National Forest, lat. 64 deg. 55 min. N, long. 17 deg. 30 min. E, on altitudes 365 to 470 m. above sea level, see Figure 3. Two of the stands are seed tree stands, one (plot A) was established in 1983 and the other, (plot C) was release cut and then scarified by disc trenching in 1975 - 1976. Plot B was laid out in an older, mature, mixed stand that was cleared of second growth and bushes in the mid 1970:s. Plot D was set in an older



Plot A: Seed tree stand established in 1983 at an altitude of 365 m. 19 seed trees and 16 cub.m. per ha, 100 % pine.



Plot D: Older pine stand at alt. 470 m. 840 trees (48 % pine 28 % spruce 24 % birch) and 151 cu.m. per ha. (90 % pine 8 % spruce 2 % birch). No silvicultural operations carried out recently.




Plot B: Old mature stand at alt. 365 m. 355 trees (79 % pine 17 % spruce 4 % birch) and 174 cu.m. per ha. (95 % pine 4 % spruce 1 % birch). The stand has been cleared of advanced second growth in the mid 70:s.



Plot E: Older uneven-aged mixed stand at alt. 440 m. 644 trees (15 % pine 67 % spruce 18 % birch) and 114 cu.m. per ha (83 % pine 16 % spruce 1 % birch). No silvicultural operations recently.

Figure 3. Distribution of seed trees and seed collecting baskets at plot A to E. The height of the lines representing the trees is proportional to the real size of the trees. Numbers in circles denote seed collecting baskets.



Plot C: Pine seed tree stand at alt. 420 m 24 seed trees and 29 cub.m. per ha. 100 % pine. The stand was release cut and scarified by disc trenching in 1975-1976.

pine stand on shallow soil on the bedrock and plot E in an unevenaged, mixed stand dominated by spruce. On plot D and E no silvicultural measures have been carried out for a long period of time.

The soil on plot A is a medium sand. Plot B to E have soils of sandy-silty moraine, fairly rich in stones. The soil type is iron podsolic and a fresh *Vacc. myrtillus* vegetation type dominates on all the plots.

TREATMENTS

18 different treatments have been or are intended to be carried out according to the following Table:

1: No scarific., natural regen. from 1983
2: Scarif. spring 1983 nat.reg. from 1983
3: -"- -"- seeding in spring 1983
4: -"- -"- -"- 1984
S: -"- -"- -"- 1985
6: -"- -"- -"- 1986
7: -"- -"- -"- 1987
8: -"- -"- -"- 1988
9: Scarif. spring 1984 nat.reg. from 1984
10: -"- -"- seeding in spring 1984
11: Scarif. spring 1985 nat.reg. from 1985
12: -"- -"- seeding in spring 1985
13: Scarif. spring 1986 nat.reg. from 1986
14: -"- -"- seeding in spring 1986
15: Scarif. spring 1987 nat.reg. from 1987
16: -"- -"- seeding in spring 1987
17: Scarif. spring 1988 nat.reg. from 1988
18: -"- -"- seeding in spring 1988

EXPERIMENTAL DESIGN

The treatments are laid out in a pattern with 18 rows and 18 patches per row at plot A to C. Plot D and E have only 9 rows each, corresponding to the first and second half of a full size plot.

The 18 treatments are distributed as single method cells in a latin square design with complete sub-blocks containing all 18 treatments within every group of three rows and six consecutive patches (row 1-3, patch 1-6, 7-12, 13-18 etc), Figure 4.

The spacing between the patches is 2 metres and the total area per parcel is 36 x 36 metres (plot D and E: 18 x 36 metres respectively).

Scarifying: manual patch scarifying has been performed for actual treatments with a patch size of about 60 x 60 cm. The humus-layer has been removed and the soil loosened to a depth of 5 to 10 cm.

At each plot seed collecting baskets with an area of 0.25 square have been set out according to Figure 3.

Seeding of actual treatments has been performed with 20 pine seeds and 20 spruce seeds per patch, no seed covering.

Nr	TREATMENT NUMBER FOR ROW AND PATCH NUMBER																	
18	16	10	3	18	15	8	9	11	5	2	13	6	12	17	7	1	14	4
17	13	5	15	11	3	17	14	7	10	1	4	12	9	2	16	8	6	18
16	7	17	9	4	14	10	6	13	8	5	16	15	3	1	18	2	12	11
P 15	11	1	6	13	12	5	15	16	2	17	18	3	14	8	4	10	9	7
a 14	18	8	14	16	6	2	12	4	1	10	7	9	15	5	11	17	3	13
t 13	4	2	12	7	9	1	3	18	17	8	11	14	6	10	13	5	15	16
c 12	9	18	2	14	10	7	1	12	4	13	15	8	17	11	6	16	5	3
h 11	14	4	17	15	2	13	10	6	18	16	3	1	5	7	12	11	8	9
10	6	11	1	3	17	16	2	14	13	7	12	5	8	18	9	4	10	15
n 9	15	13	5	12	8	4	17	9	7	11	14	2	10	16	3	18	1	6
u 8	12	7	10	9	5	11	8	3	16	18	6	17	1	4	15	13	2	14
m 7	3	16	8	6	1	18	5	15	11	4	9	10	2	13	14	7	17	12
b 6	8	12	4	1	18	3	11	17	6	14	10	7	16	9	5	15	13	2
e 5	1	6	11	2	4	14	16	5	15	9	8	18	13	3	17	12	7	10
r 4	5	9	18	8	13	12	7	1	14	6	2	11	4	15	10	3	16	17
3	10	14	7	17	16	6	13	2	3	15	1	4	18	12	8	9	11	5
2	17	3	13	10	7	15	18	8	9	12	5	16	11	6	2	14	4	1
1	2	15	16	5	11	9	4	10	12	3	17	13	7	14	1	6	18	8
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18

Row number

Figure 4. Layout of treatment 1 to 18 at plot A to C and D-E. The numbers denote treatment number.

Provenances of the seed used: Pine: seed from latitude 66 deg. 30 min, altitude 300 - 400 m. Spruce: seed from latitude 63 deg. 50 min, altitude 150 m. Empty and dead seeds have been removed from the seed lot.

The distribution of the pine seeds has been to the left half of each seeded patch and of the spruce seeds to the right half.

MEASUREMENTS

The seed baskets have been collected twice a year, in the spring and in the autumn from the autumn 1983. The collected seeds have been analyzed at the seed laboratory, Dept. of Silviculture, and classified in embryo classes 4 - 0 by x-ray technique (Simak 1980). Inventories of the number of seedlings for the different treatments have been carried out since 1984. Existing understorey advanced growth has been recorded in 1986.

RESULTS

Seed Fall:

Each set of seed baskets gives an estimation of the seed fall at the actual plot during the sampling period. The bars in Figure 5 represent the total seed fall calculated as mean values of

number of seeds in undamaged baskets per plot and transformed to Figures per hectare for the period in question, see Appendix I. Due to the relatively small sample of the seed fall some Figures are approximations.




Figure 5. Recorder seed fall 1983-1986. Number of pine and spruce seeds per hectare for plot A to E.

Figure 6 gives the corresponding information for seeds of embryo classes 3 and 4 i.e. seeds with good germinability. 1983 was a good seed year for spruce and the collected number of spruce seeds from plot B, D and E corresponds to a seed fall of for B: 99 000 (19 000), D: 186 000 (27 000), and E: 950 000 (230 000) spruce seeds per hectare during the winter season 1983-84. Figures in parenthesis denote number of spruce seeds of embryo class 4 and 3. The good seed year has also resulted in a good record of seedlings in the scarified patches.

Seedling Establishment:

The inventory results from 1985 and 1986 are listed in Appendix II for natural regeneration and in Appendix III for seeded treatments. Figure 7 gives the percentages of patches with one or more seedlings per plot and treatment according to the inventory in Spring 1986. The average number of seedlings per patch, within treatment, is shown in Figure 8. For treatment 1, no scarification, the result is very poor. The seedlings occurring are to be referred to as advanced second growth, which will be discussed below.




Figure 6. Number of pine and spruce seeds of embryo class 4 and 3 per hectare for plot A to E.

Scarification And Natural Regenaration:

Treatment no's 2, 9 and 11, treatment no. 5 up to 1985 and no's 6-8 up to 1986. The establishment of seedlings has been gradual. In 1984, one year after scarification of treatm. 2-8, there were nearly no seedlings in the NR-patches. In 1985 the result was significiantly better with seedlings in 81 % of the patches scarified in 1983 at plots, D and E (mean value per treatment). The good seed fall from 1983, recorded at these plots, has surely contributed to this result. At plot A and C the result had improved in 1985, but still only about 17 % of the patches, scarified in 1983, had seedlings.

In the spring of 1986 the result was still better. At plots B, D and E there were seedlings in about 90 % of the patches scarified in 1983. The mean number of seedlings per patch was 1.9 for plot D and 5.2 for plot E counted per treatment. For plot A and C, 60 and 30 %

resp. of the corresponding patches contained seedlings. The mean number of seedlings per plot was 0.9 and 1.8 respectively. For treatment 9, scarified in 1984, the result was good at plot B (89 %) and E (78 %) while A, C and D only had seedlings in 22 - 28 % of these patches. For treatment 11, scarified in 1985, only plot A and E had seedlings in the spring 1986 with 22 resp. 11 % of the patches inhabited.

Scarification And Seeding:

Seeded treatments: no. 3 in 1983, no's 4 and 10 in 1984, no's 5 and 12 in 1985. The establishment of seedlings has been good. 89 to 100 % of the patches at all the plots contained seedlings already one year after seeding, Figure 7. The mean number of seedlings per patch, out of 40 sown seeds, was 11.8 one year after, 13.5 two years after and 8.9 three years after seeding (only treatm. 3). The Figures are corrected for naturally regenerated seedlings.




Figure 7. Percentages of patches with one or more seedlings in spring 1986 for treatment 2 to 12.

The number of seedlings in seeded patches has decreased with about 10 % from 1985 to 1986 (mean value for treatment 3, 4 and 10 at all plots, corrected for natural regeneration). The mortality for germinated seedlings is probably higher but it is compensated by new seedlings germinating one or two years after seeding.

Comparison between treatment 4 and 10 (seeding in 1984, inventory 1985) gives almost identical mean values for the number of seedlings. This indicates no difference between seedling establishment in one year old patches compared to newly prepared ones.

The corresponding comparison between treatments 5 and 12 (seeding 1985, inventory 1986) reveals that seeding in two year old patches only gives about 50 % of the number of seedlings achieved by seeding in newly prepared patches. (Mean value for all plots).

Understorey Advanced Second Growth:

The amount of understorey advanced second growth has been estimated by circular sample plots and calculated as means per hectare for plots A to E. The result is shown in Figure 9.




Figure 8. Mean number of seedlings per patch in spring 1986 for treatment 2 to 12.

Plot A, B and C were cleared of second growth in the mid 70's. Presently existing advanced growth originates from left-overs from the clearing or from later established regrowth. At plot A the advanced second growth mainly consists of somewhat clustered thicket stage pine seedlings. Since the final cut of the previous stand they have been suffering from heavy attacks of snow blight. Also at plot 3 the pine seedlings dominate but the distribution is more scattered. Due to the dense overstorey their height growth is very limited. The attack of




Figure 9. Mean number of advanced second growth coniferous seedlings in hundreds per hectare. Mean plant height in cm 1986.

snowblight is not so pronounced here. The seedlings at plot C amount to 2 780 per ha, almost exclusively pine. They are mainly established in the tracks of mineral soil or upturned humus from the disc trenching carried out after the release of the seed trees in the mid 70's. The mean height of the seedlings is only 16 cm.

Plot D and E have not been cleared of second growth earlier and the advanced seedlings here are older. At plot D the undergrowth consists of about 50 % pine and 50 % spruce, while there are only spruce seedlings at plot E. The mean heights of the seedlings, 84 and 91 cm respectively, indicate that they have been quite suppressed in these relatively dense stands.

DISCUSSION

The collected amount of seeds of embryoclasses 4 and 3 indicates that the seed supply has been satisfactory at plot B, D and E. For spruce the high production of germinable seeds in good seed year (1983) is noticeable. The intervals between good seed years for spruce can be fairly long, especially at higher altitudes and more northerly locations. The last but one good seed year for spruce in this area was in 1975. However, considerable amounts of viable spruce seeds have also been at hand between the seed years. The supply of pine seed is more evenly distributed throughout the years, but also for pine there is a marked periodicity depending on climatic conditions. The number of seed trees and their condition is crucial for the local seed production. After a harvest operation or a period with major windthrow the population of bark beetles and pine shoot borers increases. These insects impair the production of spruce and pine seeds considerably. This has been the case at plot A and C, though the poor result recorded is also a consequence of the few seed trees left on these plots.

The seedling establishment for treatments with natural regeneration reflects the seed fall. The necessity of soil scarification on the actual site type is evident. Between the scarified patches hardly any new seedlings at all have been found. The gradual growth of the number of seedlings in the scarified patches is also manifest throughout all the plots. The number of seedlings per patch has increased from 1.7 in 1985 to 2.0 in 1986 for treatments 2, 6, 7 and 8, or by about 20 %, calculated as a total mean.

For seeded patches the result is good on all the plots. A tendency toward better establishment is evident on plots, D and E, i.e. in the denser stands. This is valid also when considering the higher number of naturally regenerated seedlings on these plots.

By seeding, the maximum number of seedlings occurs after one or two years. Thereafter the number starts to decline. For treatment 3 the mean number of seeded seedlings per patch has fallen from 10.6 to 8.9 or about 15 % from 1985 to 1986 (3 years after seeding). For treatment 4 and 10 the decrease has been about 8 % between 1 and 2 years after seeding. The Figures are corrected for natural regeneration.

The density of the overstorey stand is decisive for the establishment and development of advanced second growth (cf. Kalinichenko et al. 1973). At plots B, D and E the older stands are so dense that only scattered advanced seedlings have been able to survive, and their present development is very poor. The establishment of advanced understorey growth is very dependant on silvicultural measures carried out earlier. On plots A, B and C a clearing

of second growth was performed in the mid 70's. Some seedlings were evidently left over from this operation while some of the new advanced growth has developed later.

On plot A the number of older seedlings amounts to about 1 400 stems per hectare. However, they are so clustered and impaired by snow blight that their contribution to the new stand probably will be very limited.

The advanced regrowth on plot C derives from silvicultural measures for natural regeneration taken in the mid 70's. After release cut of the seed trees, soil scarification was carried out by disc trenching. Up to now about 2 800 seedlings per ha. have been established with a fairly good distribution over the area. They are mostly growing in or just beside the trencher tracks. The number of seedlings is still increasing and the prospect for a well-stocked pine stand in the future is good on this site.

CONCLUSIONS

1. Some conclusions can be drawn already at this early stage from the findings presented above.

2. In mature stands the seed supply has been sufficient for natural regeneration even on this relatively harsh area.

3. Occurrence of both pine and spruce in a seed tree stand means that advantage can be taken of good seed years for both species (plots B, D and E).

4. The seed trees on plots A and C are too few for satisfactory seed supply. Wind throw and attacks of pine shoot borers have also impaired the seed production.

5. Scarified patches in denser stands fill faster with litter than is the case on more open ground. However, they are more effective for germination than untreated forest ground three years after scarification.

6. The establishment of naturally regenerated and seeded seedlings has been better in the denser stands B, D and E compared to the more open stands A and C.

7. The establishment of a natural regeneration spans several years. Seeded patches reach their maximum stocking one or two years after the seeding, whereupon the number of seedlings starts to decline.

8. Seeding in one year old scarified patches gave approximately the same result as seeding in newly prepared patches.

9. Seeding in two year old patches gave only 50 % of the emergence of seedlings in new patches.

10. The stand densities on plots B, D and E are too high for a successful establishment of advanced second growth in the actual area.

11. Existing advanced growth will probably contribute, even if to a limited extent, to the stocking of the new stands on all the plots.

12. Several windthrows have occurred in the release cut seed tree stands (plots A and C) but not in the untouched stands B, D, and E.

LITERATURE REFERENCES

Bergan J. 1981. Foryngelse av furuskog i Troms og Finnmark. (Regeneration of pine forest in Tromsand Finnmark) NISK, Rapport nr 10/81.

Bergman F. & Bergsten U. 1984. Improvement of germination by direct seeding through mechanical soil preparation (pyramidal indentations). Ecology and management of forest biomass production systems, Perttu (ed). Sveriges Lantbruksuniversitet, Inst. f. ekologi och miljövård. Rapport nr 15.

Bergsten U. 1985. A study on the influence of seed predators on direct seeding of Pinus sylvestris. Sveriges Lantbrukuniversitet, Inst. f. skogsskötsel, Rapporter nr 13.

Black C.A. 1968. Soil — plant relationships. John Wiley & Sons, New York 1968, p 153-201.

Björkman E. 1948. Studier over snöskyttesvampens (Phacidium infestans, Karst.) biologi samt metoder för snöskyttets bekömpande. Studies on the biology of the Phacidium-blight (Phacidium infestans, Karst.) and its prevention. Medd. fr. Statens Skogsforskn.inst., Vol 37 nr 2.

Burschel von P., Eder R., Kontarci D. & Rehfuess K.E. 1977. Wirkungen verschiedenen Bodenbearbeitungsverfahren auf Wachstum, Phytomasseakkumulation und Nährelementvorräte junger Kiefernwaldökosysteme (Pinus sylv. L.). Forstwissenschaftl. Centralblatt, Jahrg. 96:1., p 321-338.

Hagner S. 1962. Naturlig föryngring under skärm. (Natural regeneration under shelter-wood stands) Medd. fr. Statens Skogsforskn.inst., Vol 52 nr 4.

Hansson L. 1975. Forestry problems with seed-eating mammals. Royal College of Forestry, Inst. of Forest Zoology, Research notes No. 20, 33 pp.

Heikkilä R. 1977. Destruction caused by animals to sown pine and spruce seed in North. Finland. Comm. Inst. For. Fenn. 89 (5), 35 pp.

Kalinichenko N.P., Pisarenko A.I. & Smirnov N.A. 1973. Lesovosstanovlenie na vyrubkakh. (Reforestation after final felling) Markberedning, naturlig föryngring och beståndsföryngring vid aterbeskogning i Sovjet översättning av valda avsnitt av ovanstående arbete. (Site preparation, Natural regeneration and understorey regeneration in the Soviet Union Translation of chosen sections from Kalinichenko et al 1973) Sveriges Lantbruksuniversitet, Inst. för skogsskötsel, Rapporter nr 6.

Kinnunen K. 1982. Männyn kylvö karuhkoilla kangasmailla Länsi-Suomessa. (Scots pine sowing on barren mineral soils in western Finland) Folia Forestalia 531, 1982, 20 pp.

— 1985. Forest regeneration experiment in Kuru. IUFRO WP S.1.05-08, Natural stand regeneration, Excursion guide, Parkano Research station, Finland, 10. Sept. 1985.

— 1985b. Prospects for natural regeneration of pine in Finland. and: On natural regeneration of Scots pine in northern Finland. Lectures given at IUFRO WP 5.1.05-08, Natural stand regeneration, Parkano research station, Finland, 10. Sept. 1985.

Leikola M., Raulo J., & Pukkala T. 1981. Männyn ja kuusen siemensadon vaihteluiden ennustaminen. (Predictions of variations of the seed crop of Scots pine and Norway spruce). Folia Forestalia 1981.

— 1982. Naturlig foryngring av barrskog. Tidskrift for Skogbruk 1982, p 114-121.

Långström B. 1984. Windthrown Scots pines as brood material for Tomicus piniperda and Tomicus minor. Silva Fennica 1984, Vol. l8 nr 2, p 187-198.

Lundmark T. & Hallgren J.-E. 1987. Effects of frost on shaded and on exposed spruce and pine seedlings in the field. Can. Journ. For. Res. 1987.

Odin H., Ottosson M. & Degermark Ch. 1987. Ståndortsförhållanden i tre hoga tallskarmar. Sveriges Lantbruksuniversitet, Inst. f. Skogl. Ståndortslära, Inst. f. Skogsskötsel, Vindelns försöksparker, Umeå Jan. 1987.

Olsson H. 1965. J. E. Wretlind in memorian. Norrl. Skogsvårdsförb. Tidskr. 1965.

Pohtila E. 1977. Reforestation of ploughed sites in Finnish Lapland. Comm. Inst. Forest. Fenniae 91:4.

Simak M. 1980. X-radiography in research and testing of forest tree seeds. Swedish Univ. of Agricultural Sciences, Dept. of Silviculture, Report nr 3, 29 pp.

Tatarinov V.V. 1971. The effect of competition between standing timber and seedling on regrowth in pine — whortleberry thickets. Soviet Journal of Ecology 1971, vol 2, p 212-219.

Teikmanis A. 1956. Om den naturliga foryngringen efter markberedningar i Norrland. (Uber die Naturverjungung auf älteren Bodenvorbereitungsflachen in Norrland) Norrl. Skogsvårdsförb. Tidskr. 1956. p 385-440. s.72

Wiklund K. 1986. Predation på skogsfrö vid sådd i fält — en metodstudie. Sveriges Lantbruksuniversitet, Inst. f. skogsskötsel, Arbetsrapporter nr 8, 1986.

Wretlind J. 1934. Bidrag till belysande av föryngringsNorrl. Skogsvårdsförb. Tidskr. p 261-342.

Yli-Vakkuri P. 1961. Experimental studies on the emergence and initial development of tree seedlings in spruce and pine stands. Acta For. Fennica 75:1 1963.

Appendix I. Collected seeds for plot A to E during summer and winter seasons 1983 to 1986 transformed to thousands of seeds per hectare.

Ebc. 4-3 = Seeds of embryo class 4 and 3.

	1983		1984		1985		1986	
Plot A:	Su.	Wi.	Su.	Wi.	Su.	Wi.	Su.	
Total number:	21	12	20	7	22	44	80	
-"- pine s:	21	12	20	7	19	44	73	
-"- spr. s:	0	0	0	0	3	0	7	
Ebc. 4-3 tot:	4	12	0	0	9	22	0	
-"- pine s:	4	12	0	0	9	22	0	
-"- spr. s:	0	0	0	0	0	0	0	
Plot B:	Su.	Wi.	Su.	Wi.	Su.	Wi.	Su.	
Total number:	212	111	188	8	95	131	237	
-"- pine s:	212	12	182	8	95	131	210	
-"- spr. s:	0	99	6	0	0	0	27	
Ebc. 4-3 tot:	37	28	71	8	22	55	40	
-"- pine s:	37	9	71	8	22	55	40	
-"- spr. s:	0	19	0	0	0	0	0	
Plot C:	Su.	Wi.	Su.	Wi.	Su.	Wi.	Su.	
Total number:	160	18	10	0	120	31	320	
-"- pine s:	160	0	10	0	120	31	320	
-"- spr. s:	0	18	0	0	0	0	0	
Ebc. 4-3 tot:	22	0	0	0	46	9	104	
-"- pine s:	22	0	0	0	46	9	104	
-"- spr. s:	0	0	0	0	0	0	0	
Plot D:	Su.	Wi.	Su.	Wi.	Su.	Wi.	Su.	
Total number:	187	195	124	0	27	34	40	
-"- pine s:	182	9	89	0	27	34	40	
-"- spr. s:	5	186	35	0	0	0	0	
Ebc. 4-3 tot:	22	31	13	0	9	11	8	
-"- pine s:	18	4	4	0	9	11	8	
-"- spr. s:	4	27	9	0	0	0	0	
Plot E:	Su.	Wi.	Su.	Wi.	Su.	Wi.	Su.	
Total number:	154	970	160	0	13	73	429	
-"- pine s:	154	20	55	0	13	73	429	
-"- spr. s:	0	950	105	0	0	0	0	
Ebc. 4-3 tot:	34	240	70	0	0	47	17	
-"- pine s:	34	10	25	0	0	47	17	
-"- spr. s:	0	230	45	0	0	0	0	

Appendix II. Natural regeneration, seedling establishment, inventory results from 1985 and 1986.

TRTM = treatment number.
NPS = number of patches with one or more seedlings.
NPSPCT = percentage of patches with one or more seedlings.
MVS = Mean number of seedlings per patch.

PLOT	TRTM	Scar. year	Inventory 1985 NPS	Inventory 1985 NPSPCT	Inventory 1985 MVS	Inventory 1986 NPS	Inventory 1986 NPSPCT	Inventory 1986 MVS
A	2	1983	2	11	0.22	12	67	0.89
A	5	1983	3	17	0.67	Seeded 1985		
A	6	1983	3	17	0.17	10	56	0.72
A	7	1983	3	17	0.22	12	67	0.89
A	8	1983	2	11	0.17	9	50	0.94
A	9	1984	.	.	.	5	28	0.44
B	2	1983	12	67	1.17	14	78	1.67
B	5	1983	14	78	1.22	Seeded 1985		
B	6	1983	15	83	1.89	18	100	2.94
B	7	1983	7	39	0.56	13	72	1.28
B	8	1983	16	89	1.50	15	83	2.00
B	9	1984	9	50	0.67	16	89	1.39
B	11	1985	.	.	.	4	22	0.22
C	2	1983	3	17	0.17	6	33	0.33
C	5	1983	4	22	0.28	Seeded 1985		
C	6	1983	3	17	0.17	5	28	0.28
C	7	1983	4	22	0.33	6	33	0.50
C	8	1983	4	22	0.28	5	28	0.33
C	9	1984	1	6	0.06	4	22	0.28
D	2	1983	8	89	1.78	8	89	2.44
D	5	1983	4	44	0.44	Seeded 1985		
D	6	1983	7	78	0.89	8	89	1.22
D	7	1983	8	89	1.33	9	100	1.67
D	8	1983	8	89	1.78	8	89	1.67
D	9	1984	2	22	0.22	2	22	0.22
E	2	1983	9	100	4.56	9	100	5.22
E	5	1983	7	78	4.11	Seeded 1985		
E	6	1983	9	100	5.22	9	100	4.78
E	7	1983	8	89	4.89	7	78	4.78
E	8	1983	9	100	4.67	9	100	5.89
E	9	1984	7	78	1.11	7	78	1.00
E	11	1985	.	.	.	1	11	0.11

Appendix III. Seeded treatments, seedling establishment. Inventory results from 1985 and 1986.

TRTM = treatment number.
NPS = number of patches with one or more seedlings.
NPSPCT = percentage of patches with one or more seedlings.
MVS = Mean number of seedlings per patch.
* ---- * = values recorded before seeding.

PLOT	TRTM	SCAR	SEED	Inventory 1985 NPS	Inventory 1985 NPSPCT	Inventory 1985 MVS	Inventory 1986 NPS	Inventory 1986 NPSPCT	Inventory 1986 MVS
A	3	83	83	18	100	7.83	18	100	6.94
A	4	83	84	18	100	11.56	18	100	10.22
A	5	83	85	* 3	17	0.67 *	16	89	6.50
A	6	83	86	* 3	17	0.17 *	10	56	0.72 *
A	7	83	87	* 3	17	0.22 *	12	67	0.89 *
A	8	83	88	* 2	11	0.17 *	9	50	0.94 *
A	10	84	84	17	94	10.00	18	100	9.56
A	12	85	85	.	.	.	16	89	7.11
B	3	83	83	18	100	12.56	18	100	11.94
B	4	83	84	18	100	16.06	18	100	15.00
B	5	83	85	*14	78	1.22 *	18	100	5.17
B	6	83	86	*15	83	1.89 *	18	100	2.94 *
B	7	83	87	* 7	39	0.56 *	13	72	1.28 *
B	8	83	88	*16	89	1.50 *	15	83	2.00 *
B	10	84	84	18	100	16.89	18	100	16.67
B	12	85	85	.	.	.	18	100	10.67
C	3	83	83	18	100	8.44	18	100	8.11
C	4	83	84	18	100	10.94	18	100	11.78
C	5	83	85	* 4	22	0.28 *	16	89	7.00
C	6	83	86	* 3	17	0.17 *	5	28	0.28 *
C	7	83	87	* 4	22	0.33 *	6	33	0.50 *
C	8	83	88	* 4	22	0.28 *	5	28	0.33 *
C	10	84	84	18	100	15.28	18	100	14.44
C	12	85	85	.	.	.	17	94	12.22
D	3	83	83	9	100	12.56	9	100	11.44
D	4	83	84	9	100	25.22	9	100	24.89
D	5	83	85	* 4	44	0.44 *	9	100	12.00
D	6	83	86	* 7	78	0.89 *	8	89	1.22 *
D	7	83	87	* 8	89	1.33 *	9	100	1.67 *
D	8	83	88	* 8	89	1.78 *	8	89	1.67 *
D	10	84	84	8	89	18.00	8	89	16.00
D	12	85	85	.	.	.	9	100	21.00
E	3	83	83	9	100	19.89	9	100	16.33
E	4	83	84	9	100	23.78	9	100	23.44
E	5	83	85	* 7	78	4.11 *	9	100	9.33
E	6	83	86	* 9	100	5.22 *	9	100	4.78 *
E	7	83	87	* 8	89	4.89 *	7	78	4.78 *
E	8	83	88	* 9	100	4.67 *	9	100	5.89 *
E	10	84	84	9	100	25.22	9	100	21.22
E	12	85	85	.	.	.	8	89	11.89

SPOT SCARIFICATION IN A MOUNTAINOUS SCOTS PINE FOREST IN NORWAY

Preliminary Results

Sverre Skoklefald

ABSTRACT: Exposed mineral soil gave a good basis for germination and seedling survival in mountain forests of Scots pine of Cladonia type. However, there was little increase in height during the first years, especially in seed tree stands of high density.

INTRODUCTION

Norway, which is a typical mountainous country, has also large areas of forest where the operational conditions are difficult. In addition the content of stones and blocks is large and the soil depth often shallow. This is the main reason for the lack of mechanical soil scarification up to this time. However, in latter years interest for scarification has increased. For example, the yearly scarified area in Hedmark county, which has the best operational conditions in the country has increased from about 300 hectares in 1975 to about 2 300 hectares in 1986. This corresponds to nearly 20 % of the yearly regeneration area.

A series of experiments has shown that mineral soil gives a better chance for germination and seedling establishment than intact vegetation, both by natural regeneration and by sowing. Of Norwegian scientists, Professor Mork was amongst the pioneers in silviculture. As early as 50 years ago he Pointed out that at a latitude of 64°N, the temperature was far under the optimal for germination of spruce seeds (Mork 1933). By removing vegetation and humus the temperature in the germination layer increased up to 3.5° C in clear-cut areas. Mork also demonstrated the positive effect of raised temperature on germination rate and germination capacity. This was of vital importance, particularly for unripe seeds which needed a long time to germinate. Seedlings which germinated at low temperatures were small and underdeveloped in the autumn, and during the winter the seedling mortality was high.

During a later investigation (Mork 1946) it was ascertained that raw humus covered with dense heather(*Calluna vulgaris*) had a particularly strong heat-insulating effect. Compared with conditions under heather, one could by soil scarification raise the temperature of the soil at 1 cm depth by up to 8.7° C on a warm day. These temperature measurements were taken in South-east Norway at about 700 metres above sea level.

Although different kinds of vegetation lower the temperature in the underlying layers, the temperature can, under certain circumstances, become very high when for example a coverage of moss or lichen dries out in hot and dry periods. Bjor (1971) found up to 63° C in the moss/lichen layer under a Scots pine stand in South-east Norway, while Bergan (1974) registered nearly 65° C in moss layer on a clear-cut area in North Norway (N.Lat. about 69°). In exposed mineral soil the temperature is never so high because mineral soil has a much greater heat conductivity and heat capacity than moss and humus layers.

Although exposure of mineral soil has a positive effect on temperature conditions in germination and seedling establishment, the effect on soil moisture is probably of even greater importance both for germination rate and germination capacity. At low levels of moisture both germination rate and germination capacity were greatly reduced, but also specially high humidity had a negative effect.

Sverre Skoklefald is Senior Scientist of Natural Forest Regeneration, Norwegian Forest Research Institute, Ås, Norway.

Periodical drying out of the seeds is probably the greatest impediment to germination (Bjor 1965). The seeds' moisture content varies greatly with weather conditions, but exposed mineral soil gives the best physical conditions for germination. Also seedling establishment is influenced positively by the more stable humidity in a mineral soil, so that seedling mortality as a result of drought seems to be considerably lower than in humus. Poor germination and establishment is to a great extent due to over-optimal and in some cases lethal temperatures combined with surface drying up (Bjor 1971).

Also several other Norwegian investigations describe the positive effects of scarification. Mork (1949) advised that the upper layer of mineral soil should be broken up. Hard-packed mineral soil, which is often found under a raw humus layer, was a poor seedbed, both because the seeds are easily found by birds and other seed-eating animals and because germinants have difficulty in establishing firm roots.

Besides producing a higher number of seedlings than other seedbeds, exposed mineral soil gives an increased rate of growth (Bergan 1981, Skoklefald 1965). Bergan's experiments also showed that it was possible to establish natural regeneration under an unexpected high number of shelter trees of Scots pine. The best results were obtained by releasing the seedlings already five years after germination, but scarification resulted in the seedlings living considerably longer than in intact vegetation.

The Norwegian investigations referred to here were all of experimental character, where all scarification was done by hand with clearly defined seedbeds. However, since mechanical scarification has become more usual, detailed projects have been started in order to evaluate the effect of scarification on sowing and natural regeneration (Solbraa 1987). Results up to now would seem to conclude that sowing gave a better regeneration than natural seed fall. There was little natural regeneration above 650 metres above sea level (South-east Norway), while sowing was fairly successful. The experiments were carried out in clear-cut areas and as expected, there was a marked decrease in natural regeneration in proportion to the distance from potential seed trees.




Figure 1. Sketch over the experimental area.

MATERIAL AND METHODS

The experimental area lies in Hedmark county in South-east Norway (Fig. 1). Before regeneration cutting the average standing volume was about 70 cubic metres per hectare, dominated by slow-growing *Pinus sylvestris* with sporadic growth of *Picea abies* and *Betula pubescens*. In the field layer *Calluna vulgaris* was dominant with elements of among others, *Vaccinium myrtillus, Vaccinium vitis-idaea, Empetrum hermaphroditum* and *Deschampsia flexuosa*. The bottom layer was thickly covered with lichen and also a good deal of moss, particularly *Pleurozium schreberi*. The vegetation was characteristic of a dry and infertile forest type, mainly *Cladonia* type. Advance growth of Scots pine was scattered over the whole area. The zero-square percentage based on 4 sq.m sample circles (Braathe 1966) varied from about 40 to about 80. During the regeneration cutting in the winter of 1974, scattered spruce and birch were removed from both inside the effective experimental area and in the buffer zones. By the seed tree cutting 40, 80 and 120 trees per hectare respectively were left, separated by 50 m wide buffer zones. In addition, all trees were cut in a series of parallel 25 and 50 m wide strips. These were separated by 25 m wide zones with 120 trees per hectare to provide seed supply.

Cone production was determined by yearly countings by field-glasses of all cones visible

from the south side of the tree-crowns. The seed fall was registered continuously by the use of seed traps with a collection area of respectively 0.50 and 0.25 sq.m as shown in Figure 1. The sampling surface of the bigger traps was located about 1.6 metres above the ground and the smaller ones on the level of the ground surface. All seeds were X-ray analysed and classified according to the method described by Müller-Olsen and Simak (1954). Spot scarification was carried out manually 2, 4, 6, and 8 growing seasons after the regeneration cutting, both under the seed tree stands and on the clear-cut strips. The scarification was done with a sharp-edged spade and within a frame of 50 x 80 cm. This made spots of equal size, and as far as possible, also of equal quality. The ground vegetation including the humus layer, was removed without disturbing the mineral soil underneath. Every time 40 scarified spots were made in each of the seed tree stands and on each of the 50 m wide clear-cut strips. On the 25 m wide strips the number of scarified spots was reduced by half.

The dynamics of germination and seedling establishment was determined by marking the seedlings already in the year of germination with plastic sticks of different colours so that each annual series had its own colour. In that way it was possible to estimate the number of seedlings of different ages during the research period.

RESULTS

As expected the cone production varied greatly from one year to another (Fig. 2). In the three first years after regeneration cutting, the observed amount of cone-setting was low, but maximum cone setting occurred already during the fourth year after felling. There is a clear tendency towards higher cone production in the most sparesely stocked seed tree stand - this was the case during the last half of the test period. Although the amount of cones varied greatly from tree to tree, nearly 100 % of them produced cones in average to good seed years. Thus in 1977, 78, 80, 82, 83, and 85 between 95 % and 100 % of the seed trees had cones. The average number of cones per tree was respectively 131, 105 and 106 for FI, FII, and FIII.

It is characteristic of Scots pine that some seeds are shed almost every year also in the mountain forests, but the variation from year to year is very great (Fig. 3). Seed year 1977 gave maximum seed fall but regeneration is on the whole affected by the many years of low seed production. The average yearly seed fall in the period 1974 - 85 was estimated at respectively 14, 23, and 35 seeds per sq.m. In the two seed tree stands with the greatest number of trees, opened cones were relatively often found in the seedbags and in such cases the number of seeds was usually considerably higher than in the other bags. The amount of seed is therefore somewhat overestimated where the number of trees is high.

In years with low summer temperatures the seeds were not morphologically fully developed. For example, of the total number of filled seeds, only 35 % and 53 % in the years 1977 and 1978 respectively had fully develope embryo (class IV). Monthly seed collections in seed tree stands showed that most of the seed was dispersed during May and June. In some years a relatively large amount of seed fell in July.

In the clear-cut strips (SI and SII) where the seed traps were only emptied each spring and autumn, the average yearly seed fall was 15 and 11 seeds per sq.m. As the traps are placed along the middle of the strips, the seed fall should be higher nearer the edge of the seed tree stands.

Detailed investigations of seed germination have not been done, but all 1-year-old seedlings were registered and noted in the yearly records.

Figure 4 shows an example of the dynamics of regeneration in seed tree stands where spot scarification was carried out two growing seasons after seed tree cutting. The material covers seedlings germinated in the period 1976-84. Even though the seed fall during the investigation period was usually modest, some new seedlings were found almost every year, and

seedling mortality was low. There is no great difference between seed tree stands of varying density as regards the patterns of regeneration, but in relation to the amount of seed recorded, the result has been best in the seed tree stand of lowest density. The seed fall in the two seed tree stands with most trees has probably been overestimated, while the seed fall in the most sparesely stocked may have been underestimated. Even though broad buffer-zones were used in this experiment, one must reckon with a certain amount of border infiltration in the amount of seed dispersal.




Figure 2. Cone production in seed tree stands during the years 1974 - 1986.




Figure 3. Seed fall in seed tree stands during the years 1974-1986.




Figure 4. Seedling population composition 1-9 growing seasons after scarification.

On the whole the results indicate that spot scarification on dry sites stocked with pine creates good conditions for germination and seedling establishment through several years, both with relatively high and low numbers of seed trees.

Table 1 gives a general view over the regeneration situation 11 growing seasons after the regeneration cutting. Scarification carried out in 1977, immediately before the best seed year of the experimental period, also gave the best result. There was on the other hand no great difference between seed tree stands of different densities (FI-FIII). The result was poorest on the 50 m wide clear-cut strips, but even though the number of seedlings was low, 75 % or more of the scarified spots had one or more seedlings. Results would seem to indicate that seed fall has been quite evenly distributed and that there has been little variation in quality between scarified spots.

Registration of the tallest seedling in each scarified spot, carried out 10 growing seasons after regeneration cutting, showed that the seedlings had grown very slowly. As an example, for seedlings germinated in 1978 the average height was only 3 cm in seed tree stands with 80 - 120 seed trees per hectare, against 6

cm where 40 trees were left. On the 25 m and 50 m wide clear-cut strips the average height was 13 cm and 10 cm. The seedlings were 6 years at the time of registration. The results show that even though scarification gives a relatively high number of seedlings, also in dense seed tree stands on poor sites, the seedlings cannot develope as long as the seed trees are maintained.

Table 1. Total number of seedlings per scarified spot (N) and percentage of spots with one or more seedlings (P) 1984.

Scarified	F I		F II		F III		S I		S II	
Year	N	P	N	P	N	P	N	P	N	P
1975	4.0	88	6.1	98	5.1	83	3.4	92	2.2	79
1977	7.4	100	5.7	100	7.9	98	4.8	98	3.0	90
1979	5.8	93	4.1	93	3.8	85	2.3	75	1.7	75
1981	5.2	98	5.8	100	4.5	95	3.1	95	2.2	85

1/ Symbols F I, F II etc. see Figure 1.

Registration of natural regeneration in intact vegetation six years after regeneration cutting, showed that the number of plants had decreased somewhat, both in seed tree stands and on clear-cut strips. Few new plants were found, and the zero-square percentage had increased (variation from 65 - 85).

CONCLUDING REMARKS

The preliminary results presented here, indicate that spot scarification in Scots pine forests at high altitudes can utilize the modest amount of seed very well. Some seedlings appear nearly every year and seedling mortality has been low up to now, probably particularly because the competition with other vegetation is so negligible on these dry and infertile sites. In order that seedlings may develope satisfactory, the seed tree stands with a low number of trees should be used, if not, the seed trees must be removed after a relatively short time. Even in clear-cut areas the seedlings' height increment is very slow in the first phase, probably mainly on account of low summer temperature and poor nourishment. It will therefore take several years for the seedlings to grow over the average depth of snow.

In mountain forests in South-East Norway the plants of Scots pine are often exposed to heavy attacks of fungus infections. Before the plants grow over the snowcover the problems are particularly caused by *Phacidium infestans*. During these experiments attacks of *Phacidium infestans* were observed as well, especially on the clear-cut strips where the plants were tallest.

The *Cladonia* type has as a rule a considerable amount of advance growth, and in the lowlands there are seldom any problems in obtaining successful natural regeneration without any soil preparation. However, in higher altitudes where the seed supply is low and the plants partly are severely damaged by *Phacidium infestans* and other fungi, there are often great problems in getting satisfactory results. The mature stands, dominated by Scots pine, are as a rule sparesely stocked, and during a long period plants of extremely varying age and height have been established. In some of these cases the advance growth may be a fairly good basis for a new forest generation, but usually the regeneration is rather scattered. By eventual mechanized scarification a great part of the advance growth is probably destroyed and the regeneration period may be long, particularly on account of the seedlings' weak growth in the first years of their life.

LITERATURE CITED

Bergan, J. 1974. Jordbunnsklimatiske undersøkelser i ulike spireleier under skjerm og på snauflate i naturskog av furu (Pinus sylvestris L.) i Troms (Soil climatological investigations in various seed beds under shelterwood and on clear cut area in natural stands of pine (Pinus sylvestris L.) in Troms). Medd. Nor. inst. skogforsk. 31: 117- 148.

— 1981. Foryngelse av furuskog i Troms og Finnmark (Regeneration of Scots pine forests in Troms and Finnmark). Nor. inst. skogforsk. Rapp. 10/81: 69 p.

Bjor, K. 1965. Temperaturgradientens betydning for vannhusholdningen i spireskikt og rotsone. Norsk Skogbr. 11: 375-381.

Bjor, R. 1971. Forstmeteorologiske, jordbunnsklimatiske og spireøkologiske undersøkelser (Forest meteorological, soil climatological and germination investigations). Meddr norske SkogforsVes. 28: 429-526.

Braathe, P. 1966. Registrering av gjenvekst 1962-64 (Survey of forest regeneration 1962-64). Meddr norske SkogforsVes. 21: 81-170.

Mork, E. 1933. Temperaturen som foryngelsesfaktor i de nord-trønderske granskoger (Über die Bedeutung der Temperatur für die Verjüngung in den Fichtenwäldern von Nord-Trøndelag). Meddr norske SkogforsVes. 5: 1-156.

— 1938. Gran- og furufrøets spiring ved forskjelling temperatur og fuktighet (Germination of spruce and pine seed at various temperatures and degrees of moisture). Meddr norske SkogforsVes. 6: 225-249.ork, E. 1946. Om skogbunnens lyngve getasjon (On the dwarf shrub vegetation on forest ground). Meddr norske SkogforsVes. 9: 269-356.

— 1949. Forsøk med markberedning og såing i Ljørdalen statsskog (Experiments on screefing and sowing in Ljørdalen state forest). Meddr norske SkogforsVes. 10: 227-304.

Müller-Olsen, C. and Simak, M. 1954. X-ray photography employed in germination analysis of Scots pine (Pinus silvestris L.). Meddr St. SkogforskInst. 44(6): 1-19.

Skoklefald, S. 1965. Forsok med ulike spireleiebehandlinger i samband med direkte såing av gran- og furufrø (Experiments with various seedbed treatments in connection with direct seeding of Norway spruce and Scots pine). Meddr norske SkogforsVes. 20: 205-247.

Solbraa, K. 1987. Markberedning og såing. Resultater og økonomi. Aktuelt fra statens fagtjeneste for Landbruket Nr. 6 1987: 25-33.

TECHNIQUES AND TECHNOLOGIES OF USING CONTAINERIZED PLANTING STOCK ON CLEARANT AREAS WITH WATERLOGGED SOIL IN THE NORTHWEST USSR

D.V. Ogievsky

ABSTRACT: Various machines and mechanisms are considered which provide transportation of the containerized planting stock (CPS) to the forest culture areas and planting into waterlogged soil. The peculiarities of the area and soil preparation are characterized in case of a cultivation of clearant areas in various growing conditions. Techniques and technologies of using CPS are proposed as well as their differentiation according to areas with different soil moisture content, including the cases of discrete and continuous soil cultivation. The prospects of using CPS in the USSR and mechanizations of planting cultures with the use of CPS in the USSR are described.

Key words: containerized planting stock (CPS), clearant areas, waterlogged soils, forest culture, mechanization of planting.

INTRODUCTION

The problems of production and using the CPS (Maslakov et al. 1981) have been under investigation at the Leningrad Forestry Research Institute for a long time. At present many aspects of technology of forest culture creation have been developed; various forest planting machines and mechanisms have been designed.

Considering the designs of mechanisms and proposed technologies it is essential to emphasize that in general the problem of mechanization is still at the stage of experiments in many countries, the work on the modification of mechanisms is very intensive, therefore at present it is hardly possible to compute particular technical and economic characteristics of technologies for forest culture creation with the CPS use, i.e. most of the figures below will be approximate. Nevertheless, the information available is quite sufficient to detect the main trends in the CPS use on clearant areas with water-logged soils in the USSR Northwest.

D.V. Ogievsky, Leningrad Forestry Research Institute, Leningrad, USSR

Firstly, the machines and mechanisms operating within the technological schemes of forest culture creation under the above conditions will be described.

The CPS from greenhouses and nurseries is transported to the forest-culture areas by a special mechanism UPS-4000A mounted on a truck ZIL-131 of a high cross-country capability.

A loading device and a renovable frame are mounted on the truck to place six pallets in 3 decks one on another. The UPS-4000A capacity is up to 4 000 seedlings of "BRIKET" (the substrate lump volume being of 400 cm^3).

In case of necessity one or two trailers with mounted UPS-4000A mechanisms may be attached to the ZIL-131 truck.

In this case the truck carries up to 12 000 of "BRIKET" seedlings.

Not counting the UPS-4000A mechanism, a container truck ONK-28.8 is widely used in USSR forestry; this container truck has been designed at the "Silava" Scientific and Production Association (Broks 1984). It is based on the KamAZ truck. In spite of two container trucks available, one of which is of a high cross-country capability, we do not think that the problem of the CPS transportation to the forest-culture areas is solved. A safe CPS delivery to the specified area along the roads in

the USSR taiga zone requires a design of transport means on the "tractor basis".

CPS PLANTING

The CPS planting is the second operation after transportation; it greatly affects the technical and economic characteristics of technologies of the CPS use in the forest culture production. Specific CPS features (big mass and dimensions, possibility of planting for a long time period, etc.) result in the fact that in some cases the CPS use technology is not routine, for which new means of mechanization are developed, etc. In general, foreign specialists (Stjernberg 1985), using small-sized CPS, consider that the growing of forest cultures with the manual CPS planting would prevail in the foreseeable future since no mechanism is able to select the best microconditions for planting as it can be done by man. In this case the mechanized CPS planting would be the second less wide-spread method of forest culture growing. These considerations are valid for those countries where population density is usually high, woodland areas are not very large, clearant areas are not vast and man power is available. In our opinion, the manual CPS planting will not be a perspective in the USSR since the forestry conditions here differ greatly from those in the majority of developed capitalist countries. Only total multi-purpose mechanization and automatization of the production processes of forest-culture-growing with the use of CPS may be perspective in the forestry development of the USSR.

Let us describe forest planting machines and mechanisms used for CPS planting in greater detail (Table 1).

Forest-Planting Machine (LA) on TB-1 Tractor Basis (Experimental Model)

The machine is to operate on oxalis heath, in complex, bilberry forest conditions, on ungrubbed areas with felling debris removed, on burns, wastelands, open woodlands, etc., after preliminary drainage. It provides an even CPS planting of no less than 2 500 pieces per 1 hectare on the forest culture area with up to 800 stumps per hectare; in case of more stumps the planting density is no less than 2 000 pieces per ha.

The forest planting machine on the basis of TB-1 tractor is supplied with a hydromanipulator and a pump station. The tractor is supplied with technological equipment consisting of the main components: frame, plow, casing with soil chamber, planting device, device to apply fertilizers, device to apply herbicides, platform with a load lift, hydraulic motor, mechanism for stable position, base and drives.

The forest-planting machine moves over the forest-culture area with stops; during these stops microhills are formed with a simultaneous planting of seedlings and application of fertilizers and herbicides. The width of the cultivated stripe is a double maximum overhang of the hydromanipulator arm.

The working cycle starts from a lift of the planting section at a certain height above soil. The tiller drive is switched on, providing its maximum rotation and the tiller is easily dropped onto the soil. When tilling is started the soil mixture is thrown away to the soil chamber where microhills are formed. At the specified moment in time the drive of the planting device pusher is switched on.

The forest-planting mechanisms are operated by a tractor driver in the TB-1 cabin.

When microhills are formed, the briquetted seedlings are placed, fertilizers are applied and the soil surface is treated by herbicides, the planting section is raised above soil and moved to the site of the next microhill formation where the cycles is repeated. The site of the next microhill formation is visually determined by the tractor driver taking into account stump numbers, stones, slash and natural regeneration. When planting over an arc of the maximum radius (the maximum overhang of the manipulator arm) is over, the planting section is moved to the arc of a lesser diameter moreover. The space between the formed microhills is selected and proceeding from the

requirements of provision an evenly distributed planting over the area and maximum conservation of the natural undergrowth is achieved.

Table 1. Characteristics of Forest-Planting Machines and Soil-Cultivating Mechanisms Used for CPS Planting.

Indices	Mechanism			
	Forest-planting machine on TB-1 base	SL-2**	SAB-1***	ORM-1.5
1	2	3	4	5
Type of interaction between soil cultivation mechanism & soil	point	continuous furrows	continuous furrows	point
Type of machine moving on clearant area	with stops	without stops	without stops	without stops
Simultaneous soil scarification	+	-	-	+
Simultaneous application of fertilizers	+	-	-	-
Simultaneous application of herbicides or insecticides	+	-	-	-
Number of rows of planted seedlings	1*	2	1	-
Type of planting material applied	CPS	CPS, BR seeds	CPS	-
Number of operators (tractor driver incl.)	1	3	2	1
Tractor trade mark & capacity	LHT-55, TB-1 58.8 kWt	LHT-55 58.8 kWt	LHT-55 58.8 kWt	LHT-55 58.8 kWt
System of CPS delivery to planting site	Automatic	Manual via delivery mech.	Automatic	Manual
Stage of development	EM	FSP	FSP	FSP
Cost, in roubles (without tractor)	about 3,000	about 4,000	about 5,000	about 4,000

Legend:
BR - bare-rooted planting stock;
EM - experimental model;
FSP - full-scale production
* - surface planting (without rows);
** - Use of CPS probably after slight modification;
*** - operates in drained conditions

SL-2 Forest Planter-Sower

The forest planter-sower SL-2 (mentioned below as planter) with accessory sections for planting and sowing may be based for CPS planting after modification. The planter provides for forest cultures growing on the plain terrain on microhills (layers) along drained ditches made on grubbed stripes with soils of various mechanical composition: on felling areas with temporary waterlogged soils, on felling areas with permanently waterlogged peat up to 20 cm deep; on drained swamps and excavated peatlands. According to the operation principle and design the SL-2 planter may be related to the machines of the first generation when the furrow opener is in constant contact with soil. The supply of the planter with a special device to cover roots with an active drive attached makes the planter much more efficient, it provides the increase of annual load by using CPS more than thirty, and annual yield — almost twice: 30 shifts — to plant seedlings and saplings with bare roots and 70 shifts - to plant CPS.

The planter is combined with tractors with tractive force of 30 kN and more with a hanging attachment on the back (LHT-55, LHT-100, T-130BG-3, DT-75B and LHT-100B). The planter consists of the following main parts: a trailer and two planting sections (left and right).

About 500 pieces of CPS may be placed on every section after modification. The major portion of the CPS is placed in the LHT-55 tractor body. When the forest planting unit starts motion, the tractor moves over the furrow while the central wheel of the planter trailer rolls along the furrow bottom. The planting sections, fixed at the specified width of the row-spacing, touch the soil and move along the furrows driven by the trailer. The spherical discs of openers make half-open planting furrows with the walls at the angle of 70-80°. Depending on the type of the planting stock the furrows on the top may be 5-18 cm wide.

The planter may be applied for a single-row case on ungrubbed clearant areas with removed felling debris and up to 600 stumps per ha left. In case of more stumps the planter is applied along stripes with sawn stumps. Its efficiency will be no less than ha per shift. When the CPS is used the SL-2 efficiency will be lower if compared with the use of usual seedlings. This is explained by great technological time losses for the CPS treatment since the CPS is not technological from the viewpoint of size, mass and handling. An increase of the planter efficiency per shift is possible due to a decrease of the volume of the soil lump covering the roots which will reduce time losses for the CPS treatment and will enlarge the CPS amount on the forest planting machine.

The use of the SL-2 planter is rather labour-intensive (5 workers). A decrease of the CPS dimensions and mass as well as a high-quality planting will reduce the number of workers and will provide automation of the CPS delivery.

ORM-1.5 Mechanism for Microhills Preparation

At present various types of plows are applied to make microhills (layers) (PL-2-50, PKNL-500A, PSh-1, etc.), but they operate on open clear areas. One of the ways to increase the forest regeneration efficiency is to eliminate costly and labourous work on stump pulling, i.e. to cultivate ungrubbed felling areas. Therefore, a rotor mechanism has been designed at the Leningrad Forestry Research Institute, which is intended to make "point microhills" for planting of coniferous saplings and seedlings in containers and with bare roots and to treat soil for natural soil regeneration. The mechanism should be applied on new clearant areas with drained and temporary waterlogged and mineral soils with up to 1 100 stumps per 1 ha.

The operation principle of the mechanism is based on the use of passively rotating 4-blade rotor with its periodic brake to make the hole deeper and to reduce the mass.

The mechanism is assembled with the tractors of traction class 3 and higher (LHT-55, LHT-100). It consists of a frame, a rotor and two brakes.

The rotor mechanism operation on the ungrubbed clearant area is as follows. When the tractor with the hanging attachment moves over the clearant area, the rotor rolls on the soil surface and the rotor blades alternately penetrate into soil which is accompanied by a periodic operation of brakes. Due to the use of a connecting mechanism the cam makes four revolutions during one rotation of the rotor. When the cutting blade penetrates into soil, the cam pushes the lever and the brakes are applied to stop the rotor. This produces an extra resistance moment on the rotor shaft and the blade cuts the soil. The brakes act during the cam-lever interaction which corresponds to the rotor turn at 65-70°. During this time the blade goes deep into soil with the soil on the blade surface. Then the brakes operation is over and the blade turns the soil layer accumulated on the blade surface onto the soil surface and puts it next to the hole produced. Moreover, when the rotor rolls over the formed microhill, the turning blade presses the microhill to the surface of the uncultivated soil.

When one of the blades comes into a contact with an obstacle which cannot be overcome (stump, stone, etc.), the microhill is not formed and the rotor overcomes the obstacle by rolling over it. The mechanism operates quite reliably, practically without damage.

In case of ungrubbed clearant areas the rotor mechanism may produce about 70 % of microhills (from the total number of efforts) suitable for planting. A subsequent plantation into the formed microhills requires the preparation of the planting site, which is a labour-intensive and low-efficiency procedure if done manually.

TRENDS IN FOREST-PLANTING TECHNIQUE DEVELOPMENT

The analysis of the forest planting technique development in various countries makes it possible to separate the main stages in the design of the forest-planting machines (Stjernberg 1985), which may be classified according to the mode of moving along the clearant area as follows:

I. generation — forest-planting machines of continuous motion and furrow making;
II. generation — forest-planting machines of continuous motion and periodic furrow making;
III. generation — forest-planting machines for point planting: (a) continuous motion along the clearant area; (b) discrete motion along the clearant area.

The forest-planting machines of the Ist generation (design was started during 1920-1930's) were characterised by a permanent contact of the soil-cultivating mechanism with soil during operation (the principle of continuous furrows). These machines are widely applied in the world at present. They require a careful soil cultivation before planting. The forest-planting machines of the IInd and IIIrd generations are characterised by a short-time contact of the soil-cultivating mechanism with soil (the principle of interrupted furrows) or by a point contact (when soil is cultivated at a point while the soil-cultivation mechanism at the moment of operation is motionless relative to the soil surface). The first forest-planting machine of the IInd generation only appeared in 1965 only. It manifested much better results when operating in difficult conditions (on areas with numerous obstacles) if compared with the Ist generation machines. This is the reason why late in 1970's a development of more advanced machines of point operation was initiated. All foreign forest-planting machines of the IIIrd generation are based on the tractors of "Forwarder" type; the operation of these machines is controlled by mini-computers. Since the experience with forest-planting machines of the IInd and IIIrd generations is rather poor, the information available is insufficient to make any conclusion which generation (the IInd or IIIrd) is most efficient. A prospective use of forest-planting machines with discrete motion along the clearant area

(III(b) generation) is most doubtful. In general, these machines are of a low productivity.

Considering the Soviet designs of machines and mechanisms from the above positions, the forest planter is related to the III(b) generation of forest-planting machines and SL-2 planter - to the Ist generation. Besides, soil cultivating machines have been designed at the Leningrad Forestry Research Institute, which may be used to plant forest cultures with the use of CPS (ORM-1.5). In general, the use of simple and cheap mechanisms, and forest-planting machines is preferable for the USSR at present, if compared with the majority of other countries. This is explained by specific features of the forestry in the USSR and by impossibility to provide numerous enterprizes with costly and powerful techniques — forest-planting machines of the IInd and IIIrd generation. Nevertheless, the machines of the IInd and IIIrd generations will be widely used in the future since they ensure several operations during one run of a tractor along the felling area, e.g. preparation of soil, planting application of fertilizer and herbicides. The operation of such machines saves much energy, reduces labour losses and number of shifts. Concurrently, the use of these machines would hardly save money since the assignment for amortization of costly techniques is quite significant.

One of the most advanced Soviet designs of forest-planting machines is a mechanism on the basis of TB-1 tractor. Its wide use will be possible after elimination of the following shortcomings:

- irregular distribution of plants over area;
- increase of productivity of operation;
- increase of reliability of tiller operation in case of an obstacle in soil.

TECHNOLOGY OF FOREST CULTURES CREATION

A particular technology is selected for forest cultures creation proceeding from the nature of soil moisture content and soil fertility. The forest fund in the RSFSR Northwest characterized by at least temporary soil waterlogging, is classified into the types of the habitat conditions in the following way.

Forest with *Hylocomium*, haircap-moss forest and groups of forest conditions with temporary soil waterlogging.

In case of temporary waterlogged areas a technology is proposed to work in May-September. In humid bilberry heaths and haircap-moss forest the work may be done at any time during the vegetation period: when mechanisms may operate despite waterlogging, i.e. during most of the dry period when summer is wet, and during May-August when summer is dry.

When the period with waterlogged soils is short the whole area is divided into stripes 30 - 40 m wide. "Technological corridors" (3 - 4 m wide) are made to provide the passage of machines and mechanisms; they are made by tilling or stump sawing on the boundaries of these stripes. These "technological corridors" are arranged around the whole area. The "corridors" are also arranged within the stripes, if necessary the stumps are grubbed. The corridors within the stripes are necessary for subsequent forest thinning, boundary corridors are required for area cultivation. The lengths of these stripes depend on the conditions of the most suitable cultivation of the area.

Plots with temporary waterlogging are also divided into stripes, 30 440 m wide. Technological corridors are made between the stripes in the same way, but within the corridors the stumps are grubbed on the stripe 3.0 - 3.5 m wide. These technological corridors and consequently the grubbed stripes are on the lines of the greatest slope of the terrain. If the direction of the maximum slope cannot be determined visually or from plant distribution, an elementary altitudinal survey of the area is made. The plot perimeter is contoured by

technological corridors, made by tilling or grubbing of stumps. After the work on the plot cultivation the drains are made in the ungrubbed stripes by plow ditchers (PKNL-500, LKN-600) which are joined by a collector laid over the contour passage. The collector, depending on the conditions of soil moisture content, may be done by plow ditchers (passive mechanism) or by excavators (active mechanism). The pass length is fixed with the account of slope, it should not exceed 100 m. This type of drainage network is termed "minor reclamation".

Soil cultivation and planting of cultures are made simultaneously. This is possible when the CPS is applied. The work is done by ORM-1.5 mechanism and by LA combine. In oxalis and bilbery forest and in hard forest-growing conditions both the ORM-1.5 mechanism and LA combine may be applied. In case of haircap-moss forest the combine application is most preferable.

The ORM-1.5 mechanism operation is as follows. The mechanism in combination with LHT-55 tractor, equipped for the CPS delivery when moving straight and parallel to the technological corridors over the fixed stripes, forms a number of microhills. These microhills are produced by turning the soil layer without disturbing the soil horizons. These horizons are composed in such a way that doubled organogenic horizons are found at the base. The dimensions of the microhills are: height — 25 cm, length — 40-60 cm, width — 50 cm (the length is measured along the pass, while the width is measured across the pass). In case of forest with *Hylocomium*, *Dicranum*, etc. and shallow organogenic horizons the "survival" of microhills with such composition and size may be quite satisfactory.

In haircap-moss forest and in transition types of the forest when organogenic horizons are highly developed (up to 35 cm) the discrete microhills produced by ORM-1.5 mechanism, due to a low volumetric weight, may poorly "survive" and may have unstable water regime. Therefore, the ORM-1.5 mechanism operation in case of developed organogenic horizons (turf, litter, decaying timber, etc.) is not recommended. Microhills produced by the ORM-1.5 mechanism are not always tightly pressed to the uncultivated soil surface. In 30 % of cases the attempts to make microhills are not a success due to obstacles on the way (stumps, stones, debris, etc.), or the produced microhills have the shape or size not suitable for planting (they are often formed on the edge, or they are too small). Therefore, the number of mechanism runs should be higher to provide the required planting density despite gaps. In general, the runs should be spaced 2.5 m. In this case about 2 600 microhills suitable for the CPS planting would be available on the area of 1 ha.

Concurrently with the microhills formation the worker, being in the body of the tractor, throws, by a tray, briquetted seedling near every properly-formed microhill. The workers who follow the tractor make the following manual operations; they prepare the site for planting in the microhills, they pick the briquetted seedling and adjust it into the microhill. Since the natural soil composition is disturbed, the work on the preparation of the hole in the microhill is less labour-intense if compared to when the seedling is planted into the virgin land. The tractor carries 800 - 900 pieces of the CPS. To provide an effective operation of the mechanism, it is recommended to envisage sites with the CPS storage to pick them during the mechanism run. A special tractor may be used to deliver the CPS along the technological corridors.

The LA combine operation under such conditions will be as follows. The LA combine has a movable arm 5 m long. During the run it makes a stripe 10 m wide. It provides 3 or 4 runs on the stripe 30 - 40 m wide. The combine makes up to 25 microhills during one stop. Discrete microhills formed by a tiller have a shape of a truncated pyramid and they consist of organic and mineral soil with the optimum volumetric weight (0.7 - 1.2 g/cm^3) all over the microhill volume. This is the main difference of the microhills from those made by the ORM-1.5 mechanism; the latter consist of layers with various volumetric weights. Microhills made by the LA combine have the following

dimensions: height — 30 cm, width and length of the base — 60 x 60 cm. They are located over arcs. Since microhills are made by a tiller and the sites are selected by a worker individually, 100 % of microhills are practically suitable for planting the CPS. The microhill composition and shape in forest with *Hylocomium*, *Dicranum*, *Rhytidiadelphus* and in complex types of forest-growing conditions as well as in haircap-moss forest on peat and peaty soils provide complete "survival" of microhills. In case of about 1 000 stumps on the plot of 1 ha. the LA combine made up to 3 000 microhills per 1 ha with practically complete conservation of the undergrowth. Concurrently with the microhill formation a hole is made in it and the CPS is planted; moreover, the covering of the hole is made by pouring the soil around the plant which provides a high quality of the work done. Thus, the LA combine operation provides a mechanization of two labourous operations such as preparation of soil and planting of the CPS. The tractor carries the CPS storage of 1 200 pieces, consequently, the combine is loaded by the CPS twice when it operates on the area of 1 ha. Another tractor may be used to deliver the CPS to the combine.

When the ORM-1.5 rotor mechanism is applied for soil cultivation and planting, undesirable plants are removed, if necessary, by routine methods. The rows of cultures are thinned by manual "Sekor" mechanism. When LA combine is applied a preventive thinning is made which is as follows: there is a special arrangement on the combine which makes a chemical treatment of the area around microhills immediately after planting. This arrangement is equipped with special controls to change the dose of chemicals in accordance with the type and degree of area overgrow.

If microhills are made by the ORM-1.5 mechanism, the fertilizers are applied manually, while microhills made by the LA combine are treated by fertilizers using a special mechanism mounted on the arm, simultaneously with planting. Fertilizers are put into a hole 5 - 10 cm deep apart from the planting site. Fertilizer doses may be different.

Undesirable trees are removed from technological corridors spaced every 30 - 40 m by the same mechanisms as in the above technological scheme.

Protection against fire is provides by the same scheme.

Sphagnum, Horsetail-Sedge and Herbaceous-Marsh Groups of Forest-Growing Conditions

The creation of forest cultures in these groups of forest-growing conditions was very difficult. These conditions are characterized by permanent stagnant, flowing or transit waterlogging and the use of mechanisms is possible there only in summer when the planting stock began to grow. The CPS makes it possible to work at time suitable for the run of mechanisms and to keep the required agricultural dates. This is of particular importance for herbaceous marsh group of conditions where soils are rich and the planted cultures may be very productive there. The basis of the technological scheme under such conditions is the traditional technology of the Leningrad Forestry Research Institute developed for the conditions with water surplus (Shutov 1985) when the work is done during the driest period providing the motion of mechanism and high-quality work.

On such areas stumps are grubbed away by stump pullers (D-496A, D-513A, D-695) and stripes 3.5 - 4.0 m wide are made along the area with the maximum slope; the distance between the centres of these stripes is 7 - 8 m. Stripes are also made around the plot. These contour stripes are used for passing the machines and mechanisms and for drain ditches. Dense ditches are explained by water surplus. When the work is over the ditches are joint by a collector dug. by an excavator. The collector discharges into drainage network. In case of necessity an over-slope ditch is made. The mechanism run in these conditions should not exceed 100 m.

Depending on the particular conditions, the following mechanisms may be applied for soil cultivation:

- heavy gutter plow PKNL-500 in case of numerous boulders;
- auger plow PL-2-50 and PSh-1 in case small bouldered area;
- auger plow PSh-1 or PL-2-50 in case severe overgrowth by herbaceous vegetation, since these plows provide the passage of mechanisms after planting.

A selection of the soil-cultivation mechanism should eliminate the effect of the most "harmful" factor. Microhills made by the above plows should be at least 55 ± 5 cm wide, and 25 ± 5 cm high irrespective of the position of the drain ditch; their composition should be suitable for the CPS planting. The length of the microhills is 2.8 - 3.0 km per ha.

The planting of cultures by SL-2 planter is made in combination with the LHT-55 tractor; it moves above the microhills. The working organ makes a continuous furrow 5 - 15 cm wide and 14 ± 3 cm deep. The working organ places the CPS into the furrow slightly pressing it for 0.2 sec until the CPS meets the covering device. The mechanism carries up to 600 - 1 000 plants in briquettes. If plants are spaced 1 m and cultures are planted on the area of 1 ha, the mechanism should be filled by new portions of briquetted stock 3 - 5 times. The CPS may be delivered by a wheeled tractor during dry times, the tractor will move along the contour stripes. It should be noted, that the preparation of the area according to this technological scheme is of an utmost importance since a great number of additional portions of the CPS is required. Otherwise it will require much time for delivery and loading of new CPS portions and the efficiency of the work will be lower.

If they apply plows providing the passage of mechanisms after the planting of cultures, undesirable plants may be eliminated by chemicals using the forest chemical device ALH and tractor forest sprayer TOL. If they apply plows which do not provide such passage of mechanisms, the undersirable vegetation should be eliminated by using a manual "Sekor" tool.

Application of fertilizers is quite necessary for poor fertile conditions (sphagnum and horsetail vegetation). Techniques and technologies for this operation have not yet been designed. In highly fertile conditions (herbaceous and spirea vegetation), application of fertilizers is not reasonable.

Undersirable trees are eliminated chemically using ALH device; therefore technological corridors are left unplanted every 30 - 40 m.

The water collecting ditches in the second technological scheme are used to stop fires.

Thus, two technological schemes are described to create forest cultures using the CPS. The data obtained show that the first technological scheme may be applied on the area of 55 % of the forest fund in the RSFSR Northwest characterized by waterlogged soils; the second scheme may be applied on the remaining 45 % of the area;

- moistening regime, specific features of area overgrown by various vegetation and fertility characteristics are key characteristics to select a particular technology;
- preparation of the area and peculiarities of planting site formation (density of drain ditches, continuous or discrete microhills) depend on the regime of moistening
- specific features of area overgrowth and fertility characteristics determine a set of agrotechnical measures essential to create forest cultures;
- in connection with the work done on the modification of machines and mechanisms used in the technological schemes for forest culture creation it is impossible at present to give accurate technical and economic parameters of these technologies. Preliminary data, however, show that the cost of these culture creations will not differ greatly from the cost of traditional planting. But the use of the CPS will prolong the dates of work on forest culture planting substantially.

CONCLUSION

Thus, specialized technologies with the CPS use in the forestry are under development in the USSR at present. The design of fundamentally new forest-planting machines and mechanisms operating automatically, and of simple mechanisms providing the CPS transportation and soil preparation on clearant areas is very intensive.

In the USSR CPS may be widely spread from multi-purpose mechanization of all the production processes starting from seedlings growing up to a creation of productive plantations. At the present stage of forestry development in the USSR, the creation of forest cultures with the CPS is made in general by using simple forest-planting machines and mechanisms of the Ist generation (permanent contact of the working organ with soil during operation) or by simple soil-cultivating mechanisms (for example, ORM-1.5). This is explained by the specific features of the material and technical basis of development of forestry in the USSR. But in the future only the planting machines and mechanisms of the IInd and IIIrd generations (discrete or point interaction between the working organ and soil during operation, point planting, combining and automatization of the production processes) may provide a multi-purpose solution of the forest regeneration problem with the use of the CPS.

LITERATURE CITED

Broks, Ya.Ya. 1984. Biological, technological and economic aspects of forest regeneration by containerized planting stock. Transactions of the Latvian Academy of Agriculture, no 221: 32-44.

Maslakov, E.L. et al. 1981. Planting material with ball-rooted system. Moscow, "Lesnaya Promyshlennost" Publishing House; 1981. 144 p.

Shutov, I.V. et al. 1986. Planting and growing of spruce and pine plantations. Leningrad, Leningrad Forestry Research Institute; 1986. 106 p.

Stjernberg, E.I. 1985. Tree planting machines: a review of the intermittent-furrow and spot planting types. FERIC N-SR- 31 October, 1985. 118 p.

GUIDELINES OF THE NATIONAL BOARD OF FORESTRY FOR SITE PREPARATION IN LAPLAND

Kari Pelkonen

BACKGROUND FOR PRESENT GUIDELINES

The present guidelines of the National Board of Forestry are the result of long development. On grounds of increased research results and experience they have continuously been revised, and will be revised in the future. Thus a review of the earlier practice is necessary in order to understand what has been done in Lapland during the past few decades and what is done today.

The National Board of Forestry administers about 42 per cent of the forestry land in the Province of Lapland. Until WW II, logging activities were carried out only on a small portion of this area. Cuttings were mostly focused on pine stands close to waterways. As a regeneration method, natural regeneration was applied almost without exception.

After WW II, the reconstruction and the revival of the commercial and industrial life of Lapland required the starting of larger-than-before cuttings in the northern woods. Cuttings were mostly carried out in virgin spruce stands. By means of clearcuts, the aim was to regenerate these rather fertile spruce stands with pine. Prescribed burning was the prevalent site preparation method. This method was extensively used in the 1950's. The largest annual prescribed burning areas exceeded 30 000 hectares.

In the early 1960's, prescribed burning areas decreased because of the forest fire risk involved and the large number of workers required. The occurrence of some biotic forest damages was also linked with prescribed burning.

The decrease in prescribed burning was also expedited by the fact that mechanical site preparation methods were developing. It was thought that these would greatly replace prescribed burning. Firstly, mechanical "Spot scarifying" became common. It was applied to a large variety of site types, and the results of regeneration were very variable.

The extensive failures in artificial regeneration slowly resulted in the abandonment of spot scarifying. One of the reasons for the failures were the exceptionally cold and humid summers in the early 1960's.

In the mid-1960's scarification was substituted by wing ploughing which had developed to a practical method. The results in artificial regeneration on wing ploughed sites were promising, and it was generally believed that wing ploughing was the final solution to the problems in artificial regeneration in Lapland. During the 1950's and 1960's, practical site preparation was not based on any detailed guidelines. Methods and their use were mentioned in circulars of general nature, and thus the areas where these methods were used, turned out to be rather extensive.

The first guidelines for site preparation on regeneration areas were given as late in 1973. The introduction of the guidelines constituted a remarkable improvement to the earlier practice. In these guidelines Finland was divided into two parts. The line was drawn in the lake and river system of River Oulujoki; the areas north and south of this had guidelines of their own.

In the guidelines for Northern Finland, the soil types were divided in three groups, within which one could choose from 2 to 3 different site preparation methods. These guidelines already recognized all the currently applied mechanical site preparation methods. Prescribed burning, on the other hand, was not mentioned at all. The guidelines were drawn in collaboration with forest researchers using the knowledge available at that moment. They provided a fairly good setting for the choice of a correct site preparation method. In practice, wing

ploughing became, however, the prevailing method, because of the great faith in the advantages of ploughing; also some factors concerning the use of equipment contributed to this development.

DEVELOPMENT OF PRESENT GUIDELINES

The basis for the present site preparation guidelines was created in the guidelines for artificial regeneration given in 1978. These guidelines, first of all, defined the areas for use of various site preparation methods. In more detail, areas for use were given in the so-called regeneration chain tables drawn separately for Southern and Northern Finland.

Here Northern Finland comprised nearly as large an area as in the guidelines given in 1973. Otherwise the guidelines were much more detailed than earlier, and the choice of the site preparation method was affected by a larger number of factors than earlier.

These guidelines were defined more closely in 1981, when site preparation guidelines were drawn for each of the three regions of the National Board of Forestry. The area of the Province of Lapland got four different regeneration chain tables: one for the commercial forests in the northern protection forest zone, second for the mineral soils of commercial forests, third for the peatlands in commercial forests, and fourth the mineral soils of the commercial forests in the District of Inari. The details in the tables had been further specified. The choice of site preparation method was affected by the following factors:

- site type
- soil type
- thickness of raw humus
- stoniness
- hydrology

Methods to choose from were:

- prescribed burning
- disc trenching
- spot scarifying
- wing ploughing
- mounding

Practice has proven these guidelines to be successful. They give good grounds for sufficiently precise consideration of the soil factor affecting artificial regeneration. The site preparation methods for the Region of Northern Finland were renewed in 1985. It was not considered necessary to change the regeneration chains defined in 1981. On the other hand, the new guidelines emphasized very detailed planning that takes into account the variations in soil type. Also the importance of local expertise when choosing regeneration methods was emphasized. Wing ploughing should be used only to a limited extent on sites where it, from the viewpoint of regeneration, is necessary. The reason for this is the pressures on wing ploughing caused by other forms of land use and the failures in the wing ploughed areas that have not so far been explained. The use of prescribed burning, on the other hand, is increased where it is applicable.

Prescribed burning has enjoyed a renaissance. This has been made possible by the new technology with increased fire safety and reduced labour costs. The annual record in Lapland has been 2 000 hectares on prescribed burning, and this record will be broken.

The current guidelines for site preparation emphasize close consideration of the other uses of forests, such as reindeer husbandry, game management, landscape protection and recreation, in planning and carrying out of the work.

Earlier it has been difficult to comply with the guidelines because of lack of appropriate equipment and the consideration of costs.

In the 1980's there has been strong development to get appropriate equipment. The results of this work were the more applicable disc trenchers and spot scarifiers. Another development line has been the so-called multi-

purpose site preparators. The goal has been a site preparation unit which can make a varying preparation result according to the requirements of the soil. Thus the transfer costs caused by the use of various separate pieces of equipment can be saved. This line of development has already resulted in some efficient practical solutions. To save in costs, the planning of work has continuously been developed.

FUTURE OUTLOOK

Determined development of guidelines and machinery has contributed to the use of purposeful site preparation in regeneration. Development work is necessary also in the future. The basics of site preparation still require research. Especially the growth disturbances and plant mortality in ploughed areas after good initial development require clarification. The practical guidelines will be revised as research knowledge increases. In the field of machine development, the further development of the multipurpose site preparers continues. The importance of landscape and environment protection in the planning and implementation of work is further emphasized. Waterways protection should especially gain more significance than at present.

EFFECT OF SITE PREPARATION ON REGENERATION RESULTS IN LAPLAND

Eljas Pohtila

ABSTRACT: Site preparation has been common in the forests of Lapland since the 1950's. The receptivity of prepared soil to regeneration degrades quickly, which makes it difficult to choose the optimal date for site preparation in natural regeneration. Burning, scalping and disc ploughing make a better combination with sowing than with planting; and wing ploughing makes a better combination with planting than with sowing. Burning alone does not guarantee adequate germination after sowing.

EARLY PRACTICE

Site preparation has been common in the forests of Lapland since the 1950's when a concerted large-scale regeneration of over-aged stands was begun (Fig. 1). Site preparation connected with sowing and planting has been done experimentally in Lapland since the beginning of this century. The experiments carried out by Renvall (1912, 1919) in the northernmost Lapland are worth mentioning first. He found that sowing was very successful where the humus layer was thin (< 1.5 cm). Where the humus layer was thick (> 2 cm), however, sowing gave poor results. He also found that wild fires usually improved conditions for seedling growth.

The experiments carried out by Heikinheimo (1939) during the 1920's and 1930's were important and indicative for future silviculture in Lapland. Sirén (1952) continued these experiments in the 1950's. The procedure especially suitable for the reforestation of over-aged stands proved at that time to be clear cutting, prescribed burning, scalping and sowing of pine. When mechanical scalping was adopted, it was regarded as the final solution to soil preparation problems.




Figure 1. Site preparation in Lapland in 1952 - 1985.

INCREASE OF PLOUGHING

In the 1960's the needs of site preparation had to be re-evaluated when cool summers caused severe damage to artificially reforested sapling stands; considered to be already established. There were failures especially in attempts to change old spruce stands into young pine

Eljas Pohtila is the Director of The Finnish Forest Research Institute in Helsinki, Finland.

stands. Etholén (1972) has documented these failures thoroughly. Ploughing of forest soil was adopted as a new method, since the failures were considered to be at least partly due to insufficient soil preparation. Wing ploughing proved to be a very reliable method and not significantly hampered by the stoniness of the glacial till. In addition to creating spaces for planting stock, ploughing also considerably facilitated planting work. These factors together revealed ploughing to be a versatile method, which made other site preparation methods almost completely obsolete. Ploughing has been used in connection with natural regeneration, too.

RECENT RESEARCH ACTIVITIES

The failures of the 1960's led to the launch of new research. Modern mechanical soil preparation methods had to be compared with the old ones in connection with different approaches to regeneration. At the beginning of the 1970's both Scots pine and Norway spruce gave rich seed crops, which were collected into stores in such abundance that it was possible once again to use direct seeding, and even broadcast sowing, in practice. Modern soil preparation methods improved the germination of seeds and emergence of seedlings, and reduced seed use, in turn intensifying broadcast sowing. It was also possible to obtain information from the broadcast sowing experiments about the effects of soil preparation on natural regeneration.

COMPILABILITY OF DIFFERENT METHODS

The results of these experiments confirmed some earlier ideas about the compilability of different site preparation and regeneration methods (Pohtila 1977, Pohtila and Pohjola 1983, 1985). Prescribed burning, scalping and sowing proved to be a successfull combination also in later experiments in which they were compared with ploughing as well as other methods (Table 1). On the other hand the planted seedlings have had far less success than sowed ones on burned areas. The risk of death is high, especially for seedlings planted immediately after burning. Planted seedlings dry up more easily than sowed ones, which is probably the main reason for the difference. There is no evidence to show that Rhizina root rot (*Rhizina undulata* Fr.) has contributed to the results.

The best site preparation method with planting has been wing ploughing, which, however, has proved to be relatively poor with sowing (Fig. 2). The height growth of both sowed and planted seedlings was, however, faster in these areas than on scalped or disc-ploughed plots.

Table 1. Order of superiority of different method combinations on the basis of survival of seedlings and transplants in the experiment carried out by Pohtila (1977). Forest site types: Empetrum-Myrtillus and Hylocomium-Myrtillus.

1.	Burning + scalping + sowing	81.7 per cent
2.	Ploughing + sowing on the shoulder	80.9 "
3.	Scalping + sowing	79.3 "
4.	Ploughing + planting on the shoulder	75.1 "
5.	Ploughing + planting on the tilt	69.3 "
6.	Burning + ploughing + sowing on the shoulder	69.1 "
7.	Scalping + planting	69.0 "
8.	Ploughing + sowing on the tilt	67.1 "
9.	Burning + ploughing + planting on the shoulder	61.3 "
10.	Burning + ploughing + sowing on the tilt	59.3 "
11.	Burning + ploughing + planting on the tilt	58.9 "
12.	Burning + scalping + planting	48.3 "




Figure 2. Mean number of seedlings capable of development per hectare in stands reforested in 1970 - 75 by soil preparation methods (Pohtila and Valkonen 1985).

One important reason for the failure of sowings on the wing-ploughed plots seems to be frost heaving (Fig. 3). Ploughing in combination with prescribed burning, in contrast to scalping only, has increased the damage caused by frost heaving. In the thin surface layer of ploughed soil the germlings are probably more exposed to the effects of unfavourable weather than are planted seedlings. On the other hand, technical considerations are apparently more important for planting than for sowing. The more thorough the soil preparations, the more easily the planting operations can be done.




Figure 3. Frequency of damage caused by frost heaving in stocked sowed patches (Pohtila 1977). Substrates: 1 = hoed patch, 2 = burned, hoed patch, 3 = ploughed shoulder, 4 = ploughed tilt, 5 = burned, ploughed shoulder, 6 = burned, ploughed tilt.

Observations on the interaction between site preparation and reforestation methods are to some extent new. Generally speaking, prescribed burning, scalping and disc ploughing make a better combination with sowing than planting, whereas wing ploughing makes a better combination with planting than sowing. After closer study, site quality has also proved to be an important factor. The combination of wing ploughing and planting is favourable for moist spruce dominant sites. On sub-dry pine dominant sites where differences in success between the different combinations of methods have been relatively small, a wider choice of methods is apparently available.

SITE PREPARATION IN BROADCAST SOWING

Broadcast sowing on snow has given inconsistent results. On an average 2 - 3 times more seedlings have emerged on pine-dominant sites than on spruce-dominant ones. Restocking has been best on ploughed plots with the most mineral soil. Seedlings have been recorded most commonly on the shoulder of the ploughed ditch and the furrow made by the disc plough. The poorest substrate for germination in all preparation methods has been humus (Fig. 4). Substrate microtopography effects restocking as well as the quality of germination. Though the climate in Lapland is generally humid, the ridges created by wing ploughing are obviously too dry to serve as germination substrates. Large patches, and especially the centres of such patches, prepared by mechanized scalping have also proved to be favourable germination sites.

Prescribed burning alone does not guarantee adequate restocking in broadcast sowing. Seedlings have emerged on thoroughly burnt spots with mineral soil but not on non-cultivated plots (Fig. 5).

By and large an increase in the amount of soil prepared and in the number of seeds sowed correspond with an increase in the number of seedlings. Sirén (1952) presented some estimates about the quantities of seeds needed on different substrates in Lapland to achieve fully-stocked seedling stands. Empirical data, how-

ever, are still scant. In principal, it is possible to solve the problem of combining the amount and spreading of seed and site preparation. Even so, the problem remains as yet unsolved.




Figure 4. Proportions of different substrates in the compared soil preparations and the average number of seedlings on different substrates emerged from broadcast sowings (Pohtila and Pohjola 1985).




Figure 5. Degree of burning and average number of seedlings emerged from broadcast sowings in different research areas (Pohtila and Pohjola 1985).




Figure 6. Effect of the sowing date and the amount of seeds on stocking with seedlings in broadcast sowings on ploughed areas (Pohtila and Pohjola 1985).

There are several different techniques for sowing. Much of the equipment used in agriculture can also be used in the forest. Sirén (1957) tried sowing from aircraft as far back as the early 1950's. The technical problems of sowing have apparently been solved.

The results of broadcast sowing can be affected by the choice of date for sowing. Previously, broadcast sowing on snow was considered to be more advantageous than sowing in the summer, an idea proved false by new studies. In Lapland the richest stocks are achieved by sowing in June (Fig. 6). The rule connecting the longer time lag between sowing and germination with the emergence of fewer seedlings also applies in Lapland. June is the peak time for natural seed fall from Scots pine in Lapland (Heikinheimo 1937). To achieve fully-stocked stands (c. 2 000 seedlings/ha) using normal soil preparation and the most efficient sowing date,

the minimum amount of seeds needed (laboratory germination 80 per cent) seems to be 0.5 - 1.0 kg per hectare on sub-dry, pine-dominant sites in Lapland. On moist, spruce-dominant sites the need for seeds is higher, 2 - 6 kg per hectare, depending on the site preparation methods.

On completely cultivated soils the corresponding seed requirement is probably about half of the above amounts.

STABILIZATION OF PREPARED SOIL

Stabilization of the soil after preparation has a negative effect on reforestation results. In particular stocking with sowed seedlings is clearly poorer when the interval between soil preparation and sowing is increased (Fig. 7). Previously, the effect of soil stabilization was considered to be favourable because of a decrease in frost heaving (Pohtila 1977). It would be desirable, however, for there to be only a single winter, between soil preparation and sowing or planting.




Figure 7. Effect of the interval between soil preparation and broadcast sowing on stocking with seedlings (Pohtila and Pohjola 1985).

The advantage of fresh soil preparation is probably a result of soil porosity. Rain condenses the upper mineral soil layer, thus decreasing the number of favourable sites for seed germination. If the seeds remain uncovered on the bare mineral soil they are exposed to many kinds of damage. To preserve site productivity, cultivated areas should be sown as soon as possible. The risk of nutrient leaching is evident, especially on ploughed sites. Huss and Sinko (1969) have proved experimentally that there is a risk of nutrient leaching, even on burned areas, if reforestation is delayed

SITE PREPARATION AND NATURAL REGENERATION

The results of the broadcast sowing experiments can also be applied to natural regeneration. Only immediate seeding after site preparation will assure the best possible result. In natural regeneration, however, there is no certainty about the mature seed crop in Lapland. To achieve an abundant cone crop for Scots pine, the temperature sum in the summer preceding flowering, i.e. in the period when the flower buds are formed, should be at least 910 d.d. in Lapland (threshold value +5° C). To have, say, fifty per cent mature seed, the temperature sum in the summer following flowering should be at least 845 d.d. (Sarvas 1970). If the recurrence of warm summers follows the normal distribution pattern, the probability of the coincidence of such summers is, according to weather statistics, only 0.18 x 0.33 = 0.06 in Sodankylä (67°22'N, 26°39'E), for example.

Our practical experience corresponds well with these calculations, so it is difficult to choose the optimal date for site preparation. The interval between soil preparation and natural seeding may be so long that the investment in soil preparation will be wasted. Perhaps regeneration areas with soil preparation should be sowed instead of left in anticipation of natural seeding. If such areas are sowed, large supplies of seed are necessary. We are dependent on natural seed crops until the seed orchards established for Lapland are in full production.

CURRENT PRACTICE

The observations described above have contributed to a situation in which the proportions of site preparation methods used in practice have again changed. Wing ploughing has decreased and disc ploughing increased (Fig. 1). Burning is coming into use again.

LITERATURE CITED

Etholén, K. 1972. Männyn viljelyn tulos Pohjois-Suomessa ja siemenen alkuperä. Summary: The Success of artificial regeneration of Scots pine in Northern Finland and origin of seed. Folia For. 160: 1-27.

Heikinheimo, O. 1937. Metsäpuiden siementämiskyvystä II. Referat: Über die Besamungsfähigkeit der Waldbäume II. Commun Inst. For. Fenn. 24(4): 1-67.

— 1939. Kokemuksia paksusammaltyypin metsien käsittelystä. Referat: Erfahrungen betreffend die Behandlung der Wälder wom Dickmoostyp. Silva Fenn. 52: 121-139, 292.

Huss, E. & Sinko, M. 1969. Effekt av hyggesbränning. Skogshögsk. Instn. Skogsföryngr. Rapp. Uppsats. 17: 385-424.

Pohtila, E. 1977. Reforestation of ploughed sites in Finnish Lapland. Commun. Inst. For. Fenn. 91(4): 1-98.

— & Pohjola, T. 1983. Vuosina 1970 - 1972 Lappiin perustetun aurattujen alueiden viljelykokeiden tulokset. Summary: Results from the reforestation experiment on ploughed sites established in Finnish Lapland during 1970 - 1972. Silva Fenn. 17(3): 201-224.

— & Pohjola, T. 1985. Maan kunnostus männyn viljelyssä Lapissa. Summary: Soil preparation in reforestation of Scots pine in Lapland. Silva Fenn. 19(3): 245-270.

— & Valkonen, S. 1985. Varttuneiden viljelytaimikoiden tila Lapin piirimetsälautakunnan alueen yksityismetsissä. Summary: Development and condition of artificially regenerated pine and spruce sapling stands in the privately owned forests of Finnish Lapland. Folia For. 631: 1-19.

Renvall, A. 1912. Die periodischen Erscheinungen der Reproduktion der Kiefer an der polaren Waldgrenze. Acta For. Fenn. 1: 1-154.

— 1919. Mäntymetsän elinehdot sen pohjoisrajalla sekä tämän rajan alenemisen syyt. Suojametsäkysymyksestä 1. Acta For. Fenn. 11: 1-143.

Sarvas, R. 1970. Männyn siementarpeen tyydyttäminen Pohjois-Suomessa. Stencile in the Finnish Forest Research Institut; 1970, 4 p.

Sirén, G. 1952. Havaintoja Perä-Pohjolan valtion mailla 1948 - 1950 suoritetuista männyn kylvöistä. Summary: Observations on pine sowings on state owned lands in Peräpohjola (Far North) in 1948 - 1950. Silva Fenn. 78: 1-40.

— 1957. Lentokonekylvön tulokset. Summary; Results of broadcast sowing by airplane. Metsätal. Aikak. 1. 73 (10): 305-309.

EXPERIENCES WITH LARIX SPECIES IN NORTHERN FINLAND

Max. Hagman

ABSTRACT: This paper gives a short review about the experiences collected over a period of about 100 years of larch cultivation in Northern Finland. Almost all results concern the Siberian larch origin and provenance are discussed and results are presented from provenance and seed source trials. Survival and height growth are compared to native Scots pine and it is suggested that on right sites the Siberian larch is a possible alternative. Further research must concentrate on selection of good seed sources and study of genotype/site interactions.

INTRODUCTION

In the Nordic countries there has always been an interest in the possibilities of extending the forest to the mountains, and as early as in the 18th century there are speculations if the larch could be used (Linnaeus 1754). The use of larch for shipbuilding brought the interest of the admiralties in Sweden as well as in Russia to the larch forests and raised the question of possible cultivation.

One hundred years later the construction of wooden warships was no longer of any importance, but the good growth of the larch cultivated and also the impressive figures brought back by foresters making inventories for exploitation of the virigin northern larch forests in Russia. This aroused a new interest, which resulted in seed importing and new cultivations all over the country.

When we here are talking about larch the main species to be discussed is the Siberian larch *Larix sibirica* Ledebour and *L. sukaczewii* Dylis.

EARLY HISTORY

In Finland the real impulse to larch cultivation was the rediscovery of the Raivola larch forest on the Karelian isthmus not far from present Leningrad. This forest in which the first part was established in 1738 has been described by several authors (see e.g. Ilvessalo 1916, 1923, Timofejev 1961 and others). In Russian literature it is mentioned as the forest of Lintulovskoj rosce and it is at the present situated in the forest district of Roščinsk, Leningrad oblast.

Although the forest had been known earlier its existence had been forgotten, but in 1869 the director of the Finnish Forest High School at Evo, A.G. Blomqvist visited the place and called the attention of the Russian authorities and forest scientist to its impressive yield.

This visit prompted Blomqvist to raise the question of larch cultivation in Finland in several papers (Blomqvist 1877, 1887 and 1893), and engaged him in activities to procure larch seed and to produce plants. A centre for his activities was the school at Evo. To make himself familiar with the larch forest he made long travels in different parts of Russia and at the same time contacts with people who could provide seed.

Many seed lots were also obtained and distributed. Further enlargements were suggested by the circular letter of 21.11.1889 from the National Board of Forestry about the cultivation of larch in the state forests.

In the north, cultivations were also started but due to the limited sources and the general situation in forestry of those days the cultivations concentrated around foresters' offices, forestry schools etc.

MAX. HAGMAN is a emeritus professor of forest genetics at the Finnish Forest Research Institute, Vantaa, Finland.

In the Tornio river valley several cultivations were made (Reuter 1918) and other cultivations are listed by Parvela (1930 and 1932) and Tammelander (1914). Correspondence between A.G. Blomqvist and X. Nordling led to the establishment of larch cultures as far north as at Toivoniemi in Kaamanen NW of Inari where also a few other attempts were made by the forester Waennerberg.

Also in Sweden there arose an interest in larch at the same time and many cultivations were made in the northern parts with seeds obtained in co-operation with the Finnish forest service (Schotte 1917).

LATER DEVELOPMENT

At the turn of the century there seems to have been a trend from cultivation forestry towards natural regeneration and there is a decrease in the interest for exotics. The larch, however, continued to be of interest on a small scale and scattered reports also from the north occur (see Ilvessalo 1916).

After the first world war and the Russian revolution access to the old seed sources became limited, except for the Raivola stands since the Raivola larch forest was left in Finland and its administration taken over by the Finnish Forest Research Institute in 1922.

Seed collections were immediately started in this forest and seed of Raivola origin brought to Lapland and the Cavil Research Forest (Heikinheimo 1956). The good development of the sample plots in Cavil roused great hope for the larch as an alternative species in the regeneration of the old spruce forest and the cultivations were extended and new provenances brought in.

Conditions of war and the transfer of the Raivola forest to the Soviet Union in 1940 and again in 1944 and in addition the war in Lapland 1944 - 1945 more or less brought the cultivations of larch to an end for some time.

When the rebuilding work started and the forestry of Lapland was greatly activated in the 1950's the role of the larch was again taken up to discussions.

Lack of Finnish seeds led the National Board of Forestry to contact seed dealers in the Soviet Union with, as we will see, very unfortunate consequences, particularly when one considers the scale of the operations compared with earlier activities.

In 1950 larch plantations in the state forests in Northern Finland were summarized as follows:

Region	Number of cultivations	Area
Northern Finland	4	0.37 ha
Ostrobothnia	20	11.74 "
In the period 1951 - 1957 there were added the following		
Northern Finland	6	4.01 ha
Ostrobothnia	1	0.25 "
thus the total area in 1957 was		
Northern Finland	10	4.38 ha
Ostrobothnia	21	11.99 "
Total	31	16.37 ha

These figures do not include the plantations of the Forest Research Institute in its research forests.

Larch in private forest was not listed at that time but in 1971 the Northern Regional Office of the forest service made an inventory of all larch plantations in its region with the intention of local seed collection. This inventory includes state as well as private and research plantations of seed bearing age. At that time approximately 4 000 trees were listed as suitable for seed collection.

Later figures have not been compiled but an idea might be obtained from the production of seedlings.

The nurseries of the Northern Regional Office delivered in the years 1958 - 1976 larch plants as follows:

Year	Number of plants
1958	4 000
1959	172 300
1960	267 515
1961	211 000
1962	150 000
1963	34 000
1958 - 63	839 515
1968	2 200
1969	-
1970	-
1971	17 215
1972	14 180
1973	68 355
1974	82 000
1975	65 000
1976	23 550
1964 - 76	272 500

Thus, during the period 1958 - 1976 in total 1 112 015 plants were delivered.

In addition the nurseries of the Ostrobothnian Regional Office delivered in the years 1958 - 1960 a total of 550 700 plants and in the period of 1970 - 1976 the number of plants delivered was 157 000. It is important to distinguish between the periods 1958 - 1963 and 1968 - 1976 due to the provenances used. This will be discussed later in this paper. In the period 1977 - 1976 the Pakatti nursery of the Northern Regional Office delivered 77 697 larch plants including 3 672 plants for research experiments.

The figures from the later years reveal a growing interest in the cultivation of larch, no doubt partly due to the increased possibilities for obtaining seed from the new seed orchards. Thus, the number of plants delivered from the Northern and Ostrobothnian Regional Office nurseries were as follows:

Due to the extremely cold winter 1986/87 and the very small amount of snow, larch plants growing in containers at the Imari nursery near Rovaniemi were killed by 90 % and thus the number of plants that could be delivered in the spring of 1987 was minimal.

Year	Northern For. Distr.	Ostrobothnian For. Distr.
1977	40 000	27 000
1978	20	51 000
1979	109 700	174 000
1980	187 913	36 000
1981	101 580	234 000
1982	214 588	1 036 000
1983	43 300	1 125 000
1984	82 280	1 147 000
1985	355 593	1 803 000
1986	835 160	1 948 000
1987	120	1 400 000
1977-87	1 970 254	8 981 000

If we suppose that the larch cultivations were made at spacing of 3 x 3 meters it means approximately 1 000 plants per hectare and thus the plants mentioned above, would correspond to a cultivated area of about 1 000 ha. up to the year 1976 and about 10 000 ha. between 1977 and 1987.

The earlier results were, however, not as good as expected. To understand this, we must now turn to the question of the seed sources.

ORIGIN AND PROVENANCES

When lntroducing an exotic species the choice of the right seed source is of utmost importance. This is particularly clear with the Siberian larch which has a very large distribution and great geographical variation.

Here is not the space to go into a detailed discussion of the systematics of the Siberian larch so the reader is referred to the numerous papers that have been published (Dylis 1947, Bobrov 1972 and further papers listed in these works).

Following Dylis and other Russian authors I have distinguished the western Siberian larch as *Larix sukaczewii* and the central and more eastern one as *Larix sibirica*.

Unfortunately, very little is exactly known about the origin of the earlier cultivations of larch in Finland. Of the famous Raivola forest we only know that the seed for the first culti-

vation was ordered from the city of Archangelsk but if it was collected there is unknown.

Since the Raivola forest was extended five times with different seed sources or even with seed collected in the earliest plantations the origin of the different plots is very difficult to trace.

Already Ilvessalo observed that the 1 000 grain weight of seeds from the different plots differed but his comparative sowings were, unfortunately, destroyed by chickens in the nursery.

The question of the origin of the Raivola forest has been discussed in detail by Mezger (1935) who expresses the opinion that at least some of the material was from the government Ufa, which means west of the central part of the Ural mountains.

Raivola was, however, not the only seed source used in Finland. The tracing of their origin is just as difficult since the archives at Evo were destroyed by fire and the notations in the field are often incomplete. It is known that much seed was imported east of the Ural, particularly from Nishnij Tagilsk (Granit 1936) and also that seeds were obtained from the regions west of the Ural towards the SW limits of the distribution of the larch.

Frequent seed lots were obtained from Archangelsk but whether this meant the government Archangelsk and in that case, from which parts of it, is unknown. Blomqvist himself mentions larch from the Mesen river valley in connection with the cultivations made at Toivoniemi in Inari but it is uncertain if seeds from Mesen were really the source.

Other sources mentioned, are Pinega, Perm, Nishni Novgorod, Olonets and Vologda, but whether all seed lots really arrived and were used is uncertain. The obtaining of larch seed from Russia seems, even in the old days, to have been difficult.

For the oldest plantations in Northern Finland one may assume that the provenances might have been Raivola, Archangelsk region and, perhaps, also the Nishnij Tagilsk region.

For the younger plantations the records are neither so exact as desirable. The Raivola seed source is, of course, known also in second generation, from cultures in Southern Finland, but since sections of that forest are not recorded we do not know exactly which part was collected.

Imports in the 1930's were not always well documented and we have to be satisfied with such notions as Novosibirsk, Pinega, Archangelsk, Nishnij Tagilsk etc.

To give an example of the confusion that might occur: The provenance of the Siberian larch planted at the Kivalo research forest (No. 26) is expressed as Archangelsk, 64° N lat., 40° E long. (Lähde et al. 1984). However, Heikinheimo (1956) mentions that the seed for this plantation was obtained from a Finnish forest officer Mr. S. Remes, and that the origin was stated as the Pinega and Šenkursk regions.

From Russian maps it can be seen that the latitude of the capital of the Pinega region, Karpogor is 64° N and longitude 44°15' E. The latitude of Šenkursk on the other hand is 62°07' N and longitude 42°55' E. If the Pinega region reaches further to the NW the difference Between the two origins might be even greater than 2°.

From the map published by Melehov, Certovskoj and Moiseev (1966) it can be seen that the distribution area of the Siberian larch in the Archangelsk oblast is discontinuous with a gap between the Šenkursk and the Karpogor localities. Larger areas of larch forests occur NW of the city of Pinega and to the NE along the Mesen river.

Unfortunately, we have no records which could explain if the seeds obtained by Mr. Remes were obtained separately from the two regions or as a mix, and if they were, in the former case, sown separately.

Vagueness in descriptions might even have been the reason for the mistake made in the 1958 - 63 period when seeds were imported, from "Krasnojarsk". A closer study has revealed that the seeds in many cases were collected from Krasnojarskij kraj but from its most southern parts, and also from the Chakasskoj autonomous oblast. Other notes mention the "Sajan mountains". Unfortunately, none of the original documentation, perhaps sent from the Soviet Union, has been found.

The alarming reports about the performance of these Central Siberian origins, which hence belonged to the species *L. sibirica* Ledeb. forced the forest service to look for other seed sources.

Fortunately seed orchard activities had started in the 1950's in the south of Finland and for the seed orchard No. 16 at Oitti; plus trees of Raivola provenance were selected. When seed from this seed orchard were available they were used also in the north, particularly since the experimental plots at Kivalo were of the Raivola origin and no drawback had been observed from using this provenance.

In addition, the search for local seed sources mentioned above, and the occurrence of good seed years in the early 1970's gave an opportunity to collect local provenances. These were also used in the experiments reported here.

We have to remember, however, that many of these local Lapland seed sources consist of only a few trees and so varying degree of self-pollination may occur. In a few cases there is also slight possibilities for hybridization with other species.

Thus, the question of which is the correct origin and provenance of larch for the different parts of Northern Finland is still unsolved.

Guidelines from the natural distribution of the species in the western regions of its area are not so easy to obtain since the natural, original distribution has been disturbed by cutting and roding of land for agriculture over a very long time. As can be seen from various papers by Russian authors (Köppen 1889, Nevrli 1912, Drobov 1914, Tovstoljes 1916, Kuznecov l927, Iljinskij 1929 and others) the Siberian larch seems to have a discontinuous and somewhat scattered distribution where limited forest areas are separated from each other. The same is observed in the paper by Melehov, Certobskoj and Moiseev (1966) for the Archangelsk and Vologda districts and this problem has also been discussed by Simak (1979).

Attempts have been made to correlate the western distribution of the Siberian larch to climatic and edaphic factors (see e.g. Tolskij 1938). Cajander (1901) who visited the region at the turn of the century was of the opinion that it was mainly the presence of lowland with boggy and poor soils that had prevented the larch from proceeding further westward. He also mentions the effect of the shifting cultivation in the Olonets area as partly promoting, partly preventing the further spreading of the larch.

Some of the best descriptions available for the conditions for larch growth in these parts of Russia are the papers by Hemberg (1877, 1899) which are still well worth studying.

Also the travel report by Arnborg and Edlund (1962) and that by Simak already mentioned, give good information. The very large literature in the Russian language is, of course, the test source, but it is, unfortunately, out of reach to many of us for linguistic reasons.

Although much advice might be obtained from the knowledge of the species in its natural regions, the final proof will always be the trials in the area where the exote is going to be used. We must therefore now turn to the results, so far, obtained in Lapland and other parts of Northern Finland.

SURVIVAL

The first sign that a species is adapted to a new area is that it survives in the new conditions for a long enough time. Only if the survival is acceptable may we consider growth, yield and quality factors in judging the value of the species.

Our knowledge of the survival of the Siberian larch in the area discussed is for the oldest cultivations limited by the lack of records on the development. Success or failure are reported in a general way but there are nevertheless old plantations which show that the larch has survived for more than 100 years as far north as in Inari.

More details are to be extracted from the sample plots of the Forest Research Institute of which the latest figures are published by Lähde, Werren, Etholén and Silander (1904).

Nevala (1980) made a comparative study of larch and Scots pine cultivations made in

1970 - 1972. The same results were also discussed by Tigerstedt, Pohtila and Nevala (1983). In these experiments, 38 in total, and situated in the effective temperature sum region between 630 and 910 degree days (base +5° C) the survival of larch and of bare root pine plants was studied.

The survival after 9 years was 62.9 % for larch and 10.9 % for pine. In the 1971 trials after 8 years the corresponding figures were 90.3 %. and 35.9 %. In their experiments from 1972 the results were slightly different in the region with temperature sum less or equal to 800 d.d.: 76 % for larch and 47 % for pine, and in the region with a temperature sum above 800 d.d. where the corresponding figures were 73.5 % for the larch and 58.1 % for the pine.

The very low survival rate of the origins from the Central Siberia have been mentioned several times. These reports from the practice are supported by the results of the experiment No. 46 which I planted in 1963. These are shown in Table 1.

Table 1. Survival and mean height of Larix sibirica Ldb. and Larix sukaczewii Dylis in the experiment No. 46 near Rovaniemi, lat. 66°29'N, long. 26°42'E, alt. 220 m. The experiment was planted in 1963 and assessed in 1980.

Lot No.	Seed lot No.	Species	Origin	Number of replicates	Total number of plants	Survival %	Mean height m
1	57-017	L. sibirica	USSR, Hakassk. Auton. oblast, Sarala 54°50'N, 89°10'E	4 + 9	925	10.6	4.77
2	58-105	L. sukaczewii	USSR, Sverdlovsk oblast, Straja Ljalja 59°05'N, 59°50'E	4 + 4	425	34.7	3.75
3	58-117	L. sukaczewii	USSR, Archangelsk oblast, no locality given	3	75	81.3	3.61
4	58-118	L. sibirica	USSR, Hakassk. Auton. oblast, approxim. 53°N, 90°E	4 + 3	325	8.0	4.70
5	58-122	L. sibirica	USSR, Altaiskij kraj, approxim. 52°N, 85°E	4	100	14.7	4.58
7	58-120	L. sibirica	USSR, Altaiskij kraj, approxim. 52°N, 85°E, 700 m	4	100	6.7	3.21

As can be seen, the survival of the origins from Altaiskij kraj and the Hakasskoi aut. oblast is almost the same and very low. In the same experiment there is one origin from the eastern slopes of the Ural, fairly close to the old Nishnij Tagilsk-area, and this origin is clearly better than those from more south but even this source is not adapted well enough. In contrast to these, is the origin from the Archangelsk oblast, although it must be noted that this source is represented by much fewer plants.

The continuous lack of seed of known origin from northern sources has, so far, pre-

vented us from making a large provenance experiment. On the other hand, data from the early development of cultivations from domestic seed sources are now available. These experiments were planted in 1974 and 1976 as repeated, randomized block experiments and the location and design is shown in Table 2.

Table 2. Location and design of the Larix-experiments.

Exp. No.	Locality	Lat. N	Long. E	Alt. m	Number of repl.	Plants/ plot	Establ. year	Age of plants	Remarks
501/1	Pello, Ruuhijärvi	66°57'	24°36'	300	6	49	1974	1+1	
501/2	Rovaniemi, Hirvas	66°26'	25°13'	120	6	49	1974	1+1	
501/3	Simo, Ahmavaara 1)	66°05'	25°40'	100	6	49	1974	1+1	
	2)	66°05'	25°29'	150	6	49	1974	1+1	
501/4	Rovaniemi, Tiskivaara-	66°30'	25°04'	170	1	59-242	1974	1+1	
556/1	Simo, Yli-Kärppä	65°46'	25°42'	95	10	49	1976	1+1	Autumn plant
556/3	Kittilä, Kolvalehto	67°57'	25°22'	230	10	49	1976	1+1	"
556/4	Savukoski, Kesäyön-kuusikko	67°31'	27°43'	220	10	49	1976	1+1	"
556/5	Salla, Isomaa	66°39'	28°22'	300	10	49	1976	1+1	"

These experiments were assessed in 5 year intervals and the results are presented in Table 3 and Table 4.

As can be seen from Table 3 the survival had decreased somewhat through the years the mean being in 1979 = 66.1 % and in 1984 = 51.2 %. The variation between the different sites is not very high, neither the variation between seed sources with the exception of the provenances 1 Vuomanlehto and 15 Hannukkalanniemi.

The survival in the experiment No. 556 is a little lower than in the experiment No. 501 but the differences are not large except for the plantations 556/3 and 556/4 where a radical change seems to have taken place between 1980 and 1985. Both experiments are situated in the northern parts of the testing area and the site of experiment 556/4 is a very dense, cold, silty soil. It might well be, that although the plants have grown well at the beginning a combination of these soil conditions and a cold summer has been too much for most of the sources. The provenance Kolari, Aitamännikkö (6) is, however, an exception and is in both cases growing better.

In experiments 501 as well as in 556 the seed source Hausjärvi seed orchard No. 16 was included, and it is encouraging that its performance does not differ too much from the others.

In the experiments here described no comparisons were made with native species, but the same seed sources were partly used also in the species trials whose results are reported as a poster at this meeting. In these experiments the survival rate for larch is around the same as for Scots pine, in some cases a little better in some cases a little worse.

Table 3. Survival in the experiments No. 501/1 - 501/4, assessed in 1979 and 1984 except exp. 501/4 which was not measured in 1984.

Lot No.	Seed No.	Provenance	501/1 1979	501/1 1984	501/2 1979	501/2 1984	501/3 1979	501/3 1984	501/4 1979	$\bar{x}$ 501/1-4 1979	$\bar{x}$ 501/1-3 1984	Rank 1984
1	M29-70-90	Rovaniemi, Hirvas	64.0	51.4	73.7	60.4	46.7	34.8	82.0	66.6	48.8	16
2	M29-70-26	" , " , P6105	57.1	48.0	64.6	64.6	63.6	51.7	71.4	64.2	54.7	12
3	M29-70-27	" , (P.Nylander)	67.0	59.9	72.4	62.6	56.7	47.8	83.2	69.8	56.7	10
4	M29-70-28	" , Rautiosaari	63.6	42.9	62.8	49.1	46.2	28.7	-	57.5	40.2	19
5	M29-70-29	" , Maatalousoppilait.	60.2	58.2	60.5	50.2	51.7	48.3	79.6	63.0	52.2	13
6	M29-70-30	" , (P.Paakkolanvaara)	43.2	39.8	60.1	52.2	68.0	57.1	85.5	64.2	49.7	15
7	M29-70-31	Kittilä, hoitoalueen piha	77.2	68.7	81.2	71.6	70.8	65.0	57.6	71.7	68.4	2
8	M29-70-32	" , Alakylä	50.0	47.6	81.4	75.2	66.0	60.2	80.1	69.4	61.0	7
9	M29-70-33	Tervola, (Elsa Lumpus)	56.5	55.4	77.7	77.6	63.0	61.2	58.5	63.4	64.8	5
10	M29-70-34	Kemi, Liedakkala (Niemi Niem.)	40.5	24.8	80.3	54.8	61.6	41.5	13.6	48.9	40.4	18
11	M29-70-51	Kolari, Vuomanlehto	28.9	6.1	65.8	9.4	36.0	7.5	-	43.5	7.6	22
12	M29-70-86	" , Aitamännikkö	75.6	75.5	86.6	79.2	66.4	64.6	32.4	65.3	73.1	1
13	M29-70-88	Ylitornio, Vaarasaari	60.5	36.0	85.0	66.7	52.0	32.6	70.2	66.9	45.1	17
14	M29-70-91	" , Aavasaksa	61.6	55.4	87.8	79.6	54.3	53.6	88.6	73.1	62.8	6
15	M29-70-92	" , Hannukkalanniemi	46.9	17.4	68.5	20.1	47.5	6.8	-	54.3	14.7	21
16	M29-71-59	Rovaniemi, Hirvas	61.6	48.6	84.8	67.7	-	-	-	73.2	58.2	9
17	M29-71-60	" , Muurola	68.7	53.7	84.3	76.3	-	-	69.6	74.2	65.0	4
18	M29-71-61	Kemi, Törmä (E.& P.Vaahtola)	61.9	43.5	89.0	75.0	-	-	81.9	77.6	59.3	8
19	M29-71-62	" , Liedakkala (Niemi Niem.)	49.7	27.9	85.6	67.0	68.4	59.7	78.2	70.5	51.5	14
20	M29-71-63	Simo, Simonniemi	58.2	19.0	92.3	51.1	64.6	42.2	64.9	70.0	37.4	20
21	M29-71-64	Tervola, Saares	71.4	53.1	88.7	82.9	69.4	63.6	77.6	76.8	66.5	3
22	T3-71-sv16	Hausjärvi, seed orchard No.16	67.4	54.4	85.2	69.8	60.9	43.5	-	71.1	55.9	11
Mean of experiment, %			58.7	44.9	78.1	62.0	58.3	46.9	69.1	66.1	51.2	

Table 4. Survival in the experiments 556/1 - 556/5, assessed in 1980 and 1985.

Lot No.	Seed No.	Provenance	556/1 1980	556/1 1985	556/3 1980	556/3 1985	556/4 1980	556/4 1985	556/5 1980	556/5 1985	$\bar{x}$ 1980	$\bar{x}$ 1985	Rank 1985
1	T3-71-SV16	Hausjärvi, seed orchard No. 16	61.1	55.6	41.0	11.6	29.9	5.8	67.5	65.9	49.9	34.7	7
2	M29-70-26	Rovaniemi, Hirvas, P6105	65.3	63.3	60.8	27.2	51.0	14.9	85.4	83.1	65.6	47.1	2
3	M29-70-32	Kittilä, Alakylä	47.7	42.0	53.6	18.3	46.1	16.7	80.0	73.0	56.8	37.5	4
4	M29-71-62	Kemi, Liedakkala, (Niemi Niem.)	50.7	47.2	50.2	14.8	39.4	10.2	72.7	67.8	53.2	35.0	6
5	M29-71-64	Tervola, Saares	64.2	60.0	63.0	27.6	59.6	21.8	73.9	67.4	65.2	44.2	3
6	M29-70-86	Kolari, Aitamännikkö	53.4	50.0	64.2	52.9	67.8	45.0	85.2	79.4	67.6	56.8	1
7	M29-71-63	Simo, Simonniemi	62.8	54.5	58.1	17.5	43.4	8.2	73.2	61.1	59.4	35.3	5
8	M29-70-92	Ylitornio, Hannukkalanniemi	52.6	32.6	51.1	9.7	29.0	5.3	-	-	44.2	15.9	8
9	M24-70-50	Kuhmo	26.3	22.1	17.0	1.4	16.2	3.3	35.0	32.1	23.6	14.7	9
Mean of experiment, %			53.8	47.4	50.7	18.2	42.1	12.9	72.4	66.7	54.0	35.7	

In passing, it might be asked, could good results be obtained by using Scots pine from the same region as the larches? In Northern Finland I have only one experiment (No. 357 at Sotkamo, Loukka, Lat. 63°52' N, Long. 28°17' E, Alt. 300 m), where two eastern pine sources are included. The survival at age 8 years in this experiment is as follows:

Scots Pine	%
Sotkamo (local)	24.7
Ranua	64.1
Salla	54.6
Kuusamo	43.9
Enontekiö	43.2
Posio	37.1
Archangelsk obl. Cekujevo	28.3
Olonets obl. Zaonetzsk	8.0

Siberian larch	%
Kitee	45.9
Kemi	43.7

Norway spruce	%
Hyrynsalmi	69.4

Thus, it seems, that it is better to try only larch in transfers to the west in our conditions.

GROWTH AND YIELD

The general growth and yield of Siberian larch in Finland is well documented (Vuokila 1960). As in the case of the survival, comparative information about growth and yield in the north is difficult to extract from the oldest plantations. From the paper by Nevala (1980) we can

see that the total yield from a 67 year old stand in Kuusamo was 154 m^3 solid volume under bark.

In the paper by Lähde et al. mentioned earlier are reported the latest results from the Kivalo plots. From these might be quoted.

The height development of younger stands are recorded from the experiments No. 501 and 556 and are presented in Tables 5 and 6.

Origin/provenance	Age	Total yield overbark m^3/ha
Archangelsk area	52	162
Nishnij Tagilsk	50	100
Raivola	55	235
Raivola	36	85

Table 5. Mean height, cm, in the experiments No. 501/1 - 501/4, assessed in 1979 and 1984 except exp. 501/4 which was not measured in 1984.

Lot No.	Seed No.	Provenance	501/1		501/2		501/3		501/4	$\bar{x}$ 501/1-4	$\bar{x}$ 501/1-3	Rank
			1979	1984	1979	1984	1979	1984	1979	1979	1984	
1	M29-70-90	Rovaniemi, Hirvas	44.3	108.5	79.7	153.4	58.0	176.2	68.2	62.5	146.0	10
2	M29-70-26	" , " , P6105	48.8	127.0	64.9	150,0	64.2	196.2	65.0	60.7	157.7	3
3	M29-70-27	" , (P.Nylander)	45.7	101.5	68.9	119.1	54.2	152.2	62.1	57.7	124.3	20
4	M29-70-28	" , Rautiosaari	38.3	93.4	67.0	140.0	53.4	149.7	-	52.9	127.7	19
5	M29-70-29	" , Maatalousoppilait.	48.0	128.6	63.7	125.7	59.2	184.6	63.6	58.6	146.3	9
6	M29-70-30	" , (P.Paakkolanvaara)	41.5	103.5	72.9	165.0	62.2	198.2	59.5	59.0	155.5	5
7	M29-70-31	Kittilä, hoitoalueen piha	45.8	119.5	79.1	151.6	68.0	214.9	58.0	62.7	162.0	2
8	M29-70-32	" , Alakylä	48.5	125.0	71.5	145.8	58.1	180.4	53.9	60.0	150.4	7
9	M29-70-33	Tervola, (Elsa Lumpus)	39.2	112.4	75.8	152.7	64.9	190.3	42.8	55.7	151.8	6
10	M29-70-34	Kemi, Liedakkala (Niemi Niem.)	32.9	92.1	72.1	126.1	53.0	184.7	48.6	51.6	134.3	18
11	M29-70-51	Kolari, Vuomanlehto	46.4	115.6	66.3	150.6	51.4	163.0	-	54.7	143.0	12
12	M29-70-86	" , Aitamännikkö	41.8	105.7	71.0	140.6	59.4	184.5	55.7	56.9	143.6	11
13	M29-70-88	Ylitornio, Vaarasaari	38.2	80.3	70.8	134.6	51.0	138.1	49.3	52.3	117.6	22
14	M29-70-91	" , Aavasaksa	40.2	99.9	75.6	142.6	58.4	171.8	45.7	55.0	138.1	15
15	M29-70-92	" , Hannukkalanniemi	38.6	96.6	58.9	122.6	53.7	184.4	-	50.4	134.5	17
16	M29-71-59	Rovaniemi, Hirvas	52.3	145.4	78.6	148.6	-	-	-	65.4	147.0	8
17	M29-71-60	" , Muurola	46.7	113.6	82.5	156.0	-	-	53.3	60.8	134.8	16
18	M29-71-61	Kemi, Törmä (E.& P.Vaahtola)	40.1	93.5	78.4	151.1	-	-	53.2	57.2	122.3	21
19	M29-71-62	" , Liedakkala (Niemi Niem.)	38.0	109.4	73.6	120.2	55.6	189.1	46.7	53.5	139.5	13
20	M29-71-63	Simo, Simonniemi	40.3	85.5	77.3	125.8	61.0	205.5	59.0	59.4	138.9	14
21	M29-71-64	Tervola, Saares	46.5	106.0	82.4	149.8	62.6	211.0	66.9	64.6	155.6	4
22	T3-71-sv16	Hausjärvi, seed orchard No.16	48.5	112.8	83.7	155.6	70.7	259.5	-	67.6	175.9	1
Mean of experiment, %			43.3	108.2	73.4	142.2	58.7	183.9	56.0	58.1	143.0	

Table 6. Mean height, cm. in the experiments 556/1 - 556/5, assessed in 1980 and 1985.

Lot No.	Seed No.	Provenance	556/1		556/3		556/4		556/5		$\bar{x}$	$\bar{x}$	Rank
			1980	1985	1980	1985	1980	1985	1980	1985	1980	1985	1985
1	T3-71-SV16	Hausjärvi, seed orchard No. 16	70.9	138.6	37.1	85.3	27.4	40.7	60.3	202.6	48.9	116.8	3
2	M29-70-26	Rovaniemi, Hirvas, P6105	75.6	156.5	43.8	67.9	29.1	50.9	61.7	208.2	52.5	120.9	1
3	M29-70-32	Kittilä, Alakylä	61.7	120.3	43.7	86.4	29.8	44.3	56.3	170.8	47.9	105.4	5
4	M29-71-62	Kemi, Liedakkala, (Niemi Niem.)	52.0	109.9	28.8	59.0	21.9	27.2	51.2	168.3	38.4	91.1	7
5	M29-71-64	Tervola, Saares	64.7	146.7	36.6	87.2	28.1	44.7	53.7	188.6	45.8	116.8	3
6	M29-70-86	Kolari, Aitamännikkö	58.6	139.8	38.7	90.3	28.3	64.1	58.7	186.9	46.1	120.3	2
7	M29-71-63	Simo, Simonniemi	61.9	135.4	38.7	80.0	25.8	37.8	52.2	167.0	44.6	105.1	6
8	M29-70-92	Ylitornio, Hannukkalanniemi	58.1	109.9	38.5	68.6	24.4	26.9	-	-	40.3	68.5	8
9	M24-70-50	Kuhmo	70.3	142.9	37.2	93.9	27.4	50.3	47.9	166.8	45.7	113.5	4
Mean of experiment, cm			63.8	133.4	38.2	79.8	26.9	43.0	55.3	182.4	45.6	106.5	

As can be seen the height development is well as in all provenances.

It might be noted, that the height of the seed orchard source in both experiments is fairly good.

If we again refer to the poster the height growth has been compared for larch and Scots pine and mean height 19 in the latest measurements very much the same. Why the superiority in height of the larch at young age is now disappearing is not yet clear.

A look at the damages by climate diseases and pests is therefore necessary.

DAMAGES DISEASES AND PESTS

Generally speaking, the Siberian larch has in Finland been free from climatic damages. Not even the spring frost, which has prevented the cultivation of this species in Central and Western Europe has damaged the vegetative growth. The generative development, on the other hand, is frequently disturbed, and damaged meiosis and frozen flowers are in many cases the cause of poor seed production.

But in recent years, when the cultivation of the Siberian larch has extended further north, reports increase about frost damage on the leading shoots. In this case, it is the question of early frost in the autumn or early winter. This is a sign of poor adaptation to the length of the growing period and must be further studied in all provenances. If the top shoot is repeatedly cut back by frost it is understandable that the height growth will suffer.

The diseases and pests of Siberian larch are well known (Rozhkov 1970) but very few diseases have been recorded in Finland and none of them have been serious.

Of the pests, there were in the earlier reports observation of damage by the aphid *Adelges laricis* Vallot and epidemics of this insect could be dangerous for the development of larch stands. In recent times, this pest seems to be increasing again in young larch plantations. A close look should therefore be kept on the situation and preventive measures taken, when necessary.

More damage has been caused by vertebrates. The elk has damaged stems and shoots in many cultures and, especially in the older days, the plantations and sowings were damaged by reindeer.

A particular pest is the vole who in certain years can make great damage. In the winter 1978 - 79 the voles killed 96 % of the plants in the experiment 556/2 belonging to the series here discussed.

Also the hare has been found to eat young plants in the winter time.

There are up to now no observations about possible differences between the seed sources as far as diseases and pests are concerned.

SILVICULTURE

Too many studies have not been made about the silvicultural aspects of larch cultivation. In the oldest days plantation as well as sowing were used, but lack of seed and the improvement of the nursery techniques have in recent years led to the almost exclusive use of planting.

In my experience the planting of 1 + 1 or 1 + 1 + 1 stock is better than 2 + 0 or 1 + 2, that is, the rapid development of the larch roots has to be checked by frequent transplantation.

When growing containerized plants care should be taken to protect the roots well with snow or other means. As mentioned earlier, a severe winter cold may cause damages on unprotected seedlings.

In some cases the method of sowing might have advantages and experiment has recently been laid out at the Toivoniemi research station as a co-operation between Helsinki University and the Forest Research Institute.

Plantation in the autumn has been successful in our experiment No. 556 and this method should perhaps be more frequently used.

Russian experts have told me that also sowing in the late autumn might give a beneficial seed stratification and a good start in the spring. When more seeds are available this should be tried.

Most of the plantations in Northern Finland have been established as pure larch stands at a fairly wide spacing. It is well known that the crown of the larch is sensitive to stand density and that larch stands should be kept light by frequent thinnings.

One might, however, consider, whether or not in the north the larch could be used also in mixed cultivations, as a speculation one could think of coppice with standards together with *Betula tortuosa*.

Great care should be taken in selection of the right site for the Siberian larch cultures. The larch is a tree of the good slopes where aeration and water flow are suiTable for its root system. It does not grow on silty soils, neither on swamps. It will not grow satisfactory on poor sites and is thus not an alternative to pine on very dry and poor soils.

For difficult soil conditions we have, perhaps, to look at other larches.

OTHER SPECIES OF LARCH

The other species of larch have been grown in the north on a very limited scale, and most of the cultures have been single trees around schools, in parks and cemeteries.

Larix decidua Mill. seems to grow fairly well where it occurs in the southern parts of the area. Big trees of unknown origin can be seen in the parks of the city of Oulu and at the Hirvas Forest School near Rovaniemi there is at least one good tree. A good young plantation, provenance Kitee, will be seen at Kivalo during the excursion. European larch might also have been planted in the Tornio river valley but the species has not been checked, so far.

In 1912 there were planted 5 plants of European larch and 50 plants of Siberian larch as far north as at Järvenpää, north of the lake Inari (Anon. 1917). Turtiainen (1969) reported that more than 20 trees were still growing but did not specify which species.

Larix gmelini var. *japonica (*Maxim. ex Regel) Pilg. has also been planted as an ornamental at the forestry school at Hirvas. One tree has been recorded in the Swedish city of Haparanda on the Swedish/Finnish border (Julin 1959). A small plantation was made in the 1950's at Kivalo.

Recently a small seed lot was obtained from a very northern source at Magadan in the Soviet Union, Lat. 59°38' N, Long. 151°50' E. This origin which might represent the species *Larix gmelinii* Rupr. the true Dahurian larch, has been planted in the forest limit experiments at Utsjoki in 1980. The survival of these plants after three seasons in the field in the autumn of 1982, was 89,5 %.

The Kurilean and maybe Dahurian larches should perhaps be tried on swamp soils where they seem to occur in their natural area (see e.g. Luukkanen 1977). If northern origins from Kamchatka or from the Magadan region could be obtained it could be an alternative at least in the Oulu region and, perhaps, in southernmost Lapland where bogs of this type are common.

So far the only larch species tried on swamp soils is the tamarack, *Larix laricina* (Du Roi) R. Koch. Also for these species the experiences are very limited.

At the Kolari research station there is a tamarack plantation from seeds obtained from Fairbanks, Alaska which has been growing quite well and has not in the beginning been attacked by voles. In another experiment with several origins from Alaska at the same place vole damage has occurred.

In the Utsjoki trials there are two origins from Alberta and Saskatchewan which, after three years, had survived 93.8 % and 96.9 % respectively.

The tamarack plantations are too young for a judgement of the-possibilities of this species, but it is one of the larches for which much more trials with northern seed sources should be planted.

Larch hybrids have not at all been tried in the northern parts of Finland but have given good results in the south. It might be considered if hybrids between Siberian and European larch should be tried in the best climate and perhaps also the hybrid between Siberian and Kurilean larch on swamp soils.

Of provenance hybrids we have no results in the north and also in the south the experiences are limited. A cross made between trees from Pinega and trees from Nishni Tagilsk did not show heterosis compared with the pure provenances. More southern provenances have not been tried yet.

CONCLUSIONS

On the basis of experiences hitherto, it may be concluded that the Siberian larch is a promising exotic for cultivation in the northern parts of Finland.

Great attention must be paid to the use of the right seed sources. Results, so far obtained, indicate that the origins from the western parts of the species' range are to be preferred. Further experiments with northern sources, e.g. Mesen, Petchora etc., should be established, could only seed samples be obtained.

Local seed sources from old plantations can be used, but the results given should be observed. Seed orchards with plus tree material from the northern cultures should be, and in fact are, established.

On the right site and with the right origin the yield of Siberian larch might be of the same magnitude or slightly better than the yield of Scots pine. Comparisons with other exotics must wait.

These conclusions are very similar to those of Edlund (1966). Future activities should concentrate on breeding Siberian larch further, on provenance trials with tamarack and on limited experiments with other larch species and hybrids in the southern parts.

LITERATURE CITED

Anon. 1917. Metsähallituksen kertomus kruunun metsätaloudesta, metsänvartijakoulujen toiminnasta sekä metsänhoidon edistymisestä sotilas-, siviili- ja kirkollisvirkataloilla vuonna 1913. Suomen virallinen Tilasto. 17: 1-487.

Arnborg, T. & Edlund, E. 1962. Lärkskogar i Sibirien, rapport från en resa 1960. Norrlands Skogsvårdsförbunds Tidskrift 1962(1): 1-111.

Blomqvist. A G. 1877. Om läkträdet. Tidskrift for Skogshushållning, 5: 33-46.

— 1887. Iakttagelser angående sibiriska läkträdet, pichtagranen och cembratallen i deras hemland samt om forstliga förhållanden därstädes. Finska Forstföreningens Meddelanden. 5: 149-181.

— 1893. Hvilken erfarenhet finnes angående lämpligaste sättet for lärkträdets odling i Finland och huru kunde denna erfarenhet tillgodogöras vid de lärkträdskulturer som äro afsedda att utföras i landets kronoskogar? Finska Forstföreningens Meddelanden . 11: 52-55.

Bobrov, E.G. 1972. Istorija i sistematika listvennic. Komarovskie ctenija. 25: 1-96.

Cajander, A.K. 1901. Siperialaisen lehtikuusen (Larix sibirica Led.) länsirajasta. Meddelanden af Societatis pro Fauna et Flora Fennica. 27: 24-34.

Drobov, V.K. 1914. Voprosu o proizrastanii sibirskoj listvenicy b predjelah Olonecskoj gubernii. Isvestija Obščestva izučenija Oloneckoj gubernii. 3(3): 113-129.

Dylis, N.V. 1947. Sibirskaja listvennica. Summary: Siberian larch. Materiali k posnanijo fauni i flori SSSR.N.S. Botanitjeskii 2(X): 1-137.

Edlund, E. 1966. Den sibiriska lärken i Norrland och Dalarna som skogsträd och industriråvara. Sveriges Skogs- vårdsförbunds Tidskrift. 461-560.

Granit, A.W. 1936. Den sibiriska lärken i Finland. Forstlig Tidsskrift, 53(3): 58-60.

Heikinheimo, O. 1956. Tuloksia ulkomaisten puulajien viljelystä Suomessa. Referat: Ergebnisse von einigen Anbauversuchen mit fremdländischen Holzarten in Finnland. Communicationes Instituti Forestalis Fenniae. 46(3): 1-129.

Hemberg, E. 1877. Rysslands skogstyper. En skogsbotanisk skiss. IV. De sibiriska barrträdens gebit. Tidskrift for Skogshushållning. 5: 193-203.

— 1899. Sibiriska lärkträdet. Tidskrift for Skogshushållning. 1899(2): 33-106.

Iljinskij, A.P. 1929. Metod i zadači izučenija geografičeskogo rasprostanenija drebesnih porod v SSSR. Summary: Problems and methods of the study of the geographical distribution of the trees in the USSR. Bulletin of Applied Botany, of Genetics and Plant-Breeding. 21(3): 3-46.

Ilvessalo, L. 1916. Lehtikuusiviljelys Suomessa. Suomen Metsänhoitoyhdistyksen Julkaisuja. Erikoistutkimuksia. 5: 1-103.

— 1923. Raivolan lehtikuusimetsä. Referat: Der Lärchenwald bei Raivola. Communicationes ex Institutum Questiones Forestalium Finlandiae editae. 5: 1-101.

Julin, L. 1959. Träd och buskar i Haparanda. Lustgården. 39-40: 89-124.

Kuznecov, N.I. 1927. Jugo-zapadnaja južnaja i jugovostočnaja granicu rasprostanenija listvennicy (Larix sibirica Ledeb.) v Europejskoj Rossii. Jobile-

jnyj Sbornik posbjaščennyj I.P. Borodinu. Leningrad. 251-256.

Köppen, Fr. Th. 1889. Geographische Verbreitung der Holzgewächse des europäischen Russlands und des Kaukasus. Zweiter Teil. Beiträge zur Kenntnis des Russischen Reiches und der angrenzenden Länder Asiens. 3 Folge. 6: 489-509.

Linnaeus, C. 1754. Carl Linnaei Tankar om nyttiga växters planterande på de Lappska fjällen. Kunggliga Svenska Vetenskaps-Akademiens Handlingar.15: 182-189.

Luukkanen, O. 1977. Tutkimusmatkailijana Amurinmaalla III. Bogorodskoje -Sofijsk. Dendrologian Seuran Tiedotuksia. 8: 23-34.

Lähde, E., Werren, M., Etholén, K. & Silander, V. 1984. Ulkomaisten havupuulajien varttuneista viljelmistä Suomessa. Summary: Older forest trials of exotic conifer species in Finland. Communicationes Instituti Forestalis Fenniae. 125: 1-87.

Melehov, I.S., Čertobskoj, V.G. & Moiseev, N.A. 1966. Ljesa Arhangelskoj i Vologodskoj oblastej. Ljesa SSSR, 1. Moskva, Izdatelstvo Nauka. 78-156.

Mezger, C. 1935. Zur Kenntnis der sibirischen Lärche. Forstliche Wochenzeitschrift Silva. 23: 209-216, 217-224.

Nevala, S. 1980. Lehtikuusen menestyminen Lapissa. Helsinki. Helsinki University, thesis for the B. For. degree, on file at the Institution for Silviculture. 1980. 56 p.

Nevrli, I. 1912. Lesa severa Evropejskoj Rossii. Isvestija Imperatorskago ljesnogo instituta. 22: 221-242.

Parvela, A.A. 1930. Oulun läänin viljelyskasvit, niiden historia ja nykyinen levinneisyys. Referat: Über die Kulturpflanzen in Län Oulu (Uleåborg), ihre Geschichte und Verbreitung, Annales Societatis Zoolog. - Botanicae Fennicae Vanamo, 13(1): 1-354.

— 1932. Oulun läänin viljelyskasvit, niiden historia ja nykyinen levinneisyys. II. Erikoisosa. Deutsches Referat: Über die Kulturpflanzen in Län Oulu (Uleåborg), ihre Geschichte und Verbreitung. II. Spezieller Teil. Annales Botanici Societatis Vanamo. 2(5): 1-144.

Reuter, E. 1918. Lehtikuusikokeilut Tornionjokivarrella. Metsätaloudellinen Aikakauskirja. 35(10): 294-297.

Rozhkov, A.S. 1970. ed. Pests of Siberian Larch. Jerusalem, Israel Program for Scientific Translation; 1970. 393 p.

Schotte, G. 1917. Lärken och dess betyydelse for svensk skogshushållning. Meddelanden från Statens Skogsförsöksanstalt. 13-14, 539-840.

Simak, M. 1979. Larix sukaczewii: naturlig utbredning, biologi, ekologi och fröanskaffningsproblem. Sveriges Lantbruksuniversitet, Institutionen för Skogsskötsel, Rapporter. 1: 1-76.

Tammelander, K. 1914. Ulkomaalaisia, meillä viihtyviä havupuita. Metsätaloudellinen Aikakauskirja 1914(1): 14-21.

Tigerstedt, P.M.A., Pohtila, E. & Nevala, S. 1983. Lehtikuusestako Lapin puulaji. In: Kortesharju, J., ed. Uutta ilmettä Lapin kasvivarojen käytossä. Research Institute of Northern Finland, University of Oulu. C 47: 46-55.

Timofejev, V.P. 1961. Rol listvennici v podnjatii produktivnosti ljesov. Moskva, Isdatelstvo Akad. Nauk SSSR; 1961. 159 p.

Tolskij, A.P. 1938. Analiz klimatičeskih uslovij; proizrastanija sibirskoj listvennicu. Trudy po selskohazjaistvennoj meteorologii. 25: 133-175.

Tovstoljes, D.I. 1916. Hod rosta sibirskoi listvennici po izsljedovanijo b Permskoj i Kostromskoj guvernijah. Sbornik statlej po ljesnomu hazjajctvu v čest 25-ljetnei djejatelnocti prof. M.M. Orlova. Petrograd. 33-64.

Turtiainen, M. 1969. Lehtikuusiko Lapin puulaji? Metsä ja Puu. 1969(4): 6.

Vuokila, Y. 1960. Siperialaisten lehtikuusikoiden kehityksestä ja merkityksestä maamme metsätaloudessa. Summary: On the development of Siberian larch stands and their importance to forestry in Finland. Communicationes Instituti Forestalis Fenniae 52(5): 1-111.

RESEARCH ON LARIX LARICINA IN SWEDEN

Milan Simak and Evert Jeansson

ABSTRACT: Seventy sources of tamarack (*Larix laricina*) from Canada and the USA were analysed in different experiments in Sweden. Seed weight increases from the western to the eastern part of the American continent. Tamarack showed very sensitive reactions to photoperiod and to inter-mittent light, which can be used in practice when growing seedlings in greenhouse. A series of 12 provenance trials was laid out in Sweden between lat. 55°35' and 65°05'N. In general, tamarack provenances can be planted in Sweden 7-8 degrees more towards the north than what is the latitude of its origin. The maximum survival coincides rather well with the maximum growth. Different types of damage to tamarack occurring on these experiment plots were discussed.

INTRODUCTION

Tamarack, *Larix laricina* (Du Roi) R. Koch, occurs naturally in the whole of Canada with the exception of large parts of B.C., Yukon, the southern parts of Alberta, Saskatchewan, and the northernmost parts of Canada. It also grows in the USA around the Great Lakes and in Alaska.

This is an area roughly limited by longitudes 53° - 150°W and latitudes 40° - 68°N. In the western parts of its natural range, it ascends to elevations of 500 m and in the eastern part up to 1 200 m. It occupies all types of soils but usually swampy lands, etc. where the competition with other tree species is not so hard. Tamarack frequently grows with one or more associates, the most common ones are black spruce, northern white-cedar, balsam fir, paper birch, quaking aspen, eastern white pine, red maple, black ash, white spruce and American elm. Associates vary geographically and according to site conditions (Rudolf 1966).

Tamarack was regarded for a long time as a less interesting species in American forestry. Only in recent years the foresters became more aware of this larch which on well-drained sites shows the fastest juvenile growth among the boreal Conifers growing on similar sites (Mac Gillivray 1962, Johnston 1973, Mead 1978). Several provenance experiments with tamarack have been started during the last decennia both in Canada and the USA (Pauley 1965, Sajdak 1970, Jeffers 1975, Cech, Keys and Weingartner 1977). Recently, also a breeding strategy was proposed by Park Fowler (1982) and Simpson (1983).

In Sweden the interest in tamarack awoke in earnest about 30 years ago, principally because of its fast growth at young age and the great tolerance to growing on swampy soil types where it is difficult to grow other tree species. On these types of soils tamarack can be at least a good pioneer tree paving the way for planting other species later on. For the short rotation programme of conifers, tamarack seems to be a very good candidate both with regard to its fast growth and its good wood properties. Moreover, tamarack with its wide ecological adaptability is a suitable partner to be crossed with other better growing larch species, since the hybrids may show a better growth and survival than the parent trees (cf. Mac Gillivray 1967, 1968, Riemenschneider and Nienstaedt 1983). Especially hybrids with Siberian or Dahurian larch could be useful as alternative tree species for many sites in northern Sweden. These were some of the reasons why a series of different experiments was started with tamarack at the Swedish College of Forestry. Four groups of

MILAN SIMAK, professor, Head of Seed laboratory, and EVERT JEANSSON, researcher in natural regeneration, both at Sw. Univ. of Agr. Sci., Dept of Silviculture, S 901 83 UMEÅ, Sweden.

Table 1. Seed sources used in the experiment.

P no	Ex no	State	County	Lat. N o '	Long. W o '	Alt. m	1000 seed weight g. Fill.	Empty	Empt. %	Coll. Y.
1	11	ALASKA	TANANA RIVER	65 00	147 30	150	1.15	.	21	71
2	118	N.W.T.		58 58	111 40	229	.	.	41	64
3	110	ALBERTA	WATERWAYS	56 39	111 14	335	1.61	0.68	30	64
4	7	B.C.	FORT ST. JOHN	56 38	120 35	732	1.87	.	2	68
5	12	SASKATCHEWAN	BUFFALO NARROWS	56 05	108 55	427	2.13	.	.	71
6	109	MANITOBA	THE PAS	53 55	101 15	260	1.55	0.79	41	64
7	13	SASKATCHEWAN	MEADOW LAKE	53 50	108 40	640	1.84	.	1	.
8	1	ALBERTA		51 00	101 00	740	1.66	.	0	69
9	117	MANITOBA	WINNIPEG	50 05	95 25	229	2.05	0.92	24	64
10	132	ONTARIO	GURNEY TWP	49 30	82 14	213	1.82	0.85	75	64
11	3	QUEBEC	CHAGEL	48 55	79 03	290	2.19	.	30	70
12	16	QUEBEC	PREISSAC	48 30	78 15	.	2.18	.	.	.
13	4	QUEBEC	ROBERVAL	48 26	72 16	336	2.47	.	30	70
14	23	QUEBEC	ROBERVAL	48 26	72 16	.	2.47	.	6	70
15	116	MICHIGAN	ISLE ROYALE	48 05	88 42	186	.	.	89	64
16	112	MINNESOTA	ST. LOUIS	48 02	91 37	397	1.89	0.94	47	64
17	5	QUEBEC	PREISSAC	48 01	78 17	321	.	.	1	70
18	20	QUEBEC	GUERIN	47 45	79 20	.	2.19	.	1	.
19	17	QUEBEC	LAKE LORTIE	47 40	74 15	.	2.28	.	5	.
20	6	QUEBEC	SEIGN D.L.MALBAIE	47 40	70 20	244	1.58	.	35	70
21	21	QUEBEC	CABANO	47 39	68 57	.	2.30	.	.	.
22	2	QUEBEC	CABANO	47 39	68 57	244	2.29	.	16	70
23	158	MINNESOTA	ITASCA	47 31	94 05	396	1.64	0.83	59	64
24	15	QUEBEC	LA MALBAIE	47 20	70 20	.	2.27	.	.	.
25	103	MINNESOTA	ITASCA	47 07	93 20	389	1.55	0.73	63	64
26	128	MICHIGAN	HOUGHTON	47 01	88 25	201	2.16	0.92	30	64
27	101	MINNESOTA	ST.LOUIS	47 00	93 00	387	1.81	0.71	27	64
28	18	QUEBEC	RADNOR	46 45	72 50	.	2.43	.	.	.
29	102	MINNESOTA	CARLTON	46 42	92 31	335	2.29	0.92	46	64
30	9	NOVA SCOTIA	CHIGNECTO	46 35	64 25	80	.	.	.	.
31	22	QUEBEC	LANGEVIN	46 21	70 22	.	2.39	.	.	.
32	120	MICHIGAN	ALGER	46 21	86 20	244	1.83	0.87	24	64
33	153	MICHIGAN	ALGER	46 20	86 20	244	2.07	0.91	59	64
34	154	MICHIGAN	ALGER	46 20	86 20	244	1.95	0.94	37	64
35	122	MICHIGAN	CHIPPEWA	46 19	84 14	183	1.95	0.94	31	64
36	160	MICHIGAN	GOGEBIC	46 15	89 10	488	1.87	0.79	59	64
37	14	QUEBEC	BERTHIER PARTAGE	46 15	73 15	.	2.18	.	.	.
38	19	QUEBEC	LAKE CHERTSEY	46 11	73 52	.	2.21	.	2	.
39	10	NOVA SCOTIA	BEDDECK	46 07	59 45	30	.	.	.	.
40	8	NEW BRUNSWICK	ACADIA FOREST	46 00	66 20	98	2.36	.	.	.
41	124	ONTARIO		46 00	77 26	146	1.99	0.87	76	64
42	151	WISCONSIN	FOREST	45 48	88 56	457	1.60	0.91	59	64
43	152	WISCONSIN	ONEIDA	45 46	89 12	366	1.40	0.95	46	64
44	127	MAINE	SOMERSET	45 38	70 16	362	2.35	0.96	35	64
45	100	MINNESOTA	ANOKA	45 10	93 05	244	2.00	0.93	76	64
46	125	VERMONT	FRANKLIN	44 57	73 05	70	2.22	0.97	86	64
47	131	NOVA SCOTIA	ANNAPOLIS	44 48	65 03	229	2.36	0.96	56	64
48	119	WISCONSIN	SHAWANO	44 38	88 27	235	2.00	0.86	83	64
49	114	VERMONT	LAMOILLE	44 30	72 37	229	2.31	1.02	29	64
50	118	MAINE	MT. DESART IS.	44 30	68 00	30	2.14	1.02	41	64
51	155	MICHIGAN	WEXFORD	44 15	85 31	393	1.36	0.87	70	64
52	156	MICHIGAN	WEXFORD	44 14	85 32	396	1.58	0.85	90	64
53	121	MICHIGAN	WEXFORD	44 13	85 30	393	2.09	1.06	23	64
54	111	WISCONSIN	TREMPEALEAU	44 09	91 28	224	1.97	0.93	68	64
55	157	WISCONSIN	LACROSSE	43 51	91 08	206	2.36	1.00	53	64
56	129	ONTARIO	OXFORD	43 13	80 35	297	2.19	0.92	51	64
57	113	MICHIGAN	LIVINSTON	42 30	83 30	274	1.73	0.80	68	64
58	145	MICHIGAN	LIVINGSTON	42 30	84 20	244	1.87	1.04	81	64
59	147	MICHIGAN	LIVINGSTON	42 29	84 20	244	1.88	0.83	62	64
60	148	MICHIGAN	LIVINGSTON	42 29	84 20	244	2.13	0.96	87	64
61	149	MICHIGAN	INGHAM	42 28	84 50	244	2.23	1.15	81	64
62	130	ILLINOIS	LAKE	42 27	88 02	244	2.38	0.89	62	64
63	146	MICHIGAN	LIVINGSTON	42 27	84 25	244	2.02	0.91	82	64
64	115	MICHIGAN	KALAMAZOO	42 23	85 22	256	1.92	0.94	64	64
65	133	CONNECTICUT	LITCHFIELD	41 51	73 16	439	1.67	1.07	96	64
66	126	PENNSYLVANIA	LACKAWANNA	41 15	75 39	598	2.58	1.16	82	64
67	105	MARYLAND	GARRETT	39 42	78 56	820	2.22	1.01	80	62
68	106	MARYLAND	GARRETT	39 42	78 56	820	1.98	0.87	77	62
69	161	B.C.	.	. .	. .	.	1.28	0.57	66	.

P no = Provenance number Ex no = Suppliers number

experiments are reported here: I Seed analyses, II Nursery research, III Provenance research, and IV Damage to tamarack.




Figure 1. Weight of 1 000 filled seeds for provenances of Larix laricina gathered in latitude and longitude groups. Each latitude group comprises 2 lat.degr. Longitude group 1 = 58-73; 2 = 73-83; 3 = 83-93; 4 = 93-148. Figures above the columns indicate number of sources analysed within the respective latitude group.

I Seed analyses

Material and methods: Seeds to the provenance trials were supplied by different forestry organizations in Canada and the USA. Most of the seeds were received by courtesy from Prof. Pauley, Minnesota, USA (Ex. Nos. 100-161 in Table 1). The same material was used in several provenance trials in the USA (Pauley 1965, Jeffers 1975). The material originates from a very wide area limited by the latitudes 39°42' N and 65°00' N and by the longitudes 59°45 W and 147°00 W. The latitudinal range of the seed sources would correspond to approximately the distance between Skellefteå (Sweden) and the southern part of Albania. Although nearly 70 seed sources were represented totally, the material does not cover satisfactorily the whole range of natural distribution of tamarack, because some areas, especially those in the northern regions, were difficult to reach for cone collection. Thus, only 5 provenances of the totally 69 originate from latitudes passing the Scandinavian peninsula. The cones were collected in autochthonous stands according to the information received from the suppliers.

Result: The technical quality of the seeds was studied at our laboratory. Some of the results of these analyses can be of interest to be presented here. This species has the smallest seeds among all larch species. The average weight of 1 000 pure seeds rarely exceeds 2 grams. Filled seeds were separated from empty ones in most of the samples by the aid of x-radiography and the thousand-grain weight of each fraction and sample was determined. The average weight of 1 000 filled seeds for all the investigated sources was 2 grams and it varies between 1.15 and 2.58 grams. The weight of the empty seeds constitutes about 46 % of that of filled seeds. The mean frequency of empty seeds in the samples Ex. 100-161 was 58 % (23-96 %). Not all samples were included in this analysis, since empty seeds had been removed from some of the samples by the suppliers. The average weight of filled seeds shows a tendency to increase with decreasing longitudes, i.e. from West to East of the American continent and in western America possibly also with decreasing latitudes (Fig. 1). The material is too scanty to be the subject of a detailed statistical analysis in this respect. The radiographic analyses also showed some insect infestation in some of the sources. The seeds had a good anatomical development, even those from the northernmost latitudes (P 1) and from the highest latitudes (P 67-68). The radiographic image of tamarack seeds is characteristic, as the coat in the micropylar end is characteristically pointed.

Discussion: According to earlier investigations, the frequency of empty seeds in tamarack varies between 15 and 90 % (Duncan 1954, Hall 1981). The mean frequency of empty seeds in the present material is 58 %, and a removal of those improductive seeds would be necessary in rational plant production. The relatively big difference in weight between filled and empty seeds (about 2:1) makes it easy to remove empty seeds from a seed lot by

aspirator or by flotation in absolute alcohol, as has been shown by x-radiographic test. Interesting is the increasing seed weight in tamarack provenances in the direction from west to east in the natural distribution range of this species.

Table 2. Larix laricina plots laid out 1973-1974 in Sweden.

Plot No.	Locality	Long. W	Lat. N	Alt. m	Area m^2	Planted year	No. of provenances 1/ L.l.	P.s.	P.a.	B.v.	Exp. 2/ type	No. of plants/ prov.
1901	Svevekull	14°08'	55°35'	80	3600	1973	53	1	1	2	PP	30
1902	Svevekull	14°08'	55°35'	80	2451	1973	54	1	1	1	D	-
1903	Svevekull	14°08'	55°35'	80	1800	1974	20	-	-	-	LN	20
	Remningstorp											
1904	" Jonstorpsmossen	13°36'	58°28'	115	9000	1974	55	2	2	1	PP	40
1905	" Jonstorpsmossen	13°36'	58°28'	115	2500	1974	53	2	2	1	D	-
1906	" Jonstorpsmossen	13°36'	58°28'	115	2160	1974	20	-	-	-	LN	20
1907	" Storängen	13°37'	58°28'	125	4500	1974	45	2	2	1	PP	30
1908	" Storängen	13°37'	58°28'	125	2160	1974	20	-	-	-	LN	20
1909	Röskär	18°10'	59°25'	30	432	1974	20	-	-	-	LN	12
1910	Bärmyren, Håknäs	19°35'	63°32'	30	2200	1973	9	1	-	1	PP	50
1911	Bärmyren, Håknäs	19°35'	63°32'	30	1650	1973	9	1	-	1	PP	50
1912	Bärmyren, Håknäs	19°35'	63°32'	30	1452	1973	9	1	-	1	PP	33
1913	Bärmyren, Håknäs	19°35'	63°32'	30	2200	1973	9	1	-	1	PP	50
1914	Höglunda, Sörmjöle	19°57'	63°43'	50	9500	1973	10	1	1	1	PP	90
1915	Höglunda, Sörmjöle	19°57'	63°43'	50	9500	1973	10	1	1	1	PP	90
1916	Falträsk, Lycksele	18°30'	64°48'	250	5500	1973	9	1	1	1	PP	75
1917	Falträsk, Lycksele	18°30'	64°48'	250	500	1973	9	1	1	1	D	-
1918	Falträsk, Lycksele	18°30'	64°48'	250	480	1973	9	1	1	1	P	10
1919	Rökå, Malå	18°53'	65°02'	325	3360	1973	9	1	1	1	P	10
1920	Rökå, Malå	18°53'	65°02'	325	1440	1973	9	1	1	1	D	2
1924	Enafors	12°20'	63°18'	560	360	1974	20	-	-	-	LN	10
1925	Storbränna	20°45'	65°05'	205	1080	1974	20	-	-	-	LN	10
1926	Höglunda, Sörmjöle	19°57'	63°43'	65	520	1973	10	1	1	1	D	-

1/ L.l. = Larix laricina, P.s. = Pinus silvestris, P.a. = Picea abies, B.v. = Betula verrucosa
2/ PP = provenance plot, single tree parcel, LN = LN-treated plants, D = demonstration plots, rows

This direction corresponds to the way that tamarack wandered over the North-American continent after coming from Asia. *Larix decidua* (Simak 1967) shows similar clinal increase with the altitude from about 2.5 grams (Polish larch, about 300 m a.s.l.) to about 12 grams (Western Alpine larch, about 2 000 m a.s.l.). The increasing seed weight of these two larch species could be seen as an evolutionary young character that probably made it easier for the larch to occupy new territories. Subject to the limited seed material from the marginal area of distribution, the anatomically always well developed seeds of tamarack indicate that the species is generatively well adapted as a pioneer tree for climatically harsh conditions. A comprehensive study on seed ecology of tamarack in interior Alaska was carried out by Brown (1983).

II Nursery research

Tamarack and the other larch species are known to be strictly adapted with their photoperiodic reactions to the latitudinal position of their origin. Therefore, with respect to the wide latitudinal distribution of the present provenance material (39°42' N - 65°00 N), it stands to reason that provenances from extreme northern and southern localities could suffer as to growth and survival if raised in one central nursery. Two nursery experiments have been carried out with the aim of finding out how to counteract such problems.

a) Long-night treatment (LN-treatment) in order to accelerate the maturation processes in one-year-old plants of the southern provenances.
b) Intermittent light treatment (IM-treatment) in order to break the long-night obstructive effect on the growth of the plants of the northern provenances.

Material and methods (LN-treatment): For the LN-treatment, seeds from 16 provenances (P: 1, 4, 5, 7, 8, 11, 12, 13, 17, 20, 22, 24, 30, 37, 39 and 40) originating from a latitudinal range between 46° and 65°N were selected. Though P 1 originated from a much more northerly latitude than the geographical location of the experimental nursery (65° resp. 59°N), it was used in the experiment, too, in order to study its reactions on LN-treatment. Seeds of each provenance were sown in rows on each of two blocks in a plastic greenhouse at Röskär (59°24'N) on April 1, 1972. Between August 13 and October 31 the plants in one of the blocks were covered by black plastic between 16°° and 08°° daily, i.e. they were kept in artificial darkness for 16 hours (in practice, the LN-treatment can be accomplished in 3-4 weeks). Plants on the other block that were not covered by plastic served as controls (C-treatment). In spring 1973 the one-year-old plants of both treatments were transplanted on the spot. In the spring of the next year the LN- and C-plants were set out on experimental plots on six different localities (plots 1903, 1906, 1908, 1909, 1924 and 1925, cf. Table 2).

Result (LN-treatment): The following observations were made on the plants in Röskär nursery and field (cf. Fig. 2). At the end of the first growing season in the nursery the total length of the treated plants was on an average 62 % of that of the C-plants. At that time, the LN-plants had finished their growth, set buds and lignified their shoots while C-plants were still active in growth. At the end of the first winter the C-plants were damaged by frost to 59 % of their total length while the LN-plants were in a very good condition and had higher survival than the C-plants. At the end of the second growing season, the LN-plants were about twice as high as the C-plants. As the covering experiment was performed only at the end of the first growing season, from the second growing season the LN-plants run as great risk of frost damage as the C-plants. In spite of this, three years after planting in the field the LN-plants of southern provenances in most cases still showed a better development and survival than the C-plants (Simak 1974 and 1977).




Figure 2. Comparison in mean height and frost damage between LN-treated and untreated plants of 16 provenances. LN-treatment was performed at the end of the first growing season at Röskärs nursery (Lat. 59°24'N).

The northernmost provenance (P 1) diverges from this general trend because it originates from 65° C, i.e. six degrees more northerly than the experimental nursery. C-plants of this provenance showed poor vigour, since they had to grow at a shorter day length than that in their natural habitat. Moreover, the condition of the LN-plants was still inferior to that of the C-plants because the short growing season in the nursery was additionally shortened by the covering. Northern provenances cultivated in a southern nursery require a prolonged photoperiod, otherwise they will finish their growing season too early. A prolonged photoperiod can be achieved by IM-treatment.

Tamarack plants of particular origin stop growing and start setting buds when the increasing night length in autumn exceeds the so-

called "critical night length". These reactions are genetically controlled. Nights longer than the critical night length can be split up by IM into two "short nights" to which the plants will then adjust their reactions as to two separate short nights, i.e. the plants will continue to grow and bud initiation does not occur. The length and intensity of IM vary for different species (Simak 1975, Ericsson and Simak 1977).

Material and methods (IM-treatment): The northernmost provenance, P 1 (65°N), was selected for IM experiment. Seeds were sown one by one in boxes in a plastic greenhouse at Röskär. The boxes with the plants were placed at five different distances from an artificial light source (Sylvania Grolux, VHO-WS 215 W) which was switched on automatically every night between $00.^{00}$ - $01.^{00}$ during the period July 18 -September 15. (In practice, one starts and finishes the IM-treatment at an earlier date than in this pilot study in order to get a longer growth period and well maturated plants before winter comes). Otherwise, the plants were exposed to the prevailing environmental conditions in the greenhouse. The light intensities of the IM at different distances from the light source were 1 000, 250, 110, 60, 40 lux. The control plants were grown under normal night conditions. After the IM treatment, bud development and height growth were determined for each plant.



IM-lux	1000	250	110	60	40	0
Mean height, cm	5.0 ±0.3871	4.6 ±0.4456	2.0 ±0.3195	1.9 ±0.0976	1.8 ±0.1204	1.1 ±0.0484
% seedlings with term. buds	5	8	33	87	70	97

Figure 3. Height of the plants and bud setting at the end of the IM-treatment at different light intensities.

Result (IM-treatment): A light intensity of about 300 lux during IM treatment was enough to nullify the inhibitory influence of the long night on plant growth. The height of the plants in the series 250 - 1 000 lux was four to five times that of the controls. The bud setting was effectively prevented by IM. Even the plants exposed to 40 lux were significantly taller than the control plants (Fig. 3). More details about this experiment in which also *Pinus sylvestris* and *Picea abies* were IM treated, are given by Simak (1975).

Discussion (LN- & IM-treatments): Our experiments with tamarack in the nursery showed that the untreated southernmost provenances grew late into the autumn and thus the most tardy plants within a provenance were damaged or eliminated by early frost. A new population of surviving plants with another genetic constitution than the original population was thus formed. Also the untreated northern provenance, P 1, showed very poor development in the southerly located nursery due to the less appropriate photoperiodicity. Of course, plant material raised like this is not suitable for a provenance experiment. The selection and treatment of plants during the first year in the nursery influence the plant growth and reactions during the following years and thus an interpretation of the results of the field experiments can point in the wrong direction. It is therefore desirable that a provenance test in the field is started with unbiassed plant material.

The nursery experiments described here showed that through LN- and IM-treatments plants of extremely southern and northern origin, respectively, can be conditioned to a level corresponding to the development they would reach if raised in their natural habitat. The LN-treated tamarack plants of southern origin, i.e. unselected and undamaged by frost, grew better than the controls, at least in the next three years after being planted in the field, thanks to their good initial condition and fast growth away from the hostile frost and competitive vegetation layer just above the ground surface (Fig. 4). Similarly, the negative effect of the short photoperiod on the development of P 1-



Figure 4. 1-1 plants of P 4. Left: An untreated plant; height 35 cm, ø at the root neck = 6.1 mm, ø at the base of the 2-year shoot = 2.4 mm. Right: An LN-treated plant; height = 74 cm, ø at the root neck = 6.8 mm, ø at the base of the 2-year shoot = 5.0 mm.

plants can be counteracted by the IM-treatment. The LN- and IM-treatments were carried out as pilot studies only on a limited material, since it was the first time in Sweden that these treatments were applied to forest tree plants under greenhouse conditions. At present both these methods are performed in Sweden by routine. Hence, the LN-method is used to produce seedlings in 2 - 3 turns within a growing season. The IM-method is applied in order to prevent terminal bud setting for greenhouse seedlings produced very early in the year when the still prevailing long nights outdoors would introduce dormancy to growing seedlings at cotyledon stage (Ericsson and Simak 1977). Consequently, treating all plants with LN or IM in a provenance project like this would be no problem. Of course, one could also desist from sowing seeds from sources of extreme photoperiodic reaction in a central nursery in order to avoid the described stress effects. However, raising a provenance material at different nurseries can cause other problems in this kind of experiments.

Tamarack plants are often set out in autumn, i.e. during the still progressing growing season. The success of the autumn planting is depending on many factors, particularly on the maturity of the plants. Larch provenances, even those ecologically fitted for Swedish conditions, can become sensitive to frost if taken up from the nursery bed early in autumn before they have reached full maturity. If set out in hostile field environment in the autumn such plants usually have no chance to accomplish the interrupted maturity processes before winter comes and will therefore suffer from frost. LN-treatment of plants intended for planting in the autumn would make them resistant to frost damage in the coming winter.

III Provenance research

Tamarack was occasionally planted In Sweden already at the end of the previous century (Schotte 1917). The first provenance trial was established in 1958 in southern Sweden by the National Board of Forestry in the province of Halland. The trial was discontinued at an early stage since the plants were heavily damaged by frost and noxious animals. In 1969 the same organization planted 12 provenances of tamarack at Egernahult (56°37'N) and 7 provenances at Åkulla 157°08'N). The results of both these trials were reported by Ahlberg and Johansson (1984). At the same time (1968) the Swedish College of Forestry (Department of Reforestation), Stockholm, planted as pilot study 3 plots in the vicinity of Simrishamn on different soil types (55°35'N, Alt. 80 m) and 2 plots in northern Sweden, one of them at Skallsjö (63°29'N, Alt. 465 m, Jämtland) and the other at Hedmark (64°46'N, Alt. 470 m, Västerbotten). The number of planted tamarack provenances varied between 5 and 12 on the plots. On three of the plots also provenances of other larch species were planted. Some preliminary information about the

growth of the best tamarack provenance in comparison with other larch species is given by Simak (1979).

On the basis of this first series with tamarack, a second series of field experiments was laid out over the country by the College of Forestry (Table 2). The purpose of these field experiments was to study mainly the growth and survival of different tamarack provenances under the ecological conditions prevailing in Sweden. This second tamarack series presented here is only outlined since the material is too comprehensive for detailed analyses in this limited report.

Material and methods: When studying the suitability for introduction of an exotic species in short-term experiments (15 - 20 years) and on a great number of provenances, as in this tamarack project, a single tree parcel design seems to be the most advantageous method. This design was used in the present provenance trials.

The provenance plots were laid out on 12 different localities between latitudes 55°35' and 65°02'N. The plots 1901, 1904, 1907, 1910-1916, 1918 and 1919 were planted in autumn 1973 or in spring 1974 using 1-1 stock (Table 2). On the three southern plots 1901, 1904 and 1907, 45 - 55 provenances were tested. On the remaining northern plots only 9-10 provenances were planted; 7 respectively 8 of them originating from latitudes over 50°N. To study the growth of tamarack on different sites, some of the plots with the same provenances were situated close to each other but on different soil types. In this way three groups of plots, 1904, 1907 and 1910 - 1913 and 1916, 1918, were laid out. Local origins of birch, Scots pine and Norway spruce, one to two provenances of each per plot, were also planted for comparison with the larch. Several inventories have been made on the plots since they were established. Here only height growth and survival of 10-year-old trees on plots 1901, 1904 and 1907 as well as that of 9 year-old trees on plots 1914-1916, 1918 and 1919, are presented.

Results. The correlation between origin of the provenances (latitude) and height of the 9-respective 10-year-old trees was calculated for each plot. Hereby curves of second degree ($Y = a + bx - cx^2$) with a rather clear maximum were obtained. According to these curves the best growing tamarack provenance originates from a latitude 7-8 degrees more southerly than the latitudinal position of the particular experimental plot. Thus, on the experimental plot 1907 located at 58°28'N latitude the best growing tamarack provenances originate from a latitude of about 50°N in America (Fig. 5), etc.

In the range 42° to 49°N from where most provenances originate (P 11-64) the variation in average height growth among provenances on plots 1901, 1904 and 1907 is very wide. For instance, on plot 1901 the 12 provenances in the range between 46° to 47°N had an average height of 328 cm with maximum at 385 cm (P 38) and minimum at 268 cm (P 26). In contrast, the few northern provenances planted on the northern plots 1914 - 1916, 1918 and 1919 showed a high correlation between height and latitude of origin. The correlation coefficients are R = 0.88 to 0.96 with the exception of R = 0.69 for plot 1918.

The survival of plants in the field experiments was checked at each inventory. In Table 3 the survival of the provenance's on plots 1901, 1904, 1907 and 1914 - 1916 in 1981 is presented. In general, the highest survival coincides with the best growth. Possible, there is a slight tendency that provenances showing maximum survival originate from latitudes about 2-3 degrees more northerly than those showing maximum growth. This relation was particularly apparent on the southern plots 1901 - 1907.

Plots 1910 - 1913 planted on sites with extremely inferior soil conditions (Sphagnum swamp and peat) were discontinued in 1982 due to low survival. The other twin plots, 1904 and 1907, as well as 1915 and 1918 showed great differences in plant growth and survival depending particularly on the soil type (Fig. 5).




Figure 5. Mean height of 9- and 10-year-old plants of different provenances in relation to the latitude of their origin and the geographical position of the plot (●). Figures close to the curves indicate the survival percentage of the respective provenance. The positions of southern provenances are not indicated in the figure for plots 1901-1907 (cf. text in Table 3).

Table 3. Average height growth (H) and survival (S) of tamarack provenances within latitudinal groups of origin in comparison with local species according to the inventory in 1981. Index at H-value indicates number of analysed provenances.

Lat.	1901		1904		1907		1914		1915		1916	
^{o}N	H cm	S %	H cm	S %	H cm	S %	H cm	S %	H cm	S %	H cm	S %
39-42	266^{2}	48	244^{3}	84	-	-	-	-	-	-	-	-
42-44	306^{5}	54	264^{5}	75	356^{2}	58	-	-	-	-	-	-
44-46	338^{11}	69	254^{8}	83	327^{8}	61	-	-	-	-	-	-
46-48	331^{19}	71	285^{21}	88	362^{19}	72	188^{1}	41	191^{1}	38	75^{1}	81
48-50	318^{6}	71	292^{8}	90	347^{6}	73	204^{1}	74	223^{1}	73	98^{1}	89
50-52	326^{2}	73	326^{2}	90	393^{2}	77	233^{2}	66	229^{2}	66	101^{2}	90
52-54	292^{2}	72	289^{2}	94	341^{2}	73	251^{2}	80	251^{2}	82	116^{2}	98
54-56												
56-58	268^{3}	73	266^{3}	95	334^{3}	77	245^{3}	81	249^{3}	81	121^{2}	99
58-60	236^{1}	70	245^{1}	98	354^{1}	80	-	-	-	-	-	-
64-66	- ^{1}	0	110^{1}	68	157^{1}	20	198^{1}	75	208^{1}	73	93^{1}	99
Local species												
Birch	190^{2}	13	341^{1}	78	415^{1}	63	176^{1}	52	158^{1}	53	149^{1}	71
N. spruce	124^{2}	83	70^{2}	28	148^{2}	83	100^{1}	38	97^{1}	50	50^{1}	96
S.pine	111^{2}	35	128^{2}	74	174^{2}	53	103^{1}	13	103^{1}	12	79^{1}	88
Plot Lat.^{o}N	55°35'		58°28'		58°28'		63°43'		63°43'		64°48'	

Birch had grown best on three of the plots. Growth of spruce and pine was on all plots comparable to that of the most badly growing provenances of tamarack (Table 3). All the three native species had suffered from moose damage and frost.

Discussion: Provenances of more southern origin than 46 N were not planted on the northern plots 1910 - 1916 and 1918, 1919 since they would not prosper at these latitudes according to our earlier experience from pilot studies with tamarack. Also the curves in figure 5 confirm that it would be meaningless to plant southern provenances like P 28 so far to the north. All the curves in this figure show that a certain tamarack provenance grows and survives best in Sweden if planted 7-8 degrees more northerly than the latitude of its origin. Ahlberg and Johansson (1984) came to similar conclusions when evaluating the 15-year-old tamarack plots in southern Sweden and found that provenances originating from southern sources (45-47° N) were more successful in growth. In Sweden the climate is particularly influenced by the Gulf Stream, a circumstance that makes this transfer towards the north possible. Maybe, that transfer of tamarack should be modified with regard to the altitude of the locality of the origin. Unfortunately, the present material is not sufficient for such studies, *inter alia* because in many cases the altitudinal data for the origin of the provenances are missing.

Cech et al.(1977) analysing 16 provenances of 7-year-old tamaracks on a pilot situated on the latitude about 40° N in the USA, i.e. on the southernmost border of tamarack's natural distribution, found a negative linear correlation between growth and latitude of the origin. Similar results were reported by Sajdak (1970). This pattern, showing a lower growth of provenances of northern origin with regard to the geographical position of the experimental plot, agrees well with the results obtained on all of the plots in Sweden (cf. Fig. 5 and Ahlberg and Johansson 1984).

The high correlation between the latitude of origin and height of the trees on plots 1914 - 1916, 1918 and 1919 makes it easier to choose tamarack seed sources suitable for transfer to northern Sweden. However, on plots 1901, 1904 and 1907 the great variation in growth among provenances originating from an area south of about 47°N latitude makes such choice tricky. Also Ahlberg & Johansson (1984) observed great differences in growth among southern seed sources originating from the same provenance region. The reasons for this variation are unknown, so far, but it is highly desirable to identify them in order to improve the Criteria for introduction of tamarack to southern Sweden.

The good growth of tamarack in comparison with pine, spruce and even birch on most experimental plots is a consequence of the vigorous growth of this larch at an early age. Maybe, that in later stages the growth of the tamarack will cease and therefore it is too early to make definite conclusions about tamarack's growth in comparison with other species. In any case, on southern plots in Sweden the best tamarack provenances grew as well as the best ones on the experimental plots in the USA (cf. Jeffers 1975 and Cech et al. 1977). A factor

that has not been considered in this report is the shape of the trees. Tamarack is rather scrubby at early age but the shape can be improved with age and therefore its evaluation will be made on a later occasion.

Plant survival depends on the interference of the abiotical and biotical environmental factors as well as on the inherited ability of the plants to stand out against these factors. In case the plants possess the appropriate resistance, they can counteract the external perils, e.g. frost, diseases, otherwise when the internal defence is lacking they can be injured or killed, e.g. by voles and moose.

In the present material, the mortality of the plants depends mainly on the factors that are causing most injuries on the respective plot, i.e. frost, moose and insects (Table 4). In general, the survival is good, especially for the provenances with the best growth (Table 3). The direct relation between growth and survival of a provenance can be understood in principle as a better growth being the consequence of better plant vigour. Plants with better vigour grow faster away from the stages at which a certain type of damage frequently occurs.

However, this occurrence of damage at a certain stage of tree development, i.e. at certain height, diameter, etc., can cause unexpected differences in survival and growth among provenances with different patterns of development (cf. damage on plots 1914 and 1915 in Table 4). The 10-year observations show that "survival" is hardly a crucial factor for introduction of tamarack into Sweden.

The growth of tamarack varied considerably on different sites within a geographic area. This appears clearly when comparing the two plots 1904 and 1907 situated next to each other at Remningstorp. The ten-year-old tamarack trees were on average 68 cm longer on the highly fertile site of 1907 than on the poor peat of 1904.

The parallel course of the two curves for average tree height plotted against latitude of origin (Fig. 5) indicates the difference in the effects of the ecological factors of the two site types without changing the latitudinal position of the maximum growth. Similar relations were also found on the twin plots 1916 and 1918 at Falträsk. The discontinued plots 1910 - 1913 can serve as an example that even if the tamarack has a high capacity to encounter poor soil types, its potential in this respect has limitations. The rather sterile peat moss and waterlogged Sphagnum swamp were limiting factors for the survival of the tamarack on these plots. However, in rare cases tamarack can grow even at open Sphagnum and other barren sites and therefore it would be desirable to make pedological studies of different soil types to clarify the minimum factors for the growth and development of the tamarack.

IV Damage to tamarack

Besides the genetic adaptability of a species to a new habitat there are some ecological factors that are more decisive than others for the growth and survival of a species introduced into a new habitat. Experience from these 9- to 10-year-old test plots shows that frost and especially noxious animals seem to be the most decisive factors for the growth of tamarack in Sweden. However, it is to be expected that when the planted tamarack trees grow older, other types of damage will also occur.

Material and methods: By revision of the field experiments the cause and degree of damage to the plants/trees were registered. In case of several injuries, e.g. frost and insect damage, only the most serious damage was noted. In this report the most frequent types of damage and the degree of damage per plot are presented summarily as well as the effect of this damage on plant growth. Only the damage on plots 1901, 1904, 1907 and 1914 - 1916 registered in 1981 is discussed (Table 4). Plots 1901, 1904 and 1907 were protected by fence that, however, could not prevent efficiently the moose from entering.

Results: From Table 4 it is evident that the frequency of damaged plants varies very much for the different plots. Thus, on plot 1914, 88 dead and damaged plants were registered, while the corresponding value on plot 1904 was only 11 %. Also the intensity of the dam-

age varied among the plots. In general, the performance of the tamarack trees was considerably reduced by the damage. Of the about 20 various types of damage registered the main types were injuries caused by frost, moose (incl. roe-deer) or insects. These three types of damage have also been evaluated separately for each plot. Table 4 shows that each plot had its own specific spectrum of damage.

Discussion: It is evident that the occurrence and degree of various types of damage on a plot depend on the geographic position and topographic situation of the plots, on the soil and vegetation types, etc., i.e. on the biotype in which the plot is located. A damage-doer usually prefers a certain biotype. Thus, the two plots 1904 and 1907 are located next to each other but in different biotypes. Plot 1904 was planted on drained peat soil without undergrowth except for a dominating Calluna cover. Here the frost was the main factor causing damage to the plants. In contrast, plot 1907 was planted on fertile, humid alder bog surrounded by mixed spruce and hardwood forest. The seedlings were planted in a vegetation of *Filipendula ulmaria* that was over one metre high. In the beginning the meadow-sweet was removed yearly around each plant. To some extent, this vegetation protected the young tamarack plants from frost. The plot was frequently visited and damaged by moose (Table 4). Similarly, plots 1914 and 1916 can be compared since they are planted on about the same latitude though located far from each other. Plot 1914 was planted on a surged moraine with abundantly growing bushes of birch, aspen, sallow and young pine trees. The site was an El Dorado for moose and insects. Much damage was caused by the larvae of *Pristiphora* spp. that had defoliated the trees, many times completely, in the last few years. Moose damage up to 1981 was slight since the plants were too small and there were other shrubs and trees on the plots tempting the moose more. However, in recent years when the tamarack became taller, the moose damage increased. Plot 1916 is situated on a well drained slope facing a lake. Tamarack grows well on this site. With the exception of slight but frequent frost damage, no other serious damage was observed on the plot.

The effect of the damage has been reflected in the growth development. The height of the trees decreased with increasing degree of damage (Table 4) except for on plots 1914 and 1915. The explanation of this reversal situation on the two plots may be that the tallest plants were more exposed to larvae than the smaller plants which were better protected by the surrounding vegetation.

The frequency of damage to each provenance has not been presented separately due to the fact that the actual damage with the exception of frost injuries was not provenance-specific. The external damage can seriously influence the growth of tamarack and can eventually be an obstacle to cultivating this larch. One can reduce the damage by cultivating the tamarack in biotype where the damage-doers occur rarely or not at all. The varying spectrum of damage in Table 4 supports this assumption.

SUMMARY

In this report, information is given about experiments carried out with tamarack (*Larix laricina*) in Sweden during the last 20 years. Seeds for the experiments have been supplied from 69 autochthonous stands in Canada and the USA.

The nursery experiments showed that the growth of tamarack is extraordinarily sensitive to photoperiodic conditions. This has been demonstrated in some experiments in a plastic greenhouse in which the effects of long night and intermittent light were tested on different tamarack provenances. The experiments were continued also in the field. Depending on the reaction to the photoperiod, suitable methods for raising tamarack seedlings from photoperiodically widely separated provenances in a central nursery are discussed.

Table 4. Damage situation on six experimental plots according to the inventory in 1981 (only tamarack considered).

Plot	1901	1904	1907	1914	1915	1916
Survival % 1981	67	87	69	73	70	94
	Per cent of damaged trees					
No damage	87	89	81	12	16	59
Slight d.	1	2	11	28	13	32
Moderate d.	11	9	6	48	41	9
Heavy d.	1	+	2	12	30	0
	Mean height of the trees (cm)					
No damage	331	284	366	191	149	118
Slight d.	238	226	307	233	227	92
Moderate d.	236	190	268	240	239	69
Heavy d.	289	132	201	236	244	
	Type of damage (%)					
Frost	44	72	6	0	0	72
Moose	32	1	42	1	+	+
Insect	1	4	3	96	98	18
Others	23	23	49	3	2	10

The reaction of a tamarack provenance to a certain night length is genetically determined. This must be considered when introducing the species into Sweden. Fortunately, the maritime influenced climate in Sweden modifies the latitudinal transfer of tamarack from America to Sweden in such a way that tamarack provenances can be planted in Sweden 7-8 degrees more towards the north than what is the latitude of its origin. This relation was confirmed on 12 provenance plots in Sweden planted between latitudes 55°35'N and 65 02'N. The tamarack has grown much better than the local Norway spruce and Scots pine during the first 10 years. The survival was high within the limits proposed for transfer. The shape of the young trees was not quite satisfactory. Damage to the trees was mostly caused by frost, moose and insects. These injuries can be reduced by planting tamarack in biotypes where the damage-doers are less abundant or can be controlled.

LITERATURE CITED

Ahlberg, Gudmund & Johansson, K-E. 1984. Är tamarack lärken ett konkurrenskraftigt alternativ for de sydsvenska mossmarkerna. Swedish University of Agricultural Sciences. School for Forest Engineers. Report 2; 1984. 29p.

Brown, Kevin R. 1982. Growth and reproductive ecology of Larix laricina in interior Alaska. A Thesis submitted to Oregon State University for the degree of Master of Science. Completed December 16; 1982. 154p.

Cech, Franklin C., Keys, R. & Weingartner, D. 1977. Seventh-year results of a tamarack provenance study. Proceedings. 24th North-eastern Forest Tree Improvement Conference. University of Maryland. Center for Environmental and Estuarine Studies. College Park Maryland; 1977: 55-65.

Duncan. Donald P. 1954. A study of some of the factors affecting the natural regeneration of tamarack (Larix laricina) in Minnesota. Ecology. 35(4): 498-521.

Eriksson, Anders. & Simak, M. 1977. Intermittent ljus for reglering av skogsplantors tillväxt. (Growth response of coniferous seedlings to intermittent light). Dept. of Forest Genetics. Royal College of Forestry, Sweden. Research Notes 27: 40-47.

Hall, J. Peter. 1981. Yield of Seed in Larix laricina in Newfoundland. Can. For. Serv. Res. Notes 1: 1-21.

Jeffers, Richard M. 1975. Survival and height growth of tamarack planted in Northern Wisconsin. North Central Forest Experiment Station, Forest Service-U.S. Department of Agriculture. Research Note NC-190; 1975. 3p.

Johnston, William F. 1973. Tamarack seedlings prosper on broadcast burns in Minnesota Peatland. North Central Forest Experiment Station, Forest Service-U.S. Department of Agriculture. Research Note NC-153; 1973. 3p.

MacGillivray, H.G. 1967. Progress in tree improvement in the maritimes region. Proceedings of the tenth meeting of the committee on forest tree breeding in Canada. Dept. of Forestry and Rural Development of Canada, Ottawa 2: 95-98.

— 1967. Hybrid between Tamarack and Japanese Larch Appears Promising in South-central New Brunswick. Bi-Monthly Research Notes. Dept. Or Forestry and Rural Development of Canada, Ottawa 23(1): 2-3.

— 1968. Progress in provenance, progeny, and species tests and larch breeding in the maritime provinces, April 1966 and March 1968. Proceedings of the eleventh meeting of the Committee on forest tree breeding in Canada. Quebec; 1968: 119-126.

Mead, Douglas A. 1978. Comparative Height Growth of Eastern Larch and Black Spruce in Northwestern Ontario. The Forestry Chronicle. 54: 296-297.

Park, Y.S & Fowler, D.P. 1982. Effects of Inbreeding and Genetic Variances in a Natural Population of Tamarack (Larix laricina (Du Roi) K. Koch) in Eastern Canada. Silvae Genetica 31: 21-26.

Pauley, S.S. 1965. Seed sources of tamarack, Larix laricina (Du Roi) K. Koch. In Fourth Cent. States

For. Tree Improv. Conf. Proc., 1964. Nebr. Agric. Exp. Stn., Lincoln, Nebr. 1965: 31-34.

Riemenschneider, Don E. & Nienstaedt, H. 1983. Height growth to age 8 of larch species and hybrids in Wisconsin. North Central Forest Experiment Station, Forest Service-U.S. Department of Agriculture. Research Note NC-239; 1983. 6p.

Rudolf, Paul O.1966. Botanical and Commercial Range of Tamarack in the Lake States. North Central Forest Experiment Station, Forest Service-U.S. Department of Agriculture. Research Note NC-17; 1966. 4p.

Sajdak, Robert L. 1970. Provenance Testing at Michigan Technological University. Ninth Lake States For. Tree Improv. Conf. Proc., 1969. North Cent. For. Exp. Stn. USDA For. Serv. Res. Pap. NC-47; 1970: 4-5.

Schotte, Gunnar. 1917. Lärken och dess betydelse for svensk skogshushållning. (The Larch and its Importance in Swedish Forest Economy). Medd. från Statens Skogsförsöksanstalt. 13-14: 529-842.

Simak, Milan. 1967. Seed weight of larch from different provenances (Larix decidua Mill.). Studia Forestalia Suecica, Royal College of Forestry. 57; 1967. 31p.

— 1971. De amerikanska lärkarterna: Larix occidentalis, Larix lyalii, Larix laricina. Sveriges Skogsvårdsförbunds Tidskrift. 1: 59-80.

— 1974. Artificiell invintring av skogsplantor vid odling i plastväxthus. (Artificial Wintering of Forest Plants in Plastic Green House). Sveriges Skogsvårdsförbunds Tidskrift 72 (2): 291-300.

— 1975. Kort nattbelysning av skogsplantor i plastväxthus ger bättre odlingsmaterial. (Intermittent Light Treatment of Forest Plants in a Plastic Green House Produces Better Plant Material). Sveriges Skogsvårdsförbunds Tidskrift 73 (4): 373-381.

— 1977. Artificiell invintring av 1/0 lärkplantor och uppföljning i fältförsök (Larix laricina). (Artificial hiemation of 1/0 tamarack plants and their development in field experiments). Experimental Genecology. Dept. of Forest Genetics. Royal College of Forestry. Research Notes 27: 145-152.

— 1979. Larix sukaczewii: Naturlig utbredning, biologi, ekologi och fröanskaffningsproblem. The Swedish University of Agricultural Sciences. Dept. of Silviculture, Umeå. Rapporter 1; 1979. 76p.

Simpson, J. Dale. 1983. The New Brunswick tree improvement council's breeding strategy for tamarack. 28th North-eastern Forest Tree Improvement Conference. Institute of Natural and Environmental Resources University of New Hampshire, Durham, New Hampshire 1982. Proceedings 219-224.

THE DISTRIBUTION AND REGENERATION OF LARIX FORESTS IN NORTHEAST CHINA

Chou Yi-Liang & Wu Hong-qi

INTRODUCTION

Northeast China includes Heilongjiang Jili, Liaoning Prov. and the east part of Inner Mongolia Autonomous Region situated between 38°43' and 53°40'N latitude, 115°40' and 135°3'E longitude in extreme eastern part of Eurasia near the Sea of Japan and affected by the south-eastern monsoon. Forests are distributed over the eastern half part of Northeast China where there is a major base for timber-production in China. Larix forest is one of the principal forest types in the area.

The Larix forests in Northeast China consist of 1 species, 2 varieties and 1 form: *L. gmelini* and f. hsinganica, *L. olgensis* var. changpaiensis and var. heilingensis which are edificator or dominant tree species and have similar ecological habits. They are very intolerant and cold-resistant trees, and can grow in dry, infertile or swamped soil even on the permanent frozen ground. But they are best adapted to grow in drained moist and sandy soil. Therefore, they can be discussed together in "Larix forests". but they have different distributions (Fig. 1) in Northeast China. They are endemic species in Northeast China except *L. gmelini* extending from East Siberia which are discussed respectively as follows.

Larix olgensis var. changpaiensis Yang et Y. L. Chou in Act. Phytotax. Sinica 9(2): 169. fab. 16 - 17. 1964. *L. olgensis* auct. non Herry: auct Fl. Chinae Bor-Or. (Mansh.) (Fig. 2).

CHOU, YI-LIANG, Professor, Forest Botanical Laboratory, Northeast Forestry University, Harbin, P. R. China, WU, HONG-QI, Dr., Forest Botanical Laboratory, Northeast Forestry University, Harbin, P. R. China.




Figure 1. The distribution of the principal Larix of Larix forests in Northeast China: 1. L. gmelini; 2. L. gmelini f. hsinganica; 3. Larix olgensis var. changpaiensis; 4. Larix olgensis var. heiligensis.

The variety is distinguished from the type by annual shoot with scattered hairs, generally a pecies separately on both lateral sides of pulvini at apex, easily deciduous, usually, without hairs except the bases of the shoots; wider leaves about 1 mm. wide; surface of scales with sparse glandular verruca or hairs.

Larix olgensis var. heilingensis (Yang et Y. L. Chou) Y. L. Chou, Ligneous Fl. Heilongjiang. 40. fab. 3: 6 - 8. 1936. *L. heilingensis* Yang and Y. L. Chou in Act. Phytotax. Sinica 9(2): 173. fab. 19. 1964. *L. dahurica* Turcz. 2. var. heilingensis (Yang and Y. L. Chou) Kitag. Neo-Lineam. Fl. Mansh. 47. 1979. (Fig 2).

The distribution of the variety is between *L. olgensis* var. changpaiensis and *L. gmelini* (Fig. 1). Somewhat intermediate in morphology between them. But it is easy to distinguish and the comparison is following in detail (Tab. 1).

The ecological habit, timber quality and uses of the variety are same with the type and

L. gmelini. But *L. olgensis* var. *heilingensis* grows faster than the type and *L. gmelini*, which is fast growing tree adapted better in Northeast China.

Larix gmelini f. hsinganica (Yang and Y.L. Chou) Y. L. Chou, Ligneous Fl. Heilongjiang 36. 1986. *L. gmelini* var. *hsinganica* Yang et Y. L. Chou in Act. Phytotax. Sinica 9(2): 177. fab. 21. 1964 (Fig. 2).

Table 1. The comparison of morphological characteristics of Larix.

Characteristics \ Species		L. olgensis var. changpaiensis	L. olgensis var. heilingensis	L. gmelini
Annual shoots	Colour	pale reddish-brown	pale brown	pale yellow brown
	White powder	a little	✓ 1	no
Leaves	Length	shorter, 0.8-2(2.5) cm	✓	longer 1.5-3.5 cm
	Numbers of stomatic lines	3(4)	(3)4-5	2-3
	Shape	round-obovate, broadly ovate or roundish	pentagonoid ovate	pentagonal ovate
Scales	Glandular varruca or hair	yes	✓	no, glossy
Size of bract		1/3 - 1/2 scale	about 1/2 scale	about 1/3 scale
Shape of wing		obtriangular	broadly sickle-shaped	sickle-shaped

1/ ☑ uniform characteristics




Figure 2. The morphology of scale, bract, seed: upper — *Larix olgensis* var. changpaiensis; middle — *Larix olgensis* var. heiligensis; lower — *Larix gmelini*.

Differ from the type by pubescent shoots. It sprouts earlier than the type about 7 - 8 days in spring and its growing period is longer.

The vegetation in Northeast China is divided into 3 forest regions and 1 grassland region. Larix forests are distributed in the two largest forest regions, e.g., Cold-temperate Coniferous Forest Region, and Temperate Coniferous and Broad-leaved Mixed Forest Region. The specific composition, distribution and natural regeneration of Larix forests are quite different in the two regions.

LARIX FORESTS IN THE COLD-TEMPERATE CONIFEROUS FOREST REGION

The region including the north of the Greater Khingan Mts. situated from 46°26'N latitude (nearby Aershan, Inner Mongolia) to Amur river about a span of 8° latitude is the extreme northern forest region in China. The climate is

different in the area. Two portions are divided by 49°20'N latitude (Yakeshi, Inner Mongolia). The north lies in cold-temperate zone in which the zonal vegetation is the cold-temperate coniferous forest (boreal forest), the south is located in temperate zone in which the zonal vegetation is temperate steppe and the cold-temperate coniferous forest extends southwards along the range of the Greater Khingan Mts. forming montane vegetation and joining with the cold-temperate coniferous forest.

The ridges of the Greater Khingan Mts. are generally 700 - 1 000 metres altitude in the forest region. The mountain tops are round, and most of their gradients are gentle below 20 degrees. The higher peaks are about 1 400 metres above the sea level and the highest peak in north — the 1 530 metres Mt. Aokeliduishan and in south — the 1 720 metres Mt. Taipingling.

Annual mean temperature is from -2° C to -5.6° C in the area. Because it is far from ocean, the continental climate is marked. The frost-free period lasts from May to September about 90 to 110 days. Mean annual precipitation is from 360 to 500 mm., but the evaporation exceeds the rainfall by 250 %.

The forest region is arid from May to June when it is cloudless and fogless, humidity of the air is very low and solar radiation is high. This makes the flammability high and forest fires occur frequently. Forest fires become a important factor affecting the forests in the area.

Affected by the climate, most of plants are eurytopic and fire-resistant in the forest region. Particularly, the composition of tree species is simple. Larix is almost single dominant species forming Larix forest which is the extenuation of the Larix forest in the Eastern Siberia, and similar in the specific composition and physiognomy. *Larix gmelini* is principal tree mixed with *f. hsinganica*.

Owing to the influence of south-eastern monsoon more or less, some broad-leaved trees in the temperate coniferous and broad-leaved mixed forest region appear in the Larix forests. The horizontal forest-cold-temperate coniferous forest is boreao-nemoral forest in the forest region. With increasing elevation, the specific composition of Larix forest is changing markedly showing the vertical distributions of the Larix forests in the forest region (Fig. 3):

A. Larix forest with broad-leaved trees;
B. Larix forest;
C. Larix forest with spruces;
D. Open Larix forest.

The Specific Composition and Distribution of the Larix Forests

Larix forest with broad-leaved trees: It is horizontal forest in the forest region distributed in the area at low elevations. With the increasing latitude, the upper limit of the Larix forest is descending gradually (Fig. 3). Because the elevations of the mountainous area generally exceed the upper limit, the Larix forest with broad-leaved trees is not distributed widely in the forest region. The zonal soil is brown forest soil.

Mixed with temperate broad-leaved trees is the important characteristics of the specific composition in Larix forest affected by the temperate coniferous and broad-leaved mixed forest region. Dryresistant trees, *Quercus mongolica* and *Betula dahurica* are principal broad-leaved trees. In addition there are *Populus davidiana*, *Tilia amurensis*, *Fraxinus mandshurica*, *Phellodendron amurense*, etc. They do not grow well usually from secondary tree layer in which the numbers of the individual trees are also fewer. The Larix forest is similar to the temperate Larix forest.

Larix forest: It is distributed widely in the forest region because the distribution is uniform with the elevations of the area. With increasing latitude, the vertical distribution of the Larix forest descend gradually (Fig. 3). Soil is typical brown forest soil which is shallow and better in water permeability. The Larix forest is similar to the "South Taiga" in Eastern Siberia in physiognomy and specific composition in which the simple specific composion is a major characteristic.

Larix forest with spruces: It appears in upper areas of the mountains but not distributed widely at higher elevations (Fig. 3) in the forest region. The climate becomes humid in the vertical belt and the soil is podzolized brown forest soil.

Larix forest with spruces is similar to "Middle Taiga" in specific composition and physiognomy, the characteristics of dark boreal forest (spruce-fir forest) consisting of a single dominant tree — Larix and accompanied by *Picea koraiensis* and *P. jezoensis*. *Sorbus amurensis* and *Betula ermanii* often appear in the Larix forest. They are the accompanying broad-leaved trees in the dark boreal forest (spruce-fir forest). Due to the influence of forest fires, there are only some seedlings found occasionally in the Larix forest. Because of the temperature inversion, the Larix forest also occurs in the wet and cold local areas at lower elevations as a "zonal forest".

Open Larix forest: It is scattered to occur on some higher peaks. The elevations of its distribution are increasing from north to south, e.g., 1 200 - 1 350 metres altitude Mt. Aokeliduishan (51°50'N lat., 122°08'E long.) in the north and 1 450 - 1 720 metres altitude Mt. Taipingling (Fig. 3).




Figure 3. The vertical distribution of the various Larix forests in the coldtemperate coniferous forest region: DBF — Deciduous broad-leaved forest.

The soil in which the Larix forest grows is rocky soil. The soil layer is shallow and with bare rock. The climate is very cold and wind is very strong in the areas. Other trees could not grow in the areas. Larix grows barely forming open Larix forest as zonal vegetation on the vertical belt which is the upper forest limit in to the forest region. Open Larix forest is similar to "North Taiga" in Eastern Siberia in specific composition and physiognomy. The canopy density is below 0.3 - 0.4 and the growth of Larix is very poor. Larix is single dominant tree species forming pure Larix forest or mixed with a few numbers of *Betula ermanii*.

The Growth and regeneration of the Larix Forests

The vertical distribution, specific composition and physiognomy of the various Larix forests are quite different in the forest region mentioned above. Also there are many differences of the growth and regeneration among them.

For convenience, the various Larix forests are respectively represented by the following symbols in text and figures:




Figure 4. Height growth of the various Larix forests in the cold-temperate coniferous forest region: A. Larix forest with broad-leaved trees; B. Larix forest; C. Larix forest with spruces; D. Open Larix forest.

Type A. Larix forest with broad-leaved trees;
Type B. Larix forest
Type C. Larix forest with spruces;
Type D. Open Larix forest.

Growth. The growth of height, D.B.H. and volume: The growth curves of height, D.B.H. and volume (Fig. 4, 5 and 6) show that Larix grows most rapidly in type A, more rapidly in type D, and slowly in type C and B in the primary stage of growth, which is closely related to the structure of the overstory canopy and the characteristics of the regeneration. This indicates that the overstory trees in type A and D are approximately even-aged and the regeneration of Larix in the understory is very poor. The overstory trees occured in open. There is no suppressed period in the young stage of Larix in type A and D. But the natural regeneration of Larix is better and the overstory trees occured in the understory which has a marked suppressed period in the sapling stage in type B and C. When they are free from the overstory, they grow rapidly and exceed the growth of trees in type D. Larix grows always rapidly in type A because of the better site. At last the total growth increment of the various Larix forest increases in order of descending altitude.




Figure 5. D.B.H. growth of the various Larix forests in the cold-temperate coniferous forest region: A. Larix forest with broad-leaved trees; B. Larix forest; C. Larix forest with forest with spruces; D. Open Larix forest.

The mean increment and annual increment of volume: Mean increment indicates the mean increment of tree each year and the annual increment is the actual increment each year. The annual increment increases gradually and reaches at maximum. Then it begins to reduce. During the reduction of annual increment, the mean increment reaches at maximum. At this time the both growth curves are intersected. The age at the intersecting point is called quantitative mature age which is a major basis

for determining the age of final felling. The stem analysis (Fig. 7) reveals the differences of the quantitative mature age and stem volume at the age among the various Larix forests. The quantitative mature age comes very early in type D and puts off with the descending altitude. From Figure 6, the volume of Larix is lowest at the quantitative mature age in type D (The same result is gotten according to the annual increment and mean increment curves of height and D.B.H.) and increases with descending elevation reaching maximum in type. A (the horizontal forest in the forest region) in which large timber can be gotten.




Figure 6. Volume growth of the various Larix forests in the cold-temperate coniferous forest region: A. Larix forest with broad-leaved trees; B. Larix forest; C. Larix forest with spruce; D. Open Larix forest.

Regeneration. The natural regeneration is quite different among the various Larix forests in the forest region (Fig. 8). The regeneration is best in type B and poor in others. It is better in type A than C and very poor in type D. The proportions of the seedlings above 30 cm high and below 30 cm high are approximately uniform, which reveals that there are always differences of regeneration among the various Larix forests in the regeneration process of Larix seedlings not caused by the difference of mortality under competition after a large number of seedlings occur among the various Larix forests. After the Larix forests, particularly, type C and B are disturbed, *Betula platyphylla* often occurs. *Betula platyphylla* is a light-demanding tree adapted to grow in the site like Larix except the swamp. Betula can occupy the open Larix forest and clear lands with the luxuriant mosses and herbs in which Larix is difficult to grow because of its relatively poor competitive ability with weeds. *Betula platyphylla* produces large quantities of seed each year (in Larix, good cone and seed crops occur at 3 to 5 year intervals in the forest region) and has more widespread small seed dispersal. Therefore it often occupies the better sites forming birch forest even though the sites are also suitable for Larix. But *Betula platyphylla* will be replaced by Larix at last because its relatively short lifespan about 70 to 100 years.

Although Larix is a light-demanding tree, the luxuriant moss and herb layers are more important than the shading affecting the natural regeneration of Larix. Thick ground cover makes the rooting of Larix difficult. The natural regeneration of Larix is still poor even though the overstory is open after clear-cutting. To the contrary, the regeneration is very excellent in the bare soil and fire slash. This shows that the cause inhibiting the regeneration of Larix is the luxuriant moss and herb layers. Therefore, the ground cover must be removed so that the regeneration condition of Larix is improved.

Besides *Betula platyphylla*, other broad-leaved trees, e.g., *Quercus mongolica*, *Betula dahuria*, *Populus davidiana*, etc. appear forming mixed forests after disturbance, which causes the regeneration of Larix to be more difficult.




Figure 7. Mean increment and annual increment of volume of Larix in the cold-temperate coniferous forest region: A. Larix forest with broad-leaved trees; B. Larix forest; C. Larix forest with spruces; D. Open Larix forest.




Figure 8. The regeneration in the various Larix forests in the cold-temperate coniferous forest region: total numbers of Larix seedlings per hectare; 2. frequency of Larix seedlings; 3. numbers of Larix seedlings (height >30 cm) per hectare; 4. frequency of Larix seedlings (height >30 cm). A. Larix forest with broad-leaved trees; B. Larix forest; C. Larix forest with spruces; D. Open Larix forest.

The quantity and growth of Larix seedlings are quite different in the various Larix forests. The growth of the seedlings in type D is very poor in comparison with the others. The growth of seedlings in type A, B and C is only discussed as follows. The height growth of seedlings is slower in type C (curve C, Fig. 9) which is maybe related to the thicker moss layer inhibiting the rooting in soil causing the lack of nutrients and shading of overstory. The seedlings grow rapidly in type A (curve A, Fig. 9). This shows that the site in type A is not suitable for the regeneration of Larix, but for the growth of Larix seedlings. Therefore, the artificial regeneration is the major method in type A. Although the growth of seedlings in type B is slower than in type A, and faster than in type C. In addition, there are large numbers of seedlings in type B. The typical Larix forest belt is the best area of the natural regeneration of Larix, where the major regeneration method should be natural regeneration with artificial improvement.




Figure 9. Height growth of seedlings of Larix in the various Larix forests in the cold-temperate coniferous forest region: A. Larix forest with broad-leaved trees; B. Larix forest; C. Larix forest with spruces.

Owing to the differences of the regeneration and growth of Larix in the various Larix forests, different ways should be adopted in silviculture and management which are concluded following:

Larix forest with broad-leaved trees, which is not widespread in distribution, occurs at low altitudes in the forest region and denotes deeper, fertile soil and a higher quantity of heat in the site. The area of primary forest has been very small due to the human activity. The silviculture and management of secondary forest is major task. The growth of artificial Larix stands is very fast on the vertical belt. But the natural regeneration is poor. Therefore, artificial regeneration is major method.

Typical Larix forest distributed most widely is a major portion of the Larix forests in the forest region which is becoming the base of timber production. The natural regeneration is best in the belt and should be the main way in silviculture and management of the Larix forest. By rational final felling, the better natural regeneration condition should be provided .

Larix forest with spruce, which is mainly distributed in the upper reaches of small streams, has a cold and wet site in which the moss layer is developed in the understory. It is more significant for water and soil conservation and should be managed as protection forest . Timber production is secondary purpose.

Open larix forest which is valueless for the management of timber production only appears on some scattered higher peaks and should be determined as protection forests

LARIX FORESTS IN THE TEMPERATE CONIFEROUS AND BROAD-LEAVED MIXED FOREST REGION

The forest region including the eastern mountainous area in Northeast China is situated at 45°15' - 52°20'N latitude, 126° - 135°30'E longitude just like a new moon. Main mountains are the Lesser Khingan Mts., Wandashan Mts., Zhangguang-chailing Mts., Laoyeling Mts. and Changpai Mts. forming undulating hills and complex mountainous topography. Most of the mountains are not over 1 300 metres above the see level and the highest peak is the 2 691 metres Mt. Baiyunfeng in the Chang-

pai Mts., which is also the highest peak in Northeast China.

The forest region is located at the extreme east of Eurasia near the Sea of Japan, which has a marine (moist) temperate monsoon climate affected deeply by the Pacific Ocean. The precipitation is from 500 mm to 800 mm concentrated within a few summer months (June, July and August), about 70 % to 80 % of the annual rain-fall. The forest region has higher temperatures in summer and the July mean temperature is from 20° C to 26° C or more. The maximum temperature may achieve 39° C. These are suitable climate conditions for the growth of plants in the forest region where luxuriant forests thrive as one of the major bases for timber production in China. The forest region, far east of USSR and north of Korea belong same natural zone called commonly "flora of Manchuria".

The horizontal forest is temperate coniferous and broad-leaved mixed forest. *Pinus koraiensis* is principal tree accompanied by many temperate deciduous broad-leaved trees, more than ten species, and cold-temperate conifers, e.g., *Picea jezoensis, P. jezoensis* var. komarovii, *P. koraiensis* and *Abies nephrolepis*. With increasing elevation, the coniferous forest consisting of spruce and fir gradually makes the transition to montane cold-temperate coniferous forest (spruce-fir forest) in vertical distribution in the forest region.

Larix is abundant in the forest region. *Larix gmelini* and *f. hsinganica* are distributed in the north of the area, *L. olgensis* var. changpaiensis in the south and *L. olgensis* var. heilingensis in the crossed area between the distribution of *L. gmelini* and *L. olgensis* var. changpaiensis (Fig. 2). Most of Larix forests are secondary forests in the forest region. Here there is only a large and continuous area of Larix forest in the Changpai Mts., formed by the affecting of volcanic activity (the last volcanic eruption was in 1 702). But the typical Larix forest is restricted in swamp, in which other trees are not adapted to live, because of the relatively poor competitive ability of Larix forming swamp-inhabiting Larix forest which appears discontinuously but in widespread distribution in the forest region.

According to the specific composition, distribution, the occurrence and development of Larix forests, three main types of Larix forests are classified in the forest region:

A. Montane cold-temperate Larix forest;
B. Temperate Larix forest;
C. Swamp-inhabiting Larix forest.

The Specific Composition and Distribution of the Various Larix Forests

Montane cold-temperate Larix forest: derived from the montane cold-temperate spruce-fir forest is distributed at higher elevations (Fig. 10). It is concentrated to appear in the Changpai Mts. and has marked characteristics of dark boreal forest (spruce-fir forest) in the gradually replaced state. The over-story is almost consisted of Larix accompanied *by Abies nephrolepis, Picea jezoensis* var. komarovii, *P. jezoensis* and *P. koraiensis* in the understory forming the compound storied forest.

Because of shading in Larix forest, the regeneration of Larix is very poor. There are large numbers of seedlings of fir and spruce or a few seedlings of *Pinus koraiensis* which is the endemic tree in the forest region and annual or biennial slender seedlings of Larix in the understory. According to the investigation in a sample plot, there are about 4 000 seedlings of fir per hectare, 1 000 seedlings of spruce per hectare, 200 seedlings of pine per hectare and 700 seedlings of Larix per hectare in the understory of the Larix forest. Because of the luxuriantly overgrowing mosses, the regeneration of various trees is difficult. Generally, most of seedlings occur on the fallen trees on which the moss layer is thin. For example, 95 % of seedlings occurs on fallen trees in a sample plot. One seedling which did not occur on fallen tree, at age of 14 yr., 30 cm high is covered 12 cm high by mosses and its lower lateral shoots, covered up by mosses has withered without leaves. The seedlings about 1 to 3 yr. old, 3 to 12 cm high, grow very poorly and are difficult to grow up in the understory. The individuals of Abies nephrolepis at age of

4 - 48 yr., 6 - 163 cm high and *Picea jezoensis* var. komarovii at age of 9 - 31 yr., 14 - 104 cm high, grow better in the Larix forest, which will form dense understory causing a dark and wet Larix forest. The trend of development of the Larix forest is forming spruce-fir forest. In the process of succession, a series of transitional types is realized, which include: *Picea koraiensis*-Larix forest *Picea jezoensis* var. komarovii-Larix forest, *Abies nephrolepis*-Larix forest, etc., according to the investigation on the west slopes of the Changpai Mts.




Figure 10. The vertical distribution of the various Larix forests in the temperate coniferous and broad-leaved mixed forest region: A. Montane cold-temperate Larix forest; B. Temperate Larix forest; C. Swamp-inhabiting Larix forest.

Temperate larix forest: It is derived from the temperate coniferous and broad-leaved mixed forest — the horizontal forest in the forest region distributed at low elevations (Fig. 10). Although the temperate Larix forest is not distributed widely, it is unique type in Northeast China, which has the characteristics of the temperate coniferous and broad-leaved mixed forest. It consists of Larix, *Pinus koraiensis*, *Tilia amurensis*, *Ulmus japonica*, *Fraxinus mandshurica*, *Acer mono* and *Quercus mongolica*, etc. Larix is the dominant tree in the overstory, the broad-leaved trees grow beneath the over-story and *Pinus koraiensis* often occurs in the understory, which forms compound mixed forest.

After disturbance, the grasses will be luxuriant in the site inhibiting the natural regeneration of Larix. But the broad-leaved trees and *Pinus koraiensis* can occur in the site. *Fraxinus mandshurica*, *Tilia amurensis*, *Ulmus japonica*, *Quercus monqolica* and *Phellodendron amurense*, etc. are principal regeneration trees in the understory of Larix forest in which the numbers of seedlings can reach at 10 000 per hectare. The specific composition of regeneration trees is similar to the one of the broad-leaved trees in the horizontal forest. After Larix is replaced by broad-leaved trees, the horizontal forest-temperate *Pinus koraiensis* and broad-leaved mixed forest will gradually restore.

Swamp-inhabiting Larix forest: It appears in widespread distribution in the forest region and is the primary forest restricted in the low and humid valleys or undrained soils in which there is permanent stagnant water. The soil is bog soil or swamped meadow soil and has the different level of the peat accumulation in which other trees have difficulty living, but Larix can grow forming the Larix forest. Generally, Larix is single dominant tree or there are a few number of *Abies nephrolepis*, *Picea koraiensis*, *Betula costata* and the indicative small tree *Alnus hisuta*, etc. mixed in the Larix forest. *Fraxinus mandshurica* and other broad-leaved trees occur in slightly drained soil forming the transitional types to the temperate Larix forest. The most marked characteristic of the specific composition is that most of plants in the understory are the typical helophytes in the swamp-inhabiting Larix forest. They have xeromorphism. *Sphagnum* spp. are principal mosses and there are also insectivorous plants. They indicate the moist soil, physiological drought and lack of mineral nutrients in site. Though Larix can survive, it grows poorly in the inhibiting state, which shows that Larix is not better adapted to grow in that ecological condition. Particularly, in heavy swamp and high levels of peat accumulation, the growth of Larix is very poor, low tree height, small crown, shorter leaves, small cones, and at the age of 115 to 125 yr., only 6.5 to 8 m high, 9 to 11 cm in girth, is called "small old tree". The density of stand is very low, 0.3 - 0.4 in closure and the life span is shorter. The stand consists of living, dying and dead trees replaced by each other, about 30 to 40 percent of

dead trees. Because of the luxuriant sphagnum mosses and permanent stagnant water in undrained soil, the humidity of air is higher in the forest so that there are large numbers of mosses, e.g., *Leudocon pendula*, and *lichens*, e.g., *Usnea longissima*, *U. diffracta*, attached to the stems and branches forming a peculiar landscape which is almost valueless for forest management.

Growth and Regeneration of the Various Larix Forests

Growth. There are the differences not only in specific composition but also in the growth among the various Larix forests in the forest region, which results from the differences of water, heat and soil conditions. See Figures 11 and 12. The growth of height and D.B.H. of Larix in temperate Larix forest is better than in the montane cold-temperate Larix forest and is very poor in the swamp-inhabiting Larix forest. Temperate Larix forest distributed at low elevations has dark brown forest soil, and better water and heat conditions, in which the process of biological small cycle containing much more mineral materials is faster so that the nutrient elements reverting to soil are more. Compared with the brown forest soil (taiga soil) in montane cold-temperate Larix forest, dark brown forest soil is more fertile which is more suitable for the growth of trees, Therefore, Larix grows best in temperate Larix forest. In contrast the bog soil, permanent stagnant water, poor aeration and lack of mineral nutrients, is infertile. The growth of trees is extremely poor in inhibiting state called "small old tree".

Regeneration. The Larix forests, except swamp-inhabiting Larix forest, in the forest region are secondary forests respectively derived from montane cold-temperate coniferous forest (spruce-fir forest) and the horizontal forest-temperate coniferous and broad-leaved mixed forest, and also provide the better regeneration condition for the primary forests. The specific composition in the Larix forests is similar to that in the primary forests except the upper story consisting of Larix. with the gradual changing of site gradient. There are the transitional types of the Larix forests among the three main Larix forest types, which belong to the corresponding Larix forest depending on the specific composition.




Figure 11. Height growth of the various Larix forest in the temperate coniferous and broad-leaved mixed forest region: A. Temperate Larix forest; B Montane cold-temperate Larix forest; C. Swamp-inhabiting Larix forest.




Figure 12. D.B.H. growth of the various Larix forests in the temeperate coniferous and broad-leaved mixed forest region: A. Temperate Larix forest; B. Montane cold-temperate Larix forest; C. Swamp-inhabiting Larix forest.

The natural regeneration of Larix is governed not only by the shading but also by the much thicker moss and herb layers inhibiting the rooting of Larix. Generally the natural regeneration of Larix is poor even in open cut-

ting slash, but better in fire slash because Larix occurs greatly in the bare soil. The ground cover must be removed ensuring the natural regeneration of Larix. In the open area in Larix forest or the felling slash, *Betula platyphylla* often appears forming birch forest or mixed forest with Larix. Their regeneration and development have been mentioned above. In the case of lacking the seed sources of Larix and *Betula platyphylla*, the disturbance causes the invitation of intolerant herbs (e.g., *Deueuxia angustifolia*, *Osmunda cinnamomea* and *Sorbaria forbifolia*, etc.) and shrubs, which makes the soil swamp out and the regeneration of Larix and *Betula platyphylla* more difficult. There are a few numbers of Larix seedlings, which are 9 to 10 yr. at age, 35 to 50 cm high, growing on the fallen trees. The regeneration under clear-cutting should be adopted in the silviculture and management of Larix forest in the forest region according to the biological characteristics of Larix. But the seed source of Larix and the luxuriant mosses and herbs are both important affecting the regeneration of Larix. Therefore, seed trees must be reserved and the ground cover should be removed. That *Betula platyphylla* is mixed rationally in Larix forest is a better way in the silviculture and management of Larix because it is better a tree in the improvement of soil, increasing the soil fertility, and has many uses and high value.

LARIX IN THE USSR

A.I. Iroshnikov

ABSTRACT: Genus Larix Mill with comparatively small number of species is widely spread in the boreal regions of North America and Eurasia. It particularly dominates in the forests of continental regions of East Siberia, Central Asia and Far East, occupying up to 70-90 per cent of their territory.

Larch forests occupy about 279 mln ha, that is 40,5 per cent, of forest covered territory of the USSR (Drozhalov M. M., 1984). Moreover, three polymorphic species — *Larix sibirica* Ldb., *L. dahurica gmelinii*) Turcz. et Trautv. and. Kajanderi Mayr. are absolutely prevailing. *Larix Sukaczewii* Djilis, *L. kurilensis* Mayr and *L. Gzekanovskii* Szaf. have comparatively small area and *Larix olgensis* Henry, *Lubarskii Sukacz.*, *L. polonica* Racib., *L. decidua* Mill and *L. moritima Sukacz.* occupy isolated plots.

USSR's Larix gene pool is studied with different completness but available information about form diversity of the most valuable Larix species is sufficient base for systematic utilization of their genotypic potential.

Description of intraspecific differentiation and egologo-biologic properties of the main Larix species, growing in the USSR, is given in the report.

Key words: Larix (larch), area, gene pool, intraspecific differentiation, biological and ecological properties, hybridization.

INTRODUCTION

In the study process of Larix genus individual species have been revised repeatedly. At the same time Larix species nomenclature is rather disputable up to now because of different notions of the botanists about species distinguishing criteria, their genetic relations and evolution. Debatableness of many taxons is also dependant on an insufficient genus gene pool study and natural hybridization (its distribution and the role in Larix species formation).

Total number of Larix species recognized by some systematists varies from 6 to 29, and species growing in the USSR territory — from 3 to 15. Such considerable fluctuation in genus Larix taxonomic differentiation related to the fact that some botanists together with "good" species distinguish in the same range climatic ecotypes or hybrid forms, appearing in the area contact zone and obtained after artificial crossing. Others do not admit the species status of many geographically isolated populations which are distinctly differ by the morphological features complex.

At the first stage of Larix investigation in Russia evaluation of its individual properties was carried out in botanical gardens and parks where its different species, forms and spontaneous hybrids were represented. But the decisive significance in gaining wide popularity by the Larix had its cultures, established at the second half of the XVIII and in the XIX century in some regions by Fokel (Greshner, 1843), Ch. Mayer (1850), I.N. Shatilov (1885), K.F. Turmer (1891), P.I. Levitsky (1903) and others.

It is significant that hybrid forms (Keppen, 1885; Shreder, 1899) and works in Larix artificial crossing (Kurdiani, 1912, 1932; Piatnitsky, 1933; Albensky, 1939, 1959; Jablokov, 1962; Kudasheva, 1964; Kruklis, 1968; Avrov, 1974; Kniazeva, 1978) revealed in Russian botanical gardens, were arranged mainly for the zone where Larix was introduced. Only from 40-50 years of the XX century Larix natural populations became the subject of more systematic study. At the same time the interest towards its natural hybridization processed in the individual species area contact zones (Kolesnikov, 1946; Dylis, 1947, 1959, 1961;

A.I. Iroshnikov, Central Research Institute of Forest Genetics and Breeding, Voronezh, USSR

Bobrov, 1961, 1972, 1978; Koropachinsky, Milutin 1964; Kruklis, Milutin, 1977; Konovalov, Pugach, 1978 et al.) which earlier were interpreted only fragmentary (Middendorf, 1867; Sukachev, 1912, 1931; Sukachev, Poplavskaya 1914).

Larch forests occupy about 279 mln ha - 40,5 per cent of forest covered territory of the USSR (Drozhalov 1984). Moreover, three species — *Larix sibirica* Ldb., *L. dahyrica* Turcz. et Trautv. and *L. Kajanderi* Mayr. are absolutely prevailing. Other species have a rather smaller area (*Larix Sukaczewii* Djilis, *L. kurilensis* Mayr. *and L. Czekanovskii* Szaf.) or occupy extremely limited isolated plots (*Larix olgensis* Henry, *L. Lubarskii Sukacz., L. decidua* Mill., *L. polonica* Racib. and *L. maritima* Sukacz). Such species as *Larix leptolepis* (Sib. et Zuc) Endl., *L. occidentalis* Mutt., *L. principis-ruprechtii* (Mayr) Pilger, *L. Laricina* (Du Roi) K. Koch and *L. potanini* Batalin are represented only by artificial stands or by separate trees in botanical gardens and parks. *Larix lyallii* Parl., *L. griffithii* Hooker and *L. masteriana* Rehder et Wilson practically haven not been introduced in the USSR up to now.

Larix Sukaczewi Dyl.

This species occupies certain rather limited ecological niches in the European north-east and Trans Ural — the regions with temperate continental climate. *Larix Sukaczewi* area is attributed by A.P. Iljinsky (1929) to the reductioning net (or regressive. area perforate) type. By its number of morphological characteristics and biological properties it clearly differs from the nearest "neighbours" — *Larix polonica* in the south-west and *L. sibirica* — in the west. *Larix Sukaczewi* contacts with *L. sibirica* only at the north-western part of the area in the lower reaches of the Ob river. In this region the two species introgressive zone is, compared with the Middle and South Taiga and partially-wooded steppe districts of the vast Western Siberia lowland where they are fragmentary embedded among dark-coniferous pine, aspen and birch forests, more clearly expressed. Moreover, *Larix Sukaczewi* is arranged for the more "warm" places, than *L. sibirica*.

As a result of anthropogenic factors influence on *Larix Sukaczewi* representation is reduced in several times in the western part of the area. Although it disappeared in some regions already in historic time, *L. sukaczewi* in the postglacial period had not significant contact with *L. polonica*.

Originally *Larix Sukaczewi* was characterised as a comparatively monomorph species with weak intra- and interspecific variation (Dylis 1947). More detailed study of its natural populations (E.A. Pugach, 1964, 1970; N.V. Kuprianov, 1968; V.N. Nikontsuk, 1970, 1972) specific genotypical composition displayed features of larch forests of Gorky region, situated on the left bank of the Volga, the Upper Kama, Northern middle and Southern Ural districts. Certain genetics links of the Udmurtian and Gorky district stands with middle Ural northern part population were revealed.

Together with regional race singling out by the morphological characteristcs complex, species differentiation on a number of climatic ecotypes: zone-provincial in the European north-east and zonebelt in the Ural was shown. *Larix Sukaczewi* climatic (physiological) races were found out in the result of some populations' progeny trial in the geographical cultures established at different times in Moscow, Voronezh, Leningrad, Briansk, Sverdlovsk districts and in Bashkirian and Udmurtian autonomous republics. The same experiments became the base of the *Larix Sukaczewi* forest seed-zoning elaboration. According to the investigations, its most valuable gene pool is concentrated in the Soviet Union European part of Mixed and Southern Taiga forest zone. Its utilization also gives high effect in partially-wooded steppe districts of Western Siberia, Northern Kazakhstan and European part. In the warmer and more moist regions *Larix Sukaczewi* is not just as good as *Larix decidua* and *L. polonica* in productivity.

For *Larix Sukaczewi* populations (A.S. Jablokov, 1962; A.I. Iroshnikov, 1970, 1977; N.V. Kuprianov, 1968) absolute domination of green cone forms through the whole area is

typical. Trees with red cone and transitional in ripe female cone colour are represented in populations individually as a rule.

In mircostrobile colour during flowering period the following forms are distinguished: pale green, whitish, pink and violet crimson.

Through the whole area two forms well distinguished in cone seed scales are found (Dylis 1947). One of them have rounded, at the tip - well rounded scales. Another form — with broad avoid, at the tip — obtuse triangular scales. Between these forms in all populations there are a number of fine and gradual transitions.

In the middle and Southern Ural and also in Udmurthia very rare in populations one may come across the form with turned outwards scales and small cones, similar with *Larix leptolepis* cones. In *Larix Sukaczewi* cultures was found out by B.V. Grozdov (1960) large-cone form. As was shown by V.N. Nikontchuk (1970) in the stands there are forms with low (3 %) and high (up to 17 %) seed yield. According to the ripening time early and late ripening forms are distingished. According to the degree of sexual dimorphism display in all populations specimen of the 3 types are represented: strobiles (more than 80 %), male (macrostrobiles are poorly represented) and female (with macrostrobiles primary development).

According to the growth character, crown form, foliage colour, form and the time of needle fall the following *Larix Sukaczewi* forms are distinguished: with narrow piramid-shapped or columnar crown; with sogged ("weeping") branches, dense crown with small branches; with bent top, often not separated from the upper horizontal lateral branches; spruce-like; with blue-greyish foliage; with very long needles; with fine branches; with rough branches; little and very barrel-butted, with early and late needle fall in the autumn.

By the bark form in the Ural (E.A. Pugach 1970) trees with finely and deeply fissured bark were distinguished. But they have transitional types. V.N. Nokonchuk (1972) indicates only 4 forms without transitional types: hard barked, thick barked, with bark cracked into square plates and bark with deep fissures. Because of the absence of clear bounds between numerous form distinguished by bark form, he considers that it is reasonable to use type classification of its variability. All bark distinctions are brought together to the two main groups of its formation type: A. Ridged bark (broad ridged and narrow ridged types, thick barked, coarse barked, deeply fissured and craked into plates forms), B. Flaked bark (broad flaked type with alder-like thick barked and pine-like plate subtypes and narrow flaked type).

Investigations in the Middle and Southern Ural found out that according to productivity, growth rate, physico-mechanic characteristics and seed quality finely fissured form trees have higher characteristics (Konovalov, Pugach, 1978 et al.). But cultures established in the central partially wooded steppe (V.I. Birukov) higher growth rate, bole quality and insect resistance had deeply fissured, crimson barked soft barked and green cone forms (the author classified the Larix under study to the *Larix Sibirica*, but this needs verification).

V.N. Nikonchuk (1970) points out the following morphologic characteristics' complex, inherent to the *Larix Sukaczewi* trees (in Smolensk region cultures) characterized by fast growth rate and good bole quality: dense spreading crown with thick branches pointed horizontally or slightly upwards and thick barrel-butted bole, covered with thick coarse bark. The colour of the bark in the cut is crimson or red-greyish-brown.

Larix Sukaczewi with *L. leptolepis* and *L. decidua* interspecific hybridization high efficiency have been shown in many trails (Albensky, 1951, 1959; Jablokov, 1362; Kudasheva, 1964 et al.). But problems of population provenance selection, which ensure maximal heterosis under interspecific and separate intraspecific crossing are not worked out. Selection intensity among hybrid progeny and principles of individual selection with long-term heterosis effect enlightened unsufficiently.

Larix polonica Racib.

In the USSR territory natural populations of this species are represented only by several small plots in Ukranian' Carpathians. All of them are situated in the upper mountain zone with temperate cold climate. *Larix polonica* area (A.P. Iljinsky 1929) belongs to the fragmental (disjunctive) type. Its quick reduction is connected with human activity.

In spite of extremely limited forest areas with *Larix polonica*, the latter for a long time already is represented in West Ukranian, Kaliningrad region and Lithuanian Republic's cultures. In all cases it is necessary to identify its stands.

Larix polonica is represented by two geographical (climatic) races, distinguished by the complex of morphological characteristics and growth conditions: typical (var. Typica Sz.), growing in Poland's central and north-western regions (and in the Western USSR regions in the past) and mountain (var. pienina Sz.), growing in Carpathisna, Tatra Mountains and Pienine. It differs from *Larix decidua* and *Larix sibirica* by the smaller micro- and macrosrtobiles. At the same time green cone form domination and construction of seed scales testifies *L. polonica* (especially its typical race) genetics connection with *L. Sukaczewi*. It is possible, that at the south-eastern border of its distribution it (mountain race) hybridizes with *L. decidua*. But we haven not enough grounds to classify *L. polonica* as hybrid larch (*L. decidua* x *sibirica*), as E.G. Bobrov (1972, 1978) does. Its populations (especially near Visla) are rather mono-morph and do not have intermediate or supposed parent forms. Moreover, *Larix polonica* individuals essentially differ from available *L. decidua* and *L. Sukaczewi* hybrids. History and phylogeny of *L. polonica* need further study with wider natural and introduced populations' hybrodological analysis.

Larix decidua Mill.

In the USSR it grows in Carpathians. In artificial stands in Western and number of Central USSR's European part districts it, like *L. polonica* often exceeds in productivity *L. Sukaczewi* and *L. sibirica* cultures (sometimes worse in wood quality).

Since *Larix decidua* area is arranged mainly for different Alps and Tatra Mountains zones, its populations are very unequal. Mother stand altitude and its gene pool differentiation by separate geographical provinces are different in their history and introduction perspectives influence on the *Larix decidua* progeny growth and resistance first of all.

Larix sibirica Ldb.

The greater part of the species area is arranged to the low moisture region in the continental mountainous districts of Southern Siberia. *Larix sibirica* occupies. more cold places in comparison with *L. Sukaczewi*. At the same time it is less cold resistant than *L. gmelinii*.

The border with the latter coincides with the permafrost soil distribution limit. In the *Larix sibirica* and *L. gmelinii* areas boundary zone hybridogene populations of these two species are concentrated, they are called *Larix Czekanovskii.*

In the result of the herbarium collection study, Szafer (1913) singled out *Larix sibirica* Altai form. Subsequent investigations (V.N. Sukachev, 1924, 1934, 1938; N.V. Dylis, 1947) differentiated *L. sibirica* on Altai, upper Enisei (Saian), upper Lena and subarctic geographical races. At different times these races were considered as varieties, climatic (geographical) ecotypes or subspecies.

Larix sibirica significant polymorphism was proved by its gene pool, detailed study in natural populations and in geographical cultures. Silviculturists' special attention was attracted by *Larix sibirica* populations pronounced unequality in the different mountain altitude zones of Southern Siberia.

Detailed study of *Larix sibirica* variation in natural populations and geographical cultures established in the different Siberian zones allows to varify its intraspecific differentiation

and to use its gene pool more effectively (Iroshnikov, 1981, 1985).

Altai race comprises middle mountainous and high mountainous populations of Saura, Central, Southern and Mongolian Altai. It characterises by comparatively weak polymorphism (green cone form with elastic pointed and oval scales are absolutely prevailing).

Enisei race is the most large and heterogeneous. It includes populations of north-eastern Altai, Kuznetsk Alatau, Western and Eastern Saian, Tannu-01, Khamar-Daban, Khangai, Khetenei and near Angara river. Moreover, Selenga, upper Enisei and especially upper Ob populations experience strong gene migration pressure from the Altai race population. This fact causes its high polymorphism. Populations of the Eastern Saian, Khetenei are more uniform, they are remarkable for absolute domination of red-cone forms with hard broad oval seed scales. In the Eastern Khetenei spurs this race crosses with *Larix gmelini*.

Subarctic race is represented by forest tundra and Northern Taiga subzone populations; from the Nadim basin in the West up to the Norilka basin in the East. In the lower Ob *Larix sibirica* and *L. Sukaczewi* introgressive hybridization zone is pronounced. The latter is arranged for less cold locations than *Larix sibirica*.

Baikal and Lena races in the north-western part of its area exercise *Larix gmelinii* pressure and in the south-eastern part — Enisei race population pressure. These races are close to the latter. Rare isolated populations of the Western Siberia lowland central part and also hybridogene populations in the *Larix sibirica* and *L. Sukaczewi* contact zone need supplementary study.

Pointed out *Larix sibirica* race division reflects species location history at the post glacial period. In the process of migration, mutation, crossing and tolerant genotypes selection further race differentiation in connection with latitude and altitude took place. The most valuable *Larix sibirica* gene pool is concentrated in its optimum area: in the Southern Siberia plain, pre-mountainous and low mountainous populations. Cultures established from seeds of those populations in the Siberian Southern Taiga regions are characterized by the highest growth and resistant properties (Table 1). Progenies from the Northern Taiga high mountainous populations have extremely low productivity.

Table 1. Average height and total yield of the 17-years old Larix sibirica Ldb. cultures in Krasnoyarsk partially-wooded steppe.

Seed origin			Height		Total yield	
Region, Autonomous Republig	Forest district	Subzone altitude, m	cm	% from the control	m^3/ha	% from the control
Khakasia	Sonsk	700-900	744±12	100	87	100
Kransoyarsk	Aban	Southern taiga	785±15	105	112	128
Irkutsk	Irkutsk	500-900	733±50	99	95	109
Krasnoyarsk	Ust-Angarsk	middle taiga South	730± 8	98	80	92
Tuvinskaya	Kaa-Khem	900-1 200	642±20	86	61	70
Mountain-Altai	Chemal	900-1 500	574±16	77	50	57
Mountain-Altai	Ust-Kansk	1 000-1 600	524±18	70	44	51
Tuvinskaya	Turansk	900-1 500	552±18	74	36	41
Mountain-Altai	Verkhnekatun	1 100-2 000	482±26	65	24	28
Eastern Kazakhstan	Marakol	1 450-2 000	170±24	23	3	2
Eastern Kazakhstan	Kurchum	1 500-2 200	50± 6	7	0	-
Krasnoyarsk	Turukhansk	forest tundra	30± 3	4	0	-

Cultures, established from seeds of the middle mountainous and middle taiga subzone populations are characterised by intermediate properties. *Larix sibirica* from forest tundra and from its upper growth limit in the Altai-Saian mountainous country (1 800 - 2 200 m) practically eliminates by 10 - 15 years during its cultivation in low mountain and partially wooded steppe regions. The reason for that population progeny failure is shoot destruction by frost because of its growth process rhythm destruction in new locations.

Larix sibirica subarctic race (as well as its *Larix gmelinii* and *L. Kajanderi* corresponding races) present for special attention the investigation of the forest and arctic tundra relations; the possibility that the Northern forest zone limits artificial displacement and establishment of protection stands in tundra and study of woody species vital functions in the North limit of its location, subarctic conditions adaptation mechanisms and forest growth in tundra limiting or proventing factors.

Larches, growing in the Siberian Far North and characterized by short vegetation period; vegetation beginning and passing at low air and soil temperatures fast reaction on temperature change: good development of assimilation mechanisms; brachyblast primary formation (in comparison with aucsiblast); protection substances and highly energetic metabolism significant accumulation; long photoperiod; vital forms and mutants (stunted, bush-like, dwarfish) high lability; low reproduction, compensated by rather high life length; high inbreeding and polyembriony frequency (Iroshnikov A.I., 1983; Iroshnikov A.I., Fiodorova A.I., 1974).

Dendroflora adaptation to the far north conditions is long evolution product, which is characterized by northern populations' genotypic composition quality change. The less adaptive to the extreme Northern conditions are reproductive systems of the majority coniferous species and larch among them. Vary rare seed years, bad pollen regime, flowering, fertilization and seed ripening unfavourable conditions cause its deficiency or even complete sterility and that is one of the main reasons of many woody species low competebility in the Northern part of its area. In that sense contemporary northern continuous and isolated forest growth boundary is climatic as far as termic regime here determine the efficiency of woody species sexual reproduction.

Larix sibirica mountainous populations (altitude more that 900 m) should satisfy only seed requirements of high-altitude zones corresponding in natural division into districts. Breach of these requirements leads to quick reduction of productivity and resistance in artificial stands.

In *Larix sibirica* populations occur in the same forms as in *L. Sukaczewi* but some regions in its area essentially differ by its representation. Certain shifts in the genotypic composition result from latitude and altitude change (for example, in representation of forms with narrow-oval or pointed seed scales. Increase of thick-barked form frequency in populations occurs in more continental climate. Representation of some forms in different area parts allows it to reveal its adaptive significance and larch migration ways in the post glacial period (see Figure 1). But breeding significance of some *Larix sibirica* forms is poorly studied; its available values (for example, green- and red-cone forms) are rather contradictory.

Larix gmelinii Rupr.

The species occupies a large part of the middle Siberian plateau, Western Trans-Baikal, Northern China and Western part of the Mongolian People's Republic, which are characterized by continental climate and long or permafrost soil distribution. On the south-western border it hybridizes with *Larix sibirica*, on the north. eastern — with *L. Kajanderi* and on the south-western — with the far eastern species mainly with *Larix kurilensis*. It clearly differs *from L. Kajanderi* by more rounded form and less angle seed scales deflection from cone axis, by oval form and more dense cone consistency.

For the species populations geographical and individual variations are typical. In the

Larix gmelinii populations there are small and have large-cone forms, green and red cones and also intermediate in cone colour forms, bush-like and others. In the *Larix gmelinii* south-western area green-cone partly may be observed form domination. But its representation decreases in central and especially North Yakutia regions.

During the introduction from low-mountainous populations of the south-eastern area part to the more temperature climate regions it characterizes by very good growth during the first 15 - 25 years. But later it appears to be unresistant or slow down its growth. That is why it is necessary to select fast growing forms in the optimum zone for introduction and hybridization.

Larix gmelinii northern populations (as *L. sibirica*) are absolutely unresistant during its introduction to the Western or Southern regions. In the whole climate races of the species are not studied yet.

Larix Kajanderi Mayr.

Many botanists do not approve its status of the species. V.L. Komarov (1934), for example, considers it to be of northern, more continental *Larix gmelinii* race. Its species area to a great extent coincides with the steady Yakutsk anticyclone and the lowest in the Northern hemisphere winter air temperature region.

In the contact zone with *Larix gmelinii* A.P. Abramov and I.U. Koropachinsky (1984) recorded hybridogene populations of these species. On the South Western border of its distribution *Larix Kajanderi* crosses with *L. kurilensis*. Larch, growing on the central Kamchatka regions, was classified by E.G. Bobrov as *L. Kajanderi*. But N.V. Dylis (1961) singled it out (and larch from the Okhotsk coast and Northern Sakhalin) as Northern, Okhotsk-Kamchatsk race of *Larix kurilensis*.

In *Larix Kajanderi* a number of form was singled out by the colour, size and cone and seed scales type. In the whole geographical and intraspecific variability of the species is poor studied. Progeny trials of some *L. Kajanderi* populations above its area testify the species unpromising introduction. In the less continental climate, its cultures are characterized by weak resistance and bad growth.

Larix kurilensis Mayr.

Besides above mentioned northern race N.V. Dylis (1961) singled out southern, island, race which is spread in the Southern Kuril Islands (Shikotan and Inturup) and in the large part of Sakhalin. *Larix kurilensis* is typically maritime form. Besides two geographical races it has several types by the cone form.

The species was widely tested in cultures only in Baltic Republics where it demonstrated good growth. *Larix kurilensis* x *L. decidua* hybrid in Leningrad demonstrated especially high growth characteristics (Dylis 1961). But they were poorly frost resistant there. Similar hybrid in FRG (Bavaria) had total height growth of 15 m in the age of 17 years. These experiments testify that in more warm and moist USSR's regions *Larix kurilensis* can be used as the fast growing larch breeding form.

Larix olgensis Henry

The species has very limited area - area solitaria (it is located in one very limited point), occupying most from the Valentine bay up to Vladimir Bay. Some authors say about its distribution in Korea and China's north-eastern regions. But V.L. Komarov's (1934) collections did not prove it.

I.K. Shishkin (1933) and B.P. Kolesnikov (1946) singled out a number of morphological forms and ecotypes. But it is not yet clear whether it is connected with species' polymorphism or with *Larix olgensis* natural hybridization with other Far Eastern Larix species.

G.V. Gukov (1976) considers that *Larix olgensis* is more warm loving than other Sikhote-Aline Larix species. In his opinion it is a poorly resistant form (because of slow growth rate, bad seed quality, etc.).

Larix olgensis during its crossing with *Larix sibirica* gives fast growth in the first years hybrid progeny. One can believe that the species gene pool became poor as the result of intensive' exploitation during 150 years and intermittent fire. That is why through protection of available plots and fast-growing resistant forms selection is needed. Wide progeny and hybrid trails in the regions with warm and moist climate are also necessary.

Larix maritima Sukacz.

One of the least studied USSR's larches. Its species status is rather disputable. E.G. Bobrov (1972, 1978) considers *Larix maritima* as a natural *Larix Kajanderi* x *L. kurilensis* hybrid. Its area according to G.V. Gukov's data, is rather limited: in the river Koppy and Botchy basisns flown into Tatar strait. In cultures *Larix maritima* is studied unsufficiently and its growth rate data are contradictory. G.V. Gukov considers that *Larix maritima* is one of the most fast growing species of the Far East. It is almost absolutely resistant to fungus diseases.

Natural hybridization processes on the species area boundary have been mentioned already. Some systematists consider hybridogene populations as independent species, others as hybrid larches. On the USSR's territory N.V. Dylis (1961) singled out 4 hybrid groups: *Larix Gzekanovskii, L. ochotensis, L. amurensis, L. Lubarskii*. Besides he pointed out larches hybridization in the contact area of *L. Siberia* and *L. Sukaczewi*.

E.G. Bobrov (1972, 1978) singled out 5 larches formed in the introgression hybridisation process: *Larix Czekanovskii, L. maritima, L. Lubarskii, L. polonica* and *L. Kajanderi* x *kamtshatica* hybrid.

Among hybridogene species only *Larix Czekanovskii* is the most fully studied (Kruklis, Milutin, 1977). For that species introgression specific pecularities in the parent species populations were shown in the result of isolation mechanisms (ecological barriers in the first place) and character of pecularities combination and splitting in hybridogene populations. It was established that this natural hybrid does not have a specific kariotype. Increased hybridogene *Larix Czekanovskii* variability level is distinctive only for quality characteristics. Hybridogene species regardless of occupied territory are interesting for breeding of individuals with heterosis effect.

SUMMARY

Rapid growth rate, high wood quality, practically unlimited possibility of distant crossing (with hybrid progeny significant heterosis effect), high polymorphism, adaptation extreme environmental conditions, wide introduction perspectives beyond area boundaries of many Larix species attracted attention of silviculturists, botanists and plant-breeders. Some of the species, races and populations form the forest boundary on the Northern limit of dendroflora distribution and its upper boundary in the mountains. Within Eurasia, with the increase of the continental climate, the following species change is observed: *Larix Sukaczewi Dyl.* — *L. sibirica Ldb.* — *L. Czekanowskii Sz.* — *L. gmelinii Rupr.* — *L. Kajanderi* Mayr. Subpolar populations of the mentioned species are a convenient object for the study of the woody species adaptation mechanisms to the extreme environmental conditions.




Figure 1. Structure of the Larix sibirica Ldb. populations within the species area and Larix Sukaczewi Dyl. population in the south-eastern part of the area according to female cone colour: 1. green cone, 2-3 intermediate forms (2. green cone with narrow red edge of seed scales; 3. red cone with small green spots in the lower part of seed scales), 4. red cone.

LARCH IN NORTH AMERICA

Edmond C. Packee

ABSTRACT

Three species of *Larix* are native to North America *L. laricina* is a transcontinental component of the Boreal Forest Zone; *L. lyallii* is a scattered component of the upper Subalpine Zone of the Rocky Mountains and Cascade Mountains of the northern United States and southern Canada; and *L. occidentalis* is a component of the lower elevation, Montane Zone, of the same mountainous region, The silvics, emphasizing range, productivity, habitat, and reproduction characteristics of the two species most suited to northern regions is reviewed.

INTRODUCTION

Three species of *Larix*, *L. laricina* (Du Roi) K Koch, *L lyallii* Parl., and *L. occidentalis* Nutt. are native to North America. Within *L. laricina* is placed *L. alaskensis* W.F. Wight which has been shown to be neither a separate species nor a subspecies (Ostenfeld and Larsen 1930) although some botanists give it varietal status (Fowells 1965).

L. laricina has the broadest range of the three species (Figure 1). It is transcontinental, ranging from the Atlantic shore of Newfoundland nearly to the shore of Norton Sound of the Bering Sea in Alaska (Fowells 1965; Viereck and Little 1972). Its east-west range covers approximately 107 degrees of longitude. It reaches its southern limit in the eastern United States in the Appalachian Mountains of West Virginia at approximately 39° N. Latitude and its northern limit, on the delta of the Mackenzie River in the Northwest Territories of Canada, is about 68.5° N. Latitude. East of the Mackenzie River, it is commonly a tree line species whereas to the west it commonly does not reach as far north as *Picea glauca* (Moench) Voss. The north-south range covers approximately 30 degrees of latitude; the northern most portion of its range is in the west, particularly in the Mackenzie River drainage. It grows from sea level to 520 m in the western portion of its range and to 1 220 m in the east.

Inspection of the range maps (Fowells 1965; Viereck and Little 1972; Dobbs et al. 1976) for *L. laricina* indicate three distinct populations: 1) Mackenzie River drainage and eastward, 2) Alaska, and 3) the Prince George-Quesnel area of the Fraser River drainage in British Columbia. Within the Yukon Territory, the gap is not as pronounced as suggested by the range maps; the status of the gap in Alaska has not been adequately defined.

L. lyallii and *L. occidentals* are much more limited in their range Both are confined to the Rocky Mountains and Cascade Mountains and particularly, but not exclusively, to the drainages of the Columbia River and Fraser River systems. *L. occidentalis* is confined to drainages west of the Continental Divide in Montana, Idaho, Oregon, Washington, and British Columbia. The latitudinal range is approximately 7.5 degrees, from approximately 44° to 51.5° N. Latitude and the longitudinal range is nearly 9 degrees, between 112.5° to 122° W. Longitude. It typically occurs at elevations between 500 and 2 100 m.

L. lyallii is a sub-alpine species with two distinct populations: 1) Cascade Mountains of Washington and British Columbia between 47.5° and 49.5° N. Latitude and 2) Rocky Mountains of Idaho, Montana, British Columbia, and Alberta between 45.5° and 51.5° N.

Edmond C. Packee Assistant Professor of Forest Management Agricultural and Forestry Experiment Station University of Alaska Fairbanks, Alaska, USA 99775

Latitude (Arno and Habeck 1972; Dobbs et al. 1976). In the Cascades it occupies a longitudinal range of nearly one degree and in the Rocky Mountains, a longitudinal range of nearly five degrees. In the Rocky Mountains it occurs primarily west of the Continental Divide especially in British Columbia; however it Crosses the Divide in numerous places. The absolute elevational limits of *L. lyallii* are about 1 520 and 3 010 m (Arno and Habeck 1972); however, it typically occurs at elevations from 1 800 m to alpine tree line (Arno and Habeck 1972; Krajina 1969). The Cascade Mountains' populations are at lower elevations than the Rocky Mountains populations; this reflects regional differences in the elevational limits of the Subalpine Zone. The range is relatively discontinuous; populations are confined to the higher mountains and separated by the lowlands. The range is much more restricted than that suggested by Ostenfeld and Larsen (1930).

From the range data, it is obvious that there is little likelihood of natural hybridizing between *L. laricina* and *L. occidentalis* or *L. lyallii*. Generally, *L. lyallii* and *L. occidentalis* are separated from each other by at least 150 m of elevation; occasionally the two species do mix and hybridize (Carlson 1965; Little 1979). Dobbs et al. (1976) state that the two species may naturally hybridize where their ranges approach or overlap one another.

In addition to the native *Larix*, species native to Europe and Asia and hybrids have been planted quite extensively in North America. Species include: *L. decidua* Mill., *L. gmelini* (Rupr.) Lit. (*L. dahurica* Turcz.), *L. kaempferi* (Lam.) Carr., and *L. sibirica* Ledeb.

L. occidentalis reaches the greatest size of all the Larix species. Franklin and Dyrness (1973) suggest typical ages in excess of 700 years and diameters of 140 cm and heights of 50 m in the Pacific Northwest, Fowells (1965) reports a record, maximum age of 915 years and diameters greater than 200 cm. On the best sites, trees can be 70 to 80 m tall (Hitchcock et al. 1969). However, it has limited potential in the northern forest since it is unique as the only *Larix* species "definitely not a tree of arctic or alpine timberlines" (Arno and Habeck 1972) and is generally associated with a moderately long vegetative season .

L. lyallii, although a species of the subalpine timberline, reaches relatively large sizes. Arno and Habeck (1972) report trees up to 160 cm in diameter and 26 m tall in the Bitterroot Mountains of Montana; the largest tree found was in the Cascades and has a diameter of 190 cm. They report an average life span for the species of 500 years with many individuals reaching ages of 700 years and the oldest being nearly 1 000 years. *L. lyallii* occupies sites having rigorous climates; temperatures are below freezing for more than one-half the year and recorded minima are less than -55°C (Arno and Habeck 1972, Krajina 1969). Hence, *L. lyallii* may have some potential in the northern forest, especially at lower latitudes.

L. laricina, primarily a species of the Northern Forest, does extend southward to intermingle with the Grasslands in the west and the North American Deciduous Forest in the east. It reaches neither the great age nor the size of its North American relatives. Fowells (1965) gives a maximum reported age of 335 years but notes that typically the maximum age is 150 to 180 years and Harlow and Harrar (1958) state that maturity is reached in 100 to 200 years. Brown (1983) reports trees 130 years old from a bog in Alaska. Tree diameters are typically under 60 cm; Harlow and Harrar (1958) report a maximum diameter of 91.5 cm and Fowells (1965) citing reports in the literature states that a few reach 91 to 101 cm. The U.S. Forest Service (1908) states that it rarely attains a diameter greater than 76 cm. The largest tree in Alaska is reportedly 33 cm in diameter; however, there are reports of trees slightly larger. In north-eastern British Columbia, on a wet hydrothermal site at Liard River Hot Springs (Latitude 59.4° North) several large trees occur in one grove, the largest is greater than 50 cm in diameter. *L. laricina* trees occasionally may exceed 25 m in height (Harlow and Harrar 1958). The U.S. Forest Service (1908) states maximum heights rarely exceed 30 m.

Hence, two species of North American *Larix*, *L. lyallii* and *L. laricina*, have potential

for management in the Northern Forest. These two species, especially the latter will be emphasized in further discussions. There is, however, little published information concerning *L. lyallii*.

PRODUCTIVITY

Only Krajina (1969) provides comparative site index (base age = 100) information for the three North American species of *Larix* (Table 1). However, he provides no height-over-age curves.

Table 1. Growth classes and associated site indices (base age = 100) for the North American species of Larix (from Krajina 1969).

Growth class	Site Index in metres		
	Lala	Laly	Laoc
Ia	24	15	39-42
Ib	22.5	13.5	36
IIa	21	12	33
IIb	19.5	10.5	30
IIIa	18	9	27
IIIb	16.5	7.5	24
IVa	15	6	21
IVb	12	4.5	18
Va	9	3	15
Vb	6	1.5	12
Vc	<5	<0.75	<4

Note: For species codes see Appendix I.

Gevorkiantz (1957) published anamorphic site index curves (base age 50 years, total age) for *L. laricina* (Figure 2); these curves must be questioned. Heffernan (1987) located eight sites in Alaska with *L. laricina* having a breast height age equal to or greater than 50 years. Free hand curves of her data are presented in Figure 2 for comparison. Bolghari and Bertrand (1984) developed site index curves for plantation grown *L. laricina* in Quebec province, they used total age = 25 years for the index age. Their curves are also presented in Figure 2. It is apparent that existing site index curves for *Larix laricina* require considerable refinement.

No site index curves exist for *L. lyallii*.

The growth and productivity of *Larix laricina*, despite the species' wide range, has not been seriously studied until quite recently. Kellogg (1907) reports on one small plantation (less than 0.05 hectare) in Bureau County, Illinois, which is south of the species' natural range; at 45 years, trees within this plantation having an initial spacing of 1.5 x 1.8 m averaged 18.5 cm dbh and 17.4 m in height. These trees averaged 0.21 cm of radial increment per year and 0.5 m of height growth. Beeftink (1951) reports similar height growth for natural stands in Alberta.

Stiell (1986) provides some of the most detailed growth information available on its early growth. His data are for a 1970 levels-of-growing-stock plantation in which the first measurements were obtained in the autumn of 1978; a portion (three of the six spacings) of his data are presented in Table 2. For the six year period, 1979 through 1984 growing seasons inclusive, mean annual radial growth at breast height ranged from 0.25 to 0.55 cm and was positively correlated with spacing; mean annual height growth ranged between 0.6 and 0.7 m and was not correlated with stand density. Stand mean annual basal area growth ranged from 0.7 to 2.0 m 2/ha and was inversely related to the number of stems per hectare.

Hall (1983) compared early height growth of *L. laricina* with that of other native and exotic conifers in Newfoundland (Tables 3 and 4). His data show that height growth of plantation grown *L. laricina* exceeds that of the other native conifers and may equal, exceed. or be less than non-native *Larix* species. With respect to the non-native species of *Larix*, the relationship depends upon species and/or provenance. The height growth relationships among the species of *Larix* is certainly unclear. Reimeschneider and Nienstaedt (1983) present five and eight year old height growth data for various species and hybrids of Larix planted in

Wisconsin; their data are presented in Table 5. Note how the ranking of the various species and hybrids changed over a three year period.

Table 2. Average stand characteristics for 15-year-old *L. laricina* plantations of various spacings on an upland site at the Petawawa National Forestry Institute, Ontario, Canada (from Stiell 1986).

	Year	Nominal planted spacing, m		
		1.75	3.00	4.25
Trees/ha	1978	2,488	1,058	550
	1984	2,262	1,043	532
Mean dbh, cm	1978	3.7	4.2	4.6
	1984	8.0	10.0	11.3
Mean height, m	1978	4.4	4.6	4.6
	1984	8.4	8.7	8.5
Dominant height, m	1978	5.8	5.8	5.9
	1984	10.0	9.6	9.8
Basal area, m^2/ha.	1978	2.6	1.5	0.9
	1984	11.0	8.2	5.4
Total volume, m^3/ha.	1984	46.1	35.1	21.4

Table 3, Average total height of planted 15-year-old *Larix laricina* and other conifers on four sites in Newfoundland (from Hall 1983).

Species/Provenance	Location			
	Bottom Brook	North Pond	Windsor Lake	Avondale Heathland
	(height, m)			
Lala/Nova Scotia	4.58	4.68	2.90	4.12
Lade/Central Europe	4.72	2.16	1.88	
Lade/Germany Region 6	4.52	1.86	2.27	
Laka/Germany Region 7	4.97	3.03	2.52	
Laka/Germany Region 7	4.79	3.64	3.15	
Laka/Honshu Japan	5.31	2.45	2.87	
Pigl/Nova Scotia				1.21
Pima/ New Brunswick	3.13	1.48	1.68	
Pima/Newfoundland				1.20
Piba/New Brunswick				3.28
Pisy/Scotland, Morayshire				2.73

Table 4. Average total height of 8 year old *L. laricina* and exotic species of *Larix* planted on a productive forest site in western Newfoundland (from Hall 1983).

Species/Provenance	Height m	Statistical relationship
Lala/Petawawa, Ontario	1.21	b
Lasi/Krasnojarsk, USSR	.92	d
Lasi/Krasnojarsk, USSR	.62	e
Laka/High Meadow Forest, England	1.32	b,c
Laeu/Newton Seed Orchard, Scotland	1.56	a
Laeu/Mabie Seed Orchard, Scotland	1.49	a,c

(Note: Statistical relationship: means with the same letter are not significantly different from each other at 0,99 probability.)

Table 5. Mean heights at five and eight years for various species and hybrids of *Larix* at one site in northern Wisconsin (from Reimenschneider and Nienstaedt 1983).

Species	Number of Seed-lots	5-year Height m	5-year Rank	8-year Height m	8-year Rank
Lasi	1	1.83	8	4.31	3
Lade	9	1.85	6	4.19	4
Laka x	4	1.85	7	3.70	8
Laka	3	2.16	1	4.69	1
Laka x Lade	1	2.09	2	4.48	2
Laka x (Laka x Lade)	5	1.90	5	3.94	6
Lade x (Laka x Lade)	10	1.93	3	4.17	5
Lala (Ont)	4	1.93	3	3.80	7

Vallee and Stipanic (1983) provide height growth data for 3 *Larix* provenance trial at the Lotbiniere, Quebec arboretum. After 10 years, thirteen provenances of *L. laricina* had a range in mean height of 4.9 to 6.0 m; the average height of all provenances was 5.4 m. The range of mean height for four provenances of *L. decidua* was 4.8 to 5.8 m and the average of the four was 5.3 m. The range for two prove-

nances of *L. kaempferi* was 5.5 to 5.8 m and the average was 5.6 m; one of these seed sources was from the Honshu seed orchard. Thus on the basis of these early results, certain provenances of *L. laricina* appear to have height growth comparable with that of non-native Larix species.

Bolghari and Bertrand (1982) cited by Vallee and Stipanic (1983) sampled a large number of conifer stands in southern Quebec and found the *Larix* species to be the fastest growing.

Their height data (from Vallee and Stipanic 1983) at 25 years are presented in Table 6. Note that on the better sites, the exotic Larix had better heights than *L. laricina* and off-site, the poorer sites, the situation is reversed. Bolghari and Bertrand (1984) later produced yield tables for the 118 *L. laricina* plantations. Site index (index age = total age of 25 years) ranged from 8 to 18 m.

Table 6. Mean, minimum, and maximum height (site index) of various coniferous species' plantations in southern Quebec, Canada (from Bolghari and Bertrand 1982 as cited by Vallee and Stipanic 1983).

Species	Number of plots	Height at 25 years, m		
		Mean	Minimum	Maximum
Pire	289	11.8	6.0	18.1
Pist	59	9.4	5.8	12.7
Pisy	149	10.3	5.8	14.4
Pigl	249	8.9	4.4	15.1
Piab	120	9.9	6.6	15.7
Lala	118	14.3	9.3	18.2
Lade/Laka	70	16.2	8.4	23.7

Jeffers (1975) compared the height growth of nine-year-old planted *L. laricina* provenances on good upland sites at two locations in northern Wisconsin. At the Forest County site, the range of heights for six provenances was 2.6 to 3.2 m with a mean of 2.8 m; at the Onieda County site, the range of heights for four of the same provenances was 2.1 to 3.2 m with a mean of 2.4 m. He also reported on the growth of eight-year-old plantings. At the Forest County site, the range of heights of 18 provenances was 1.3 to 2.3 m with a mean of 1.95 m. At this location, five provenances, three from Wisconsin, one from Minnesota, and one from Maine, exhibited the best height growth with means above 2.1 m; two Michigan and the Alberta sources had the poorest height growth with means below 1.8 m. It is noteworthy that the Alberta source (Latitude 56.6° N and Longitude 111.2° W) only reached a height of 1.3 m at this site (Latitude 46.0° N and approximate Longitude 89° W). At the Oneida County site, 16 provenances (the Alberta source was not included) had a range in heights of 1.4 to 2.0 m with a mean of 1.7 m. The five best provenances, including two (Wisconsin and Maine) from the five best at the Forest County site, had mean heights in excess of 1.9 m.; the other provenances were from the upper peninsula of Michigan, southern Ontario, and Nova Scotia. The three poorest seed sources, with height growth less than 1.5 m, were from Minnesota and Michigan. One of these poor sources, the Minnesota (Anoka County) near the south-western edge of the range, ranked second among the top five at the Forest County site.

The above growth rates for young plantations could be considerably greater than that suggested for natural stands.

On a variety of sites in Alaska, Heffernan (1987) compared the competitive ability of *L. laricina* and its associates. She determined the time necessary for natural, established seedlings (15 cm tall), seedlings or hardwood sprouts, to reach breast height (1.4 m). *L. laricina* typically reached breast height sooner than *Picea glauca* (Moench) Voss and *P. mariana* (Mill.) B.S.P.; its height growth was only slightly less to slightly better than that of its hardwood associates, *Betula papyrifera* Marsh., *Populus balsamifera* L., and *P. tremuloides* Michx. She found on many sites that it took established seedlings three to seven years to reach breast height; however, on poor sites, the time to reach breast height was often greater than ten years. She also developed height-over-age curves for trees 25 years and older and found typical heights ranging from 6.2 to 12.2 m at 25 years of age. Best growth was on the drier

sites having a thin organic horizon and/or where there was a high component of broadleaf trees, *Salix* spp., and/or *Alnus* spp. Poorest growth was on wet soils with permafrost and a thick organic horizon and/or where *L. laricina*, *Picea mariana*, and *Ledum qroenlandicum* Oeder were dominant. Thus, for apparently free-growing trees in natural stands, she found height growth rates to be similar to that reported for plantations.

Cooley (1904) states that the height of the average *L. laricina* in Hancock County, Maine at 15 years of age is 4.9 m, at 30 years it is 13.4 m, and at 45 years it is more than 18 m. She also refers to old trees in Wisconsin often being 30 m tall.

Information on diameter growth is limited. For Hancock County, Maine, Cooley (1904) reports the following diameters, the mean of many measurements:

2.5 cm at 8 years
6.4 cm at 11 years
19.0 cm at 20 years
21.6 cm at 25 years
45.7 cm at 45 years.

Thus over a period of 45 years, the mean annual radial growth is 0.51 cm. In northern Indiana she refers to trees 14 to 15 m tall being nearly 14.5 cm in diameter and trees between 18 and 21 m tall being 55.9 to 66.0 cm in diameter.

Data from Carpenter (1983) from four "representative natural" *L. laricina* stands in north-eastern Minnesota suggest mean annual radial growth rates of less than 0.30 cm for trees 50 to 75 years old. Data from northern Alberta (Wang et al. 1985), albeit the growth representing the mixed condition of before and after drainage, suggest relatively slower rates of radial growth, trees with a stump (50 cm above the ground surface) age of less than 35 years had mean annual radial growth rates of 0.17 to 0.25 cm. Our data from better sites in Alaska suggest mean annual radial growth rates of 0.20 to 0.25 cm for trees 30 to 40 years old.

As stated previously, Stiell (1986) reported that diameter growth of plantation *L. laricina* begins to be strongly affected by spacing between 10 and 15 years of age. His data indicate mean annual radial growth rates of 0.22 to 0.38 cm over the 15 year life of the plantations at Petawawa, Ontario. During the five year, initial period of competitive expression, mean annual radial growth ranged from a low of 0.25 cm on the high stocking plots to 0.50 cm on the low stocking plots.

Bolghari and Bertrand (1984) provide yield information for plantation grown *L. laricina* in southern Quebec province. Table 7 summarizes that yield data. Note that for wide spacing, 2.75 x 2.75 m, diameters range from 9.8 cm on poor sites to 24.3 cm on the better sites; the mean radial growth per year averages 0.14 to 0.35 cm, respectively.

Wang et al. (1985) demonstrated that drainage has an effect similar to release on *L. laricina*. Hence, the data of Bolghari and Bertrand (1984), Stiell (1986), and Wang (1985) demonstrate that management activities can greatly influence radial growth of *L. laricina* and must be considered in any effort to utilize the species successfully.

Arno and Habeck (1972) provide limited information concerning the growth rate of *L. lyallii*. They found stands with trees in excess of 25 m tall. In the Bitterroot Mountains of Montana-Idaho they found trees up to 26 m and they found trees near Harts Pass in the North Cascades of Washington 24 to 27.5 m tall. Often times, however, trees are stunted; trees several hundred years old may be only two to three metres tall. Individuals on the most favourable sites maintain growth rates of one centimetre radially per 8 - 10 years for at least 200 centuries. Individual trees can reach breast height diameters of 25 or more centimetres in 120 to 150 years and occasionally diameters greater than 60 cm by 200 years of age. Under harsh environmental conditions or strong competition, growth may be as little as one centimetre per 80 years centuries; one tree found on a dry site with strong competition from *Pinus albicaulis* Engelm. grew radially only six millimetres in 115 years! The limited data on the growth rate of *L. lyallii* in its natural habitat does not suggest the species for fi-

bre production; however Franklin and Dyrness (1973) note that its ameliorating influence on the site allows typical, lower elevation subalpine species (understory plants and trees) to ascend to higher elevations than would be otherwise possible. Hence, in spite of its slow growth, it may find an important role in the establishment of protection forests.

Table 7. Yield information for 35-year-old L. laricina in southern Quebec province, Canada (from Bolghari and Bertrand 1984).

Site index m	Spacing m	Dominat Height m	Mean Diameter cm	Basal Area m^2/ha	Volume Total m^3/ha	Volume Merchantable m^3/ha
8	1.50	10.1	9.8	18.75	86.76	60.58
	2.75	10.1	12.4	14.45	67.76	43.09
10	1.50	11.9	11.1	23.63	114.98	86.28
	2.75	11.9	14.8	18.57	90.56	64.01
12	1.50	13.7	12.4	28.51	145.62	114.59
	2.75	13.7	17.2	22.70	116.11	87.32
14	1.50	15.5	13.7	33.38	178.68	145.36
	2.75	15.5	19.5	26.82	143.71	112.81
16	1.50	17.2	15.0	38.26	214.17	178.53
	2.75	17.2	21.9	30.94	173.35	140.39
18	1.50	19.0	16.3	43.14	252.09	214.05
	2.75	19.0	24.3	35.06	205.05	169.99

HABITAT

The North American species of *Larix* are extremely shade intolerant. Fowells (1965) reports that although *L. laricina* can tolerate some shade during the first three or four years, once established, it must maintain an overstory position to survive. Armson (1983) states that as long as it is in the upper canopy of mixed stands, it can compete favourably with its associates. Because of its high shade intolerance, natural stands are largely restricted to wetlands (Spurr and Barnes 1980). Arno and Habeck (1972) report that *L. lyallii* is less tolerant than any of its associates which include *Pinus albicaulis* Engelm. and *P. contorta* Dougl. ex. Loud.

Both species tolerate extreme temperatures. Lowest recorded temperatures for *L. laricina* range from -29° to -62° C; maximum temperatures range from 29° to 44° C (Fowells 1965). Mean annual temperatures range from -9° C to more than 7° C (Rowe 1972). The average frost free period ranges from less than 75 days in Alaska and northern Canada to 180 days in the southern part of its range. Arno and Habeck (1972) report the lowest recorded temperatures within the range of *L. lyallii* are from the Rocky Mountains with the minima being -51° to -57° C. Temperatures in the Cascade Mountains are not as severe because of the maritime influence. Mean annual temperatures range from a low of at least -3°C in the Rocky Mountains of Alberta to 4°C in the Cascades of Washington. The average frost free period is extremely short; often every month has temperatures below freezing.

Krajina (1969) considers both *L. laricina* and *L. lyallii* to be calciphiles. Unfortunately does not present supporting data. Jeglum's (1971) investigated the correlation between plant species and pH and water level in peatlands near Candle Lake, Saskatchewan. He used pH to assign each stand to one of five fertility classes. Based on abundance and presence, he placed *L. laricina* in the eutrophic

class. Unless one considers the presence of *L. laricina* across the peatland landscape, this could be easily misinterpreted to mean that the species is nutrient demanding. Table 8 presents Jeglum's (1971) information regarding *Larix*. One interpretation of the data is that seedbeds characterized by a pH range of 5.0 to 6.9 are more conducive to the germination of seed and the early survival of *L. laricina* this could be due to species' interaction/competition. Also, the percentage of stands in which *Larix* is present appears to decline with increasing pH.

Fowells (1965) states that *L. laricina* tolerates high acidity. Curtis (1959), in describing the typical northern wet forest community found on Histosols in Wisconsin and in which *L. laricina* is a dominant. provides a community summary which suggests a typical pH of 4.7 and a calcium content of 755 ppm. On upland Spodosols and Inceptisols of the Boreal Forest where *L. laricina* is a minor species the suggested pH is 5.7 and the calcium content is 2 780 ppm. On the rich Histosols of the northern wet-mesic forest, where *Larix* is also a minor species, the typical pH is listed as 5.5 and the calcium content as 3 780 ppm. This suggests that *L. laricina*, at least in the Great Lakes portion of its range, tolerates a considerable range of available calcium.

Table 8. Distribution of Larix laricina near Candle Lake, Saskatchewan by pH class based on mean values of abundance/percentage presence (from Jeglum 1971).

pH range Fertility class	3.0-3.9 Very Oligotrophic	4.0-4.9 Oligotrophic	5.0-5.9 Mesotrophic	6.0-6.9 Eutrophic	7.0-7.9 Very Eutrophic
Number of stands	5	10	19	59	15
Size, cm dbh Trees, ≥10	67/40	7/10	14/11	67/19	6/7
Saplings, 2.5-10	50/20	18/40	41/21	485/17	11/7
Seedlings, <2.5	306/60	286/30	1420/21	1248/15	76/7

Tilton (1978) investigated the relationship of habitat to growth and foliar elemental concentrations. He found that *L. laricina* on northern peatlands and forested bogs with *Sphagnum* species present had lower foliar concentrations of N, P, Ca, and Mg and lower site index values than on fens with *Carex* species dominant and without *Sphagnum* species. However site indices were higher on sandy mineral soils where N and K concentrations were similar to that of the fens and the Ca and Mg concentrations were less!

Marie-Fortin (1927) reports that *L. laricina* is rare in the extensive lime stone areas of eastern Quebec.

Based on a sample of 127 stands throughout the range of *L. lyallii*, Arno and Habeck (1972) found *L. lyallii* sites often to be calcium poor.

In their search of the literature, they found only the statement of Krajina (1969) that this timberline species is associated with calcium-rich sites. In Montana, they found the species largely absent from limestone substrates. In Alberta where there is an abundance of limestone and dolomite, it was found mostly on quartzite, sandstone, and shales — the same type of substrate as in Montana. They conclude, it "seems to prosper on acidic substrates, generally low in calcium carbonate, throughout its distribution. Preliminary indications are that its development may be retarded or possibly even inhibited on basic calcareous soils." Mineral soil pH for the 127 plots ranged from 3.9 to 5.7 except for the Grave Peak site in Idaho which had a pH of 6.2.

With reference to *L. laricina*, it appears to grow on nearly every forest site within the northern forest zone (Fowells 1965). Cooley (1904) comments on finding it on deep mineral soils as well as shallow soils overlying bedrock in Maine. Mineral soil texture does not appear to be limiting since it is found on heavy clays to coarse sand (U. S. Forest Service 1908). Fowells (1965) reports its occurrence on woody peat and sphagnum peat. It can tolerate a wide range of soil moisture conditions. Best growth is on well-drained but moist soils (Wile 1981; Fowells 1965). Seedlings and saplings are susceptible to flooding and droughts (Duncan 1954, Armson 1983). Fowells (1965) comments that short periods of flooding do not seriously impact it; however, prolonged flooding will kill it.

REPRODUCTION

Cone and seed yield information are provided in Tables 9 and 10. Duncan (1954) studied the natural regeneration of *L. laricina* in Minnesota; much of what is known about its regeneration is still based on his work. He recognized it as the pioneer tree species on many sites. He identified four factors as affecting the success of natural regeneration: 1) the extreme shade intolerance of the species; 2) the need for a relatively constant water level and that both flooding and drought cause seedling mortality; 3) a satisfactory seed source (seed trees no more than one to two times their height from the site); and 4) rodent populations.

Good cone crops occur every three to six years (Cooley 1904; Duncan 1954) with trees less than 12 years old occasionally producing some cones. However, Armson (1983) points out that good crops on individual trees only begin to occur after 40 years of age. Both germinative energy and germinative capacity are low, 33 and 47 percent, respectively (Schopmeyer 1974), compared to most species of *Pinus* and *Picea*. Compared to other species of *Larix*, these values are not that low (Schopmeyer 1974). Farmer and Reinholt (1986) evaluated the influence of stratification, light, temperature, and genotype on L. laricina germination. They noted substantial variation in the germination response of individual families to the experimental conditions which suggests genetic control. They also commented on the high percentage of unsound seed due to failed embryos, 9 to 79 percent, and speculate that it also may have a genetic basis.

Table 9. Cone characteristics of North American species of Larix (from Schopmeyer 1974; Dobbs et al. 1976).

Species	Cone bearing age begins Years	Cone length mm	Period between collectable cone crops Years	Weight of hectolitre of cones kg	Seeds per hectolitre of cones kg
Lala					
US/LS	20-40	13-19	3-6	25	0.92
BC	40	10-15	5-6		0.17
ONT					0.68
Laly					
US	30-100	30-51	1-10		
BC	30	40-50			
Laoc					
US/MT-ID	25	25-40	1-10	31	0.62
BC	25	30-40	5-6		0.60

Table 10. Approximate number of clean seed per kilogram for North American species of Larix (from Schopmeyer 1974; Dobbs et al. 1976).

Species	Average	Range
Lala		
US	703 000	464 000 - 928 000
BC	629 000	595 000 - 694 000
ONT	557 000	495 000 - 725 000
Laly		
US	314 000	232 000 - 360 000
Laoc		
US	303 000	217 000 - 435 000
BC	289 000	178 000 - 343 000

In Alberta, Beeftink (1951) noted that *L. laricina* seed germinates in clumps of sphagnum moss. In Alaska we not that seedlings occur on recently exposed river alluvium high in calcium and magnesium salts (especially sul-

phate and carbonate with pH's in excess of 7) as well as the lower pH sites consisting of silty loess materials and/or organic materials; permafrost with an active zone less than one metre deep apparently is not a deterrent. Across its range, burned sites provide suitable seedbeds (Armson 1983; Johnston 1973, 1975). Although slash hinders reproduction, burning can have a negative affect on regeneration because it encourages the establishment and growth of competitive species.

Arno and Habeck (1972) report some *L. lyallii* seed is produced every year. They note that cones were not found on trees "less than about 100 years old" and that the species does not generally produce abundant crops until trees are more than 200 years old. They are of the opinion that successful regeneration occurs only at irregular intervals and then apparently under nearly ideal conditions as evidenced by the high recruitment. Shearer (1971) states that *L. lyallii* seed germinates very poorly or not at all without treatment to overcome seed dormancy. He found that soaking seed for 24 hours in a three percent solution of hydrogen peroxide increased germination from 0 to 5 to 28 percent; however, variation was great. Based on the limited data of Shearer's work, Schopmeyer (1974) gives the germinative energy as 9 percent and the germinative capacity as 14 percent.

CAUTIONS

It would be easy to say, "Both species hold promise and they are worth extensive trials." We really know very little about *L. lyallii*, but how much did we know about *Pinus radiata* D. Don) when New Zealand and Australian foresters began planting it in earnest at the turn of the century? I caution that the extreme paucity of information concerning *L. lyallii* must be recognized.

L. laricina, on the other hand, is known to have some problems-insects and disease. Cooley (1904) refers to the paucity of trees over 45 years of age in a large portion of Maine. She attributed this to a disease. It is interesting to note that in Alaska, more than three-quarters of a century later, we found a paucity of trees over 45 years-of-age. Howse (1983) states that native *Larix* was virtually eradicated from large parts of eastern North America in the late 1800's or early 1900's.

Pristiphora erichsonii Htg. (larch sawfly) has been suggested as the probably causal agent. Fowells (1965) states that it periodically becomes epidemic over large areas for several successive years with great reductions in growth and severe mortality. This is the most serious defoliator of *L. laricina* in eastern North America (Howse 1983).

Coleophora laricella Hbn. (larch casebearer), an insect introduced from Europe in the 1800's, is considered to be the second most serious defoliator of *L. laricina* in eastern North America (Howse 1983). Severe defoliation reduces growth and repeated defoliation results in mortality (Fowells 1965).

Dendroctonus simplex Lec. (eastern larch beetle) has caused serious damage and extensive mortality in the maritime provinces of eastern Canada and interior Alaska. It is commonly present in weakened stands but appears to be able to attack apparently healthy trees.

The majority of North American pathogens attacking *L. laricina* are of little consequence. The greatest concern is *Lachnellula willkommii* Hartig (European larch canker) which has been found in Nova Scotia, New Brunswick, and adjacent Maine, oldest cankers date from the mid-1970's. Howse (1983) reports, "In areas where the disease was found, from 3 to 100 % of the trees were affected and in 45 % of the infected stands examined the incidence exceeded 80 %." The disease causes mortality, reduced growth, and reduced wood quality.

In summary *L. lyallii* has some potential for afforestation and reforestation and should be considered for trial plantings in spite of the extreme paucity of information about it.

L. laricina, although it has some known, serious insect and disease problems shows great potential for fibre production in the northern forest. Much more information is needed concerning its silvics and silviculture

for its successful management on a wide variety of sites.

ACKNOWLEDGEMENT

This report is based on data collected as part of a larger program, "Predicting the Growth and Yield of Forest Stands in Interior Alaska" which is supported jointly by funds from the Agricultural and Forestry Experiment Station of the University of Alaska and a McIntire-Stennis Act contract.

CITED LITERATURE

Armson, K.A. 1983. Larch — silvics and silviculture. In: Graham, C.M.; Farintosh H.L.; Graham, 3.J. (ed.). Larch symposium, potential for the future. Proc. Symposium sponsored by Ontario Min. Nat. Res. & Univ. Toronto Fac. For., Toronto, Ontario, Nov. 9, 1982: 1-9.

Arno, S.F. & Habeck, J.R. 1972. Ecology of alpine larch (*Larix lyallii* - Parl.) in the Pacific Northwest. Ecol. Mono. 42: 417-450.

Beeftink, H.H. 1951. Some observations on tamarack or eastern larch. For. Chron. 27: 38-39.

Bolghari H.A. & Bertrand, V. 1984. Tables preliminaires de production des principales essences resineuses plantees dans la partie centrale du sud du Quebec. Gov. Quebec Min. Energie et Resources Serv. Recherche (Terres et Forets.) Mem. No. 79. 392 p.

Brown, K. 1983. Growth and reproductive ecology of *Larix laricina* in interior Alaska, Corvallis, OR: Ore. St. Univ. M.Sc. thesis. 154 p.

Carlson, C. 1965. Interspecific hybridization of Larix occidentalis and *Larix lyallii*. Missoula, MT: Univ. Mont. M.Sc. thesis. 60 p.

Carpenter, E.M. 1983. Above-ground weights for tamarack in north-eastern Minnesota USDA For. Serv. Res. Pap. NC-245. 9 p.

Cooley, G.E. 1904. Silvicultural features of Larix Americana. For Quart. 2:148-160. Curtis, J.T. 1959. The vegetation of Wisconsin. An ordination of plant communities. Madison, WI: The University of Wisconsin Press 657 p.

Dobbs, R.C., Edwards, D.G.W., Konishi, J. & Wallinger, D. 1976. Guideline to collecting cones of B.C. conifers. Brit. Columbia For. Serv./Can. For. Serv. Joint Report No. 3. 98 p.

Duncan, D.P. 1954. A study of some of the factors affecting the natural regeneration of tamarack (*Larix laricina*) in Minnesota. Ecology 35: 498-521.

Farmer, R.E., Jr. & Reinholt, R.W. 1986. Seed quality and germination characteristics of tamarack in north-western Ontario. Can. For. Res. 16: 680-683.

Fowells, H.A. 1965. Silvics of forest trees of the United States. USDA For. Serv. Agr. Hdbk. No. 271. 762 p.

Franklin, J F. & Dyrness, C.T. 1973. Natural vegetation of Oregon and Washington. USDA For. Serv. Gen. Tech. Rept. PNW-8. 417 p.

Gevorkiantz, S.R. 1957. Site index curves for tamarack in the Lake States. USDA For. Serv. bake States For. Expt. Sta. Tech. Notes No. 498. 2 p.

Hall, J.P. 1983. Comparison of the growth of larch with other conifers on reforested and afforested sites in Newfoundland. For. Chron. 59: 14-16.

Harlow, W.M. & Harrar, E.S. 1958. Textbook of dendrology. New York, NY: McGraw-Hill Book Co., Inc. 561 p.

Heffernan, T.T. 1987. Height growth of Larix laricina (Du Roi) K. Koch on a variety of sites in interior Alaska Fairbanks, AK: Univ. Alaska M.Sc. thesis. 89 p.

Hitchcock, C.L., Cronquist, A., Ownbey, M. & Thompson, J.W. 1969. Vascular plants of the Pacific Northwest. Part 1: Vascular cryptograms, gymnosperms, and monocotyledons. Seattle, WA: University of Washington Press. 914 p.

Howse, G.M. 1983. Pests of larch: Biology, damage, and control. In: Graham, C.M. Farintosh. H.L.; Graham, B.J. (ed.). Larch symposium, potential for the future. Proc. Symposium sponsored by Ontario Min. Nat. Res. & Univ. Toronto Fac For., Toronto, Ontario, Nov. 9, 1982: 35-45.

Jeffers, R.M. 1975. Survival and height growth of tamarack planted in northern Wisconsin. USDA For. Serv. Res. Note NC-l90. 3 p.

Jeglum, J.K. 1971. Plant indicators of pH and water level in peatlands at Candle Lake, Saskatchewan. Can. J. Bot. 49: 1661-1676.

Johnston, W.F. 1973. Tamarack seedlings prosper on broadcast burns in Minnesota peatland. USDA For. Serv. Res. Note NC-153. 3 p.

— 1975. Reproducing lowland conifer forests. J. For. 73: 17-20.

Kellogg, R.S. 1907. Forest planting in Illinois. USDA For. Serv. Circ. 81. 32 p.

Krajina, V.J, 1969. Ecology of forest trees in British Columbia. Ecol. West, No. Amer, 2(1): 1-147.

Little, E.L., Jr. 1979. Checklist of United States trees (native and naturalized). USDA Agr, Hdbk. No. 541. 375 p.

Martie-Fortin (Frere). 1927. Les gymnospermes du Quebec. Montreal, QUE: Montreal Univ. Bot. Lab. Contrib. 10. 147 p.

Ostenfeld, C.H. & Larsen, C.S. 1930. The species of the genus Larix and their geographical distribution. K. Dan. Vidensk. Selsk. Biol. Medd. 9(2). 106 p.

Reimenschneider, D.E. & Nienstaedt, H. 1983. Height growth to age 8 of larch species and hybrids in Wisconsin. USDA For. Serv. Res. Pap. NC-239, 6 p.

Rowe, J.S. 1972. Forest regions of Canada. Can. Dept. Environ. Can. For. Serv. Publ. No. 1300. 172 p.

Schopmeyer, C.S. (Tech. Coord.). 1974. Seeds of woody plants in the United States. USDA Agr. Hdbk, No. 450. 883 p.

Shearer, R.C. 1961. A method of overcoming seed dormancy in subalpine larch. J. For. 59: 513-514.

Spurr, S.H. & Barnes, B.H. 1980. Forest ecology. New York, NY: John Wiley & Sons, Inc. 687 p.

Stiell, W.M. 1986. Fifteen-year growth of tamarack planted at six spacings on an upland site. Can. For. Serv. Info. Rept. PI-X-62. 22 p.

Tilton, D.L. 1978. Comparative growth and foliar element concentrations of Larix laricina over a range of wetland types in Minnesota. J. Ecol. 66: 499-512.

U.S. Forest Service. 1908. Tamarack. USDA For. Serv. Silvical Lflt. 32. 3 p.

Vallee, G. & Stipanic, A. 1983. Growth and performance of larch plantations. In: Graham, C.M.; Farintosh, H.L.; Graham, B.J. (ed.). Larch symposium, potential for the future. Proc. Symposium sponsored by Ontario Min. Nat. Res. & Univ. Toronto Fac. For., Toronto, Ontario, Nov. 9, 1982: 47-63.

Viereck, L.A. & Little, E.L., Jr. 1972. Alaska trees and shrubs. USDA Agr. Hdbk. No. 410. 265 p.

Wang, E.I.C., Mueller, T. & Micko, M.M. 1985. Drainage effect on growth and wood quality of some bog trees in Alberta. For. Chron. 61: 489-493.

Wile, B.C. 1981. Tamarack. Environ. Can. Can. For. Serv. Maritime For. Res. Centre. 8 p.


APPENDIX I

Species Codes and Names

Lade = Larix decidua Mill.
Laeu = Larix eurolepis Henry.
Laka = Larix kaempferi (Lam.) Carr
Lala = Larix laricina (DuRoi) K. Koch
Laly = Larix lyallii Parl.
Laoc = Larix occidentalis Nutt.
Lasi = Larix sibirica Ledeb.

Piab = Picea abies (L.) Karst.
Pigl = Picea glauca (Moench) Voss
Pima = Picea mariana (Mill.) B.S.P.


Piba = Pinus banksiana Lamb.
Pire = Pinus resinosa Ait.
Pist = Pinus strobus L.
Pisy = Pinus sylvestris L



Larix laricina



Larix
lyallii



Larix
occidentalis

Figure 1. The natural ranges of North American species of Larix (Larix laricinia modified from Fowells 1965; Larix lyallii from Arno and Habeck 1972; Larix occidentalis from Fowells 1965).




Figure 2. Comparison of site index and height-over-age curves.

STRUCTURE AND DYNAMICS OF NATURAL CONIFER FORESTS NEAR THE UPPER FOREST LIMIT

Helmut Schmidt-Vogt

ABSTRACT: The structure of natural conifer forests near the upper forest limit is characterized by low height of trees, low tree densities, low h/d values and a thus high tree and stand stability. Tree islands occur with increasing frequency in the immediate proximity of the upper tree limit. The dynamics of natural boreal conifer forests is modified by fire through raw humus decomposition and successions, mostly of broad-leaved pioneer species. If fire is eliminated, nutrient flow has to be kept in motion by periodic soil preparation.

INTRODUCTION

Silviculture in Central Europe is laying increasing emphasis on the thorough knowledge of natural life processes in the forest as the precondition of rational silviculture. Leibundgut (1982) is pointing out, that our present silvicultural knowledge is still to a large extent based upon practical experience and research results, which were obtained from semi-natural and artificial commercial forests or from trial plots with similar conditions. Over the last decades, this opinion has stimulated an increasing number of studies in natural forests and remnant patches of virgin forest. Since only small remnants of former virgin forest are left in Europe, we carried out investigations primarily in the northern part of North America. They were concentrated on the genus spruce (*Picea*).

STRUCTURE OF BOREAL CONIFER FORESTS NEAR THE UPPER FOREST LIMIT IN COMPARISON TO CONIFER FORESTS ON SITES WITH HIGH GROWTH PERFORMANCE.

The life cycle of a virgin forest can be divided into a sequence of different formation phases, which are characterized by a specific stand structure (Leibundgut 1978, 1982). In studies which were carried out in Central Europe, the following phases are generally distinguished: Juvenile phase: very high stem number, small diameter, basal area and volume strongly increasing Optimum phase: closed, +/- one-storied stands with high stem number, basal area and volume increasing until maximum Age phase: decreasing stem number, decreasing basal area, large timber prevails Disintegration phase: low stem number, significant decrease of basal area and volume "Regeneration phase: disintegrating old growth stands with openings and rich young growth Selection phase": all-aged stands, similar in structure to selection forest The optimum phase in a virgin forest corresponds most closely to a commercial forest stand having reached maturity.

Using a number of forest transects, we will, in the following, compare the structure of stands on sites with high productivity with the structure of stands near the upper forest limit. Natural spruce forests on good sites are characterized by high tree density. In the Austrian Alps, Mayer (1966) studied a 100 year old spruce-larch forest (*Picea abies* - *Larix decidua*) which had become established after forest fire. The number of trees with a d.b.h. over 8 cm is 4 300, the number of trees over 10 m height, with a maximum height at 30 m, is approx. 1 500, basal area is 95 m^2 and volume 1 000 m^2. High tree density in conjunction with a relatively great tree height are the cause of high h/d-values (Fig. 1) and of the development of small uneven crowns. This accounts for the relative lability of single trees and of the whole stand, particularly with respect to snow pres-

HELMUT SCHMIDT-VOGT is professor em. for silviculture at Freiburg University, Federal Republic of Germany.

sure and wind, Increasing development towards a one-storied structure and elimination of larch are concomitant phenomena of a marked tendency towards rapid disintegration and large-scale collapse.

We compare this spruce forest with a spruce virgin forest in the north of the boreal conifer zone. Figure 2 presents a transect in the Ormtjernkampen National Park/Norway at 900 m elevation. Height growth is reduced, the tallest trees attain 20 m at the most. The stands are open, the number of trees with a height over 5 m is 350 - 400 spruce trees and 30 - 50 birch treas. Basal area in the optimum phase is around 25 m^2. The spruce crowns reach down almost to the ground, h/d-values are as low as 50 - 60. High stability of single trees condition stability of the whole stand.

Rowe (1977) designates the sub-alpine forest in the Canadian Rocky Mountains as the Mountain Counterpart of the boreal forest. Two transects from Jasper National Park provide data for the change in stand structure, as we are approaching the upper forest limit.

The first transect represents a spruce-fir virgin forest in 1 650 m altitude (probably *Picea engelmannii* x *P. glauca*, *Abies lasiocarpa*). The number of trees over 10 m height is about 800, with a maximum height up to 35 m. In this transect, optimum phases alternate with disintegration phases over a small area, the stand has a very differentiated age structure and accordingly a complex vertical structure. H/d-values of dominant spruce trees: (100) 85 - 63.

The next transact is located near the upper forest limit at 2 100 m elevation (Fig. 3) in a pure spruce virgin forest (*Picea engelmannii*), aged (at 1.3 m) over 350 years. A few Abies lasiocarpa trees grow outside the transect. Tree height is somewhat reduced, but trees still attain a height up to 25 m. The number of living trees with a height over 10 m is about 310. The h/d-values of dominant spruce trees are between 60 and 33. Tree islands consisting of spruce and subalpine fir develop in typical disintegration phases. As a result of very low h/d-values, the isolated spruce trees are very stable.

A long period without fire may be inferred from the great age of the tallest trees. Thus, high stability of dominant trees concurs with small-scale disintegration and regeneration phases of a mosaic-type structure.

Tree height and stem number are reduced in the same way near polar tree limit. Viereck, Van Cleve and Dyrness (1986) describe a *Picea glauca — P. mariana — Alnus crispa — Betula glandulosa* community type on a treeline site at 747 m elevation in interior Alaska. The nature stand is very open with a tree density of 262 trees/ha and a canopy cover of 8 %. Most of the trees are white spruce. Height averages 5 m, tree diameters average 8.4 cm d.b.h., some of the larger white spruce are up to 21.5 cm in d.b.h. and 10 m in height. Basal area of the stand is only 1.3 m^2 /ha. Tree ages range from 110 years to about 150 years.

Relatively low tree height and low stand densities are important characteristics of the stand structure of conifer forests near the upper forest limit. Relatively high chest height diameter due to the large growing space of trees, and accordingly low h/d-values and high tree and stand stability. The natural forests are thus well adapted to the rigorous environmental conditions.

TREE ISLANDS

Tree islands appear the more frequently, the closer one approaches to the upper forest limit. They have been described repeatedly in the literature. In the case of spruce they originate frequently through layering of branches that are pressed to the ground. They also originate from small-scale seeding on small elevations around old stumps or trees. In comparison to single plants, the tree island is obviously better equipped to deal with snow, wind and possibly frost drought. The endowment of some tree species with the ability to regenerate through vegetative reproduction can also be seen as a measure adopted by nature to support tree — growth near timberline, under conditions detrimental to generative reproduction.




Figure 1. Natural larch-spruce forest within the subalpine maximum of conifer trees in the Austrian Alps with very high tree density, high h/d-values and limited tree and stand stability (Mayer 1966).




Figure 2. Natural spruce -birch forest in the Ormtjernkampen National Park / Norway near timberline with low tree density, low h/d-values and high tree and stand stability.




Figure 3. Natural spruce forest in Jasper National Park/Canada near tree line. Low tree density, very low h/d-values, regeneration in disintegration patches in the form of tree islands.

DYNAMICS

At the northern limit of the boreal conifer forest in North America and the USSR, fire plays an essential role. Fire-induced rotation cycles fluctuate generally between 50 and 200 years.

Heinselmann (1981) regards the fire regime as an integrated component of boreal ecosystems. Since in the boreal zone, on cold sites, decomposition of organic matter in the ground does not keep pace with the accumulation of humus and moss, fire plays an important part in the periodic reduction of organic layers. Nutrients, which had been fixed by the formation of moss and raw humus in closed conifer stands, through fire, return again into the nutrient cycle. Upon fire follows in most cases a pioneer forest of birch, poplar and other broad-leaved pioneer species, which, by leafshedding, also act favourably upon the soil.

Through a periodically renewed sequence of forest stages, from pioneer forest to mature conifer forest, the energy flow is always set in motion anew, and a permanent fixation of nutrients in raw humus is prevented. What we actually have here, is a cyclical stability of conifer-ecosystems.

From our investigations in the Ormtjernkampen National Park/Norway followed, that in the disintegration phase of spruce virgin forest on this mountainous site, already relatively small surface units are sufficient to bring about alternation of associations. In an opening of 0.03 ha, the regeneration will be 80 % birch (Hanisch 1983). The pioneer stage with conditions favourable to the decomposition of raw humus will thus materialize on small surface units (micro-succession).

In the dynamics of conifer forest we distinguish two cycles: the small cycle with alternation of formation phases — optimum — disintegration — regeneration phases but with no alternation of tree species, and the great cycle, after disintegration or catastrophe, with successional stages and alternation of tree species until a mature conifer forest has again become established.

CONCLUSIONS FOR MANAGEMENT OF CONIFER FORESTS NEAR THE UPPER FOREST LIMIT

The stands should be established and tended in such a manner that the trees will attain low h/d-values (spruce less than 80) while commanding sufficient growing space. Wide planting space permits natural seeding of broad-leaved pioneer species (birch, aspen). In the immediate prox-

imity to timberline, forest structures with tree islands become increasingly important. Tree island afforestation should be done on suitable micro-sites.

When fire is excluded by man, nutrient flow must be kept in motion by periodic soil preparation.

LITERATURE CITED

Hanisch, Bernhard. 1983. Analyse des naturnahen Fichtenwaldes im norwegischen Nationalpark Ormtjernkampen Villmark. Schriftenreihe des Waldbau-Instituts der Albert-Ludwigs-Universität Freiburg i. Br., Band 1; 1983. 309 p.

Heinselman, M.L. 1981. Fire intensity and frequency as factors in the distribution and structure of northern ecosystems. In: Mooney, N. A.; Bonnicksen, T. M.; Christensen, N. L.; Lotan, J. E.; Reiners, W. A., eds. Fire Regimes and Ecosystem Properties. US For. Serv., Gen. Tech. Rep. W0-26, Washington DC; 1981: 7-57.

Leibundgut, H. 1978. Über die Dynamik europäischer Urwälder. Allgemeine Forstzeitschrift. 33: 686-690.

Leibundgut, H. 1982. Europäische Urwälder der Bergstufe. Bern und Stuttgart: Verlag Paul Haupt; 1982. 306 p.

Mayer, H. 1966. Analyse eines urwaldnahen, subalpinen Lärchen-Fichtenwaldes (Piceetum subalpinum) Lungau. Centralblatt für das gesamte Forstwesen. 83: 129-151.

Rowe, J. S. 1977. Forest Regions of Canada. Ottawa: Canadian Forestry Service Department of Fisheries and the Environment, 1977. 172 p.

Viereck, L. A., Van Cleve, R. & Dyrness, C. T. 1986. Forst Ecosystem Distribution in the Taiga Environment. In: Van Cleave, K.; Chapin III F. S.; Flanagan, P. W.; Viereck, L. A.; Dyrness, C. T., eds. Forest Ecosystems in the Alaskan Taiga. New York Berlin Heidelberg Tokyo: Springer-Verlag; 1986: 22-43.

MONITORING TIMBERLINE DYNAMICS AT THE KEVO SUBARCTIC RESEARCH INSTITUTE IN NORTHERN FINLAND

Paavo Kallio

INTRODUCTION

The environment in the northern latitudes is determined by the position of the earth in space and its movement round the sun. The energy yield from the sun at different latitudes is determined by the orbit of the earth around the sun and the angle of the earth's axis. Daily and seasonal rhythms are controlled by the same mechanism (Kallio 1984, p. 53).

Energy means energy for life, which is the same as irradiation of the sun. This is also seen in the temperature. Light and temperature account about 94 % of the photosynthetic capacity and light alone some 90 % (Hari et al. 1981, p. 186). Low soil temperature has also been to be typical factor lowering growth and photosynthesis (Larcher 1983, p. 83). The destroying of bacteria takes place slowly as already Cajander (1933), the man who started his "Metsänhoidon perusteet" already very early in the page 307 says. Low soil temperatures are common everywhere in subarctic and arctic soils, e.g. at Kevo Station. Owing to low soil temperature water can not be easily absorbed by plants. There is, however, some adaptation towards the north so that colder climate plants have roots with greater water permeability at low soil temperatures than plants native to warm climates. The net assimilation rate in the northern latitudes can have values 0.1-0.3 dm^{-2} vk^{-1} (Warren Wilson, 1960).

The northern plants, ability to use even midnight sun was known as early as 1930 (Kostytschew et al. 1930, Warren Wilson 1960). In spite of the continuous daylight, however, there are differences in different seasons. Hence two maxima are observed in osmotic pressure in several plants (Lewis et al., 1920).

Light conditions in the northern latitudes differ, both in average intensity as well in rhythm: The difference in light intensity is reflected in the fact that the overnight sunshine causes the total hours of sunshine to be higher than in the south. Hence while in Leningrad at 60°N it is 0.33 g dm^{-2} wk^{-1} at 43°N only 0.25 dm^{-2} wk^{-1} (Warren Wilson 1960). This is, however, a possibility for northern plants only and it is based on long adaptability of evolution. It is also seen in alpine vegetation zones, which in each site of the mountains can be different (Fonda and Bliss 1969). The same is also seen in the different number of schrubs.

Hardening for winter is a proberty which is normal for all plants in the arctic and subarctic zones. The hardening is of two different kinds. Some of plants are always hardened. That means that even in summer they can tolerate frost, as do lichens and mosses (Kallio and Heinonen 1971, 1973, 1975, Lange 1965, Karunen and Kallio 1976, Skreel and Oechel 1981, Larcher 1980, Pohle 1917). The hardening needs certain particular climatic conditions, e.g. some light and temperature requirements (Tumanov 1967, Kallio and Valanne 1975, Martin, Mårtensson and Öquist 1978). Lipid acid and lipids are also components of hardening. In winter it is important linolenic and linolic acid contents are raised, while in summer these contents are normally lower (Michaelis 1934, Jönsson and Olin 1898). The saturatity and unsaturation are most important in winter conditions (Karunen and Kallio 1976, Levitt 1980, 1956). Thereafter when all the prerequisites are fullfilled southern plants are southern plants able to tolerate chilling (Drake and Raschke 1974, Taylor et al. 1974), or they are

Prof. emeritus Paavo Kallio †
The University of Turku,
Kevo Subarctic Research Station

able to tolerate many degrees C ° of frost (Sakai 1962, 1966, Öquist et al. 1980, Cloutier and Andrews 1984, Martin, Mårtensson and Öquist 1978, Sakai and Otsuka 1970). In general the most suitable conditions for hardening are a short day and temperature about 0° C. In these conditions Chl-bleaching also take place and chlorophyll-protein complexes are destroyed (Öquist et al. 1980, p. 530). There are many destructive events, but usually a northern plant is able to adapt and exploit them. Hence, plants are able to translocate the stored reserve energy to a part of the plant can use it, e.g. in new shoots (Kozlowski 1971, Ericsson 1978). Even in defoliated trees it was possible, due to reserve energy, to get new shoots to grow (Junttila and Heide 1981, Ericsson 1978). Desiccation is also very important for hardening (Scholander et al. 1953). There is an example in p. 6. When the moisture content in a buttercup (*Ranunculus asiaticus*) has decreased to 9.6 %, the plant can survive 18 days at the temperature of liquid nitrogen (-190° C). Low temperature and high light intensity typical of northern latitudes can in some circumstances cause solarization and photosynthesis inhibition at high latitudes (Taylor and Rowley 1971, p. 717).

Other light conditions distinguishing northern latitudes from the southern ones are the light intensity rhythms. The rhythm is of two different kinds: the annual and daily variation. Ecologically the daily rhythm is more important. There are some good ecological examples of unicellular algae reaction to continuous illumination (Kallio 1957). Continuous illumination is usually destructive in mosses and lichens (Pearson 1970, Valanne 1977, Kallio and Valanne 1975, Kallio and Kallio 1975, Kallio and Heinonen 1975, Aro and Valanne 1979). In lichens they recover their ability to photozynthetize very rapidly overall (Lange 1965, Kallio and Kallio 1975, Heide 1985, Lechowicz 1981, 1978, Kallio and Kärenlampi 1975, Savile 1961).

Mosses and lichens are able to recover their ability to photosynthetize very rapidly after a period of intense cold (Kallio and Heinonen 1971, 1975).

When it comes to the low concentration of soil nutrients, which is typical of the north, there are two different ways for life to adapt to these particular conditions Sörensen (1941), One of these is possibilities described by McCown (1978). McCown has studied the adaptation to low nutrient contents in soil. Plants adapted to northern conditions are able to increase production in tundra conditions if they are able to get new fertilization. Non-adapted (southern plants) can only do so when the soil temperature rises. Another way to adapt to changed environmental features compared with the south, is the use of mycorrhizal fungi. Hence the mycorrhiza problem is a northern form of adaptation (Marks and Kozlowski 1973, Moser 1958, 1967, Kallio 1982, Miller and Laursen 1978, Kobayasi 1982, Linkins and Antibus 1982, Savile 1981). (From the Antarctic has been described already as early as 1847 by Berkeley).

In the North there are even more possibilities to animal demands for plants than in more southern latitudes. This is due to the high selectivity which has led to many monospecies ecosystems, e.g. Betula-stands at northern latitudes in Fenno-Scandia Iceland and Greenland. In this case it is possible that small insects such as *Epirrita autumnalis* can destroy an area of 5000 km^2, as occurred mid-60's this centure (Kallio and Lehtonen 1973, 1975). This has led to some kind of defence mechanism in the north. Good examples have been described by Haukioja (1980, 1982). It is possible to explain the rhythmic occurrence of these defoliation's of the birch (Haukioja et al., 1983). The birch has many difficulties with the herbivores (Haukioja et al. 1981, Neuvonen 1987 a, b). In addition, there are many other animals, e.g. among herbivores, which have the same effect on plants, e.g. microtines (Laine and Henttonen 1983, Batzli, 1983).

The treeline is dependent on many different ecological features (Hustich 1966, 1973). In the last Hustich has brought a new concept to northern forest line ecology. Hustich has spoken a long time of what he has termed the "climatic hazard coefficient", which increases towards the north. This means that climatic

changes are greater towards the north. The significance in northern latitudes is more dependent on climatic influences. We have a good example: in the Kevo area in northernmost Finland the pine can form germinable seeds even at a temperature, where the thermal sum is 600 dd., but to get such a situation that half of the seeds are germinable it needs about 950 dd as the thermal sum (Pohtila 1980). How are the plants able to adapt in these conditions? They have only one possibility: to collect reserve energy. But there is a question of whether northern plants are able store energy more than southern ones. Have these, especially been able to collect more than only one year? This can be determinated e.g. in ^{14}C-method. Perhaps even by mycorrhizal activity. These show, however, not to be likely.

Some plants are able to place themselves in the warmest layer of the thermal layering, i.e. to the lowest layer close to the surface. This is the case with *Betula pubescens* war. apressa (Kallio and Mäkinen 1978, Salisbury et al. 1968). It grows only a few cm above the surface of the soil, only so that a small layer of snow covers it totally providing excellent insulation. Consequently the plant is as well protected against cold in winter time as in summer.

Genetic differences in plants at northern and southern latitudes The mountain birch problem

In Southern Finland and in Central Europe all the birch species, *Betula pubescens*, *B. Pendula* and *B. nana*, have their own evolution (Hagman 1971). In Lapland, however, all these birches cross and quite a new genotype has arisen (Kallio et al. 1983, Sulkinoja 1981: Sulkinoja, Inki and Valanne 1981, Inki and Valanne 1979, Vaarama and Valanne 1973, Raulo 1977). The same feature is circumpolar. In Alaska there is found a plant which in all probability is a hybrid between *Betula papyrifera* and *B. glandulosa*, called *Betula eastwoodiae* (Viereck and Little 1972). The Far East there is a birch, *Betula middendorffii* which the Russian authors think is a hybrid with two different birch species.

Other plants

Even other plants hybridise easier in the North than in the South. Examples are Nymphaes and Nuphars Mäkinen et al. These plants are able to survive in hybrids. These plants are able to live vegetatively. Another genus is *Sparganium*, which are making many hybrids. Even some *Ericacae* are able to make hybrids. See the publication of (Mäkinen et al. in print). Even many mosses and lichens are able to form hybrids, but its form and nature have not been analyzed in more detail. They are, however, forming new once by vegetative means only (cf. Kallio and Saarnio 1986).

Productivity is lower in North their in the tropics

Biomasses in the Kevo area have been measured during the IBP-period between the years 1967 - 1972. We have included three different types of forest in our measurements: birch forest, pine forest and low alpine heath. In pine forest total production was 38 650 kg/ha, in birch forest on northern slopes it was 12 075 kg/ha and in low alpine heath, even including cryptogams value was 270 kg/ha. In the tropics biomass and production are some one hundred times higher than in tundra area and perhaps even more in arctic desert areas where the plants grow only very sparcely at great distances from each other (Rodin and Bazillevich 1964, Rodin and Bazillevich 1965). There are still some observations in a latitude effect in nitrogen fixation per area. In the tropics the nitrogen fixation is some 88 kg/ha/hear. In Oreganon it is 12 kg (Todd et al. 1978) and at Kevo (at 70 latitude N) 4 kg (Kallio and Kallio 1975). This is a typical amount and is given even in Sweden at the same latitude as that by Kallio and Kallio (1975) in a mire (Granhall and Lindberg 1978).

There is, however, a "Zeitfactor" as discussed by Larcher (1969) or Hustich's hazard coefficient (e.g. 1975, Holtmeier 1987). Both are important because the time-factor is always involved in productivity. In some years there is good productivity, but in other years the plant is totally dependent on stored energy reserves. Continentality, which is clearly seen in the distribution of *Racomitrium lanuginosum* moss in Finnish Lapland (cf. also Jalas 1955) and also in many other species in plants, is another important factor. The forest line is also dependent on the same factor as many ecologists have discussed (Kihlman 1890, Payette 1983, Hustich 1975, Holtmeier 1987). Also nutrients have a very low content especially of nitrogen and phosphorous (cf. Haag 1974, Kallio 1974, Tieszen 1978, McCown 1978, Oechel and Sveinbjörnsson 1978).

The photosynthesis of bark is a typical phenomenon in northern latitudes

All tissues which contain chlorophyll are able to fix CO, in the light. The bark of different tree species contains chlorophyll and is thus capable of fixation and can produce energy. Two Fenno-Scandian scientists can be mentioned, who have studied this problem: Larsen (1936) and Stålfelt (1962). Thereafter the study of stem photosynthesis has moved to North-America and the most popular object has been *Populus tremuloides*. Many American scientists have achieved all their results with this plant. Such examples are Ames and Tepper (1978), Schaedle (1985), Iannocence and Foote (1968), Strain and Johnson (1963), and Davis and Evert (1968). The Australian researches have studied *Vitis vinifera* woody shoots (Kriedeman and Buttrose 1971). The American researchers have also studied white pine (*Pinus strobus*), ocotillo (*Fouquieria splendens*), douglas-fir (*Pseudotsuga menziesi*), American beech (*Faqus grandiflora*), Rhododendron (Parker and Philpott 1963), *Pinus thunbergii* (in Japan) as Oku and Tomita have done (1971), in *Cercidium floridum* (Adams and Strain 1969).

In addition to all other Finnish trees we have also the bark photosynthesis of *Betula tortuosa* (cf. Kallio et al. 1983, Vaarama and Valanne 1973, Sulkinoja, Inki and Valanne 1981, Sulkinoja 1981, Elkington 1968, Chepurko 1972, Hagman 1971).

Because some institute or organization is always responsible for the studies of particular, the organization are often biological field stations, whose role e.g. Wilson has emphasized (Wilson 1982, Eisner 1982, Brussard 1982, Kallio 1980). I have stressed the botanical research possibilities in the north (Kallio 1981, Sonesson et al. 1975, Kallio 1979). Also, when speaking of the essence northern ecology (Kallio 1984), some aspects are already known, that are also important in all ecology and in all fields of biology. All these examples are indicators of lack of energy. The summer is too short. No organism are able to collect energy enough in this time, because in winter the respiration needs energy. Therefore all living beings have some adaptations to lengthen the too short growth period. Therefore even the bark photosynthesis is a fitness. It can lengthen the too short growth period, because the photosynthesis in bark starts already in the Arctic or Subarctic at -20° C, as does *Betula tortuosa*. It is possible, to find a "hardening" in barkphotosynthesis. We have not had *Pinus pumila* and other Pamir plants in our disposal. The bark photosynthesis functions even in Italy in low temperatures, which has already active photosynthesis at -10° C. Hence in all latitudes appears, that the bark photosynthesis has lower optimum temperature than the needles or leaves.

The total photosynthesis of bark can be as high as 40 % of the total photosynthesis of the tree, most of which takes place in the leaves. In winter, when there are no leaves on the tree, the role of bark photosynthesis may be as high as 86 % of the total. These figures are both from Adams and Strain (1969). Seasonal photosynthesis may be very different. Hence late March or early April is most active, when companion cells and even parenchyma cells are activated (Davis and Evert, 1968). Cessation of function begins in late September or early Oc-

tober. By late November all the structural growth is complete (Davis and Evert 1968, p. 5 and Figs, Adams and Strain 1969).

Because there is a system of reassimilation of $C0_2$ produced by respiration, there is much higher content of CO_2 in bark than in the leaves (Knowlton et al. 1978, Table 1, Adams and Strain 1969, Davis and Evert, p. 5 and Figs, Derr and Evert 1967). Consequently photosynthesis may be even higher (Billings and Godfray 1967, Kriedeman and Buttrose 1971). Because the trunk releases little light to the chlorophyllous tissue, it is clear that the trunk in different directions has a different light in the chlorophyllous layer. On the southern side of the trunk in one case it was 54, on the western side 86 and in northern side 96, while in blue shadow it was 100 (Schenk 1952). This means that light can either promote the photosynthesis or inhibit it. This can also depend on the fact that transpiration is at too low a level. In twigs or branches near the base, in one case concerning *Populus tremuloides* this ratio was as high as 100:5 when compared the base and something upwards (Pearson and Lawrence 1958, p. 385). On the other hand, as regards the whole tree the greenery is more intense in the upper part of the tree and therefore also is photosynthesis. Seasonality is very clearly seen. A 5-year old *Acer pseudoplatanus* has a photosynthetic capacity more than ten times that of a year-old one ((Schenk,1952, p. 299). Photosynthetic activity also varies according to season. In December photosynthesis produces 0.02 mg CO_2/dm^2 hour, but in July it is. 5.5 mg CO_2/dm^2/hour (Knowlton et al. 1976).

It seems that photosynthesis plays a most active role stem in cold seasons, at the time when the cambium is activated. This is early in the spring when the soil is still frozen. The stored energy cannot move, because the trunk is still frozen. Therefore the trunk can photosynthesis at the very low temperatures prevailing in polar zones. Therefore it is possible to see the bark photosynthesis as an indication of fitness in polar areas.

KEVO as a Research Station

When the Kevo research people came to Kevo some 30 years ago, it was the only possibility to study the surrounding environment, animals, plants and morphology of the landscape. The aim was to make it a "known spot" in the Subarctic. we started the study of the fauna in order to make maps of Inari Lapland, an area of some 20 000 km^2. Now we already have some 580 maps of vascular plants and samples of many other groups of many other plants, even fungi, lichens and algae as well as mosses. The fauna-research people have already published in Kevo notes one issue of on evertebrates, especially butterflies, made a list of vertebrates and have studied already the *Coleopterans*. They also have estimated the bird density and bird fauna in Kevo nature park.

Because Kevo lies at the forest line, the forest line everywhere is surrounding us. We have constructed together with the National Board of Forestry and the Forest Research Institute in Finland three different tree-line arboreta. One of those are at the birch-line (*Betula tortuosa* - line), one, near by KEVO is at the Kevo-pine-line and one is in Inari at the main pine-line. There are, however, not so many trees in the subarctic forest-line, about 12 - 15. But because we will have as many provenance as possible, the total number of trees will be some hundreds and the total number or trees in our arboreta will be about 100 000. At Kevo arboreta there are some 30 thousands of trees. We have started to study at first different Betulas, because this study is ready as soon as in some tens of years. The coniferous trees from Siberien have, perhaps already been subject to transplantation. Because the Kevo's role is to collect the seeds for the forest-line arboreta. It has caused some difficulties, because we have no money in our budget, it has some times caused some difficulties in financing. Luckily some of our students making fungal research at forest-line have helped us much in financing mycology, and our forest-line arboreta has got money for seed collection. By the way, we have some 80 000 Betulas in our forest-line arboreta at present and some thousands of

coniferous trees. Earlier we have also taken twigs and tried to get them to grow. Later, however, they strongly were affected by many pathological fungi and no longer have permission for this. Some *Larix*-species seem to thrive well and we have tried to visit the place from where the most prominent *Larix*-species have come from, the Archangel area, but in vain. Still we have some possibilities. We have had the possibility of visiting Siberia twice, in Jakutsk and in Tsuktsi peninsula, where a very large collection of *Pinus pumila* has been collected. The co-operation between the different organizations has functioned well.

Because the forest line is subject to different changes, it is necessary to follow the changes. These are of great significance and may depend on climatic changes or on pollution, caused by man as is often the case in Central Europe. There are now some 26 sites in North-Finland. They will be mapped every ten years continuously. The mapping is most important, this was started at the 1980's. All the trees and small plants of all trees will be measured with an accuracy of one centimetre. Since mapping will take place every ten years, it is possible that some of the trees will not be found, indicating that something has happened. The large trees will be measured, both for girth and height. Soil tests will also be taken since the soil can also be affected by climatic changes or pollution. All the data will be computed by the Forest Research Station in Rovaniemi and the results will be discussed together.

Kevo has embarked upon international co-operation with it's involvement in the IBP. We represent the tundra-biome together with Norway, Sweden and Iceland. We have also had contact with Greenland and material from Greenland is found in our arboreta. In the Kevo area we have three different biota: one in pine forest, in valley S of the Station, a birch ecosystem on the slope above us, and a subalpine heath on Jesnalvaara mountain. The sites have been described by Sonesson et al. (1975). The pine forest has an average productivity 38 659 kg/ha/year, while birch forest produces 12 075 kg/year. The low alpine heath produces 270 kg/ha/year. Oulanka, which lies on the Arctic circle, produces 1 000 kg/ha/year, and we can see how latitude affects productivity. When tropical rain forest produce some 100 times as much as our low alpine heath, we understand how productivity is dependent on latitude.

Kevo has co-operated with all Nordic countries even after the IBP-period. An example is SBP (Subarctic Birch Programme). Because many reindeer herders, hunters and fisher men are dependent in these forests, this is also important for man. All the Fennoscandian countries participate in this project. In addition to this Iceland and Greenland participate in the project. Every year we hold a meeting of the participating countries, although rarely in Greenland. Only one meeting has been held in Greenland, but several in Iceland. This is one way of making contacts with polar people as hunters and reindeer herders.

In the same way we have tried to make contacts with the local people, who have used old traditional methods of cultivation or, as in Finland, collected *Angelica*-roots, which have also been used by industry for flavouring alcoholic beverages. Because their aromatic content quality is better in Lapland than in Central-Europe, there are some possibilities of cultivating *Angelica* for industry. It is easily cultivated because the plant is native here and grows in brooks or the banks of brooks. We have here contacted industry and this co-operation seems to be good. Even dill grows (*Anethum graveolens*) and its aroma is better than in Southern Finland and Central Europe.

Another important subsidiary occupation for many Saami people, is collection of Arctic cloudberries (*Rubus chamaemorus*).This provides some 50 millions in Lapland, while in the best years ptarmigan can bring almost the same amount. At Kevo attempts even been made to cultivate cloudberries in order to study the insects, the enemies or fungi that use them as host. It is easily cultivated under plastic, where the too low temperatures have no effect. It has been shown that the mostly dangerous insect is *Calerucella*, which can also attack cultivated strawberries. The frost is the worst, if it comes at a time when cloudberry flowers. There are

only a few possibilities of preventing this, perhaps the desiccation of the whole bog.

Kevo has even tried to help reindeer management in some way. Although opportunities are few, one way is to weigh the calves and see whether this affects mortality. One method of improving this might be to give the mother reindeer more food. This is, however, difficult in many cases. Entomologists are also working in methods to repel or otherwise counter insects, which in many ways have affected reindeer movements.

Kevo has a major programme together with fishmen and fishery-biologists in Norway. The Tenojoki (in Norway: Tana) constitutes the border between Finland and Norway and is one of the best salmon rives in Europe. All the others have been polluted or changed in other ways. The Tenojoki is now subject to continuous monitoring. All the factors affecting salmon are monitored and the movements of the salmon followed by marking their fins. With the aid of these tests has been shown that Teno-salmon have been found in Labrador, Northern Greenland and the Faeroe Islands. Part of the programme is to follow up fishing catches so that as the salmon becomes rarer mesh sizes are increased allowing only large individuals to be netted. Protected areas are established for spawning. So far this has only affected Norway and Finland, but Soviet scientists have also shown an interest and many Kola-Peninsula fishery-biologists and Ponoifishries are interested in Teno salmon.

International co-operation between Kevo and the rest of the world

As we have already heard Kevo has its IBP, SBP, MAB and Northern lights programmes. One of these joint operations has, however, been the co-operation in Finnish birch and its herbivores. Because *Epirrita autumnata* in the mid-60's this century caused major catastrophe in Finnish Lapland and in the whole of Fennoscandia (Kallio and Lehtonen 1975, Kalliola 1941, Tenow 1972). Our lead in the whole problem has given us good conferences e.g. in autumn 1981 and later, in 1983, a whole Oikos 40 has devoted to this symposium. Research scholars from Alaska have been interested, in particular people from Fairbanks (Arctic Biology) have often visited Kevo, especially to study our forest arboreta. These scientists also have new and modern methods and their own instruments and our students have learned much from their apparatus. As results of their visits we have become familiar with the ^{14}C method for studing photosynthesis.

The forest line arboreta, as has already been mentioned, have stimulated circum-polar co-operation. Because many American scientists have their own instruments and quite new methods, we at Kevo have learned much from this co-operation. There are quite new ideas, e.g. mycorrhiza — birch co-evolution and many other new ideas.

In the same way, in every fishery-biology and fishery there have been many contacts with other countries and especially contacts with countries with which we seldom have contact, e.g. the Faroe Islands, Northern Greenland, the Falkland Islands. The contacts have also brought us into contact with Archangel and Ponoi, known from earlier periods in Finland's science.

We have made some flora studies in Labrador and Ungava Bay, Quebec (Mäkinen and Kallio 1980) for comparison with the Kevo area. The times have been many years and in this respect it may be comparable with the Kevo area studies. In the same way it has been it is important for students to see different countries and to become acquainted with the polar culture of different polar countries.

DISCUSSION

The north differs greatly from the south (Kallio 1984, Kallio 1985, Haukioja et al. 1983, C. v. Linne 1732, Kallio S. 1976) and even polar culture deviates from that of the south. There is a controversy between these two cultures and it has proved very difficult to resolve this problem. Many attempts have been tried in Canada. One of these has been to legislate but

it has not entirely successful. The Inuits (Eskimos) or Indians have been in opposition. A greater success has been the Inuit Museum University - system, IMU, in which Inuits have been participating. It has succeeded better whereas legislation has succeeded in the McKentzie River (Tizya 1975). A critical factor is that the white man comes only to extract energy of minerals from the soil, whereas polar people living permanently in the region, people from the south live only a short time, until the iron or energy is exhausted (Kallio 1984, Kallio 1985, Tizya 1975). Even small disturbances can cause permanent "catastrophes" for the polar people in their livelihood (Bliss 1962), and cause conflicts between polar people and people from the south. Because nitrogen production is small at the northern latitudes, for example it is much dependent on time, and polar people have not time, these people can die without any food, time for them is a matter of survival. They cannot wait a long time, time for them is a matter of survival. They cannot wait a long time, when they have lost four kg of soil nitrogen (S. Kallio and P. Kallio 1975), when the time needed for a new harvesting of nitrogen is some 880 kg.

Even light conditions are not the best possible because most plants cannot stand permanent light for a long period (Kallio and Valanne 1975, Valanne 1971, Aro and Valanne 1979, Aro and Karunen 1979). Because soil composition is also poor in the tundra (Rossvall et al. 1975) nutrients are replaced only rather slowly. The low nitrogen (and partly phosphorus) situation is discussed by Kallio (1974, Kallio and Kallio 1975). Nitrogen is generally low in polar areas and this is mostly poor adaptability of the nitrogenase enzyme to low temperatures (Kallio, P. 1974, Kallio, S. 1975). All in all, it is environmental factors that account discrepancy between polar people and people from farther south.

Our contacts at Kevo with one of the most important economies among polar people, that of the Saami people in Lapland, mean that we are better placed to understand the life of polar people. Consequently, I, personally, have had an opportunity to participate in the IMU-system in Canada and we at Kevo have some understanding of polar people. There is another reason for this. In Finland the polar people (Saami-people) have for many hundreds of years had some kind of contact with the polar people from more southerly regions. In other parts of the world (in Siberia, Canada and Alaska) the people from more south have been separated by a wild forest many hundreds of kms wide from the polar people. This may explain why we do not have the same problems in northern Finland as in Siberia, Canada and Alaska. We know our polar people better and have co-operated a long time at a high level.

In our programme co-operation in flora studies, e.g. with Labrador and Ungava, has been quite prominent. We are, therefore, able to compare the two different subarctic countries better than before. Without this local knowledge, it would be impossible to understand all the problems of different polar peoples environment.

If we think of polar people and their adaptation to the north, we can say that they have not had time for biological adaptation because time has been too short (Dunbar 1968). Their culture is, however, adapted to the north (Discussions with Dr. Müller-Wille in 1980). For example, they have such head-wear that they have no possibilities of snow blindness. They dress in furs, which protect them from all kinds weather. The culture of polar people is more adapted than their biological adaptation. Perhaps there is some biological adaptation, too, but our IBP-studies of Skolt Lapps and Eskimos have not revealed any such adaptation (Kallio 1985, discussions with K.O. Donner and Dr. Müller-Wille from Canada). The old traditions of polar people can partly compensate for the lack of biological adaptation in their culture.

Kevo has also participated in the MAB-programme in earlier years. The entire SBP was financed by MAB. This means that MAB started the financing of the most important Nordic international studies. Even some proceedings of IBP were started with the financing of MAB. Every country has tried to continue the IBP, but it remains unfinished in almost all

countries. We now know the methods continuation seems to be very necessary. MAB also provides such a possibility as also in many other Nordic countries. Usually, however, the object is different. So, e.g. in Norway Svalbard was another object for study.

Studies of the forest line would not have been possible without help from other research scholars than those from Kevo. Many scientists from Alaska and Canada have helped us, so also have the people financing trips to different parts of the circumpolar north. Especially welcome is the possibility to thank the many mycologists from Turku and Helsinki, whose research activity is in the same area and same season as that suitable for seed collection.

Summing up it may be said that although most plants can well adapt to long hours of daylight, some difficulties are caused by continuous light and in winter no activities are possible during the complete dark. Photosynthesis is well adapted to northern low temperatures, but the short summer causes many difficulties. Most of these, however, have been eliminated by adaptation in different ways: e.g. by rising plant temperature or ability to grow at low temperatures, but short summer causes many difficulties. Both are the long results of evolution. Life has its home in the tropics and a long period of adaptation is needed to cope with the cold of the north. Man has not adapted, but culture has to some degree, especially polar cultures. Perhaps human beings can also learn to adapt and cope with the difficulties posed by living at high latitudes.

If we compare the south and the north, there are many differences. Productivity is high in the tropics and smaller in the tundra, especially the tundra desert, where the plants grow very separately. The amounts of nitrogen and phosphorus are small and their quality is poor, but there are some adaptations for these. e.g. reindeer now have phosphorus in their dung (own observation), and the plants adapt in different ways.

Polar people have difficulties with the people from southern areas. This has an ecological basis. Mostly it is a question of isolation. In Finnish Lapland the contacts have always functioned and in Finnish Lapland the differences are smaller. Polar people's reaction are, however, understandable, because survival is important for any organism. Therefore the governments of all countries, in Siberia as well as in Canada and Alaska, have thoroughly participate in the survival of the polar people and helped them in some way. This is needed for the continuing existence of Polar culture as such, and the pluralism of all cultures gains from is this.

I am of the opinion that man has not adapted biologically to northern latitudes but his culture has. This is something we can learn from polar cultures.

Acknowledgements

I would like to thank all of the persons who have helped me in the writing manuscript. I wish to thank the staff at Kevo, all of them have been most helpful. Especially I would like to thank the head of the station, Matti Sulkinoja as well as the theorethical leader of the station, prof. Erkki Haukioja, mrs. Saini Heino and her husband Juho Heino, whose sense of humour has always stimulated me as many others he is in contact with, as well as Heli Hurme, the ancient "kenttämestari" (a person, who always is present when something happens in the science). I also thank Auli Alonen, who has made all the bark photosynthesis work, and supported me in different way. All the possible people I wish to thank, but can I not here. At least will I thank mostly the person who has checked my language, Dr. Chr. Grapes.

LITERATURE CITED

Adams, M.S. & Strain, B.R. 1969. Seasonal photosynthetic rates in stems of Cercidium floridum Benth. Photosynthetica 3(1): 55-62.

Aro, E-M. & Valanne, N. 1979. Effect of continuous light on CO_2 fixation and chloroplast structure of the mosses Pleurozium schreberi and Ceratodon purpureus. Physiol. Plantarum 45: 460-466.

Batzli, G.O. 1983. Responses of arctic rodent populations to nutritional. Oikos 40, 396-406, Copenhagen. 1983.

Billings, W.D. & Godfrey, P.J. 1967. Photosynthetic utilization of internal Carbon dioxide in hollow-stemmed plants. Ann. Sci. Natur. Bot. 19: 121-123.

Bliss, L.C. 1962. Adaptations of arctic and alpine plants to environmental conditions. Arctic 15(2): 117-144.

Brayman, A.A. & Schaedle, M. 1982. Photosynthesis and respiration of developing Populus tremuloides interposed. Plant Physiol. 69: 911-915.

Cajander, A.K. Metsänhoidon perusteet, I. Kasvibiologian ja kasvimaantieteen pääpiirteet. Werner Söderström Oy, Porvoo, 1933, 735 sivua.

Chepurko, N.L. 1972. The biological productivity and the cycle of nitrogen and ash elementsin the dwarf shrub tundra ecosystem of the Khibin Mountains (Kola Peninsula). In: F.E. Wielgolaski & Th. Rosswall (eds.) IBP, Tundra Biome. Proceedings IV. International Meeting on the Biological Productivity of Tundra in Leningrad USSR October 1971, pp. 236-248. Berlingska Boktryckeriet, Lund. 1972.

Davis, J.D. & Evert, R.F. 1968. Seasonal development of the secondary pholoem in Populus tremuloides. Bot. Gaz. 129(1): 1-8.

Derr, W.F. & Evert, R.F. 1967. The cambium and seasonal development of the ploem in Robinia pseudoacacia. Amer. J. Bot. 54(2): 147-153.

Dunbar, M.J. 1968. Ecological development in polar regions. A study in evolution. Prentice-Hall International Inc. London, Sydney, Toronto, New Delhi and Tokyo, 1968. 119 pp.

Elkington, T.T. 1968. Introgressive hybridization between Betula nana L. and B. pubescens Ehrh. in north-west Iceland. New Phytol. 67: 109-118.

Ericsson, A. 1979. Effects of fertilization and irrigation on the seasonal changes in different age-classes of needle on Scott pine trees (Pinus sylvestris) Physiol. Plant. 45: 270-280.

— 1978. Seasonal changes in translocation of ^{14}C from different age classes of needles on 20-year-old Scots pine trees (Pinus silvestris). Physiol. Plant, 43: 351-358.

Fonda, R.W. & Bliss, L.C. 1969. Forest vegetation of the montane and subalpine zones, Olympic Mountains, Washington. Ecological Monographs, 39: 271-301.

Foote, K.C. & Schaedle, M. 1976. Diurnal and seasonal patterns of photosynthesis and respiration by stems of Populus tremuloides Michx. Plant Phsology 58: 651-655.

— & Schaedle, M. 1978. Contribution of aspen bark photosynthesis to the energy balance of the stem. Forest Sci. 24(4): 569-573.

Granhall, U. & Lindberg, I. 1978. Nitrogen fixation in some coniferous forest ecosystems. Ecological Bulletin 26: 178-192.

Hagman, M.1971. On self- and cross-incompatibility shown in Betula varrucosa Ehrh. and Betula pubescens Ehrh. Communic. Inst. Forest. Fenn. 73: 1-125.

Hari, P., Hallmann, E., Salminen, R. & Vapaavuori, E. 1981. Evalution of factors controlling net photosynthetic rate in Scots pine and seedlings under field conditions without water stress. Oecologia (Berl) 48: 186-189.

Haukioja, E. 1980. On therole of plant defences in the fluctuation of herbivore Oikos 35: 202-213.

— 1982. Inducible defences of white birch to a geometric defoliator, Epirrita autumnata. Proc. 5th Int. Symp. Insect-Plant Relationships, Wageningen, pp. 199-203.

— ,Niemelä, P., Iso-Iivari, L., Siren, S., Kapiainen, K., Laine, K.J. & Jokinen, M. 1981. Koivun merkitys tunturimittarin kannanvaihtelussa (Defence mechanisms in birches and fluctuation of autumnal moth populations.) Luonnon tutkija 85, 127-140 (in Finnish).

— ,Kapiainen, K., Niemelä, P. & Tuomi, J. Oikos. 40: 419-432, Copenhagen.

Heide, O.M. 1985. Physiological aspects of climatic adaptation in plants with special reference to high-latitude environments. Åse Kaurin, Junttila, O. & Jarle Nilsen (editors.): Plant production in the North. Norwegian University Press, pp. 1-22.

Holtmeier, F-K. 1987. Der Baumwuchs als klimaökologischer Faktor an der oberen Waldgrenze. Aus: Ekkehart Köhler und Norbert Wein (Hrsg.): Natur- und Kulturräume. Ludvig Hempel zum 65. Geburtstag., pp. 145-151.

Hustich, I. 1966. On the forest-tundra and the northern tree-lines — a preliminary synthesis. Rep. Kevo Subarctic Res. Station, 3: 7-47.

— 1973. Tree-line and tree growth studies during 50 years: some subjective observations. Collection Nordicana. Tree-line ecology. Proceedings of the Northern Quebec tree-line Conference ed. by Pierre Morisset & Serge Payette, pp. 181-188.

— 1975. The next phase in northern ecological research. Proceedings of the Circumpolar Conference on Northern Ecology in 1975 in Ottawa 5: 1, 1-10.

Inki, M. & Valanne, T. 1979. The F1 hybrid between Betula glandulosa subsection Nanae and Betula pendula, subsection Albae. Rep. Kevo Subarctic Res. Stat. 15: 11-18.

Jalas, J. 1955. Rhacomitrium lanuginosum (Hedw.) Brid. als Klimaindikator in Ostfennoscandien. Arch of Vanamo, Suppl. 9: 73-88.

Junttila, O. & Heide, O.M. 1981. Shoot and needle growth in n Pinus sylvestris as related to tempera-

ture in northern Fennoscandia. For. Sci 27: 423-430.

Jönsson, B. & Olin, E. 1898. Der Fettgehalt der Moose. Lunds Universitetets Årsbok 34(2): 1-39.

Kaitala, V., Hari, P., Vapaavuori, E. & Salminen, R. 1982. A dynamic model for photosynthesis. Ann. Bot. 50: 385-396.

Kallio, P. 1957. The effect of continuous illumination on the desmids. Archivum Socitatis Vanamo 8: 58-72.

— & Heinonen, S. 1971. Influence of short-term low temperature on net photosynthesis in some subarctic lichens. Rep. Kevo Subarctic Res. Stat. 8: 63-72.

— & Heinonen, S. 1973. Ecology of Rhacomitrium lanuginosum (Hedw) Brid. Rep. Kevo Subarctic Res Stat. 10: 43-54.

— & Lehtonen, J. 1973. Birch forest damage caused by Oporinia autumnata (Bkh.) in 1965-66 in Utsjoki, N Finland. Rep Kevo Subarctic Res. Stat. 10: 55-69.

— & Heinonen, S. 1975. CO2 exchange and growth of Rhacomitrium lanucinosum and Dicranum elongatum. Billings, W.D., Golley, F., Lange, O.L., Olson, J.S. (eds). Fennoscandian Tundra Ecosystems. Part 1, Plants and Micro-organisms (Part editor F.E. Wielgolaski), 138-148.

— & Kärenlampi, L. 1975. Photosynthesis in mosses and lichens. In: Cooper, J.P. (ed.): Photosynthesis and productivity in different environments, Cambridge University Press, pp. 393-422.

— & Lehtonen, J. 1975. On the ecocatastrophe of birch forests caused by Oporinia autumnata (Bkh.) and the problem of reforestation. In: F. Wielgolaski (ed.) Fennoscandian Tundra Ecosystems. Part 2. Animals and System Analysis, 174-180.

— & Valanne, N. 1975. On the effect of continuous light on photosynthesis in mosses. Fennoscandian Tundra Ecosystems (ed. F.E. Wielgolaski). 1 Parts Plants and micro-organisms, pp. 149-162.

— & Mäkinen, Y. 1978. Vascular flora of Inari Lapland. 4. Betulaceae. Rep. Kevo Subarctic Res. Stat. 14: 38-63.

— 1979. Programmes of the Kevo Station. Holarctic Ecology 2: 275-278.

— 1980. Laaja-alainen tutkimus Lapin kehityksen pohjana. The Year book from the Research Societe of Lapland XXI, 3 - 9 (with and English summary), 1980.

— 1982. Aspects of Northern Finnish macromycology. In pp. 410-431 in G.A. Laursen and J.F. Ammirate edited Arctic and Alpine Mycology - The First International Symposium on Arcto-Alpine Mycology. University of Washington Press, Seatle and London. 1982.

— , Niemi, S., Sulkinoja, M. & Valanne, T. 1983. The Fennoscandian birch and its evolution in the marginal forest zone. In: Morisset, P. and S. Payette (eds.): Collection Nordicana. Tree-line ecology. Proceedings of the Northern Quebec Tree-Line Conference. pp. 101-110.

— 1984. The essence of biology in the North. Leo Koutaniemi (ed.). Characteristics of the North. Proceedings of the XIX conference of Finnish geographers held in Oulu, 27-28 October 1984. Nordia 18:2, pp. 53-65.

— 1984. The essence of biology in the North. Nordia 18 (2): 53-65, Oulu.

— 1984. The essence of biology in the north. Leo Koutaniemi edited the book Characteristic of the north, Proceedings of XIX Conference of Finnish geographers held in Oulu, 27-28 October 1984. Geographical Society of North Finland, pp. 53-65.

— 1985. Adaptation and evolution at the northern limits of life. Acta Univ. Oulu. Scripta Acad. pp. 131-150. 1985. University of Oulu. Printing Center.

— & Saarnio, E. 1986. The effect on mosses of transplantation to different latitudes. J. Bryol. 14: 159-178.

— & Kärenlampi, L. Photosynthesis in mosses and lichens. In: J.P. Cooper (ed.) Photosynthesis and productivity in different environments, pp. 393-422. Cambridge University Press.

Kallio, S. & Kallio, P. 1975. Nitrogen fixation in lichens at KEVO, North-Finland. In: Fennoscandian Tundra Ecosystems. Part 1. Plants and micro-organisms (ed. by F.E. Wielgolaski). Pp. 292-304.

— 1975. Nitrogen fixation in lichens at Kevo, North-Finland. Rep. Kevo Subarctic Res. Stat. 32: 1-9.

— 1976. On the effect of forest fertilizers on nitrogenase activity in two subarctic lichens. Ecol. Bullet. 26: 217-224.

Karunen, P. & Kallio, P. 1976. Seasonal variation in the total lipid content of subarctic Dicranum elongatum Rep. Kevo Subarctic Res. Stat. 13: 63-70.

Kihlman, A.O. 1980. Wissenschaftliche Ergebnisse der Finnischen Expedition nach der Halbinsel Kola. B. Botanik, Zoologie. Kuopio Druckerei. 1980. 263 pp.

Knowlton, C., Foote, N. & Schaedle, M. 1976. Physiological characteristics of photosynthesis and respiration in stems of Populus tremuloides Michx. Plant Physiol. 58: 91-94.

Kobayasi, Y. 1982. Ecology of arctic lower fungi. In: Arctic and Alpine Mycology. The first International Symposium on Arcto-Alpine Mycology. Eds: G.A. Laursen and J.F. Ammirati. University of Washington Press, Seatle and London. 1982. pp. 16-26.

Kostytschev, S.W. Tschesnokow, R. & Bazyrina, K. 1930. Untersuchungen über den Tagesverlauf der Photosynthesis an der Küste des Eismeeres. Planta 11: 160-168.

Kozlowski, T.T. 1971. Growth and development of trees. Vol. 1. New York & London: Academic Press, 1971, 433 pp.

Kriedemann, P.E. & Buttrose, M.S. 1971. Chlorophyll content and photosynthetic activity within woody shoots of Vitis vinifera (L.). Photosynthetic 5 (1): 22-27.

Laine, K. & Henttonen, H. 1983. The role of plant production in microtine cycles in northern Fennoscandia. Oikos. 40, 407-418. Copenhagen, pp. 407-418.

Lange, O. 1965. Der CO_2-Gaswechsel von Flechten bei tiefen Temperaturen. Planta 64: 1-19.

Larcher, W. 1969. Die Bedeutung des Faktors "Zeit" für die photosynthetische Stoff-production. Ber. Dtsch. Bot. Ges. 82: 71-80.

— 1980. Physiological Plant Ecology. Translated by Biederman-Thorson, M.A. Springer Verlag, Berlin Heidelberg New York.

— 1983. Ökophysiologische Konstitutionseigenschaften von Gebirgspflanzen. Berichte Deutsh,. Ges. 96: 73-85.

Larsen, P. 1935. Regenererende Kulsyreassimilation hos askegrene. Den forstlige försogsväsen 14: 1-40.

Lechowicz, M.J. 1978. Carbon dioxide exchange in Cldina lichens from subarctic and temperate habitats. Oecologia (Berl.) 32: 225-237.

— 1981. Adaptation and the fundamental niche, evidence from lichens. In: D.T. Wicklow and G-O. Carrol (eds.) The Fungal community. Marchel Dekker Inc., New York and Basel, pp. 89-108.

Lewis, F.J. and Tuttle, G.M. 1920. Osmotic properties of some plant cells at low temperatures. Annals of Botany 31 (85): 406-416.

Levitt, J. 1972. Responses of plants to environmental stresses. 1. Chilling. 1972. 697 p. New York and London.

— 1980. Responses of plants to environmental stresses. Vol. 1. Acad Press Inc. New York, 1980, 497 pp.

Linkins, A.E. & Antibus, R.K. 1982. Mycorrhizae of Salix rotundifolia in costal arctic tundra, in pp. 509-531 in G.A. Laursen and J.F. Ammirati (eds.) Arctic and Alpine Mycology. The First International Symposium on Arcto-Alpine Mycology. pp. 509-542.

von Linne, C. 1932. Lapinmatka 1732. Arvi A. Karisto Oy. 1932. 210 pp. The translator is not known.

Marks. C.G. & Kozlowski, T.T. (eds.) 1973. Ectomycorrhizae: Their ecology and physiology. Academic Press, New York, 1973, 444 pp.

Martin, B., Mårtenson, O. & Öquist, G. 1978. Effects of frost hardening and dehardening on photosynthetic electron transport and fluorescence properties in isolated chloroplasts of Pinus silvestris. Physiol. Plant. 43: 297-305.

McCown, B.H. 1978. The interaction of organic nutrients, soil nitrogen, and soil temperature and plant survival in the arctic environment. Ecological studies, 435-456.

Michaelis, P. 1934. Ökologische Studien an der alpinen Baumgrenze. IV. Zur Kenntnis des winterlichen Wasserhaushaltes. Jahrbücher für wissenschaftliche Botanik 80: 169-247.

Miller, O.K. & Laursen, G.A. 1978. Ecto- and endomycorrhizae of arctic plants at Barrow, Alaska. In Vegetation and product ecology of Alaska Arctic tundra. Edited by L.L. Tieszen. Springer-Verlag, Berlin, pp . 229-237.

Moser, M. 1958. Einfluss tiefer Temperaturen auf das Wachstum und die Lebensfähigkeit höherer Pilze mit spezieller Berücksichtigung von Mycorrhizapilzen. Sydowia 7: 386-399.

— 1967. Die Ectotrophe Ernährungsweise an der Waldgrenze. Mitt. Forst. Bundes Vers. Anst. 75: 357-380.

Mäkinen, Y. & Kallio, P. 1980. Preliminary checklist of the vascular plants in the Schefferville area of the Quebec-Labrador Peninsula. McGill Subarctic Res. pap. 30: 17-36.

Neuvonen, S. 1987a. Interaction between geometric and microtine cycles in northern Fennoscandia. Manuscript: 15 peaces.

— 1987b. Delayed induvible responses and plant-herbivore interactions. Manuscript: 24 peaces.

Parker, J. & Philpott, D.E. 1963. Seasonal continuity of chloroplasts in white pine and Rhododendron. Protoplasma 56: 355-361.

Payette, S.S. 1983. The forest tundra and present treelines of the northern Quebec-Labrador Peninsula. In Collection Nordicana, pp. 3-23. Tree-line ecology. Proceedings of the Northern Quebec Tree-Line Conference edited by P. Morisset and Serge Payette.

Pearson, L.C. & Lawrence, D.B. 1958. Photosynthesis in aspen bark. Amer. J. Bot. 45: 383-387.

— 1970. Varying environmental factors in order to grow Intact lichens under laboratory conditions. Amer. J. Bot. 57: 659-664.

Pohle, R. 1917. Wald- und Baumgrenze in Nord Russland. Zeitschr. d. Gesellsch. f. Erdkunde zu Berlin, 206-229.

Pohtila, E. 1980. Climatic fluctuations and forestry in Lapland. Holartic Ecology 3: 91-98.

Raulo, J. 1977. Development of dominalt trees in Betula pendula and Betula pubescens Ehrh. plantations. Commun. Inst. For. Fenn. 90(4): 1-15.

J.L. Reveal (eds.) Evolution today, Proceedings of the Second International Congress of Systematic and Evolutionary Biology, p. 47.

Rodin, L.E. & Basilevich, N.L. 1964. The biological productivity of the main vegetation types in the northern hemisphere in the old world. Doklady Akad. Nauk SSSR. 157: 161-177.

— & Basilevich, N.L. 1965. Dinamika organicheskogo vetchestva i biologicheskij krugovorot v osnovnykh tipakh rastitelnosti (The dynamics of organic matter and the biological turnover in the main vegetation types).

Rosswall, I., Veum, A.K. & Kärenlampi, L. 1975. Plant litter decomposition at Fennoscandian Tundra Sites. F.E. Wielgolaski (ed.). Fennoscandian Tundra Ecosystems. Part. 1. Plants and Microorganisms. pp. 268-286.

Sakai, A. 1962. Mechanism of protective action of sugars against frost injury in plant cells. Nature 193: 89-90.

— 1966. Temperature fluctuations in wintering trees. Physiol. Plant. 19: 105-114.

— & Otsuka, K. 1970. Freezingresistance of alpine plants. Ecology 51: 665-671.

Salisbury, F.B., Spomer, G.G., Sobral, M. & Ward, R.T. 1968. Analysis of an alpine environment. Bot Gaz. 129 (1): 16-32.

Savile, D.B.O. 1961. The botany of the north-eastern Queen Elizabeth Islands. Can. J. Bot. 39: 909-942.

— 1981. A naturalist looks at Arctic adaptation in: G.G.E. In: scudder G.G.E. & J.L. Reveal (eds.): Evolution today, Proceed- of the Second International Congress of Systematics and Evolution Biology, 47-53.

Schaedle, M., Iannacone, M. & Foote, K.C. 1968. Hill reaction of isolated quaking aspen bark chloroplasts. Forest Science 14(2): 222-223.

— & Foote, K.C. 1971. Seasonal changes in the photosynthetic capacity of Populus tremuloides bark. Forest Science 17: 308-313.

Schamurin, V.F., Polozova, T.G. & Khodachek, E.A. 1972. Plant biomass of main plant communities at the Tareya station (Taimyr). In Wielgolaski, F.E. & T. Rosswall (eds.): Proceedings IBP Tundra Biome Meeting in Leningrad 1972, 163-170. Swedish IBP Committee, Wenner-Gren Center, Stockholm.

Schenk, W. 1952. Untersuchungen über die Beziehungen zwischen Lichtfeld und Chlorophyllgehallt an Sprossrinden und Blättern von Holzgewächsen. Planta 41: 290-310.

Scholander, P.F., Flagg. W., Hock, R.J. & Irving, L. 1953. Studies on the physiology of frozen plants and animals in the Arctic. J. Cell. Comp. Physiol. 42, Suppl. 1: 1-56.

Seppelt, R.D. & Selkirk, P.M. 1984. Effects of submersion on morphology and the implications of induced environmental modification on the taxonomic interpretation of selected antarctic moss species. Journal Hattori Bot. Lab. 55: 273-279.

Skre, O. & Oechel, W.C. 1981. Moss functioning in different taiga ecosystems in interior Alaska. Oecologia 48: 50-59.

Slatyer, R.O. & Morrow, P.A. 1977. Altitudinal variation in photosynthetic characteristics of snow gum, Eugalyptus pauciflora Sieb. ex Spreng. I. Seasonal changes under field conditions in Snowy Mountains area of south-eastern Australia. Aust. J. Bot. 25: 1-20.

Sonesson, M.M., Wielgolaski, F.E. & Kallio, P. 1975. Description of Fennoscandian tundra ecosystems. In: F.E. Wielgolaski (ed.) Fennoscandian Tundra ecosystems. 1. Springer Verlag, Berlin-Heidelberg-New York, pp. 30-60.

Stålfelt, M.G. 1960. Das Blatt und andere Assimilationsorgane. Handbuch Pflanzen-physiology V/2: 1-7.

Strain, B.R. & Johnson, P.L. 1963. Corticular photosynthesis and growth in Populus tremuloides. Ecology 44(3): 581-584.

Sulkinoja, M. 1981. Lapin koivulajien muuntelusta ja risteytymisestä. On the variation and hybridization of Betula species in Lapland. Luonnon Tutkija 85: 111-116.

— , Inki, M. & Valanne, T. 1981. Lapin koivulajien ja niiden hybridien tutkimuksesta (English summary:) Betula species and their hybrids in Lapland. Luonnon Tutkija 85: 111-116.

Sørensen, T. 1941. Temperature relations and phenology of the Northeast Greenland flowering plants. Medd. Grönland 125 (9): 1-302.

Taylor, A.O. & Rowley, J.A. 1971. Plants under climatic stress. 1. Low temperature, high light effects on photosynthesis. Plant Physiol. 47: 713-718.

Tieszen, L.L. & Bonde, E.K. 1967. The influence of light intensity on growth and in arctic, subarctic, and alpine populations of Deschempsia caespitosa and Trisetum spicatum University of Colorado Studies. Series in Biology 25: 1-21.

Tizua, R.J. 1975. Research in the North as viewed by the communities. Proceedings of the Circumpolar Conference on Northern Ecology (September 15-18 1975 Ottawa, part V, 1-26).

Todd, R.A., Meyer, R.D. & Waide, J.B. 1978. Nitrogen fixation in deciduous forest in the south-western easteem United States. Ecological Bulletin 26: 172-177.

Tumanov, I.I. 1967. In: The cell and environmental temperature. Troshin, A.S. (ed.), 1967, pp. 6-14. Oxford: Pergamon Press.

Turner, R.M. 1963. Growth in four species of Sonoran desert trees. Ecology 44(4): 760-765.

Vaarama, A. & Valanne, T. 1973. On the taxonomy, biology and origin of Betula tortuosa Ledeb. Rep. Kevo Subarctic Res. Stat. 10: 70-84.

Valanne, N. 1977. Effect of continuous light on CO_2, fixation, chlorophyll content, growth and chloroplast structure in Ceratodon purpureus. Zeitschr Pflanzenphysiol. 81: 347-357.

Warren Wilson, J. 1960. Observations on net assimilation rates in arctic environments. Annansof Botany, N.S. 24 (95): 372-381.

Viereck, L.A. & Little Jr., E.L. 1972. Alaska Trees and Shrubs. 1972. 265 pp. Agricultural Handbook no. 410., Washington, D.S.

Öquist, G., Brunes, L., Hällgren, J.E., Gezelius, K., Hallén, M. & Malmberg, G. 1980. Physiol. Plant. 48: 526-531.

SEED PRODUCTION OF SCOTS PINE CLOSE TO TIMBERLINE IN FINLAND

Erkki Numminen

ABSTRACT: Pine seed crops are large even in Lapland. According to extensive measurements carried out by Sarvas during 19 study years over a million seeds per hectare have annually fallen in Rovaniemi and over half a million further north in Utsjoki. The figures include also empty seeds. However, seeds rarely ripen near the timberline. Seeds were last collected in the winter of 1972 - 1973 and the stores are running short. Yet, natural regeneration may succeed even with incompletely ripened seeds.

INTRODUCTION

The timberline of pine in Finland is affected by ground elevation, it is in other words alpine, for there are pine stands on the shores of Norwegian fjords and river valleys (Fig. 1) which are north of Finland. The ground rises steadily along the Kilpisjärvi road in the western border in Lapland. The northernmost roadside pine stand is in Maunu (Lat 68° 29', Long 22° 14'). Yet, further up in the north fine pine stands of commercial value grow on the shores of Lake Inari (118 m above sea level). Close to timberline there are large areas where pine does not thrive because of compact soil consisting of fine soil fractions. These areas are stocked with spruce and birch stands, the best-known of which is Pomokaira.

Research into seed crops of forest trees and regeneration have long traditions in North Finland. Renvall published his investigations of the variation in pine seed crops on timberline as early as 1912. Heikinheimo launched systematic measurements of seed crops in 1925 and published the results in 1932, 1937 and 1948. Sarvas carried on these investigations and wrote a number of publications. This very extensive material has been the basis for the investigations on flowering and seed crops (Koski and Tallqvist, 1978), the figures of which have also been used in this paper.

Erkki Numminen is the manager at Kolari Research Station of the Finnish Forest Research Institute

Information on seed ripening has been collected at the Kolari Research Station of the Finnish Forest Research Institute.




Figure 1. Pine timberline in the Arctic area of the Nordic countries. Horizontal lines indicate pine forests, vertical ones groups of pine and dots single pine trees according to Hustich (1958).

SEED CROPS

Table 1 shows pine seed crops in 13 localities in Lapland over different years. Pine seeds do not ripen until the year following flowering. The seed crops of pine do not vary as much as those of spruce. Such an overwhelming seed crop of spruce as occurred in 1970 has probably never occurred in pine.

However, good seed crops of pine, judged by its own standards, are more frequent than those of spruce. Four good and two or three satisfactory seed crops occurred during the 19 study years. Therefore, the average seed crops of pine are not much inferior to those of spruce

in the long term. The seed crops of even pine are extravagant. In a top stand at Hietaperä mineral soil site in Kivalo an average of 108 seeds fell on each square metre annually and even in the poorest site at Jyppyrä in Enontekiö 18 seeds. Even at Utsjoki the figure is 61. The seed number in Sarvas material refers to all fully grown seeds without distinguishing between full or empty seeds or different germinating capacity.

Table 1. Annual seed crop of Scots pine (seeds/m^2) in some experimental areas set up by Sarvas.

Latitude	Place of the seed traps	Stand age	Years of flowering																		$\bar{x}$
			54	55	56	57	58	59	60	61	62	63	64	65	66	67	78	69	70	71	72	
66°21'	Rovaniemi	119	5	3	14	3	77	31	133	14												48
	"	116	2	1	12	7	56	30	105	167												48
	"	100	4	2	13	5	38	53	134	159												51
	"	108						84	320	180	13	1	232	68	5	10	31	10	362	186	16	108
	"												144	20	2	2	16	26	289	164	11	75
67°22'	Sodankylä	130						28	158	130	62	7	153	73	13	40	14	14	76	173	39	70
	"	191						13	112	17	7	3	42	46	29	6	28					30
68°01'	Kittilä	216				1	9	16	132	92	36	8	22	30	8	4	6	1	71	221	8	42
	"	191				2	3	4	134	121	39	3	41	39	15	4	9	7	52	117	4	37
68°20'	Enontekiö	195						2	37	19	37	6	9	4	5	42	19					18
68°28'	Inari	199			4	0	3	11	86	42	60	23	41	54	88	7						35
	"	195					9	5	100	131	87	22	57	35	46	6						50
69°44'	Utsjoki												65	48	24	10	26	18	138	199	17	61
Temperature sum, d.d. in Sodankylä			894	768	694	800	744	826	1071	938	580	928	740	641	773	817	627	749	947	724	990	

Sarvas material shows that seed crops have been prolific all over Finland, even in the north and elevated areas where pine stands grow.

Adequate flowering is a necessary precedent for a seed crop. Flower buds mature in the preceding growing season so that the primary concern is the weather in the current summer. There is a common belief that a warm growing season leads to a large number of flower buds. Using Sarvas pine material Koski (1978) investigated the correlation between the years of vigorous inflorescence of staminata flowers and temperature sum of the previous summer as well as seed crops and the sum of growing seasons two years earlier. According to his findings, such correlation, although not very solid, exists. However, as a consequence poor flowering occurred after an exceptionally cold growing season. Thus a warm growing season does not always lead to abundant flowering in the following year and more seldom to a good and ripe seed crop in the next two years. The explanation to the latter is that the effect of the temperature sum during the growing season on the ripening of seeds is absolutely unambigous. The two-year development of a pine seed involves may factors that prevent a good seed crop from developing, such as poor pollination owing to rain, storm or other causes during the flowering. These factors may also lead to falling of conelets, as too small a number of ovules become fertilized. Severe frosts may also damage conelets. Numerous fungi and pests are harmful to cones. A vigorous flowering and seed crop may also "exhaust" a tree. Even this point is ambigous, because two good seed years may follow each other. Successive and prolific seed crops have occurred in 1926 - 1927, 1961 - 1962 and 1971 - 1972 (Fig. 3). The seeds have not necessarily been ripe in these years. The 1962 seed crop was good but remained almost totally unripened, as the temperature sum in Sodankylä was 580 d.d. This prolific but unripened seed crop in 1962 clearly seems to be caused by the preflowering summer 1960 which was the second warmest in the whole century (in Sodankylä 1071 d.d.).

Even long time series have not revealed such regularity as would help predict the future seed crops of forest trees, as the weather is the primary determining factor. In addition to the weather many other factors affect the quantity and quality of seed crops. Therefore, it is important that enough seeds will be collected for storage whenever the seeds ripen in North Finland.

RIPENING OF SEEDS

The seed crop has an afforestational value only if it is ripe enough. In Finland, especially after the Second World War, the existence, thriving and ripening of seeds of northern forests have been compared to the temperature sum, the threshold value being five degrees centigrades in Finland and six in Sweden. The temperature sum is more frequently used than the mean temperatures of June, July and August. The thirty-year period from 1941 - 1970 (Fig. 2) is nowadays used for the comparison of temperature sums.




Figure 2. Mean temperature sums of growing seasons in 1941-1970.

The long-term variation in the temperature sum can best be studied using the values released by the Sodankylä observatory (Fig 3), which is the oldest one in Lapland, established in 1908. The broken line shows a strong annual variation and rise in the temperature sum since the establishment of the station up till the end of the 1930's. The coldest summers in Sodankylä correspond to the mean values in 1941 - 1970 of the alpine birch area and the warmest years to those of the Jyväskylä area in Central Finland.




Figure 3. Temperature sums measured at Sodankylä observatory in the growing seasons in 1908-1986.

The Karesuvanto (established in 1883) and Jokkmokk (in 1865) weather stations in Sweden are older than the Sodankylä station. Their records show that the minimum values of cold summer periods occur at the turn of the century and that the previous warm period remained much colder than the warm one in the 1930's. The variation in the temperature sum in different parts of North Finland in 1971 - 1986 can be found in Figure 4.




Figure 4. Temperature sums of growing season at some weather stations in North Finland in 1971-1986.

According to Sarvas pine seeds ripen well enough in the area of 950 d.d. North of this limit ripening gradually weakens. It has proved very difficult to work out clear regularities of how ripening weakens as the temperature sum decreases and what the temperature sum limit is where even the seeds of the northernmost pine provenance do not germinate even in a germinating apparatus. All the investigators do not even agree that the temperature sum is the right way of defining the ripening of seeds. It is certainly true that one would need the correction coefficient of total radiation, hours of sunshine, rain or other factors for support. The temperature sum can, however, be a satisfactory way of finding out the level of ripening.

The Kolari Research Station has been engaged for over 15 years in the determination of the annual ripening of pine seeds in North Finland. It is carried out by X-raying and germinating seeds from sample stands and drawing curves of temperature sums from approximately 50 weather stations of the Meteorological Institute.

Each autumn the definition of the ripening of pine seeds is started by drawing temperature sum maps. Only few stations provide us with that information in September. Usually the final temperature sums will not arrive from the Meteorological Institute until January. As most of the temperature sums have accumulated till the middle of September, the advance information will help estimate the zone south of which seeds have ripened enough for collection. Cones are sampled from and around questionable areas for the investigation of ripeness, which is also affected by ground elevation from the sea level. For this purpose X-raying is the fastest, most inexpensive and accurate method.

The temperature sum investigations and consequent sampling aim at finding out the border zone of collectable seeds. There has not been much interest in studying the zone of poor ripening as it is worthless from the collection point of view. Even incompletely ripened seeds were collected in cases of emergency before 1972 when the seed stores were nearly exhausted in Lapland.

Incompletely ripened pine seed crops are common near the timberline except for infrequent warm summers. Even such seeds germinate and may suffice for the needs of natural regeneration if the weather in the seedfall year is favourable, the soil surface has been prepared or it is otherwise a favourable substrate for the development of the germlings. Occasionally cutting areas on the timberline are stocked with well-developed and naturally regenerated seedlings. It is, however, hard to say for certain which seed year they come from as post-germination does occur, in other words a seed may germinate one or two years after seedfall.

Many experiments have been carried out to improve the quality of incompletely ripened seeds. Especially researchers in Umeå and Sävar in Sweden are worth mentioning, as they have, among other things, developed the so-colled Prevac and IDS methods.

Pine seeds do not require stratifying, as they will be ready for germination during the winter in trees or seed storage until spring (e.g. Numminen, 1977). However, seeds collected in the early autumn do not germinate immediately after collecting without special measures.

The sorting of incompletely ripened seeds has gained importance along with the development of modern nursery techniques, since poorly germinating seeds cause economic losses because of empty paper pots and wasted space in greenhouses. On the other hand, the more seeds are assorted, the smaller is the amount that can be used. Possibilities of ripening seeds by keeping collected cones in warm and well ventilated stores are small if the aim is to make the endosperm or embryo grow. There is also apparent danger of seeds becoming mouldy.

The staff the Kolari Research Station have collected cones from individual trees in pine stands in various parts of North Finland for 15 years. Collection times per trees would be about 2 000 and the number of X-rayed seeds about 700 000. Figure 5 indicates that the germinability of seeds develops as the temperature sum increases faster near the timberline than south of it. Up till 700 d.d. germinability

develops equally fast in the whole of North Finland. After that differences start. These differences level down when the temperature sum reaches 950 d.d. the point at which the seed is ripe in the entire North Finland.




Figure 5. Germination development of pine seed ... close to timberline, --- in middle Lapland and ___ in south Lapland.

It is vital for natural regeneration to know what the ripening of seeds is like in North Lapland in such summers as the temperature sum reaches only 500 - 700 d.d. The X-rays taken at Kolari show that poorly germinating seeds that have ripened under favourable circumstances can be found in rather large amounts on the timberline if the temperature sum has exceeded 600 d.d. Even in colder summers some germinating seeds can be found. The limit for totally sterile seeds is at about 500 d.d. Then the only way of opening the cone is by tearing.

Seeds are more ripened in the southern than in northern sides of the crown, although no differences in ripening could be found in slopes different directions (Numminen 1974).

SEED ORCHARDS

Plenty of pine seeds were collected in the winter of 1972 - 1973 when ripening was satisfactory also on the timberline. After that winter it has not been possible to collect seeds and storages are already empty in the northern parts of the Kittilä, Sodankylä, Savukoski and Salla communes. There were abundantly seeds in the unelevated area in Inari, from where they have been transferred to the "empty" areas so that the before-mentioned stores are running short. Now the focus is the seed orchards in Central Finland. Due to background pollination the range of use has so far reached the southern parts of the Oulujoki watercourse (Kylmänen 1980). As the inflorescence of staminate flowers increases, the range of use gradually extends northward. However, it will probably a long while before seeds from these orchards can be used near the timberline. There will always be background pollination also in the seed orchards so that dense afforstation spacing should be used near the timberline. It has been suggested that new seed orchards for the needs of North Lapland should be set up further to the south than nowadays, maybe even to Central Europe or preferably outside the range of Scots pine in West Canada and Alaska where the climate would be better suited for Scots pine than in Central Europe.

FUTURE PROSPECTS

Afforestation with pine has not always been successful near the timberline or elevated areas further to the south, especially when the soil has been compact, poorly permeable to water and unaerated, and when the proportion of fine clay and sand particles has been high. Transferring seeds from the north to the south has not much improved the situation, as a limiting factor has been the unavailability of northern seeds.

Efforts have been made to find individual trees in Lapland forests that would be more easily adjusted to the short growing season, in other words trees that would provide progenies

that survive afforestation better than nowadays, grow satisfactorily and produce good-quality timber. Numerous experiments with progenies of plus trees have been carried out in Lapland. Significant differences have been found out between the plus trees. Plus trees P 629 and P 550 with successful progenies are worth mentioning (Mikola, J. orally passed information). On the other hand, it is probably right to assume that an individual tree whose seeds ripen better than those of other trees in the stand year after year, despite cold summers, is also otherwise better adjusted to the short growing season. Such trees have been searched for in the investigated stands in Lapland for years. It is not an easy task as differences in temperature sums of tree crown, health of trees, position in the stand and other environmental factors have to be precisely recorded. Similarly, it is not easy to get annually 400 seeds which would be a sufficient ripening sampling.

LITERATURE CITED

Heikinheimo, O. 1932. Metsäpuiden siementämiskyvystä. Referat: Über die Besamungsfähigkeit der Waldbäume. Common. Inst. For. Fenn. 17.3. 1932. 61 p.

— 1937. Metsäpuiden siementämiskyvystä II. Deutsches Referat: Über die Besamungsfähigkeit der Waldbäume II. Commun. Inst. For. Fenn. 24.2.1937. 67 p.

— 1948. Metsäpuiden siementämiskyvystä III. Summary: on the seeding capacity of forest trees III. Commun. Inst. For. Fenn. 35.3. 1948. 15 p.

Hustich, I. 1958. On the recent expansion of the Scotch pine in Northern Europe. Fennia 82. 1958. 25 p.

Koski, V. & Tallqvist, R. Tuloksia monivuotisista kukinnan ja siemensadon määrän mittauksista metsäpuilla. Results of long-time measurements of the quantity of flowering and seed crop of forest trees. Folia For. 364. 1978. 60 p.

Kylmänen, P. 1980. Ennakkotuloksia nuorissa männyn siemenviljelyksissä syntyvän Pohjois-Suomi x Etelä-Suomi -kaukoristeytyssiemenen käyttömahdollisuuksista. Summary: Preliminary results concerning usability of North Finland x South Finland hybrid seed born in young Scots pine seed orchards. Folia For. 423. 1980. 16 p.

Numminen, E. 1974. Rinteen ja latvuksen ilmansuunnan vaikutus männyn siemenen tuleentumiseen ja siemensadon määrään Pohjois-Suomessa. Metsäntutkimuslaitos. Kolarin tutkimusaseman tiedonantoja 6. 1974. 9 p.

— 1977. Männyn siemenen keväistämiskoe Länsi-Lapissa. Metsäntutkimuslaitos. Kolarin tutkimusaseman tiedonantoja 9. 1977. 15 p.

Renvall, A. 1912. Die periodischen Erscheinungen der Reproduktion der Kiefer an der polaren Waldgrenze. Acta For. Fenn. 1(2): 1912. 166 p.

Sarvas, R. 1962. Investigations on the flowering and seed crop of Pinus sylvestris. Commun. Inst. For. Fenn. 53. 1962. 198 p.

THE EFFECTS OF ELEVATION OF SITKA SPRUCE PRODUCTIVITY IN SCOTLAND

R. Worrell and D. C. Malcolm

ABSTRACT: Expansion of afforestation in upland Britain requires some estimation of productivity at higher elevations. Examination of the productivity-elevation relationship of existing Sitka spruce plantations indicated geographic variation which paralleled known patterns of distribution for accumulated temperature and windiness. Estimates of these factors combined accounted for 78 percent of variation in observed productivity. Addition of geomorphic shelter, aspect and soil type increased the precision of predictive equations but only to a small extent. Validation of the regression model suggested that productivity could be estimated to about ± 1.0 m^3 ha^{-1} yr^{-1}, which is adequate for management and investment decisions.

INTRODUCTION

For the last 2 500 years the climate of Scotland has been strongly oceanic in type. The climate is characterised by generally low summer temperatures, lack of severe winters, high precipitation and associated cloudiness and, in particular, the frequency of strong winds. These climatic factors must have had a marked effect on the distribution of the forest species that had invaded post-glacially and which had extended their elevation range to about 800 m a.s.l. However it is still difficult to distinguish between a depression in the elevational range of forest due to climatic change and that due to the effects of prehistoric man. A further complication is the separation of Britain from continental Europe about 5 000 BC so that only one native conifer, the Scots pine *(Pinus sylvestris* L.) became established and survived to historical times and that only in northern Scotland.

Forest destruction which began in Neolithic times continued throughout the historical period until the present century when, after the First World War, only 3 % of the land area was forested. The subsequent expansion of forest to about 11 % of the land area has been achieved by using exotic species, especially those from North West America.

The predominant species has become Sitka spruce (*Picea sitchensis* Bong. Carr.) which, apart from its desirable productivity, has demonstrated that it is generally well adapted to the climate of the Scottish uplands and is capable of adequate growth in conditions in which the native Scots pine cannot survive. Together with the development of site amelioration techniques (cultivation, drainage, fertilization) the scarcity of land led to the steady expansion of afforestation on to less fertile, more exposed sites at higher elevation. It thus became important to be able to identify the climatic limits, usually expressed in terms of elevation, for the economic production of timber — the so-called 'commercial planting limit'. Based on an evaluation of the 'internal rate of return' on the initial investment in planting, this limit is often quoted as a productivity of about 8 m^3 ha^{-1} yr^{-1}. This arbitrary value varies, of course, with the economic assumptions used in its calculation and thus the elevational limit will also vary. It is more useful therefore to be able to define the relationship between climatic factors (or elevation) with tree productivity in more general silvicultural terms and allow the investor to make his own judgement of profitability.

Diminishing productivity at increasing elevations has been demonstrated for both natural

RICHARD WORRELL is a postgraduate student and DOUGLAS C. MALCOLM is a senior lecturer in the Department of Forestry and Natural Resources, University of Edinburgh U.K.

forest ecosystems and plantations in many parts of the world. It is frequently expressed as changes in dry matter production, mean volume, height or diameter. The relationship between productivity and elevation in continental climates has been shown to be curvilinear (Oswald 1969; Ott 1976) but in Britain the relationship appears to be linear (Malcolm 1970; Mayhead 1973). The relationship is nevertheless complex as most environmental factors that influence tree productivity also vary with elevation and even distinguishing between climatic and edaphic factors can be difficult. The most obvious factor is the reduction of air temperature at higher elevations both in terms of the actual values attained affecting tissue temperatures and the duration of the period in which metabolic activity can be maintained and thus influencing the maturation of tissues. Increases in elevation reduce the so-called growing season more in oceanic than in continental climates because of the flatter shape of the march of temperature curve. Windiness increases with elevation affecting tissue temperature, plant water status and mechanical damage (Grace 1977). Cloudiness and precipitation also increase with elevation often leading to reduced light intensity and excess soil moisture in an oceanic climate. These effects are related to changes in soil temperature, nutrient availability and water status.

In general climate appears to have a dominating influence on forest productivity at higher elevations (Tranquillity 1979) but the interrelations between climatic, edaphic and topographic factors (slope, aspect) make it difficult to attribute specific effects on tree growth when the physiological processes governing productivity are also strongly interacting.

The aims of the study reported here were, therefore, to (1) characterize geographic patterns in the relationship between the productivity of Sitka spruce plantations and elevation; (2) to identify environmental factors that could be readily assessed to predict productivity and define upper planting limits.

STUDY BASIS

a) Field sampling

Productivity was estimated as yield class (m^3 ha^{-1} yr^{-1}), which is the maximum mean annual increment of stem volume. It is estimated from stand top height at a given age (Edwards and Christie 1981), a relationship which could be influenced by establishment difficulties, fertilization regimes and changes in tree form on exposed sites. This estimate of productivity (General yield class) however is readily assessed and the problems in its use can be largely avoided through site selection.

The topographic variables measured were elevation, geomorphic shelter, aspect and slope while soil factors were recorded as soil type. depth and rooting depth attained. Details of the methods used to estimate these factors are given by Worrell (1987).

Temperature was expressed as the mean accumulated temperatures above 5.6° C and the mean air temperature of the four warmest months (June - September) both derived by extrapolation from standard meteorological stations (Birse and Dry 1970) using a standard lapse rate (0.6 °C per 100 m). Windiness of the sites investigated was estimated by the rate of 'flag tatter' extrapolated from the results obtained from a network of 1100 flags deployed in over 100 locations by the Forestry Commission between 1954 and 1984. As the 'tatter rate' observed varies in different parts of the country a series of geographic 'windzones' have been demarcated (Miller 1985) to take account of this variation.

The other climatic factors assessed were mean annual precipitation, estimated potential water deficit and oceanicity, each derived from published maps (Birse and Dry 1970).

b) Distribution of experimental sites

Field sampling was conducted by establishing 187 temporary plots (0.04 ha) located at 37 sites throughout Scotland and N. England. To investigate the effect of elevation the plots

were laid out in series at 20-40 m vertical intervals (random start) in 18 main transects. A further 19 supplementary sites were chosen to increase the overall geographic cover with fewer sample plots in each.

c) Analysis of elevation — yield class relationship

Productivity (GYC) was regressed on elevations for each of the 18 main sites. At most sites the relationship proved close and $\underline{r}^2$ values ranged between 53 and 98 percent and were best estimated by linear functions. The average reduction in productivity was 4.3 m^3 ha^{-1} yr^{-1} per 100 m increase in elevation (range 1.7-7.4). When the data were pooled the overall regression coefficient was only 0.0174 with $\underline{r}^2$ = 36.1 percent and it was clear that there was considerable site-to-site variability. Examination of the data suggested that sites located at higher elevations have higher GYC values for a specific elevation and that these sites were also in relatively sheltered inland areas whereas low level sites were more coastal.

To estimate the effect of location on the elevational relationship an analysis of covariance was carried out where effectively an 'average' regression line is fitted and the mean displacement from this line of the individual site regressions gives a measure of site-to-site variation.

The analysis was done by multiple regression using 'dummy variables' to express the effect of location (Worrell 1987). The model used was:

$$GYC = a+b(elevation) +b_1X_1 +b_2X_2 \ldots b_nX_n$$

where X_1, X_2, X_3 are dummy variables (Nie et al. 1975). To solve the normal equations one site must be used as a 'reference category' (for which the value of b = 0) with which all other sites are compared. The 'reference' site chosen was Glenbranter Forest in west central Scotland. The data from the main locations were regressed in this way to give the equation:

$$GYC = 27.3-0.043(elevation)+\text{'site effects'} \quad (1)$$

The individual b coefficients (the site effects) ranged from -4.32 m^3 ha^{-1} yr^{-1} to 8.57 m^3 ha^{-1} yr^{-1} and the effect of location was highly significant (f = 27.5). When fitted to the whole data set (187 plots) the relationship was:

$$GYC=26.5-0.0404\ (elevation)+\text{'site effect'} \quad (2)$$

($\underline{r}^2$ = 80.7 percent)

Site effects now varied between -9.45 and +8.34 m^3 ha^{-1} yr^{-1} and were highest in the south and inland areas and lowest on western and northern coasts. The site effects were contoured mapped by computer (Figure 1). Using this figure and equation (2) the productivity (GYC) at any elevation within the original range of data can be estimated for any area in Scotland. Despite the relative precision of the model it assumes equal linear slopes in the elevational relationship at all locations. Although there is evidence (Worrell 1987) that a quadratic model might be a better fit for the whole elevational range a linear model seems most appropriate to the restricted elevational range sampled in this study (about 65% of plots were between 300 - 550 m).

From this initial investigation it can be concluded that productivity is strongly related to elevation at any one location but that the relationship alters between sites, productivity being lower in northern and coastal areas for a given elevation than inland or southern sites. This pattern of variation (Figure 1) bears a close resemblance to the known patterns of windiness (Hardman et al. 1973; Miller 1985) and of growing season temperature in Scotland (Met. Off. 1952).

ACCUMULATED TEMPERATURE AND WINDINESS

Tree growth is well known to respond to temperature variation in many different ways (e.g. Mikola 1962; Tranquillini 1979). Temperature effects can be conceived in terms of a threshold value for metabolic activity (e.g. 5.6° C) and a

range in which growth rate is proportional to temperature. These concepts have led many researchers to use accumulated temperatures (heat sums) to integrate growing season length with actual temperatures (e.g. Mork 1960; Farr and Harris 1979). However the paucity of meteorological data for upland and remote forest areas entails extrapolation of data both spatially and altitudinally using lapse rates. There are of course inherent sources of error in making these extrapolations but useful results can be achieved (e.g. Hunter and Gibson 1984).

Wind has marked effects on tree growth through cooling of tissues, effects on stomatal control and mechanically by altering tree form and physical damage. Windiness is also quite closely related to topography and elevation.

In an attempt to relate productivity more closely to climate, quantitative relationships between tree growth and indices of temperature and windiness were explored for the sites studied. The main indices used were:

1. Mean annual accumulated air temperature above 5.6° C (day ° C).
2. Flag tatter rate ($cm^2\ d^{-1}$).

Both indices were adjusted to sea level values and contour plotted as shown in Figures 2 and 3 (Worell 1987). Functions relating these values to those estimated for individual sample plots were then derived. In the case of tatter rate the function included elevation, topex, aspect and location (Worrell 1987). Productivity as measured at each plot proved to be significantly correlated with elevation (r = -0.601), accumulated temperature (r = 0.683), tatter rate (r = -0.587) and the cosine (r = 0.263) and sine (r = 0.290) of aspect for the whole data set. Higher values of r were obtained if the data was confined to those plots that had received current silvicultural treatments. For the latter data set the model including estimated values of temperature and windiness had d $\underline{r}^2$ value of 78 percent:-

GYC = 9.53 - 0.902 (tatter rate) + 0.0134 (acc. temp.) -(3)

The combination of tatter values with temperature acknowledges the fact that windy coastal sites experience higher temperatures than equally windy sites in inland mountainous areas. The model shown in equation (3) provides a basis for prediction of the GYC of Sitka spruce established with standard silvicultural techniques.

Other Site Variables

The inclusion of other site factors in the regression models improved their predictive ability ($\underline{r}^2$ = 86 percent). For example using stepwise regression techniques it could be shown that geomorphic shelter, aspect and soil type had an influence on GYC. The pattern of productivity in respect of aspect is the converse of that of flag tatter rate suggesting that wind exposure is more important in this context than increased solar radiation input, for example on southerly aspects. Although the effect of soil type was significant its inclusion only raised $\underline{r}^2$ values by 2-4 percent. The influence for a brown earth raised GYC by 2 $m^3\ ha^{-1}\ yr^{-1}$ from the average while unflushed organic soils (peat) decreased GYC by a similar amount.

Predictive Value and Validation

The confidence limits for the 'best' regression equation were calculated initially on the assumption that the error variance was not location-related (Worrell 1987). This gave values of ± 1.0 or 1.4 $m^3\ ha^{-1}\ yr^{-1}$ for mean or extreme values of X variables. However a location-related component of the error variance was detected and the prediction of GYC for an <u>area</u> of plantable land had confidence limits of ± 2.3 and 2.6 $m^3\ ha^{-1}\ yr^{-1}$ for mean and extreme values of X. When estimating the <u>mean</u> deviation of predicted values from actual values a precision of close to ± 1.0 $m^3\ ha^{-1}\ yr^{-1}$ is obtained which is adequate for practical purposes. Validation of the regression models was achieved by independent collection of data from 32 new sample plots distributed in 9 forest areas. Compared with the values of GYC predicted

by the regression the observed yield classes differed by an average of ± 1.48 for the 32 single plots, ± 1.01 - 1.28 for the individual forest areas and by 0.02 - 0.67 m^3 ha^{-1} yr^{-1} for the mean of all the plots. The regression of actual values on predicted values had a r^2 value of 63 percent. The values of mean deviation for individual forests are close to the estimate of precision based on the standard error of the regression (above). One could therefore expect to be able to predict GYC with a mean error of about ± 1.0 m^3 ha^{-1} yr^{-1} for a single forest block.

CONCLUSIONS

Previous attempts to classify site productivity for Sitka spruce in upland areas of Scotland (e.g. Malcolm 1970, Blyth 1981) have relied on topographic variables such as elevation and geomorphic shelter to characterize climatic conditions. They also anticipated that soil variables (physical and chemical) would account for a large measure of the variation in productivity. In the analysis the productivity relationships were dominated by elevation and soil factors played a relatively small part. In this study the elevation - productivity relationship was defined for a range of sites across the country so that it became clear that the relationship varied in a pattern that bore a close resemblance to the known distribution of accumulated temperatures and windiness. Both factors are also closely related to elevation. The good correlations between the extrapolated values of accumulated temperature and the crude estimate of wind climate provided by the tatter rate of flags encouraged the development of predictive equations. These factors together accounted for about 75 percent of the observed variation in Sitka spruce productivity while only small increases were obtained for other factors such as soil type, aspect and geomorphic shelter. Nevertheless from a practical forest management viewpoint the predictive ability of the equations were validated and offered a precision of estimate not previously available.

In studies of site-productivity variation it is usual for there to be a number of combinations of site variables that give equally good predictive ability. Their utility for management is enhanced if a few variables that are readily assessed can be used. In this study the 'best' equation comprised elevation, estimates of accumulated temperature and flag tatter rate at sea level, geomorphic shelter (topex) and crop age together with aspect and soil type and accounted for 87 percent of the variation observed in Sitka spruce stands which had received standard silvicultural treatment.

In view of the potential sources of error in extrapolation both spatially and altitudinally, of climatic measures as crude as day-degrees and tatter rate it is surprising how closely the estimated values accorded with observed productivity. The physiological basis of these variables in terms of tree growth is very unclear and they take no account of other known effects such as mechanical damage or winter desiccation. These factors however appear to integrate the effects of the general environment as it influences the growth of Sitka spruce and reflect the decreasing production at higher elevations. The lack of importance attributable to measures of moisture availability (precipitation, potential water deficit and soil depth) is probably due to the range of elevation sampled and at lower elevations (<200 m) moisture stress may limit growth.

This study was based on plantation grown Sitka spruce in a windy oceanic climate and one would expect that for other species and in other climates its applicability might be limited. Nevertheless the statistical treatment of the data by using dummy variables in regression analysis allowed the pattern of variation with location and the effects of categorical variables such as aspect and soil type to be estimated. The use of this technique in other studies where climatic factors have not been adequately represented might improve the understanding of site-productivity relationships.

LITERATURE CITED

Birse, E.L. & Dry, F.T. 1970. Assessment of climatic conditions in Scotland. Soil survey of Scotland, Macaulay Institute for Soil Science, Aberdeen.

Blyth, J.F. & MacLeod, D.A. 1981. Sitka spruce (Picea sitchensis) in N.E.Scotland: 1 Relationships between site factors and growth. Forestry 54: 41-62.

Edwards, P.N. & Christie, J.M. 1981. Yield models for forest management. Forestry Commission Booklet 48 Edinburgh.

Farr, W.A. & Harris, A.S. 1979. Site index for Sitka spruce along the Pacific coast related to latitude and temperatures. Forest Science 25: 145-153.

Grace, J. 1977. Plant responses to wind. Academic Press, London.

Hardman, C.E., Hellewell, N.C. & Hopkins, J.S. 1973. Extreme winds over the United Kingdom for periods ending 1971. Meteorological Office Climatological Mem. 50a.

Hunter, I.R. & Gibson, R. 1984. Predicting radiata pine site index from environmental variables. N.Z. J. For. Sci. 14: 53-64.

Malcolm, D.C. 1970. Site factors and the growth of Sitka spruce. Unpubl. Ph.D. Thesis University of Edinburgh.

Mayhead, G.J. 1973. The effect of altitude above sea-level on the yield class of Sitka spruce. Scott. For. 27: 231-237.

Meteorological Office. 1952. Climatological atlas of the British Isles. H.M.S.O. London.

Mikola, P. 1962. Temperature and tree growth near the northern timberline. In: Kozlowski, T.T. Tree growth. Ronald Press New York, pp. 265-274.

Miller, K.F. 1985. Windthrow Hazard Classification. Forestry Commission Leaflet 85. H.M.S.O. London.

Mork, E. 1960. On the relationship between temperature, leading shoot increment and the growth and lignification of the annual ring in Norway spruce (Picea abies L. Karst.). Medd. Norsk Skogforsøkvesn. 56: 229-261.

Nie, N.H., Haalai-Hull, C., Jenkins, J.G., Steinbrenner, K. & Bent, D.H. 1975. Statistical package for the Social Sciences. McGraw-Hill, Inc. New York.

Oswald, H. 1969. Conditions forestieres et potenialite de l'epicea en Haut Ardeche. Ann. Sci. Forest. 16: 183-224.

Ott, E. 1978. Über das Abhängigkeit des Radialzuwaches und der Oberhöhen bei Fichte und Larche van der Meereshöhe und Exposition in hötschertal. Schwei. Z. Forstwes. 129: 169-193.

Tranquillini, W. Physiological ecology of the alpine timberline Springer-Verlag, Berlin.

Worrell, R. Geographical variation in Sitka spruce productivity and its dependence on environmental factors. Unpublished Ph.D. thesis, University of Edinburgh.




Figure 1. The effect of location on the elevation-productivity relationship. For any given elevation and location GYC is increased or decreased by the amount shown by the contour line.




Figure 2. The distribution of day-degrees extrapolated to sea-level using a standard lapse rate (0.6 ° C/100 m).




Figure 3. The distribution of flag tatter rate (cm^2 d^{-1}) adjusted to sea-level.

NATURE AND RATIONAL USE OF PRETUNDRA PINE FORESTS IN THE EUROPEAN PART OF THE USSR

A.A. Listov and B.A. Semyonov

Pretundra forests of the Arkhangelsk region and Komi ASSR located north of 65°N extend as a continuous band from the eastern shore of the Dvina Inlet in the west to the border with the Tumen region in the east. The southern boundary of this zone is very tortuous. Along big rivers it rises to the north, while in the interstream areas, in the sites with poor river network, and in the Urals it moves to the south.

The terrain is characterized by the smooth relief and spreading extensive swamped lowlands. Nearness of the northern seas, frequent incursion of cold air from the Arctic Regions and Siberia, passing cyclones define the cold and humid climate with unsteady weather. In the west, an intensive influence of Atlantic cyclones becomes apparent, in the east, climate continentality increases. Snowfall and frosts are possible in any summer month. The total solar radiation does not exceed 70 Cal per cm^2 per year, but its entry during the year is highly irregular. In June-July the amount of the total solar radiation, including photosynthetically active radiation does not yield to that of the south-taiga subzone. The presence of numerous rivers, lakes, and bogs contributes to great air humidity (at an average 82 per cent a year). All of this affects the temperature regime, defines the length of cold and warm periods. The most warm month of the year is July with the mean monthly temperature of 12.8° C and the absolute maximum of 33 - 34° C in the air and 42 - 49° C on the soil surface. The most cold months are January and February when the temperature decreases to -50 - 55° C with its mean monthly value of -15 - 16° C. The mean annual air temperature is -2.9 C°. The frost-free period is 62 to 110 days, the growing season averages 109 days with the period of active vegetation of 60 days and accumulated temperatures during this period somewhat more than +710° C. Mean annual precipitation is 437 mm with 65 - 70 per cent occurring in April-October. Moisture evaporation is low; the total evaporation volume is significantly less than that of the precipitation. The depth of snow cover is irregular ranging from 40 - 50 cm to 1.0 - 1.5 m and reaching 4 m (in the Urals).

A soil-forming process is characterized by the poor microbiological activity, accumulation of peat-humus horizon and of a gleyic one under it. Tundra, podzolic-gley, and bog soils are distributed. In other habitats with leaching regime typical sandy and clay sand podzols are developing. The main parent rocks are moraine drifts, fluvioglacial and ancient-alluvial deposits represented by sands and clay sands. Soils are poor in nutrients, especially in nitrogen; soil reaction is acidic, base saturation is low.

About 70 per cent of the total land area of the pretundra zone in the Arkhangelsk region (without Nenets Autonomous Area) and Komi ASSR is turned over to various state enterprises, organizations, collective and state farms in the long-term use. Forestry possesses about 4.4 mln ha, of which 59.4 per cent are forest lands; 40.6 per cent are nonstocek forest lands, principally bogs and tundras.

Spruce occupies 73 per cent of the forested area, birch about 11.5 per cent, and larch 1.7 per cent. Aspen, alder and willow forests are also found.

Pine stands cover about 13 per cent of the area. Pine is often crowded out by spruce; the most stable positions it retains on podzolic light soils and sphagnum bogs. From time immemorial and in the first place pine forests have been subjected to felling and fires, espe-

A.A. Listov and B.A. Semyonov, Arkhangelsk Forest and Forest Chemistry Institue, Arkhangelsk, USSR

cially along the rivers and in the vicinity of settlements. With increasing climate continentality and deteriorating the site from west to east and from south to north a proportion of pine forests takes off.

Maturity and old-growth pine stands dominate covering 77.9 per cent of the area; young-growth stands occupy 10.5 per cent of the area and middle-aged ones 11.6 per cent. The total volume of pine in the pretundra forests exeeds 26 mln m^3, of which 85.8 per cent are overmaturity stands, 1.8 per cent are young-growth stands. Pine productivity is reduced (see Table 1). Stands of site index V-V^a dominate, the part of the pine stands of site index V^b is also great. Typically, the pine forests in the west of the pretundra zone (Arkhangelsk region) are characterized as a whole by higher forest assessment indices than those of the eastern part.

Typological compositon of pine forests.

In the area of the Arkhangelsk region and Komi ASSR the assessment of pine forest types was carried out only in the southern part of the pretundra zone. The vast areas under pine forests in the Nenets Autonomous Area and in the most part of the pretundra zone of Komi ASSR (64 per cent of the pine forest area) were studied very poorly from the typological point of view. The available data show that the most wide-spread type here is *Pinetum sphagnosum* occupying 35.4 per cent of the area in Komi ASSR and 35.9 per cent in the Arkhangelsk region. The widely presented types are *Cladonia*-type (18.2 and 15.4 per cent), *Vaccinium*-type (7.6 and 16.7 per cent), and *Ledum*-type (11.0 and 8.6 per cent). In the west of the zone fresh *Pinetum myrtillosum* (13.8 per cent) is distributed; in the east wet *Pinetum myrtillosum* (5.6 per cent) and *Pinetum polytricosum* (9.7 per cent) are common. Considerable areas are occupied with *Pinetum bryoso-lichenosum*, *Pinetum menyanthoso -sphagnosum*; other forest types are also found.

Table 1. Mean forest assessment indices of pretundra pine forests.

Region republic	Forest assessment indices of pine stands					
	Age (years)	Site class	Density	Volume (m^3/ha)	Increment (m^3/ha)	Volume of maturity and old-growth stands (m^3/ha)
Arkhangelsk	168	V.5	0.51	91	0.54	106
Komi	140	V.9	0.46	47	0.34	54

The pine forests of the pretundra zone are distinguished by their lower stories of vegetation. In the undergrowth *Juniperus communis, Betula nana, Sorbus aucuparia,* subarctic species of *Salix, Betula tortuosa* are common; *Lonicera coerulea, Rosa acicularis, Alnus fruticosa* are found more rarely. The soil cover is dominated by lichens and dwarf shrubs such as *Ledum palustre, Vaccinium uliginosum, Vaccinium myrtillus, Empetrum nigrum L.*, to *Arcstaphylos uva-ursi* and in the west part by *Calluna vulgaris.*

Pine forests do not form great continuous tracts. The main habitats of pine here are small hills and ridges, elevations, rolling plains, lake

boggy plains, bog edges. Pine forests are often found on sandy deposits along the rivers.

Forest management, effective conservation of pine forests, and their rational use cannot be done without regard for the typological structure and peculiarities of forest types. Regularities of woody species regeneration, formation, growth, structure, and productivity of stands are related to a forest type. Thus, *Pinetum cladinosum* stands are single-storied, mainly conditional even-aged, primarily, pure. Birch admixture is not more than 10 per cent, sometimes with spruce and larch in the composition. The stands are often formed by two or three generations of trees. Closing of leaf canopy in *Pinetum cladinosum* is 0.3 - 0.4, the stands refer to the site class V^a-V^b and at age 140 - 160 years their volume amounts to 60 - 80, sometimes 100 - 110 m^3 per ha. Under the tree canopy abundant seedling and young growth of pine (5 000 - 50 000 stems per ha) is frequent.

The stands in *Pinetum vaccinosum* are more often conditional even-aged, single-storied: uneven-aged stands forming under the influence of forest fires are also found. Along with pine (60 - 100 per cent), birch (up to 30 per cent) and spruce (up to 15 - 20 per cent), more rarely larch are common in the stands. Prevailing stand density is 0.4 - 0.5, the site class V-V^a. The timber volume makes up 80 - 100 m^3 per ha., sometimes reaching 150 - 160 m^3 per ha. The pine young growth under the canopy amounts to 3 000 - 10 000 trees per ha. The spruce seedling and young growth is more often found here; in the absence of fires its amount in continually increasing.

Besides pine (70 - 90 per cent) spruce (up to 30 per cent) and birch (up to 10 - 20 per cent) are common in the composition of fresh *Pinetum myrtillosum*. The stands are mainly single-storied; conditional even-aged stands prevail, but unevened ones are also found. The stand density is 0.5 - 0.6, site index IV-V, the stock volume ranges from 110 - 120 to 160 - 180 m^3 per ha. The main species under the canopy regenerates satisfactorily, but the proportion of spruce in the young growth makes up 20 - 50 per cent, sometimes the amount of birch is great.

In *Pinetum polytricosum* pine ,accounts for 50 - 90, spruce up to 40 and birch up to 30 per cent of its composition. The stands are single-storied, uneven-aged and have great tree height variations. Closing of leaf canopy and density are 0.3 - 0.4, the site class V^a-V^b, the timber volume amounts to 50 - 90 cm^3 per ha. The young growth is commonly sparse (1 000-3 000 stems per ha). The proportion of pine in its composition ranges from 10 to 60 per cent, that of spruce and birch is 90 and 50 per cent, respectively.

Pinetum sphagnosum is widely distributed. The stands are uneven-aged, pure, sparsely closed, open. The site class is V , the timber volume amounts to 10 - 60 m^3 per ha. The composition is commonly dominated by pine, sometimes with spruce (up to 30 per cent) and birch (up to 20 per cent). Pine young growth under the canopy amounts to 3 000 - 10 000 stems per ha, not infrequently spruce is present.

Forest regeneration is characterized by the close relation to fires, rare and low seed production of pine, slow height growth of woody species. *Pinetum cladinosum*, *vaccinosum* and *myrtillosum* are the most successfully regenerating types following fires. Especially high amounts of young and seedling growth under the canopy occur at fire age from 15 to 40 years. In pine forests growing on moist and water-logged soils forest regeneration has low relation to fires; there is a high proportion of spruce and birch in the young growth composition.

On pine forest felling sites the proportion of the seedling and young growth of advance generations depends upon their safety during logging and is defined by plant surviving in the time of their adaptation to new ecological conditions. Younger seedling growth and young growth, which are successfully adapted to conditions of cutover areas and after 1 - 5 years increase in height growth, are the most viable. Forest fires contribute to succeeding regeneration of pine on pine forest cutover areas with drained soils. However, wind and water erosion may occur following heavy and repeated burns; unfavourable conditions for seed germination and young growth are being

created. Unsatisfactory pine regeneration also occurs on cutover areas having moist and wet soils with the developed moss cover. In *Pinetum cladinosum* and similar forest types successful pine regeneration occurs there, where the soil cover is disturbed and the ground litter is loosened. On the cutover areas from *Pinetum vaccinosum*, *myrtillosum* and similar forest types favourable conditions are created after removing the soil cover and decreasing the litter depth.

Seed sources play an important role in the cutover area seeding. Pine rapidly colonizes the sites in the vicinity of seed trees. Under the conditions of the Far North the cutover areas are considered to be provided with seed trees when their boundaries are moved away from seed sources (groups, bands, single seed trees) by no more than 50 - 60 m.

Climate deterioration toward the north and associated reduction of soil fertility, deterioration of the hydrothermal regime of soils affect stand productivity and their growth intensity.

Pine forest height increases markedly until 89 - 90 years of age after that no considerable changes occur. Depending on the forest type, age structure of the stand and its density, the most intensive height growth of pine occurs at the age interval of 15 - 30 years. Average heights of pine forests at age older than 100 years in the pretundra zone are by 20 - 40 per cent less than those of the north taiga pine forests. Differences in diameter growth are expressed to a lesser degree because of a lower closing of leaf canopy in the Far North. Quantitative maturity of the pretundra pine forests was found to come in the age class IV. Production forests (*Vaccinium*-type) reach it earlier than others (at age 65). Maturity on the middle-sized wood comes in 40 - 50 years and that on the large-sized one still 60 - 100 years later. To the time of technical maturity timber assortments, mainly of middle sizes can be logged in the stands of the site classes V and v^a (68 and 46 per cent, respectively). The proportion of large logs does not exceed 10 per cent even in the most productive stands.

Not the productive potential of forests but the value of their protective functions plays a decisive role in pine forest management in the pretundra zone, because timber exploitation of pine forests with their slow regeneration and growth causes inevitably reduction of protective, environment-building properties of the areas. Therefore a natural maturity age of pine forests is of great importance when managing them. According to available data it is expedient to take the following natural maturity ages of pine forests: *Pinetum cladinosum* and *sphagnosum*: 240, *Pinetum vaccinosum* and *polytricosum*: 220, *Pinetum myrtillosum*: 200 years.

Polar location of the area, severity of the climate conditions, important protective role of the forest cover require to take protective silviculture as a principal direction of forestry. Forest management in the pretundra zone should be based on the zonal-typology principle. The nature of forests and level of managing them require development and use of the zonal pretundra forestry system. The main tasks of forestry should be conservation, rational use, and improvement of protective and environment-building properties of the forest lands by meeting local demand for timber and other products. It is necessary to maintain and increase the area of pine forests, to improve their climate-protective, environment-building, recreational functions. Along with this pine forests should be used as deer pastures and hunts, as a source of receiving the required amount of timber and side products. Forest management activities should be generally directed to forest fire protection, forest regeneration, regulation of deer grazing and other uses. It can be only allowed here sanitation and group-selection cuttings aimed at rejuvenation and sanitation of stands losing protective properties; in the zones of wind erosion of sandy soils forest regeneration is also needed.

Forest fire protection is generally carried out by aerial methods; fire-preventive organization of the areas is needed as well as protection against excessive nonregulated anthropogenic influences (cuttings, damage etc.). The main objects of forest management activities are pine forests of *Myrtillus*- and *Vaccinium*-types. In *Pinetum cladinosum*, *polytricosum*

and *sphagnosum* forest management activities are restricted. Forest regeneration should be realized by both natural and artificial ways. Main attention is given to natural overgrowing areas. Forest plantations are established by both seeding and planting pine only on economically accessiable lands. When preparing soil one should seek to its minimum mineralization, mix the litter with the upper mineral horizon. The width of the mineralized strips in *Pinetum cladinosum* and *vaccinosum* is 20 - 30 cm, in *Pinetum myrtillosum* and *polytricosum* up to 0.4 - 0.5 m, size of plots ranges from 20 x 20 to 50 x 50 cm. By reforestation of *Pinetum cladinosum* cutover areas and postfire *Pinetum vaccinosum* cutover areas no soil preparation is needed.

Thinnings may be only performed on some sites in the closed young-growth stands with a considerable proportion of hardwoods (more than 50 per cent). The principal purpose of these treatments is increasing viability and stability, improving environment-building and recreational properties of the stands, optimizing the area structure. In the mixed young stands removals and early thinnings are performed first at birch age 10 - 15 years. The succeeding thinnings are performed in 15 and 20 years, repectively.

Sanitation cuttings are only permitted in the damaged stands by removing only dead standing and dying trees.

With a great area (more than 100 ha) of conditional evenaged *Pinetum cladinosum*, *vaccinosum* and *myrtillosum* strip thinnings are used. The width of cutting areas is no more than 100 m. In process of cutting single seed trees and seed tree groups are left at a distance 30 - 40 m between the trees and from the forest edges. A date of adjoining cutting areas is defined by time of tree canopy forming on them: on the sites with the undergrowth remained it amounts to 10 - 12 years and without undergrowth no less than 15 - 20 years. On the tracts with the area less than 100 ha and without undergrowth under the canopy group selection cuttings with the annual cutting area no more than 1 ha are recommended. The succeeding thinnings are only performed following tree canopy formation on the site previously thinned.

In the mixed pine forests having 2 or 3 pine generations two-stage cuttings are possible. In the first thinning (intensity 40 - 50 per cent by volume) pines of the first generation (older than 200 - 220 years) are removed, as well as trees of undesirable species and forms, the composition and the amount of undergrowth are regulated. In 30 - 50 years the second thinning is performed. Afforestation is provided with the young growth of the previous generations and the most young trees of pine in the composition of the initial stand. In the uneven-aged *Pinetum cladinosum*, *vaccinosum* and *myrtillosum* without pronounced generations the older trees (no younger than 160 - 180 years) are removed, as well as 80 - 90 per cent of hardwoods and spruce in the first thinning. Intensity of the thinning is no more than 40 - 45 per cent by volume. Succeeding thinnings are performed in 40 - 60 years. If required, soil preparation under the canopy is carried out prior to the seed year as a measure contributing to natural pine regeneration.

In *Pinetum sphagnosum* and *polytricosum* selection cuttings are performed. Along with pine a greater part of spruce and birch (60 - 70 per cent) is felled. Selection cuttings can reach 35 - 40 per cent by stem number, 20 - 30 per cent by volume, subsequently decreasing to 15 - 20 per cent.

Young growth maintaining is a necessary condition of the regeneration and sanitation cuttings. Therefore the cuttings would be most desirable in winter with steady snow cover. When performing cuttings in summer caterpillar machinery cannot be used.

Pine forests are winter pastures for deer. However, their grazing should be regulated considering the state and nature of forests, regeneration under their canopy, forage supply, degree of soil disturbance. In some cases the deer grazing on a part of the lands should not be allowed before, the soil cover fully regenerates, mineralized soil sites are overgrown, the stand state improves. Any anthropogenic influence on the pine forests located at the boundary with tundra and in the isolated sites among

bogs and tundras (cuttings, deer grazing, transport passage etc.) should be categorically excluded.

Thus, all that indicates the necessity of increasing conservation of the pretundra pine forests under these conditions, maintaining and expanding their areas. The forest management activities discussed ensure differentiated approach to the management of pine forests considering typological diversity, peculiarities and purpose of the forests. Only in such a way one can reach the rational use, permanent maintaining and improving their protective functions with the satisfaction of the local demand for timber and other usefulness of the pine forests.

FOREST RESEARCH IN AREAS CLOSE TO THE TIMBERLINE IN SWEDEN

Mats Hagner

ABSTRACT: The paper presents current research and running projects concerning; description of the standing forests, the quality of regeneration, injuries to young conifers, natural and artificial regeneration techniques, shelter trees, soil amelioration and scarification, climate, provenances, genetic improvement, seed supply, introduced species and multiple use. Lists of literature and addresses of scientists are added.

BACKGROUND

In Sweden we have two borders in the forests drawn along the mountains covered by tundra. Mountains without trees are called "fjäll" and we call the close-laying forests "fjällnära skog". The two borders (Fig. 1) are "skogsodlingsgränsen" and "gränsen för svårföryngrad skog".

"Skogsodlingsgränsen" was set by the governmental Domänverket in 1950. Above this border one should not harvest the forest at all, the reason being unsufficient scientific knowledge about regeneration. This border was abandoned by Domänverket in 1980 but in 1985 it was re-established by the Skogsstyrelsen and extended also to private land. Some special rules about forestry were introduced at the same time.

"Gränsen för svårföryngrad skog" means "The border over which there is difficulty in regenerating the forest". Above this the forest owners have to get a permit from the Governmental Board before they are allowed to harvest the forest.

After a public debate in 1984 concerning forestry close to the mountains, eight forestry scientists were asked to state the current knowledge. In a report the conditions for forest production and regeneration are stated (Odin 1984, Bäckström 1984, Nykvist 1984, Sjörs and Zackrisson 1984, Bergman 1984a, 1984b, Lindgren 1984) as well as the knowledge about the quality of the regenerations (Hagner 1984a). The report also contains recommendations for future work put forward by the above mentioned authors (Bäckström et al 1984). Documents published by Hagner during the debate are included in five appendixes (Hagner 1984b, 1984d).

In Bäckström et al. (1984) the following is recommended.




Figure 1. 1=Border "Skogsodlingsgränsen" 2=Border "Gränsen för svårföryngrad skog" After Nyström (1986). Meter över haver = Meters above sea

The size of logged areas should be decreased to below 40 hectares in order to obtain a mosaic with stands of varying ages.

In harsh areas with fine textured soil, where problems with regeneration can be expected, clear cutting should be avoided. The same applies to areas where seed supply of hardy Scots

Mats Hagner is a professor at the department of Forest Science, Umeå University, S-901 87 Umeå.

pine is lacking. In all cases where advanced growth is available, logging and regeneration operations should be adjusted with the aim to save and use the natural regrowth. Sheltering trees shall be left in all areas where summer-frosts are frequent. A careful analysis of the stand carried out before logging should form the base of a detailed plan for regeneration activities.

The most important measure for preservation of soil fertility is considered to be a well-growing forest. Soil scarification may temporarily lower the fertility if this is a prerequisite for good regeneration. As extensive soil treatments, such as ploughing, may decrease the long-term fertility, it must be restricted to moist areas where no alternative seems to be available.

Native spruce has greater ecological amplitude than pine and it should be used wherever it is considered feasible. *Pinus contorta* should not be used on high altitudes north of latitude 64 - 65. The reason is a lack of experimental results. Several other exotics have some potential but scientific tests have to precede large-scale use.

The density of young stands should be increased by the use of smaller spacing. The recommended minimum numbers of plants per hectare mentioned in the law must not be used as a recommendation. Wherever possible direct seeding should be used as a means to increase the density of the stands. Accordingly, at least 3 000 stems per hectare should be left after the first cleaning of sown stands and natural regenerations. The final cleaning could be done fairly late and it should be remembered that production of high quality timber requires a very high density in the young stands.

The young stands have to be monitored closely and the final inventory has to be done not earlier than ten years after planting.

Finally, the group of scientists recommends additional education of foresters employed with forestry in very harsh areas and it is of special importance that detailed records are kept concerning regeneration measures taken. This enables future generations of foresters to learn from failures and successes.

In addition to this Hagner (1984d), in a special report included in the same edition, stresses the following:

Open clear cuts offer an unnatural environment. In a burnt forest (the natural environment) the dead trees are left standing for one or two decades and they give substantial shelter from wind and radiation. Accordingly, the regeneration in harsh areas should be sheltered.

The advanced growth might be saved if sheltering trees are left. If mechanical scarification could be abandoned it would be possible to use the advanced growth to a greater extent. A method comprising a plastic shelter adapted to the plant in the nursery has resulted in good survival after planting in the humus. This method should be developed for practical use.

The genetical variation in climatic adaptation among trees within all progenies is so great that the survival in areas close to the tree line is bound to be low. Planting is too expensive to enable formation of a sufficient number of trees per hectare. Direct seeding encounters an untolerable seed volume. Accordingly, natural regeneration is the only method that gives an economical solution. However, the optimal solution might be a combination of planting and advanced growth, which could be realized by employing the method "planting without scarification".

Finally Hagner stresses that where planting is used, every single container should harbor several seedlings from at least two species; spruce and pine.

CURRENT RESEARCH

The following is a condensation of current research employed today by Swedish scientists. I want to stress that the list is a result from a questionnaire put forward to the largest scientific institutions. Quite certainly, many projects that are carried out have not been mentioned. Therefore, the list should not be considered as complete.

The list contains results that recently have been published, but in addition to that currently running unpublished projects are taken into

consideration. This is done also where funding for the moment is lacking.

The list of publications is completed by a list of addresses of scientists involved in research close to the timberline.

Description of the standing forests

Kullman (1981, 1983a, 1983b, 1986a, 1986b, 1987) has paid great attention to the dynamics of tree line species and their reproduction and he has clearly demonstrated the close correlation between climate and ability to regenerate. Zackrisson (Sjörs and Zackrisson 1984) and Linder P are also working with the structure and dynamics of the stands close to the timberline. Engelmark (1987) just presented his dissertation dealing with the fire-history of forests in the Muddus national park. Engelmark will continue the Reivo-project, "The ecology of a burnt forest", started in 1973. In this eleven scientists have been engaged to demonstrate different aspects of the ecological processes after the fire in 1966. A new "wild fire" is planned to be started after scientific studies in the Reivo national reserve. In the project the following scientists are still active; Hagner M, Westman L, Rudin D, Essen P A, Karlman M, Wiklander G. Essen P A carries out a project "Fragmentation of the biotope" intended to illustrate in which way islands of uncut forest left on the clear felled areas will enable endangered species to survive. Zackrisson O is developing a special site classification for forests close to the mountains.

The quality of regenerations

The debate on forestry policy in areas close to the timberline made it clear that the knowledge about the quality of regeneration was very scarce (Hagner 1984a, 1984b, 1984d). Since then some limited investigations have been published. Gabrielsson and Tibblin (1985) investigated in great detail a few clearcuts planted with spruce. They described the position of every tree. Nyström (1986) showed that the young stands of planted pine are fairly open and that the natural regeneration from spruce and birch will constitute a major portion of the mature trees. Olofsson G is carrying out a vast inventory of randomly chosen areas that were clear cut twenty years ago. Elfving B is heading a large project, "potential production of new stands", with around 1 500 plots (100 m^2) in plantations established on a practical scale (Fig. 2). The co-ordinates of every tree is known. Zackrisson O is studying clearcuts close to the mountains to find "an elevational limit for artificial regeneration".




Figure 2. Fixed plots for monitoring the quality of young stands on high altitudes After Elfving B.

Injuries to young conifers

Martinsson et al (1983), Bergman and Odin (1984) and Karlman (1986) describe the common diseases and mechanical injuries to young trees. Karlman is continuing inventories on regenerations. In a co-operate project with Canada, *Pinus contorta* as well as *Pinus sylvestris* is compared on test sites in both countries.

Näslund (1986) used a large number of fixed plots for simulations of the long term effects of damage and mortality in young stands. Linder P and Zackrisson O are studying breakages by snow and wind in high-elevation forests. Hagner (1980b) showed hidden frost injuries in the cambium of several conifers growing in Sweden and Canada. Damage caused by reindeer was investigated by Ekberg (1987).

Natural regeneration technique

Bergman (1984) describes the presumptions of natural regeneration. Hagner (1987) estimated the potential production of advanced growth on several areas far north of the polar circle and found it most valuable. Falk J is studying in which way advanced growth can be used to form stands with two or three layers. Jeansson E carries out research on natural regeneration in harsh areas (Jeansson 1985). Several other scientists have shown interest in extensive studies on advanced growth in areas with very harsh climate. So far no funding has been raised.

Lindman (1983) showed the potential production in a few stands in which selective cutting was carried out. Jonsson B and Jacobsson J continuously follow the growth and long term production of old stands in which thinning has been done. Hagner (1980c) compared the natural regeneration in a burnt forest with the artificial regeneration on a nearby clear cut. Hagner (1987) showed that planting can be performed without scarification and he considers a combination of advanced growth and planting to be the optimal method for regeneration.

Artificial regeneration technique

Bäckström (1984) discussed areal production at different number of stems per hectare and found the present density of the regeneration in harsh areas to be low. Gemmel P and Örlander G are investigating the possibility of increasing survival by simultaneously having two species, pine and spruce, in the pot when planting containerized seedlings. Lundmark T has demonstrated that small shelters of cardboard placed on the southern side of pine seedlings had a beneficial effect on survival. Hagner and Hansson (1987) have shown that containerized seedlings can survive well when planted directly in the humus layer, if they are enclosed in a simple cylindrical plastic shelter. De Jong (1986) is studying the areal distribution of factors affecting survival and growth. He will try to use the information for design of site adapted regeneration methods.

As there is a shortage of seed for the harsh regions direct seeding in which great amounts of seed is used cannot be performed. However, much seed can be saved if seeds are covered by plastic shelters (Hagner 1981b, 1984c, Hagner and de Jong 1981).

Sheltering trees

It has been shown that the environment close to shelters has a very positive impact upon survival of pine (Hagner 1984d). Fries C is studying twenty-year-old plots with sheltering trees under which advanced growth is supplemented by planting. Hagner M is monitoring some plots where seeding and planting was done under trees that were killed at the time of planting.

Soil amelioration scarification

Nykvist (1984) gave a good general description of soil and hydrology of sites close to the mountains. Huss-Danell K and Zackrisson O are studying the ability of lupins and alder to ameliorate the site by nitrogen fixation.

Mechanical scarification and its influence upon survival and growth is studied in several projects; Bäckström P O, Juntti K, Lundmark J E, Lundberg S, Örlander G, Hagner M (1987) showed that enhanced growth occurring after ploughing may delay the inwintering process in pine. Holm and Kullman (1983) and Hagner (1985b) showed the relationship between topography, survival, growth and weather injury.

Climate

Odin (1984) describes the climatic conditions of trees growing close to the mountains and he is still working with studies of the climate in these areas.

Provenances

Lindgren (1984) describes the climatic adaptation of forest trees and its influence upon survival and growth. Provenance research on Norway spruce has recently been published (Rosvall 1982a). Prescher (1986) and Ståhl and Andersson (1985) have given the data of survival, growth and volume production at the age of 30 years for Scots pine in a large series of provenance tests. Yazdani and Nilsson (1986) showed the variation of monoterpene among natural populations of pine.

Pinus contorta, now used on a practical scale in Sweden, has been tested in many provenance trials (Rosvall and Strömberg 1980, Rosvall et al. 1984, Lindgren 1985) and recommendations have been published.

Genetic improvement

A large number of scientists are working to enhance the hardiness of the regeneration material for the most northern areas of Sweden. Great efforts are directed towards early tests and a freezing technique has been proven to be suitable (Ericsson 1983, Ericsson and Andersson 1983, Nilsson and Eriksson 1986, Rosvall 1982b). Various breeding plans are discussed (Andersson 1985a, Gullberg 1987, Nilsson 1986, Lindgren 1985, Presher 1985, Ståhl and Persson 1985). Rosvall (1985a) suggests hardiness could be increased by proper maintenance of existing seed orchards. Ståhl et al (1985) suggest that special measures should be taken to increase the timber quality of the progeny. Nilsson J E has paid extra attention to hardiness features of orchard clones (Nilsson 1985, Nilsson and Åman 1985, 1986). As a breeding population he has selected 200 pine clones very close to the tundra. Andersson (1985b, 1986), Ericsson (1986) and Ericsson and Hadders (1980) are intensively following the progeny from seed orchards with respect to their hardiness. Freezing tests are often used in this work. Lindgren (1987) has described the potential production of *Pinus contorta* and its relation to Scots pine on various sites.

Seed supply

As there is a pronounced shortage of seed for harsh areas, great attention has been paid to availability, collection practises and efficient use of such seed. Prognoses founded on climatical measurements and early seed tests are published in late fall by the Institet Skogsförbättring in Umeå and the Skogshögskolan in Umeå. Cone collection is mostly organized by the Skogsvårdsstyrelsen.

The variation of seed maturation within the tree has been studied by Bergman (1984) who showed a pronounced difference between the south and north sides of the tree crown. Hagner (1980a, 1982) found great differences between individual trees in their generative adaptation to the climate (*Pinus sylvestris* and *Pinus contorta*). Hagner M has established a seed stand by selection of generative plus trees in a very northern area. This is a co-operative project with Mo and Domsjö AB.

For efficient use of live seeds in the nurseries great effort has been paid to sorting live from dead seeds (Simak et al. 1985, Lestander 1986, Bergsten 1987) and to the use of germinated seeds (Hagner 1981a, 1985a). Methods for practical use are functioning well for pine but less well for spruce. Andersson B and Lindström A are trying to develop a suitable system with small containers, aimed to be transplanted after assorment.

Introduced species

It is well known that exotics may be hardier than native pine and spruce in high-elevation areas. One such example is *Abies lasiocarpa*

which is able to prosper in the birch zone at latitude 64, where only scattered spruce survive. Other species that are paid great attention is *Larix sibirica, Picea mariana* and *Abies sibirica*. Martinsson O and Rosvall O are heading projects encountering measurements in old test plots and establishment of new trials (Martinsson and Vinsa 1986, Rosvall 1985b).

Multiple use of the forests close to the mountains

Economic evaluation of competing forms of use of the forests close to the mountains; lumber producers, reindeer farmers, tourism, recreation etc. is carried out by Hultkrantz L and Mattsson L. The project aims to recommend rules and jurisdiction that would bring about an "incentive compatibility".

LITERATURE

Andersson, B. 1985a. Anlägging av tallplantager för kärva klimatlägen (Establishment of seed orchards for areas with harsh climate). In Nilsson ed.: Skogsodlingsmaterial för hårda nordliga lägen. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 4.

— 1985b. Frystest av norrländska tallplantagekloner (Freezing tests of northern Scots Pine seedlings from seed orchards). In Nilsson ed.: Skogsodlingsmaterial för hårda nordliga lägen. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 4.

— 1986. Freezing test of Scots Pine (Pinus sylvestris L) seed orchard crops. In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.

Bergman, F. 1976. Kott och fröegenskaper i skilda krondelar hos tall Pinus sylvestris L i norra Sverige. Skogshögskolan, Föryngring, Rapport 68.

— 1984. Naturlig förnyelse. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

— & Odin H. 1984. Skador. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

— , Bäckström, P.O., Hagner, M., Lindgren, D., Nykvist, N., Odin, H., Sjörs, H. & Zackrisson, O. 1984. Synpunkter på det framtida föryngringsarbetet i fjällnära områden. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

Bergsten, U. 1987. Incubation of Pinus sylvestris L and Picea abies L (Karst) seeds at controlled moisture content as an invigoration step in the IDS method. Sveriges Lantbruksuniversitet, Skogsskötsel, Dissertation.

Bäckström, P.O. 1984. Produktionsnivå vid olika stamantal. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

de Jong, A. 1986. Ståndortsanpassad skogsodling - hur. Skogen 11: 36-38.

Ekberg, L. 1987. Renens påverkan på tallföryngringen vid vinterbete. Resultat av en fältundersökning och en litteraturstudie. Sveriges Lantbruksuniversitet, Skogsskötsel, Examensarbete, 3.

Engelmark ,O. 1987. Forest fire history and successional patterns in Muddus National Park, northern Sweden. Sveriges Lantbruksuniversitet, Ståndortslära, Dissertation.

Ericsson, T. 1983. Härdighetstest av norrländska tallfröplantage-kloner (Hardiness tests of North Swedish pine seed orchard clones), Institutet för skogsförbättring, Årsbok.

— 1986. Pine seed orchard tests in northern Sweden. Preliminary results from an assessment in summer 1984 of a series of field trials planted 1973-75. In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.

— & Andersson, B. 1983. Scots pine breeding for north Sweden by early tests. Proceedings Plant Adaptation Workshop, University of Tromsö, Norway.

— & Hadders, G. 1980. Odlingstest av tallplantagefrö i Norrland. Institutet skogsförbättring, Information 1979/80, 7.

Gabrielsson, L. & Tibblin, G. 1985. Fjällnära skogars struktur och produktion. Sveriges Lantbruksuniversitet, Skogsskötsel, Examenarbete 9.

Gullberg, U. 1987. Studies on the utilization of adapted forms in the breeding of Pinus sylvestris. Sveriges Lantbruksuniversitet, Skogsgenetik, Rapport 38.

Hagner, M. 1980a. Geographical variation in seed quality of Lodgepole pine (Pinus contorta Dougl) between and within stands. Proceedings IUFRO, Research note 30, Skogsgenetik, Sveriges Lantbruksuniversitet, Garpenberg.

— 1980b. Frost-rings in provenances of Pinus sylvestris grown in Sweden and in autochthonous Pinus contorta and Picea glauca growing in Canada. Pro-

cedings IUFRO, Research note 30, Skogsgenetik, Sveriges Lantbruksuniversitet, Garpenberg.
— 1980c. Den naturliga föryngringen i den brända skogen jämförd med skogsmannens kultur på angränsande hygge. Reivorapport, Skoglig Produktionslära, Umeå universitet.
— 1981a. Sådd av grodda frön effektiviserar plantframställningen. Rapport 121. Skoglig Produktionslära, Umeå universitet.
— 1981b. Direct seeding. In "Forest Regeneration at High Latitudes: Experience from northern Sweden". Report 132. Pacific Northwest Forest and Range Experimental Station. United States Department of Agriculture, pp 33-37.
— 1982. Variation between trees in stands of Pinus sylvestris L. with respect to seed maturation, genetic load and generative adaptation to the climate. Rapport 125, Skoglig Produktionslära, Umeå universitet.
— 1984a. Kunskap om återväxterna i fjällnära skog. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.
— 1984b. Kan vi skogsodla i fjällnära skog. Umeå universitet, Skoglig Produktionslära, Rapport 132.
— 1984c. Överlevnad och tillväxt under nio år hos konsådd tall (Pinus sylvestris och Pinus contorta). Sveriges Skogsvårdsförbunds Tidskrift 5.
— 1984d. Synpunkter på Domänverkets skogsbruk i fjällnära områden. Umeå universitet, Skoglig produktionslära, Rapport 135.
— 1985a. Förgrodda frön. Sveriges Skogsvårdsförbunds Tidskrift 1.
— 1985b. The influence of microenvironment upon survival and growth in Pinus sylvestris. Proceedings IUFRO S1.05.12. University of Alaska, Agricultural and Forest Experiment Station, Fairbanks, Alaska, USA.
— 1985c. Skogsbruk i fjällskog - anpassning eller totalstopp Skogen 2; 68-69.
— 1987. Sambandet mellan tillväxtbefrämjande markbehandling och tallplantors (Pinus sylvestris L) invintringstid. Umeå universitet, Skoglig produktionslära, manuskript.
— & De Jong, A. 1981. Sådd i humustäcke 1980. Rapport 120, Skoglig Produktionslära, Umeå universitet.
— & Hansson, B. 1987. Försök med ett mekaniskt skydd för skogsträdsplantor avsett för plantering utan markberedning. Umeå universitet, Skoglig produktionslära, Slutrapport till Skogsstyrelsens Förskningsnämnd.
Hagner, O. 1987. Naturlig föryngring vid skogsodlingsgränsen i trakten av Gällivare - En undersökning av tillstånd och produktion (Latitud 67, 2-67, 8, 300-450 meter över havet). Sveriges Lantbruksuniversitet, Skogsskötsel, Examensarbete 2.
Holm, S.O. & Kullman, L. 1983. Mikrotopografi, överlevnad, tillväxt och väderleksskador i höglägesplanteringar av tall i norra Sverige (Microtopography, survival, growth and weather injury of planted Scots pine in high-lying parts of northern Sweden. Sveriges Skogsvårdsförbunds Tidskrift 6: 37-56.
Jeansson, E. 1985. Naturlig föryngring (Natural regeneration). Sveriges Lantbruksuniversitet, Skogsfakta 5.
Karlman, M. 1986. Damage to Pinus contorta in northern Sweden with special emphasis on pathogens. Studia Forestalia Suecica 176.
Kullman, L. 1981. Recent tree-limit dynamics of Scots pine (Pinus sylvestris L) in the southern Swedish Sandes 1915-1975. Acta Phytogeography Suecica 65: 1-121.
— 1983a. Past and present tree-lines of different species in the Handölan valley, Central Sweden, Treeline ecology. Proceedings, Northern Quebec Treeline Conference. Nordicana, 47: 25-45.
— 1983b. Short-term population trends of isolated treelimit stands of Pinus sylvestris L in Central Sweden. Arctic Alpine Research 15: 369-382.
— 1986a. Late Holocene reproductional patterns of Pinus sylvestris and Picea abies at the forest-limit in central Sweden. Canadian Journal of Botany. (in press)
— 1986b. Recent tree-limit history of Picea abies in the southern Scandes (Sweden). Canadian Journal of Botany. (in press)
— 1987. Long-term dynamics of high-altitude populations of Pinus sylvestris in the Swedish Scandes. Journal of Biogeography 14: 1-8.
Lestander, T. 1986. Application of new methods for seed treatment in order to exploit the most suitable Scots pine provenances. In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.
— & Lindgren, D. 1986. Förplantagernas genetiska effektivitet (The genetic efficiency of seed orchards). In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.
Lindgren, D. 1984. Skogsträden, deras proveniens och möjligheter till härdigare skogsodlingsmaterial. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.
— 1985. Förslag till förädlingsprogram för härdig tall (A suggested breeding program of Scots pine for harsh northern sites. In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.

Lindgren, K. 1985. Provenienser av contortatall för norra Sverige. Skogsfakta 23.

— 1987. Contortatallens produktionsföruttsättningar på olika ståndort. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Arbetsrapport 25.

Lindman, J. 1983. Fjällskogsblädning. Tillväxtstudier i fyra bestånd. Sveriges Lantbruksuniversitet, Skogsskötsel, Examensarbete 5.

Martinsson, O. & Vinsa, H. 1986. Främmande trädslag i svenskt skogsbruk Sveriges Lantbruksuniversitet. Skogsskötsel, Rapport 3.

— , Karlman, M. & Lundh, J.E. 1983. Avgång och skador i odlingsförsök av tall och contortatall 4-9 år efter plantering (Mortality and damage in semi-practical trials of Scots pine and Lodgepole pine 4-9 years after planting). Sveriges Lantbruksuniversitet, Skogsskötsel, Rapport 10.

Nilsson, J.E. 1985. Tallavkommors härdighet i frys- och fältförsök (Hardiness of Scots pine progenies in freezing tests and field experiments). In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.

— 1986. Härdigare tall för norra Sverige. Skogsfakta 32.

— & Eriksson, G. 1986. Freeze testing and field mortality of Pinus sylvestris L in northern Sweden. Scandinavian Journal of Forest Research 1: 205-217.

— & Åman, M.L. 1985. Härdiga arvsanlad vid trädgränsen längst i norr? (Hardy genes at the timberline in the far north) In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.

— & Åman, M.L. 1986. The phenological rhytm of Pinus sylvestris clones and its relationship with damage of one year old offsprings after freeze testing. In Lindgren ed. Provenances and Forest Tree Breeding for high altitudes. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 6.

Nykvist, N. 1984. Berggrund, markförhållanden och hydrologi. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

Nyström, K. 1986. Tillstånd och produktion i Hugins ungskogsytor i höjdlägen. Sveriges Lantbruksuniversitet, Skogsskötsel, Doktorandarbete.

Näslund, B.Å. 1986. Simulering av skador och avgång i ungskog och deras betydelse för beståndsutvecklingen (Simulation of damage and mortality in young stands and associated stand development effects). Sveriges Lantbruksuniversitet, Skogsskötsel, Rapport 18.

Odin. H. 1984. Klimat. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

Olofsson, G. 1985. Forest regeneration at high altitudes in northern Sweden. Proceedings IUFRO S.105.12.1985 University of Alaska, Fairbanks.

Prescher, F. 1985. Framtida förädlingsstrategi för tall - ett bidrag. Sveriges Lantbruksuniversitet, Skogsproduktion, Slutredogörelse till Skogs- och Jordbrukets Forskningsråd.

— 1986. Transfer effects on volume produktion of Pinus sylvestris L. a responce surface model. Scandinavian Journal of Forest Research 1: 285-292.

Rosvall, O. 1982a. Förflyttningseffekter i norrländska granproveniensförsök. Institutet skogsförbättring, information 1982/83, 4.

— 1982b. Tallförädling med hjälp av frystester. Institutet skogsförbättring, information 1982/83, 6.

— 1985a. Skötsel av fröplantager för att öka avkommans härdighet (Seed orchard management to improve hardiness of the progeny). In Nilsson ed.: Skogsodlingsmaterial för hårda nordliga lägen. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi, Rapport 4.

— 1985b. Val av svartgranprovenienser i norra Sverige. Institutet skogsförbättring, Skogsträdsförädlingsinformation 1985/86, 2.

— & Strömberg, S. 1980. Proveniensförsök med contortatall i norra Sverige. Institutet skogsförbättring, Information 1979/80, 6.

— , Strömberg, S. & Andersson, B. 1984. Skogsförbättrings proveniensförsök med contortatall i norra Sverige (Lodgepole Pine Provenance Trials in Northern Sweden). Institutet skogsförbättring, Årsbok.

Simak, M., Bergsten, U. & Lönneborg, A.M. 1985. Bortsortering av ej produktivt frö ur ett parti. Sveriges Skogsvårdsförbunds Tidskrift 1. 45-56.

Sjörs, H. & Zackrisson, O. 1984. Dynamik, struktur och funktion hos de fjällnära skogarna. I Bäckström ed.: Skogsföryngring i fjällnära skogar. Sveriges Lantbruksuniversitet, Skogsvetenskapliga fakulteten, Forskarrapport.

Ståhl, E.G. & Andersson, S. 1985. Avgång och skadefrekvens i 30-åriga tallproveniensförsök i hårda klimatlägen. Mortality and frequency of damage in 30 years old Scots pine trials in severe climatic conditions. In Nilsson ed.: Skogsodlingsmaterial för hårda nordliga lägen. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi. Rapport 4.

— & Persson, B. 1985. Användning av lantraser som förädlingspopulation vi skogsträdsförädling i kärva klimatlägen (Use of land races as breeding population in forest tree breeding for harsh climatic conditions). In Nilsson ed.: Skogsodlingsmaterial för hårda nordliga lägen. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi. Rapport 4.

— , Persson, A. & Persson, B. 1985. Timber quality in northern latitudes implications for forest tree improvement. In Nilsson ed.: Skogsodlingsmaterial för hårda nordliga lägen. Sveriges Lantbruksuniversitet, Genetik och växtfysiologi. Rapport 4.

Yazdani, R. & Nilsson, J.E. 1986. Cortical monoterpene variation in natural populations of Pinus sylvestris in Sweden. Scandinavian Journal of Forest Research 1: 85-93.

ADDRESSES

Below are listed addresses of the scientists mentioned in the text and presently working on projects concerning forestry in the areas close to the swedish Scandes.

Abbreviations

Sveriges Lantbruksuniversitet Umeå=SLU U
-"- Garpenberg =SLU G
-"- Uppsala =SLU UP
Umeå universitet Umeå =Um Un
Institutet Skogsförbättring Umeå = ISF

Addresses:

Andersson Bengt ISF, Andersson Berth, Mo och Domsjö AB, Örnsköldsvik, Bergsten Urban SLU U, Bäckström Per-Ove SLU U, De Jong Adriaan Um Un, Elfving Björn SLU U, Engelmark Ola SLU U, Ericsson Tore ISF, Essen Per Anders Um Un, Falk Jan SLU U, Gemmel Pelle SLU U, Hagner Mats Um Un, Hansson Björn Um Un, Holm Stig Olof Um Un, Hultkrantz Lars SLU U, Jacobsson Jonas SLU U, Jeansson Evert SLU U, Jonsson Bengt SLU U, Karlman Margareta SLU U, Kullman Leif SLU U, Lestander Torbjörn ISF, Linder Per SLU U, Lindgren Dag SLU U, Lindgren Katarina SLU U, Lindman Johan, Skogsarbeten, Spånga, Lindström Anders SLU G, Lundberg Stig, Domänverket, Luleå, Lundmark Jan Erik SLU UP, Lundmark Tomas SLU U, Martinsson Owe SLU U, Mattsson Leif SLU U, Nilsson Jan Erik SLU U, Nykvist Nils SLU U, Nyström Kenneth SLU U, Näslund Bert-Åke SLU U, Odin Hans SLU U, Olofsson Gunnar, Skogsvårdsstyrelsen, Östersund, Persson Bengt SLU G, Rosvall Ola, ISF, Rudin Dag SLU U, Strömberg Sven ISF, Ståhl Erik SLU G, Zackrisson Olle SLU U, Westman Lars UM Un, Wiklander Gunnar SLU UP, Yazdani Rheza SLU U, Örlander Göran SLU U.

RESTRICTIONS ON FOREST MANAGEMENT CLOSE TO THE TIMBERLINE IN NORTH AMERICA

J. Peter Hall

ABSTRACT: Forest management in the boreal forest is restricted by:
- the idea that forest management is unnecessary **(conceptual),**
- the failure of the landowner to assign responsibility for forest management **(political)**
- the nature of the harvesting and utilization of the forest resource **(economical),**
- the lack of knowledge needed to apply management on all forest sites **(technical)**

These restrictions are being addressed at a rapid pace in the 1980's. These trends are encouraging and suggest that in the near future intensive forest management will be the rule in boreal forests in North America — not the exception.

Forest management includes a wide spectrum of managerial objectives employed to preserve and protect the natural productive capacity of forest land, to restock recently cut sites and to protect the growing stock. Elements of forest management include improvement of site, trees and stands, site preparation, regeneration, stand conversion and protection against damaging insects and diseases (Todd 1982).

As foresters, we assume that there will be increased and more intensive harvesting of the forests in the future. As forestry shifts in emphasis from the mining of natural stands to the harvesting from managed crops a number of other factors change. The change to higher levels of management means that policy makers require different types of information on which to base decisions. High levels of silvicultural investment means that the quantity and quality of research results must also be high (Draper 1982). Research results applicable to current forestry practices may not be applicable to management of second generation forests.

The timberline, in the strict sense, is the climate-controlled ecotone between the dense forest and the open treeless barren (Arno and Hammerly 1984). In North America the timberline ranges from 68°N in Alaska southeastwards to 60°N in Manitoba to 47°N in Newfoundland. There is an altitudinal limit, as well, ranging from 1 500 m ASL in north-central British Columbia to nearly sea level in Newfoundland. Forest activities are located in forests south of the ecotone area — the boreal forest. This forest type dominates the northern part of the continent and is part of the circumpolar boreal forest (Larsen 1980, Arno and Hammerly 1984).

The economy in these areas of northern forests is dominated by forestry and forest products. Overall in Canada forestry contributes C$14 billion net to the balance of trade — more than other natural resources including mining, petroleum products and fish and agricultural products (Anon. 1986). Employment is provided for 270 000 people directly and for 750 000 indirectly. Large areas of forest are harvested, an estimated 800 000 ha in Canada, the majority of it in the boreal forest. Nearly all of this area is clear-cut and less than half of the area regenerates naturally to standards which are considered adequate. Ownership of this forest land is vested in public authorities; federal or provincial governments (Anon 1986). Forest management is practised in much of the boreal forest and at much more intensive levels than the "clear-cut and get out" philossophy which is familiar from the past. Large areas remain unstocked, untreated or treated unsuccessfully and there is a backlog of unregenerated areas from past cutting.

J. Peter Hall is a Forest Renewal Advisor at Canadian Forestry Service, Agriculture Canada, 351 St. Joseph Boulevard, Place Vincent Massey, Hull, Quebec KIA IG5 Canada

Forest management is practised in those parts of the boreal forest which are biologically capable of producing a merchantable crop of timber which currently is about 90 m^3/ha. Merchantability levels affect management options in that only the most productive sites are treated or managed. This may be to the long-term detriment of the forest if marginal sites are harvested, left untreated and do not regenerate to productive forest.

This paper discusses restrictions on the management of these productive areas of the boreal forest.

DESCRIPTION OF THE FOREST

In order to describe and discuss restrictions on management it is necessary to describe the nature of this forest. Many of the restrictions arise from the nature of the forest; location, climate, geology, species composition, effects of insect and disease damage and of succession following disturbance.

The forest occurs in a wide belt from Alaska in north-western North America (68°N, 162°W) to Newfoundland In the Southeast (47°N, 55°W). It ranges in width from 7° to 10° in latitude or 400 to 800 km (Rowe 1972, Larsen 1980).

The boreal forest is characterized by a cold climate with short summers and long cold winters. Summer mean monthly temperatures generally range from 6° to 15° C. Large continental air masses originating in the Arctic dominate the climate. There is a wide range in annual precipitation from 230 to 1 500 mm (Rowe 1972, Larsen 1980).

Soils in the boreal forest are mostly derived from granites, forming coarse grained rock and sand. Where precipitation is abundant water leaches out soluble sodium, potassium, calcium, iron and aluminium causing varying degrees of podzolization (Larsen 1980). Soils developed on clays or calcareous sites form brunisols and where drainage is poor gleying occurs. Organic matter accumulates on these cold, wet soils and slows nutrient cycling which in turn restricts growth rates. Nutrients are tied up in the organic matter; disturbance of which enhances the nutrient cycling process. Boreal forest soils are usually shallow and acidic (pH of 3.5 - 4.0 is common). Where the rate of humus accumulation exceeds decomposition peat bogs are formed which may range up to several metres in depth. Here it is difficult for trees to grow at all.

Restrictions on forest management in the boreal forests arise from the biological nature of the forest. Some restrictions are fixed; climate, elevation, aspect and to some extent soils (Vyse 1973). Others which are controllable by the forest manager include seedbed conditions, seed supply, insects and diseases, animals and vegetation.

The boreal forest is characterized by a limited number of species with wide geographical ranges and high levels of adaptability to various site conditions. The more common species are black spruce *Picea mariana* (Mill.) B.S.P., white spruce *P. glauca* (Moench) Voss, balsam fir *Abies balsamea* (L.) Mill, white birch (*Betula papyrifera* Marsh.) and trembling aspen (*Populus tremuloides* Michx.)

Other species predominate in parts of the boreal forest:

Lodgepole pine (*Pinus contorta* Dougl.) in the Northwest.

Jack pine (*Pinus banksiana* Lamb.) from Alberta west to Quebec.

White pine (*P. strobus* L.), **Red pine** (*P. resinosa* Ait.) and **Yellow birch** (*B. lutea* Michx.) along the southern limits of the boreal forest.

Balsam poplar (*P. balsamifera* L.) more common in the Northwest Alaska, Yukon) and declining in abundance towards the Southeast until it becomes a rare species in Newfoundland.

Big tooth aspen (*P. grandidentata* Michx). which is most common in the central boreal forest in Ontario and Quebec.

These species occur singly or in association with others forming distinct cover types (Rowe 1972). The cover types vary continuously throughout the forest (Larsen 1980). For example in Alaska, cold sites both upland and lowland tend to be dominated by black spruce

whereas on the more mesic sites, white spruce dominates in association with aspen and white birch. These associations vary with time as the forests respond to cutting, insect attack and fire (Viereck and Little 1972).

Successional trends are often not completely understood in the boreal forest especially where cutting has been undertaken on a large scale or where natural succession has been influenced by forest management. For instance cutting in mixed spruce-fir forests has resulted in large areas of second growth balsam fir which is damaged by the spruce budworm (*Choristoneura fumiferana* Clem.). Forest management techniques have controlled wildfires to the extent that black spruce, which depends upon natural wildfire for regeneration, is becoming less and less common in the boreal forest. In areas where forest management and harvesting are minimal such as the Yukon successional trends are better understood (Oswald and Brown 1986). When spruce or Jack pine are burnt, they generally regenerate to black spruce or Jack pine (Vincent 1965). In the continued absence of fire these stands become decadent and opengrown until they are destroyed by windthrow or fire (Larsen 1980). Black spruce can also come in as an understory in Jack pine stands and eventually dominate the stand. Before cutting became widespread in the boreal forest, fire was the major successional factor affecting all sites. This resulted in the establishment of pioneer species such as black spruce, Jack pine, white birch and trembling aspen. Balsam fir comes in later in the succession but does not maintain itself after fire because both the advance growth and seed source are destroyed.

The spruce budworm is the best documented insect affecting the boreal forests (Hardy 1985). The budworm has caused widespread damage in spruce-fir forests for at least 300 years and attacks have increased in frequency and severity during this century. Budworm maintains the spruce component of the spruce-fir forest as both insect and host have evolved together. The budworm now causes a loss of 45×10^6 m^3 of wood annually. Outbreaks are believed to begin on white spruce in mixed wood stands and then spread to balsam fir stands. The attacks cover extensive areas; in 1981, 22.9×10^6 ha had 'significant volumes of dead and dying timber' (Kettela 1983).

Large areas of the forests are harvested annually, but less than half regenerates adequately. The most common reforestation treatment is planting, (63.8 %) of treated sites, followed by direct seeding with 22.2 %. Scarification is the most common site treatment (66.4 %) followed by prescribed burning (14.8 %). Most planting stock is container-grown (since 1980, 73.7 %) and the proportion of container over bareroot is increasing (Kuhnke and Brace 1986).

For boreal species, generally, the response to seeding or planting is good; they are adapted to a wide variety of sites and seedbed types.

RESTRICTIONS ON FOREST MANAGEMENT

A review of the literature on forest management describes as many restrictions as there are forest types or forest management systems. In this paper they are arbitarily combined into four groups; conceptual, political, economical and technical.

1. Conceptual

Forest management is restricted in an overall sense by the concept that all is well and therefore nothing needs to be done. This is the most significant restriction of all and has widespread influence (Hearnden 1975). It acts as a drag on all forest management policies, plans and operations.

Overall in the boreal forest there is enough wood to meet current and projected demands and in many areas cutting does not even reach the levels of the annual allowable cut (AAC). There are, however, local wood shortages and there is a vague realization that all is not well in the forestry sector. Application of good forest management principles now cannot avoid current shortages but they can affect on medium-

term shortages and can prevent long-term shortages. The ability to produce forest products is based on the area of productive land available, the volume, age and condition of the current growing stock, the depletion rate and the intensity of forest management (Honer and Bickerstaff 1985). Unfortunately logging and silviculture are often seen as separate entities with the sole objective of getting wood as cheaply as possible (Hearnden 1975). Professional foresters too are accused of being silent in pressing for better forest management (Hearnden 1975).

There is also a historically low level of public and political awareness of forestry matters. It has been bluntly stated more than once that the main obstacle to forest management is socio-political, that reforestation methods are well known and only time and effort are lacking (Ternent 1984, Hearnden 1975). The low level of awareness also has its consequence a low level of public support. In 1986 the Canadian Council of Forestry Ministers[1] was formed to enhance public support for forestry and forest management. This restriction, the most significant of all, call be overcome by a program of public information and public education.

2. Political

Forest management in the boreal forest is restricted by the reluctance or failure of the landowner to assign responsibility for the maintenance of forest productivity. Forest land is owned by the state (public lands in the U.S., Crown land in Canada) and the state has allowed private individuals to harvest the wood from the land upon payment of fees. These fees (commonly called stumpage) have not been sufficient to cover reforestation costs and are usually part of the provincial or state revenue rather than being directed to forest management. Therefore there is no incentive for the land-owner to practise sound forest management. Ownership of forest lands is overwhelmingly in the public domain, in Canada 92.3 % of forest land is owned by Provincial (80.8 %) or by the Federal (11.5 %) government (Anon. 1986). In the boreal forests of nearby Alaska two thirds of the productive forest land in state-owned.[2]

There has been little awareness in the past of the need for assigning responsibility, however, this has changed as the possibility of wood shortages has shown the need for management.

In the Province of Alberta agreements have been developed between the landowner and the forestry companies which allows cutting and removal of timber and provides for building and maintaining access roads, reforestation and other forest improvements. The objectives of the agreements are to provide for management on a perpetual sustained yield basis (Anon. 1981).

These policies reflect a newly-developed awareness of the need for effective forest management.

The national government as a minority landowner does not apply forest management policies on a large scale; its role is confined largely to research. The Canada Forestry Act (1949) provides for the shared cost for fire protection, reforestation, inventory and research (Bickerstaff and Hostikka 1977). The federal government maintains six regional research centres and two national institutes to direct and co-ordinate forest research in Canada.

Land alienation also restricts forest management. As the population increases and more leisure time is available and forests are more accessible there is an increased demand on forest land. Land is taken out forest production for recreation and wilderness areas, hydroelectric dams, rights of way, summer cabins and for parks and wildlife habitat. Forestry has as good

[1]This group consists of the eleven Canadian Ministers responsible for forestry matters.

[2]T. Gasbarro - Pers. Comm.

a claim on land as these other demands and too often this claim is not recognized. Public awareness may be the means of overcoming these restrictions of land alienation and the failure to accept responsibility for forest management.

3. Economical

There is a restriction imposed on forest management by the nature of harvesting and utilization in the boreal forests. There is a quantitative and qualitative aspect to this problem.

In a quantitative sense there are many hardwood sites (mostly white birch and trembling aspen) where harvesting is minimal. As late as twenty years ago only a tiny fraction of the annual allowable cut in hardwoods was harvested because none of the species were of commercial value (Maini and Cayford 1968). Now the development of oriented strand board and the establishment of production facilities means that there is a demand for aspen (Anon. 1987). Contrast this with 1968 when research efforts concentrated on ways of eliminating the species (Maini and Cayford 1968). Apart from the potential loss of fibre from not harvesting these species, remnant trees left after harvesting interfere with silvicultural operations.

Even in softwood stands containing economically valuable species utilization standards are low. It has been estimated that approximately half of the standing biomass is left in the forest in the form of high stumps, tops, branches and even logs (Case 1982a). Depending on the type of method of extraction used varying amounts of fibre are left behind. Under the full tree system 20.7 oven dry tonnes/ha are left, under the tree length system 53.8 and under the shortwood system 70.7 (Case 1982b). Higher levels of utilization improves the environment for reforestation and reduces the area harvested to produce the same amount of fibre.

The qualitative effects are related to the long term productivity of the site. Before the mechanization of harvesting, the harvesting process did not greatly damage or disrupt the site. Roads and landings and small skid trails were present but soil compaction or erosion was minimal. Advance growth was only slightly disturbed. Some mixing of soil and the organic matter occurred but this was generally beneficial to natural regeneration (Hearnden 1975, Draper 1982).

Since 1950, however, the increase in use of wheeled skidders, forwarders and other heavy machinery has seriously disturbed forest sites. It is estimated that 15 to 20 % of seedbed areas are disrupted to an extent that natural regeneration is impossible (Hearnden 1975). Damage to site productivity results from soil compaction, erosion and destruction of advance growth.

Advances in logging methods have extended the boundaries of the productive forest. Steep slopes, formerly inaccessible can now be harvested. Little thought has been given to subsequent possibilities of erosion or of reforestation methods. The trend is common in forest operations where machines are designed to get wood out as cheaply as possible. This short term event has long term consequences on forest productivity.

Another effect of harvesting is the problem of nutrient depletion. Full tree harvesting, which removes most of the biomass from the site, can be employed in mixed hardwood-softwood stands with minimal nutrient losses (Gordon 1981). However, in pure black spruce stands significant amounts of nutrients can be lost using this method. Short rotation systems also result in nutrient losses. Our knowledge of the extent of these losses is insufficient (Jovic 1981).

What can be done to ease these restrictions? Products can be and are being developed to use currently unwanted species. Higher utilization standards increase efficiency and facilitate reforestation operations. Logging can be done on some sites in winter rather than summer to minimize site damage (Todd 1982). Changes then will be needed in harvesting, transportation, handling and processing of materials. This will enable site treatments to be based on biological considerations rather than the reforestation manager reacting to the harvesting method and being left with a 'problem site'

with fewer silvicultural options. Advantage can be taken of machinery already developed for extraction and adapt for reforestation purposes. For instance, cones can be collected using machinery often used or designed for harvesting (Haig 1969, Bailey and Sullivan 1981). Logging methods might be varied, black spruce is a good seed producer and strip cutting is a feasible method for regenerating the species (Haavisto 1975). Thinning or selection cutting may harvest the mortality and permit a variety of harvesting techniques other than clearcutting (Nickerson 1970, van Nostrand 1973). The manager must consider harvesting as a part of the succession of forests and not as a one-shot 'cut and run' exercise. If the forest operation is not biologically sound then in the long run it will not be economically sound.

4. Technical

Forest management is restricted in that the optimum reforestation treatment is not known for all forest sites. Although a large body of research results is available for the boreal forest, many conditions are not identified or adequately described.

This restriction arises from the failure to transmit research knowledge and in not getting the best from what we do know. This is currently being addressed by an increased emphasis on technology transfer, joint researcher-user symposia and subject working groups.

Forest management is sometimes restricted by a lack of trained personnel able to do silviculture, though this can be overcome through training and job creation projects. Management is restricted by shortages of planting stock and by the inability of current machinery to provide the micro-environment needed for seedling development. This can be overcome by the research and development of new technologies, the major change being the attitude that new machines must be designed to accommodate the biological needs of the seedlings.

There are cultural and legal restrictions on forest management. A good example of cultural restriction is that of opposition to prescribed burning. To most North Americans exposed to the Smokey the Bear culture, fire is an enemy of the forest rather than a silvicultural tool. The most prominent legal restriction in forest management is that on the use of herbicides. Court challenges mounted by various environmental groups have prevented even the testing of herbicides and widespread use on public lands. However, professional foresters seldom agree on when and where herbicides should be used nor can researchers always show what the effects of herbicides are on forest succession. Thus it is necessary to win public (hence political) acceptance through public relations efforts while ensuring that the prescriptions are based on sound scientific data.

A brief review of the literature shows that a great deal of research has been done on management prescriptions for the boreal forest. This research has gone a long way to alleviating the restriction imposed by technology. This paper lists several under three categories of research showing the type of work done and the breadth of current knowledge.

I What type of sites do we need to treat and how?

Forest management concentrates on the best sites to get the best return on investment (Forster 1969). These sites must be identified and this process has led to the development of site preparation manuals (Jones et al. 1983, Corns and Annas 1986, Anon. undated).

Productive forest land can also be extended by draining peatlands or by afforesting lands such as barrens (Payanden 1975, Hall 1987).

Site factors affecting regeneration succes have been described for white spruce (Draper 1982) and black spruce (Vincent 1965) and for other boreal species. Temperature, light, competing vegetation, soil texture, structure and nutrients, moisture and aeration have been studied. It has been demonstrated that soil inversion or mounding results in improved aeration and higher temperatures and provides some natural control of competing vegetation.

Increased planting succes can be achieved using larger rather than smaller stock.

Controlled burning has been shown to be a management tool in manipulation of species composition, and stand conversion (Hall 1973, Armson 1985, Innes 1985). The degree of fire intensity governs the success of reforestation treatments (Brown 1984).

The microsite conditions must be adequate for seedling survival but failure to provide these basic conditions is where most regeneration failures occur.

II Stand Establishment.

A considerable body of data has accumulated on natural and artificial stocking of stands. Methods for regeneration establishment have been described for Jack pine (Clarke 1984, Smith, B.W. 1984) and white spruce and black spruce (Richardson 1973). Direct seeding appears promising but is not widely used in reforestation operations (Hellum 1973). Success of seeding in strongly dependent upon precipitation which varies greatly during the growing season (Brown, 1984).

Most boreal species are also easy to regenerate, it is easy to raise them in the nursery or greenhouse, they are easy to plant and they usually have rapid juvenile growth. The problems arise when the forest manager has failed to take into account some basic biological factors necessary for success.

In some reforestation projects herbicides are needed to overcome weed competition (Dennis 1984). Evaluation of weed effects is difficult but usually only localized treatments are needed. Other methods have been studied for weed control including manual brushcutting, fire and biological control (Sutton 1985). Planting methods, mounding and use of large stock can also be used to overcome vegetation competition hindering seedling development.

Tree improvement programs designed to replace wild seed with genetically improved seed have affected reforestation programs (Miller 1984). The growth rate in boreal conifers is partly genetically enrolled and considerable advantage in growth rate can be gained by using superior genotypes (Yeatman 1984). Within reforestation programs tree improvement methods have a sound economic basis (Cornelius and Morgenstern 1986).

III Stand Tending.

Various studies have been done on fertilization and precommercial thinning (spacing) of boreal conifers. Fertilization with nitrogen, phosphorous and potassium stimulates growth in black spruce and lodgepole pine (van Nostrand 1979, Yang 1983). Greatest response is in young stands approaching crown closure but positive results have been obtained in fertilizing 60 year-old black spruce and 70 year-old lodgepole pine.

Precommercial thinning is a necessary and valuable tool when managing lodgepole pine (Johnstone 1983) and Jack pine (Smith, C.R. 1984) where considerable response in diameter growth results after treatment.

Finally insect and disease pests though theoretically serious have yet to become a serious management problem in plantations. Large reservoirs of budworm-infested stands near plantations may cause problems in the future. Planted stands tend, on the whole, to be more susceptible to damage by *Armillaria mellea* than seeded ones (Singh and Richardson 1973) although this may only be a result of early stress on planted seedlings. Previous forest pathology research was concerned with diseases of older mature trees in natural stands but now research is concentrating on plantations.

CONCLUSIONS

Forest management in the boreal forest is restricted by:

- the idea that forest management is unnecessary **(conceptual),**

- the failure of the landowner to assign responsibility for forest management **(political),**
- the nature of the harvesting and utilization of the forest resource **(economical),**
- the lack of knowledge needed to apply management on all forest sites **(technical).**

These restrictions are being addressed at a rapid pace in the 1980's. Expenditures in silviculture as a proportion of all expenditures on management have shown a steady increase over the past 10 years. Between 1977 and 1982 this increase was 54 %. New Federal-Provincial forestry agreements in Canada have provided for several hundred million dollars for forest management with emphasis to be placed on forest renewal, nursery development and stand tending. These trends are encouraging and suggest that in the near future intensive forest management will be the rule in boreal forests in North America — not the exception.

LITERATURE CITED

Anon. 1981. Report of the Royal Commission on Forest Protection and Management, Part 11 Government of Newfoundland and Labrador, St. John's, Nfld. 131 p.

— 1986. Canada's Forest Industries, 1986 Data Book. Canadian Forest Industries Council, Ottawa, Ont. Can. 119p.

— 1987. Forestry Forum. Published by the Can. Forest. Ser. for the Can. Council of For. Ministers, Ottawa, Can. 6 p.

— (undated). Forestry Field Handbook. N.S. Dep. Lands and Forestry, For. Res. Sec., Program Planning Br., Truro, Nova Scotia. 25 p.

Armson, K.A. 1985. Fire and Forest Management in Can. Forest. Ser., Forest Fire Management Symposium. Can. Forest. Ser., Great Lakes For. Res. Centre. COJFRC Symposium Proceedings 0-P-13, 125 p.

Arno, S.F. & Hammerly, R.P. 1984. Timberline — Mountain and Arctic Forest Frontiers. The Mountaineers, Seattle, Wash. 304 p.

Bailey, K.E. & Sullivan, C.D. 1981. Cone Rake Trials in Nova Scotia. N.S. Dep. Lands and For., Reforestation and Silv. Div., Truro, Nova Scotia. 10 p.

Bickerstaff, A. & Hostikka, S.A. 1977. Growth of Forest in Canada, Part 1: An Annotated Biblioraphy. Can. Dep. Fish. and Env., Can. Forest. Ser., For. Man. Inst. Ottawa, Inform. Rep. FMR-X-98. 197 p.

Brown, G. 1984. Aerial Seeding of Wildfire Areas in the North-western Region in Jack Pine Symposium. Env. Can., Forest. Ser., Great Lakes For. Res. Centre. COJFRC Symposium Proc. 0-P-12. 195 p.

Case, A.B. 1982a. Reducing Forest Biomass Losses in Logging Operations: A Canadian Overview in Seminar on Reducing Forest Biomass Losses in Logging Operations, Moscow (USSR), Joint FAO/ECE/ILO Committee on Forest Working Techniques and Training of Forest Workers. 7 p.

— 1982b. Machine Systems and Technologies for Increasing Biomass Recovery on Clearcutting Operations in Eastern Canada. Paper presented at seminar on Reducing Biomass Losses on Logging operations held in Moscow, USSR, 4-11 Dec. 1982. 13 p.

Clark, A. 1984. Ground Seeding Requirements for Jack Pine Regeneration in Jack Pine Symposium. Can. Dep. of the Environ. Can. Forest. Ser., Great Lakes For. Res. Centre, Symp. Proc. 0-P-12. 195 p.

Cornelius, J.P. & Morgenstern, E.K. 1986. An Economic Analysis of Black Spruce Breeding in New Brunswick. Can. J. For. Res. 16: 476-483.

Corns, I.G.W. & Annas, R.M. 1986. Field Guide to Forest Ecosystems of West-Central Alberta. Can. Forest. Ser., Nor. Forest. Centre, Edmonton, Alta. 251 p.

Dennis, R. 1984. Vegetation Management in Jack Pine Plantations in Jack Pine Symposium, Can. Dep. of the Env., Can. Forest. Ser., Great Lakes For. Res. Centre, Symp. Proc. 0-P-12. 195 p.

Draper, D.A. 1982. Spruce Regeneration in the Prince George Forest Region: A Research Perspective in Forest Regeneration at high Latitudes: Experiences from British Columbia. USDA For. Ser., Pacific Northwest For. and Range Exp. Stn. Misc. Rep. 82-1. 34 p.

Forster, R.B. 1969. Economic Analysis of Afforestation and Reforestation in Newfoundland. Can. Dep. Fish. and Forest., For. Economics Res. Inst., Ottawa. Inform. Rep. E-X-6. 50 p.

Gordon, A.G. 1981. Impacts of Harvesting on Nutrient Cycling in the Boreal Mixedwood Forest in Boreal Mixedwood Symposium, Can. Dep. of the Env., Can. For. Ser., Great Lakes For. Res. Centre, COJFRC Symposium Proceedings 0-P-9. 278 p.

Haavisto, F.V. 1975. Peatland Black Spruce Seed Production and Dispersal in North-eastern Ontario in Black Spruce Symposium. Can. Dep. Of the Env., Can. Forest. Ser., Great Lakes For. Res. Centre, Symposium Proceedings 0-P-4. 289 p.

Haig, R.A. 1969. Trials of Mechanical Collection of Black Spruce and Jack Pine Cones. Can. Dep. Fish. and Forest., Can. Forest. Ser., For. Res. Lab., Sault Ste. Marie, Inform. Rep. 0-X-112. 15 p.

Hall, J. Peter. 1973. Replacement of Balsam Fir by Other Softwood Species in the Forests of Western Newfoundland. Environ. Can., Can. Forest. Ser., Nfld. For. Res. Centre, Inform. Rep. N-X-98. 30 p.

— 1987. Afforestation of Heathlands in Eastern Newfoundland. Can. Forest. Ser., Nfld. Forest. Centre, Inform. Rep. N-X-253. 25 p.

Hardy, Y. 1985. Dynamics of Spruce Budworm Epidemics in Spruce — Fir Management and Spruce Budworm. USDA; For. Ser., N.E. For. Exp. Stn. Gen. Tech. Rep. NE-99. 217 p.

Hearnden, K.W. 1975. Black Spruce — The Cinderella Species and the Story of Canadian Forestry in Black Spruce Symposium, Can. Dep. of the Environ., Can. Forest. Ser., Great Lakes For. Res. Centre, Symp. Proc. 0-P-4. 289 p.

Hellum, A.K: 1973. Direct Seeding in Western Canada in Direct Seeding Symposium. Can. Dep. of the Env., Can. Forest. Ser., Ottawa. Publ. No. 1339. 178 p.

Honer, T.G. & Bickerstaff, A. 1985. Canada's Forest Area and Wood Volume Balance 1977-1981: An Appraisal of Change Under Present Levels of Management. Can. Forest. Ser., Pacific Forest Centre, Inform. Rep. BC-X-272. 84 p.

Innes, M.R. 1985. Forest Fire: Who Needs It? An Industrial Perspective in Forest Fire Management Symposium. Can. Forest. Ser., Great Lakes For. Res. Centre. COJFRC Symposium Proceedings 0-P-13. 125 p.

Johnstone, W.D. 1983. Natural Lodgepole Pine in West-Central Alberta, Part II: Juvenile Spacing in Lodgepole Pine: Regeneration and Management. USDA For. Ser., Pacific N.W. For. and. Range Exp. Stn., Gen. Tech. Rep. PNW-157. 52 p.

Jones, R.K., Pierpoint, G., Wickware, G.M., Jeglum, J.K., Arnup, R.W. & Bowles; J.M. 1983. Field Guide to Forest Ecosystem Classification for the Clay Belt Site Region 3E. Ontario Min. Nat. Res. Toronto. 123 p.

Jovic, D. 1981. Current Management Practices in the Boreal Mixedwood Forest: North Central region in Boreal Mixedwood Symposium, Can. Dep. of the Env., Can. For. Ser., Great Lakes For. Res. Centre, COJFRC Symposium Proceedings 0-P-9. 278 p.

Kettela, E.G. 1983. A Cartographic History of Spruce Budworm Defoliation 1967 to 1981 in Eastern North America. Env. Can., Can. Forest. Ser. Inform. Rep.DPC-X-14. 8 p.

Kuhnke, D.H. & Brace, L.G. 1986. Silviculture Statistics for Canada. Can. Forest. Ser., Nor. Forest. Centre, Inform. Rep. NOR-X275. 43p.

Larsen, J.A. 1980. The Boreal Ecosystem. Academic Press, New York. 500 p.

Maini, J.S. & Cayford, J.H. 1968. Growth and Utilization of Poplars in Canada. Can. Dep. of Forest. and Rur. Dev., Departmental Publ. No. 1205. Ottawa. 257 p.

Miller, L.K. 1984. Northern Region Jack Pine Tree Improvement Program in Jack Pine Symposium. Can. Dep. of the Env., Can. Forest. Ser., Great Lakes For. Res. Centre. COJFRC Symp. Proc. 0-P-12. 195 p.

Nickerson, D.E. 1970. Ten-year Results of Experimental Pulpwood Cutting in Immature Black Spruce and Balsam Fir. Can. Dep. Fish and Forest, Can. Forest. Sev., For. Res. Lab, St. John's Nfld., Inform. Rep. N-Y-45. 15 p.

van Nostrand, R.S. 1973. Commercial Thinning of 60-Year Old Black Spruce in Newfoundland. Env. Can., Forest. Ser. Nfld. For. Res. Centre, Inform. Rep. N-X-104. 13 p.

— 1979. Growth Response of Black Spruce in Newfoundland to N, P and K Fertilization. The Forestry Chronicle 55: 189-193.

Oswald, E.T. & Brown, B.N. 1986. Forest Communities in Lake Laberge Ecoregion, Yukon Territory. Can. Forest. Ser., Pacific Forest. Centre. Infor. Rep. BC-X-282. 97 p.

Payandeh, B. 1975. Growth and Economic Analyses of a Forest Drainage Experiment in Northern Ontario in Black Spruce Symposium, Can. Dep. of the Env., Can. Forest. Ser., Great Lakes For. Res. Centre, Symp. Proc. 0-P-4. 289 p.

Richardson, J. 1973. Direct Seeding the Spruces In Direct Seeding Symposium. Can. Dep. of the Env., Can. Forest. Ser., Ottawa Publ. No. 1339. 178 p.

Rowe, J.S. 1972. Forest Regions of Canada. Can. Dep. of the Env., Can. Forest. Ser., Ottawa. Publ. No. 1300. 172 p.

Singh, P. & Richardson, J. 1973. Armillaria Root Rot in Seeded and Planted Areas in Newfoundland. The Forestry Chronicle 49: 179-182.

Smith, B.W. 1984. Aerial Seeding Requirements for Jack Pine Regeneration in Jack Pine Symposium. Can. Dep. of the Environ., Can. Forest. Ser., Great Lakes For. Res. Centre, Symp. Proc. 0-P-12- 195 p.

Smith, C.R. 1984. Precommercial Thinning in jack Pine with Particular Reference to Experiments in North-eastern Ontario in Jack Pine Symposium. Can. Dep. of the Env., Can. Forest. Ser., Great Lakes For. Res. Centre, Symp. Proc. 0-P-12. 195 p.

Sutton, R.F. 1985. Vegetation Management in Canadian Forestry. Can. Forest. Ser., Great Lakes For. Res. Centre, Inform. Rep. 0-X-369. 34 p.

Ternent, L.K. 1984. Cutover Classification for Site Preparation in Jack Pine Symposium, Can. Dep. of the Environ., Can. Forest. Ser., Great Lakes For. Res. Cent., COJFRC Symposium Proceedings 0-P-12. 195 p.

Todd, A.M.D. 1982. Natural Regeneration: Policies, Procedure and Practices in the Prince George Forest Region in Forest Regeneration at High Lati-

tudes: Experiences from British Columbia, USDA For. Ser., Pacific Northwest For. and Range Exp. Stn., Misc. Rep. 82-1. 34 p.

Viereck, L.A. & Little, E.L. 1972. Alaska Trees and Shrubs. USDA For. Ser., Washington, D.C. Agric. Handbook 410. 265 p.

Vincent, A.B. 1965. Black Spruce, A Review of its Silvics, Ecology and Silviculture. Can. Dep. of Forest., Ottawa. Publ. No. 1100. 79 p.

Vyse, A.H. 1973. Economics of Direct Seeding Versus Other Regeneration Techniques in Direct Seeding Symposium. Can. Dep. of the Env., Can. Forest. Ser., Ottawa. Publ. No. 1339. 178 p.

Yang, R. 1983. Natural Lodgepole Pine in West-Central Alberta, Part III: Fertilization in Lodgepole Pine: Regeneration and Management. USDA For. Ser., Pacific NW For. and Range Exp. Stn., Gen. Tech. Rep. PNW-157. 52 p.

Yetman, C.W. 1984. The Genetic Basis of Jack Pine Management in Jack Pine Symposium. Can. Dep. of the Env., Can. Forest. Ser., Great Lakes For. Res. Centre. COJFRC Symp. Proc. 0-P-12. 195 p.

RESTRICTIONS ON FOREST MANAGEMENT CLOSE TO THE TIMBERLINE IN NORWAY

Oddvar Haveraaen

ABSTRACT: In Norway, the uppermost forests above spruce and pine consist of birch. The ecological conditions are harsh and unstable, resulting in low yield and difficult natural and artificial regeneration of conifers. Multiple use aspects based on ecological knowledge ought to be the primary guideline for management of these forests.

DEFINITIONS

The definition of mountain forest, or forest close to the timberline, is not very exact. In particular, the lower border causes difficulties whereas the common definitions of the uppermost borders are more clear in Norway. The treeline is drawn where scattered trees have a height of 2 m, while the timberline is where the maximum distance between trees is 30 m and minimum tree height 3 m (Mork and Heiberg 1937) The upper limit of what we define as a productive forest is somewhat below the timberline. A productive forest should have a mean annual yield potential of at least 1 m^3 per hectare.

A general characteristic of mountain forest is that in such forest temperature is a strong limitation for both forest yield and tree reproduction.

AREAS OF MOUNTAIN FOREST

Mork (1958) roughly estimated the average horizontal width of the mountain forest in Norway to be 500 m. By using figures for the length of the timberline, estimated by Norges Geografiske Oppmåling to be 47 000 km, we end up with nearly 2.5 million hectares, or about 1/3 of the total forest area in Norway.

Oddvar Haveraaen is professor in Silviculture, at the Agricultural University of Norway, As, Norway.

The current timberline is sometimes lower than the climatic timberline. For instance, local mountain farming, with browsing domestic animals and heavy cutting of firewood, may temporarily lower the timberline.

In the high mountain area in south-eastern Norway the climatic coniferous timberline is over 1 00 m a.s.l. Generally the height of the timberline varies considerably from south to north, from the interior to the coast, and even from the central part of southern Norway to the east (Abrahamsen et al. 1977) (Fig. 1). Hence, to relate the lower limit of mountain forest to a certain height above sea level has no meaning. According to Børset (1986), some researchers have used 60 - 70 % of the height of the timberline as the lower limit of the mountain forest.

Bergan (1974) has on the basis of climatic studies, suggested relating the lower limit to a vertical height difference from the climatic timberline. This vertical belt could then be valid all over the country. This means that under unfavourable conditions, as in the far north, all forests should ecologically be classified as mountain forest. We have no figures on the area of mountain forest in Norway today. Assuming 15 - 20 % of the total forest area would give 1.1 - 1.5 million hectares.

FOREST LAW

Since 1976 the general objective of the Norwegian forest law has included a clear multipurpose statement. In addition to production of timber, giving income to forest owners and raw material to various types of timberusing indus-

tries, forest management must have in mind the recreation aspects, the esthetic value of trees and forests, and the habitats for all types of animals, and plants.




Figure 1. Isogram in m for the climatic timberline of birch (Betula pubescens var. tortuosa) in Fennoscandia. (Abrahamsen et al. 1977.)

For the forest close to the timberline the law has for a long time contained a particular paragraph about cutting regulations. In every district of the country an imaginary line is drawn some vertical distance below the timberline, often 100 - 200 m. Above this line the forest owner can only cut dead trees without special permission. If more cutting is requested by the forest owner, the national forest service must carry out the marking. This regulation was stated long time ago, when mountain farming and heavy cutting were a real threat to the future of the mountain forests.

For various reasons the cutting activities in the mountain forests have generally been quite low some decades. This has taken the restriction paragraph out of practice, although it still exists.

TREE SPECIES CLOSE TO THE TIMBERLINE

Birch (*Betula pubescens* var. tortuosa) is the dominating tree species in the upper belt close to the timberline in the western part of Fennoscandia. Mixed with the birch we find groups or single trees of aspen (*Populus tremula*), gray alder (*Alnus incana*), mountain ash (*Sorbus aucuparia*) and bird cherry (*Prunus padus*). All these species have a temperature demand for the four summer months of about 7.5° C, while spruce (*Picea abies*) and pine (*Pinus sylvestris*) require about 8.4° C. The difference between the mentioned broad-leaved trees and the conifers means a vertical altitude difference of 100 - 150 m. Thus, on steep slopes the belt of broad-leaved trees is quite narrow, while on nearly flat ground, it will dominate large areas.

Birch also occurs quite frequently in the upper coniferous belt. In the most arid mountain regions, pines form the coniferous timberline. However, since humidity dominates the Norwegian climate, spruce is the most common conifer.

FOREST REGENERATION

The broad-leaved tree species can regenerate either generatively or vegetatively. The production of birch seeds is generally abundant. No registration is available to tell the proportion of seed or sprout regeneration. We assume, however, that vegetative regeneration is quite frequent in the mountain regions. Before the last world war farmers commonly kept their domestic animals grazing in the forest close to the timberline. Small seedlings of birch were then browsed near to the ground every year. When pasturing in the mountain regions decreased, the new vegetative shoots had the chance to develop into trees. Today we often find abundant young birch trees among scat-

tered old trees or young birch trees higher up than the old ones.

Pinus sylvestris does not regenerate vegetatively. Usually we find the most frequent pine regeneration where the layer of raw humus is thin. However, at high altitudes young pine is susceptible to snow blight fungus, *Phacidium infestans*.

The seed production of conifers, particularly spruce, decreases drastically with increasing altitude (Bonnevie-Svendsen and Skoklefald 1965). The temperature demand (average June-September) for development of mature seeds is about 10° C (Hagem 1917, Eide 1930). This is 1.5° C higher than the requirement for vegetative growth. Aslo for seed germination the temperature is an essential factor (Mork 1938b, Løken 1970) (Fig. 2). However, it seems that these factors to some extent can be modified depending on the natural seed storage conditions during the winter prior to germination.* Often in nature loss of seeds and young seedlings by predators can reduce a promising crop to a poor regeneration (Nilsen 1987).

Spruce, *Picea abies*, however, has the ability to regenerate vegetatively by sinkers. When the lower branches from a "mother tree" lay on moist raw humus for some years, the branches start to develop roots from the touching point. The branch tips bend upwards and a new generation of young spruces grow up more or less regularly around the "mother tree". In due course new generations may develop outside these again. The belt of vegetatively regenerated spruce in this way is usually limited to the uppermost, say 50 m, vertical belt from the timberline.

Young plants of spruce are very sensitive to frost damage in the summer months. This is particularly the case in flat areas such as plateaus and valley bottoms (Mork 1968, Frank and Kibsgaard 1973). Regeneration, natural or artificial, under such conditions will therefore hardly be a success on clear-cut areas.




Figure 2. Germination curves for spruce seed, _____covered and - - - - uncovered, at different temperatures (Løken 1970).




Figure 3. The relation between vertical distance below birch timberline and mean temperature June-September (Tetra T.m.). Inland and coast stations in Troms, North Norway (Bergan 1974).

The ecological balance in the forest close to the timberline is very unstable. Great differ-

* Investigations done by P. Nilsen. Manus under preparation.

ences in average summer temperature, 1 - 2° C, often occur from one year to another. There also exist oscillations with intervals of 5 to 10 years (Mork 1968, Bergan 1974) (Fig. 3), and even long term fluctuations. Treatments carried out in a climatically good period may lead to success, while the same treatments under less favourable conditions can result in a complete failure. A change in the average summer temperature of 0.6° C (June-September is equal to an altitude difference of about 100 m.

Mork (1933) found a higher soil temperature on clear-cut areas than in forest stands. In this investigation all the clear-cut areas were smaller than 1 hectare (0.2 and 0.7). Wind generally lowers the effect of maximum daily temperature. In mountain regions the positive effect of clearcutting could thus be turned to a negative effect if the clearcutting results in increased wind speed above a certain level. Flemming (1968) has found that in Middle Europe the wind speed on clear-cut areas even as small as 2 hectares approaches the wind speed on wide open land (Table 1):

Table 1. Width of clear-cut area and windspeed (Flemming 1968). Presuppositions are square areas and 15 m tree heights.

Area Width in tree heights	0	10	20	40
Wind speed in per cent of speed on open land	15	64	82	92
Size of clear cut area, hectare	0	2.2	9	36

The low temperature and in most places rather high rainfall (>800 mm) do not favour a rapid decomposition of the organic matter deposing on the top of the mineral soil. The soil material is also often acid and poor in nutrients. This again leads to a podzol profile which usually gives difficult conditions for both natural and artificial regeneration of conifers (Mork 1938a, Låg 1961).

FOREST YIELD

The factors affecting regeneration also have great influence on the yield of wood and timber (Mork 1944, 1968, Bergan 1983, 1984) (Fig. 4). The yield will vary depending on how far below the timberline we draw the lower limit of the mountain forest, but is usually less than 2.5 m^3 per hectare and year. However, higher yields can be found at relatively high altitudes on slopes facing south or southwest and where the soil fertility is aslo good.

In much of the mountain forest top and stem breakage caused by heavy load of snow and sometimes even ice occurs frequently. The wind often adds additional restrictions both summer and winter. Wind in summer reduces the maximum temperature within and close to the needles and leaves. Strong wind can also damage the needles physically in winter by snow and ice drift and by drying in both summer and winter.




Figure 4. Widths of annual rings of spruce and growth units during the growing season for the years 1932-65 (Mork 1968).

Forest close to the timberline usually has low stand density and trees with a deep crown. There are also stands with a relative high number of trees per hectare of the same size and age, but the common feature is variation (Nilsen and Haveraaen 1982b).

Investigations by Nilsen and Haveraaen (1982a) have also shown that the forest yield is sustainable to a much larger extent than in more highly productive forest. The low yield in the forest close to the timberline does not generally encourage high investments in forest regeneration and stand treatment.

From an ecological point of view it seems reasonable to take advantage of the variation that exists. Cutting the most mature trees and leaving the middle-sized and smaller individuals for further growth is a treatment that has received increasing attention the last years. Clearcutting of small areas, adjusted to local conditions, is also an alternative. At lower locations and under less harsh conditions, the ecological restrictions on forest management do not need to be so strict.

MULTIPLE USE OF FOREST CLOSE TO THE TIMBERLINE

Many factors have brought the mountain forests more in focus the last years. Higher economic living conditions makes it easier for the population to spend more of their leisure time away from home. There has been an increasing interest in and understanding of the necessity for nature conservation among many people. There is an ever-increasing demand from non-foresters, and also from professional foresters, that nature has to be treated with emphasis on ecology and multiple use.

The economical trend has for several years more favoured development of towns or town-related industry than forestry. The official policy in Norway now tries to encourage a higher level of activity and harvest in the forests away from the economic centers. It is expected that this will increase the logging activity also in the mountain forests. The technical development with more efficient equipment makes it easier and more profitable to carry out heavy cutting, like clearcutting in these regions.

Many individuals and organizations in Norway dealing with nature conservation, recreation, wildlife and hunting fear that the economic income from timber harvest, partly state subsidies, will drastically increase the logging activity in the forests close to the timberline. These organizations have recently asked the government to reconsider the management policy for the high-altitude forests. To be sure, this is a complex matter. In addition to the factors mentioned above, rural policy is of great importance. As it is, many forest owners in mountain parishes do not have sufficient income from sources other than low-yielding agriculture and forestry.

Recreation and tourism are being launched as partial substitutes for the traditional primary industries. If these substitutes are to really be of economic relevance to the landowners, they have to bring income. To achieve this, the attitude to such new land-use systems has to be changed, among both many of the landowners and the receipients of these new benefits.

LITERATURE CITED

Abrahamsen, J., Dahl, E., Jacobsen, N.K., Kalliola, R., Påhlsson, L. & Wilborg, L. 1977.Naturgeografisk regioninndeling av Norden. NU-ser. B 1977:34 Stocholm. 130 p.

Bergan. J. 1974. Varmeklimaet i forskjellige høydesoner under bjørkeskoggrensa i Troms. (The heat effect at different vertical distances below the birch timberline in Troms.) Medd. Nor. inst. skogforsk. 31: 329-353.

— 1983. Temperaturens virkning på årlige toppskuddlengder hos gran i Troms. (Effects of temperature on annual shoot growth of Picea abies (L) Karst. in Troms.) Medd. Nor. inst. skogforsk. 38.11: 1-15.

— 1984. Veksttid og vekstrytme hos gran i Troms. (Growth period and growth rhythm in Picea abies (L) Karst. in Troms.) Rap. Nor. inst. skogforsk. 8/84: 1-24.

Bonnevie-Svendsen, C. & Skoklefald, S. 1965. Frøproduksjon i granskog. Norsk Skogbr. 11: 619-622.

Børset, O. 1986. Skogskøtsel II. Landbruksforlaget. Oslo. 455 p.

Eide, E. 1930. Sommervarmens betydning for granfrøets spireevne. (The influence of summer temperature on the seed germination of Norway spruce.) Meddr norske SkogforsVes. 3: 473-508.

Flemming, G. 1968. Die Windgeschwindigkeit auf waldumgebenen Freiflächen. Arch. Forstwes. 17: 5-16.

Frank, J. & Kibsgaard, Ø. 1973. Foryngelsesproblemer i fjellskog i Vestre Gausdal. M.Sc. thesis in Silviculture, Agricultural University of Norway, 93 p.

Hagem, O. 1917. Furuens og granens frøsætning i Norge. Meddr Vestland. forstl. ForsøksStn. 1(2): 1-188.

Løken, A. 1970. Spireforsøk med nåletrefrø. (Germination experiments with coniferous seeds.) Meddr Vestland. forstl. ForsStn. 14: 51-143.

Låg, J. 1961. Undersøkelse av skogsjorda i Hedmark ved Landsskogtakseringens markarbeid somrene 1958 og 1558. (Investigations on forest soils in Hedmark county, Norway, in connection with the field work of the National Forest Survay.) Meddr norske SkogforsVes. 17: 183-235.

Mork, E. 1933. Temperaturen som foryngelsesfaktor i de nordtrønderske granskoger. (Über die Bedeutung der Temperatur für die Verjüngung in den Fichtenwäldern von Nord-Trøndelag.) Meddr norske SkogforsVes. 5: 1-156.

— 1938a. Omsetningen av humusdekket ved forskjellig temperatur og fuktighet. (The decomposition in the humus layer at different temperatures and degrees of moisture.) Meddr norske SkogforsVes. 6: 179-224.

— 1938b. Gran- og furufrøets spiring ved forskjellig temperatur og fuktighet. (Germination of spruce and pine seed at various temperatures and degrees of moisture.) Meddr norske SkogforsVes. 14: 225-249.

— 1944. Om sambandet mellon temperatur og vekst. (Über den Zusammenhang zwischen Temperatur und Wachstum.) Meddr norske SkogforsVes. 8: 1-89.

— 1957. Om frøproduksjon hos furu i Hirkjølen. (Seed quality and seed production for Scots pine at Hirkjølen.) Meddr norske SkogforsVes. 14: 349-380.

— 1958. Fjellskogens behandling. Skogeieren 48: 91-97.

— 1968. Økologiske undersøkelser i fjellskogen i Hirkjølen forsøksområde. (Ecological investigations in the mountain forest at Hirkjølen experimental area.) Meddr norske SkogforVes. 25: 436-614.

— & Heiberg, H.H.H: 1937. Om vegetasjon i Hirkjølen forsøksområde. (On the vegetation in the experimental area of the Institute of Forest Research in the Hirkjølen state forest.) Meddr norske SkogforsVes. 5: 617-668.

Nilsen, P. 1984. Fjellskoghogst — en vurdering av hogsmåten i granskog. Tidsskr. for Skogbr. 91: 22-29.

— 1987. Tap av frø og spireplanter av gran (Picea abies (L.) Karst.) etter såing på forskjellige vegetasjonstyper i fjellskog og lavlandet. (Loss of seeds and seedlings of Norway spruce (Picea abies (L.) Karst.) after sowing on different vegetation types in mountain forest and lowland forest.) Medd. Nor. inst. skogforsk. 39(8), in press.

— & Haveraaen, O. 1982a. En analyse av tilvekst i gamle granbestand. (An analysis of increment in mature stands of Norway spruce.) Rap. Nor. inst. skogforsk. 13/82: 1-38.

— & Haveraaen, O. 1982b. Dimensjonsfordeling og diameterklassevis tilvekst i eldre granskog. (Tree size distribution and increment in different diameter classes in old Norway spruce stands.) Rap. Nor. inst. skogforsk. 15/82: 1-28.

RESTRICTIONS ON FOREST MANAGEMENT CLOSE TO TIMBER LINE IN FINLAND

Matti Leikola

ABSTRACT: Pessimistic views on the regeneration capacity of Scots pine near the northern timber line created the legislation on shelter forests in Finland in the 1910's. In the Shelter Forest Area of Lapland all forest use is under state control. Also in the northern commercial forests the maximum size of the cutting areas has been restricted to 5 - 20 hectares. The conservative philosophy in forest management in the northernmost forest has proved to be successful even in modern times.

INTRODUCTION

The purpose of shelter forests, whose survival has been considered necessary for the local people and the existence of the forests themselves, is in northern Europe very old. In Sweden the first shelter forest areas were created in the 1840's and in old Imperial Russia the first Act on Shelter Forest was approved in 1888. The main intention was to protect forests that were situated near open sand dunes or steppes.

In Finland the first attempts to restrict forest utilization on ecologically vulnerable areas were made in the 1840's, but the efforts did not lead to concrete results. The Forestry Law of 1886 stated that forest was not to be "devastated open", but the supervision of the law was very superficial, especially in the northern parts of the country.

Only in 1900 the Committee on State Forests made the first serious effort to protect the northernmost forests. The committee proposed that the areas near the fell region in the north: the parishes of Utsjoki, Inari, Enontekiö, and Kuollajärvi (Salla), as well as the north-eastern parts of Sodankylä should be separated as a special shelter forest area and be kept under state administration and supervision. The border line of the shelter area could be set to run "a few scores, perhaps 30 - 50 kilometres, below that line where the dense coniferous forests end". The committee also proposed a permanent expert group to be created in order to map, survey, and mark the area in the field.

MATTI LEIKOLA, Professor of Silviculture, University of Helsinki, Addr: Unioninkatu 40 B, SF-00170 Helsinki, FINLAND.

THE PROPOSALS OF THE COMMITTEE ON SHELTER FORESTS

In 1907 a committee was appointed in order to make proposal on the shelter forest area of Lapland and the principles of forest protection and management in this area. The chairman of the committee was Chief Forestry Officer Wichman and the energetic secretary of the committee was Forestry Officer, later Professor, Olli Heikinheimo. In 1910 the more than 250 pages thick report on the northernmost forests in Finland was published. The report also included the principles of forest management in these areas and a detailed proposal to establish a special shelter forest area near the timber line.

The committee vividly described the lavish use of forests by the Finnish settlers, the old habit to cut timber trees and smuggle them to Norwegian Finnmark, and the practice to cut large areas for reindeer husbandry or only because of neighbour hate or revenge. The detailed and well made report included proposals for acts on reindeer husbandry, settlement, and forest use in the shelter forest area. Two new shelter forest areas were proposed; those of Pallas-Ounas and Pyhä-Luosto fell areas. Also the valleys of the rivers Kitka and Oulanka were proposed to be protected from all cuttings. These proposals were realised but

30 - 50 years later under the Law of Nature Conservation.

RESEARCH ACTIVITIES ON NORTHERNMOST PINE FORESTS BEGINS

The northernmost parts of the Fenno-Scandian peninsula had awakened the interest of Finnish naturalists already in the last century. The ecological conditions of the forests by the timber line were well known at the turn of the century even if the forestry points of view had not been considered very much. In 1890 A.O. Kairamo (Kihlman) had proposed his famous theory on timber line as a result of climatic conditions during the winter time, and Hult, Norrlin, Palmen, Sahlberg and Wainio, among others, had explored the northernmost forest and fell areas collecting and studying plants and animals.

Even if the report of the committee on shelter forests was officially set aside, it aroused much interest on the northernmost forests of Lapland. The first academic dissertation on forestry sciences was published by A. Renvall in 1912. He had studied the regeneration capacity of the Scots pine stands near the Arctic timber line and he ended with a very pessimistic conclusion: good regeneration years occurred on the timber line only once or twice in a century. Even in the more southern regions regeneration years were seldom, occurring only once in a decade. The need to create shelter forest area on the timber line was very urgent indeed!

Renvall published his further studies on the problems of Arctic shelter forests in 1919 as a 600- page long monography in six parts. In this he dealt with almost all aspects of the northernmost forests and forestry, analyzed deeply the philosophy of forest protection and finally made his own proposals to improve the situation: a new committee on shelter forests should be established and law on shelter forests should be made.

Renvall was the greatest Finnish authority of his time in the field of northern shelter forests, and his pessimistic views influenced decisively that the Law on Shelter Forests was approved in 1922. No shelter forest area was created in Lapland yet, but the National Board of Forestry began to take the general instructions of the Law into consideration in its own settlement policy and forest management.

After Renvall, three forestry researchers made one after another their academic dissertations on regeneration of the northernmost Scots pine forests. In 1915 O.J. Lakari confirmed that the general conditions at the timber line had stayed the same during the last 300 - 400 years and that Renvall's conclusions had been right. The general opinion on the slow and difficult natural regeneration of Scots pine in Finnish Lapland was confirmed by V.T. Aaltonen (1919) and I.K.D. Lassila (1920).

The research on the ecology and management of the forests near the timber line were not on permanent ground before the Finnish Forest Research Institute, with the leadership of Olli Heikinheimo, had established two large experimental parks near or beyond the timber line. In 1925 more than 17 000 ha. of fell and forest land at the Saariselkä area (Laanila) was transferred to the Forest Research Institute and two years later the Forest Research Institute got 54 000 ha. of barren tundra from Petsamo, near the Arctic Ocean, to serve as an experimental park for timber line studies.

THE SHELTER FOREST AREA OF LAPLAND IS FOUNDED

Interest in the Arctic shelter forest problems dimished in the 1930's when the climate turned warmer and made the general opinion more optimistic. May 4th, 1939, the Finnish government at last established the Shelter Forest Area of Lapland where all timber cutting, with the exception of taking away dry stems and twigs from the ground, was under the supervision of state forest officials. More detailed instructions were not given expect general remarks on careful forest use and management. The shelter forest area was intended to be marked in the field immediately but the work was stopped by

the outbreak of the Finnish-Soviet "Winter War" in 1939. Not until the 1970's was the task completed (Fig. 1).

Discussion on the areal size of the Shelter Forest Area of Lapland did not come to an end immediately. When Hustich (1948) and Mikola (1952) had concluded that the northernmost Scots pine stands had regenerated better than was expected earlier, Sirén (1960) proposed that the shelter area should be diminished towards the north. Later on the need for raw material of the saw mill and pulp industry of Lapland has created new interest in the Shelter Forest Area. Until now there has been no real reason to change the old regulations, at least since the more cool climatic period which started in the 1940's has made forest regeneration in whole Lapland more difficult and has required greater caution when working near the timber line (Leikola (edit.) 1979, Pohjois-Lapin...1982).

GUIDELINES FOR SILVICULTURE AND FOREST MANAGEMENT AT THE SHELTER FOREST AREA OF LAPLAND

In 1961 the research group at the Finnish Forest Research Institute: E. Oinonen, R. Sarvas, and G. Sirén, compiled the instructions for silviculture in the forests near the timber line. These instructions have remained in force until now at the Shelter Forest Area of Lapland.

The Shelter Forest Area is no nature park, the researchers emphasize at first. Its purpose is to prevent the descending of the coniferous timber line. The border line of the Shelter Forest Area can be compared to a traffic sign. It is not essential whether the traffic sign is in exactly right place, but it is important that one knows how to act in the dangerous spot. The border line of the Shelter Forest Area is a kind of alarm line. In most cases the requirements of the harsh climate must be taken into consideration already before arriving at the shelter area.

In addition to the northern situation also the vicinity of the Arctic Ocean creates difficulties north of the line: Lemmenjoki river — Lake Inari — Paatsjoki river. According to research experiences 250 - 300 meters above sea level seems to be the cardinal height above which regeneration of pine forests is really difficult and growth slow. Further down no corresponding lines from above dense and vigorous young stands. This can not take place sooner than the saplings have reached the size of 1 - 2 meters. If the forest is open or in bad condition it shall be regenerated naturally. The parent stand can not, however, be cut before the young seedling stand has well established. Stands should be kept more dense than in the south. That is why there is no reason to make thinnings with the exception of clearing advanced birch away. Thinnings — if they are done — should be from beneath.

THE MAXIMUM SIZE OF CUTTING AREAS IS RESTRICTED IN LAPLAND

At he beginning cutting areas did not have any clearly stated maximum size. The moderate size of the unmechanized logging work camps kept clear cut and seed tree areas small. At the same time as logging concentrations grew in size and logging and transportation of wood was mechanized, the size of the logging areas grew from tens of hectares to hundreds and at last to thousands of hectares.

Cold and unfavourable summers in the 1960's made the National Board of Forestry revise its cutting policy in Lapland. In 1969 new instructions were given according to which the maximum size of a cutting area that was not be exceeded was in the District of Perä-Pohjola (Lapland) 20 ha, in the District of Ostrobothnia 30 ha, and in the District of Southern Finland more than 50 ha. Cuttings were concentrated on mature Norway spruce stands where enough old Scots pines were to be found to serve as seed trees. The old strip felling system which had not been practiced in decades was again taken into use in Lapland. In the Shelter Forest Area of Lapland the instructions by Oinonen, Sarvas, and Sirén were still used almost unaltered.

Before long the direct strip cuttings created more and more public criticism. Their amount

began to diminish in the 1970's, and they were left out in 1977. In other respects, both in the state forests and in the private forests, the silvicultural principles became more conservative in the 70's.

The National Board of Forestry gave new instructions on afforestation and reforestation in 1978, and they were followed by separate instructions for all Districts in 1981 and 1985. The division of forest land into climatic regions was now made according to the average effective temperature sum (d.d.) of the place, which could be calculated when the geographic location and height above sea level were known. If clear cutting and seed tree method were used, the maximum sized of the cutting areas were as follows:

Temperature sum, d.d.	Maximum size, hectares
over 800	30
800-700	30-20
700-650	20-10
under 650	under 10

Special silvicultural instructions were given to the commercial forestry area, north of the felld ridge Saariselkä, according to which the size of the cutting areas was even more cautions than in the other commercial forest areas in Lapland. The instructions by Oinonen, Sarvas, and Sirén were still used in the Shelter Forest Area of Lapland, but clear maximum sizes of the cutting areas were now given also for this area. In the upper forests (more than 250 - 300 meters above sea level) outside Shelter Forest Area the maximum size of the cutting areas was only 5 hectares. In the corresponding areas that were inside the Shelter Forest Area, all clear cuttings as well as seed tree cuttings were prohibited with the exception of careful liberation of young forest.

DISCUSSION

Restrictions on the use of the northernmost forests in Lapland were created at a time when wood was needed for the domestic use of the local people only. It is to be concluded, however, that if protective measures had not been made so early, short sighted exploitive cuttings could have devastated the forests in the felld areas. Cautious attitude, which was based on pessimistic view on the regeneration possibilities of Scots pine in northernmost Lapland, Created the can be separated. In this respect the researchers agreed with the permanent instructions of the National Board of Forestry from the year 1956 and 1961. According to these the utmost limit for artificial forest regeneration and commercial (clear) cuttings should be 250 m. on southern (sunny side) slopes and 300 m. on northern slopes. Above this limit commercial forestry should be extended only by special permission.

According to the instructions the Shelter Forest Area was divided into two parts: upper forests and commercial forests, the height of 250 - 300 meters above sea level as a divider. In general, no cuttings are allowed in the upper forests. Only when there are enough vigorous Scots pine seedlings among the subarctic fell birch, can they be liberated. Old pine stems can be cut present day shelter forest legislation in Finland. Even if our present day picture of forest regeneration on the Arctic timber line is more optimistic than sixty years ago there is no reason to abandon the line of silviculture which has proved successful so far, not to neglect the difficulties of the timber and pulp industry of Northern Finland (cf. Kuusela 1982, Kuusela and Salminen 1978).

The only cutting method that has been allowed in the vicinity of the timber line has been cautious selection of mature trees from above the young stand, even if the harvesting and transport technology of today permit far more drastic cuttings. Accordingly, even today 60 per cent of the forests in northernmost Lapland are older than 160 years (Mattila and Kujala 1980). Since these forests have even greater value in the future for tourism and multiple use, conservation of these forests aside from heavy cuttings has received public approval. Protection measures that were planned already more than eighty years ago have proved correct and valuable even in changed conditions.




Fig. 1. Land-use classes and various protection areas in northern Finland in 1975. (Atlas of Finland 234 "Forestry", 1976).

LITERATURE CITED

Aaltonen, V.T. 1919. Kangasmetsien luonnollisesta uudistamisesta Suomen Lapissa. I. Referat: Über die naturliche Verjungung der Heidewälder in Finnischen Lappland. I. Commun. Instit. Forest. Fenniae 1(1): 1-319.

Hustich, I. 1948. The Scots pine in northernmost Finland and its dependence on the climate in the last decades. Ann. Botan. Fenn. 42.

Kairamo (Kihlman), A.O. 1890. Pflanzenbiologische Studien aus Russisch Lappland. Ein Beitrag zur Kenntniss der regionalen Gliederung an der polaren Waldgrenze. Acta Societ. Fauna & Flora Fennica 6(3): 1-263.

Kuusela, K. & Salminen, S. 1978. Koillis-Suomen metsävarat vuonna 1976 ja Lapin metsävarat vuosina 1970 ja 1974-76. Summary: Forest resources in the Forestry Board Districts of Koillis-Suomi in 1976 and Lappi in 1970 and 1975-76. Folia Forest. 337: 1-35.

Lakari, O.J. 1915. Studien über die Samenjahre und Altersklassenverhältnisse der Kiefernwäldern auf dem nordfinnischen Heideboden. Acta Forest. Fennica 5(1): 1-211.

Laki suojametsistä. (Act on shelter forests). 1922. Suomen asetuskok. 1922/196; 11.8.1922.

Lassila, I.K.D. 1920. Tutkimuksia mäntymetsien synnystä ja kehityksestä pohjoisen napapiirin pohjoispuolella. Referat: Entstehung und Entwicklung der Kiefernwälder nördlic vom nördlichen Polarkreise. Acta Forest. Fennica 14(3): 1-85.

Leikola, M. (edit.). 1979. Tutkimustoiminta Lapin metsien hoidon ja käytön suuntaajana. Summary: The role of forestry research in guiding forest policy and management in Finnish Lapland. Silva Fennica 13 (1A): 1-50.

Mattila, E & Kujala, M. 1980. Utsjoen, Inarin ja Enontekiön metsävarat 1978. Summary: Forest Resources of Utsjoki, Inari and Enontekiö, North Finland, in 1978. Folia Forestalia 436: 1-21.

Metsäojitus- ja metsänuudistustyöt; toimenpideraja. Metsähallituksen kirje no. A37/19-61. (Forest drainage and regeneration; The utmost limit of forest operations. Permanent letter by the National Board of Forestry, no. A37/19-61); 1961 (1965).

Mikola, P. 1952. Havumetsien viimeaikaisesta kehityksestä metsänrajaseudulla. Summary: On the recent development of conferous forests in the timberline region if northern Finland. Commun. Inst. Forest. Fenn. 40(2): 1-35.

Ohjekirje eräistä hakkuu- ja metsänhoitotoiminnoista Perä-Pohjolan piirikunnassa.1969. (Permanent letter on harvesting and silviculture in the District of Perä-Pohjola.) Metsähallituksen kirje Mh. 92: 1-14.

Ohjekirje metsittämisestä ja metsän uudistamisesta. 1978. (Permanent letter on afforestation and reforestation. National Board of Forestry). Metsähallitus, MH 130: 1-66.

Ohjekirje metsien käsittelystä Perä-Pohjolan piirikunnassa. 1981. (Permanent letter on managing forests in the District of Perä-Pohjola). Metsähallitus, MH 307: 1-33.

Ohjekirje metsien käsittelystä Perä-Pohjolan piirikunnassa. 1985. (Permanent letter on managing forests in the District of Perä-Pohjola). Metsähallitus, MH 110: 1-47.

Oinonen, E., Sarvas, R. & Sirén, G. 1961. Lapin suojametsien käsittelyohjeet. (Instructions to forest management for the Shelter Forest Area of Lapland). 1-23.

Pohjois-Lapin metsät. 1982. Metsäntutkimuspäivät Rovaniemellä 1982. (The forests of the northernmost Lapland). Metsäntutkimusl. tiedonant. 58: 1-51.

Renvall, A. 1912. Die periodischen Erscheinungen der Reproduction der Kiefer an den Polaren Waldgrenze. Acta Forest. Fennica 1(2): 1-154.

— 1919. Suojametsäkysymyksestä 1-6. Referat: Über die Schutzfrage. Acta Forest. Fennica 11. 1-671.

Sirén, G. 1960. Suojametsätutkimuksen nykyvaiheita ja sen tulevia suuntaviivoja. (The present day status and future development of research on northern shelter forests) Metsätaloud. aikakausl. 77: 83-85.

Suojametsäkomitean mietintö. 1910. (Report of the committee on shelter forests). Komiteanmietintö 7/1910: 1-243.

Valtioneuvoston päätös Lapin suojametsäalueesta. 1939. (Decision of the Government of Finland on the Shelter Forest Area of Lapland). Suomen asetuskok. 137/39; 4.5.1939.

Valtionmetsäkomiten mietintö. 1900. (Report of the committee on state forests). Komiteanmietintö 5/1900.

REFORESTATION EXPERIMENTS AT THE PINE TIMBERLINE IN NORTHERNMOST FINLAND

Gustaf Sirén

ABSTRACT. After a retrospect of reforestation efforts before 1950, the present-day experiments are reviewed. A Series of re- and afforestation pilot experiments initiated in 1951 along the road Kaamanen - Karigasniemi are demonstrated. Various site types at altitudes between 200 - 300 m.a.s.l. and north of the pine timberline were subjected to different reforestation measures. The influence of the solar activity cycle upon the recurrence of pine seed years is discussed.

INTRODUCTION

Research results from different disciplines indicate that climatic changes have caused both advances and retreats of the subartic and subalpine timberlines in the northern hemisphere. Compared to the present situation, the pine forests of the northernmost Finnish Lapland covered a much wider area during prehistoric as well as historic periods. In addition to the ecological causes, Man has contributed to the retreat of the forests. During the 18th and 19th centuries, the local population suffered from repeated famines to such an extent that people had to bake bark-bread and eke out their fish-soup with meal made of bast (phloem) of pine. Hundreds of thousands of young pine trees were thus used for the support of existence of the Lapps e.g. in the Utsjoki river valley.

Today the missing parts of the consumed age-classes in the age-class histogramme can still be recognized and easily observed in the landscape.

The earliest reforestation measures were carried out along the river valleys of Neiden (1911 - 14) and Utsjoki (1930 - 39). At lower altitudes about 100 m.a.s.l. the patch-sowing of pine resulted in excellent stands, especially along the Näätämöjoki (Neiden-river). Storms, however, had devastated a part of the stands of well shaped young pines since 1960. Along the Utsjoki river the altitude of the sown areas varied around 200 m.a.s.l. At high altitudes the results were usually poorer than at lower levels, with the exception of frost-exposed depressions. The most remarkable stands of sown pine can be seen on the west slope of the Petsikko mountain.

Since the beginning of the present century the climate in the North has improved considerably. Dr Ilmari Hustich was first to observe the tiny signs of change. After decades of no or only poor seed years pine seedlings appeared after the seed year 1937. Forestry people remained sceptical however. Not even new seed years in 1947 - 49 changed the pessimism. In 1951 I got the task to actively consider the problem of getting stable pine-seedling stands in the area between the tree-line and the present timberline.

INITIAL SITUATION

Within the tree line the landscape was characterized by large stands of mountain birch varying in density and height with scattered groups or single trees of pine. Because of fires and lack of pine seed trees and seed years large areas were covered entirely with birch. In these pseudo-tundra-areas artificial regeneration methods only seemed possible if a rapid change was wanted. Where pine trees were present a few seedlings from 1937 indicated that vegeta-

Gustaf Sirén, prof. emeritus, active as forest researcher in Finland during 1947 - 61 mainly in Lapland and 1977 - 78 at the Finnish Forest Research Institute. Since 1964 prof. of reforestation in Sweden and in energy forestry since 1973.

tion per se did not prevent the germination of seeds nor the stabilization of the seedlings. Old stands had usually emerged after wild fires. The trophic conditions of the moraine or sandy mineral soil was generally well reflected by the species composition and physiognomy of the vegetation. The best soils were usually covered with a thick raw-humus layer under canopies dominated by birch. Because of a very sparse network of meteorological stations before the war only extrapolations based on data from the Ivalo station (90±10 km to SE) were available for the compilation of climatic series. The growing season seemed short, cold and humid. Later collected data are in short: Mean length of growth period: 116 days, mean summer temperature: 11.4° C, mean annual precipitation: 386 mm/year and mean evapotranspiration is so far unknown. Coarse-sandy soils could now and then be very dry, while the bogs remained wet through the summers.

THE PILOT EXPERIMENTS

Because of the expected low productivity of the future pine forest, only cheap methods of re- or afforestation could be subjected to large scale experiments of pilot character. The first thing to find out was the efficiency of prescribed burning on the extremes of vegetation and humus. For the purpose two sites were selected: A fresh site of *Hylocomium-Myrtillus*-type (HMT) covered mainly by mountain birch + a few groups of pine (area I) and a dry heath land (ErCl-T) with scattered full-grown pines plus birch and only a few young pines or seedlings (area III). In both cases 50 % of the plots were burned in such a way that the seed trees left remained undamaged. The lay-out of the area I from 1951 - 53 is given in Figure 1 and that or area III in Figure 8.

After the relevant canopy treatments having been carried out, the entire area I was planted in 1951 with pine using a standard method. In spring 1952 an almost complete failure was noticed. A controlled burning-over was implemented in summer 1952. In spring 1953 both burned plots as well as control plots were sown with pine seeds of Lapland-origin. Inventories of the seedling stands have been carried out 1956, 1967 and 1986. On each 100 m^2 circular sample plot the treatment, presence of seed-trees and altitude m.a.s.l. were noticed. The most important variables were number of healthy and damaged plants, dominant plant height, number of birch bunches and coverage of herbs, grasses, dwarfshrubs, mosses and lichens. The data was processed at the Finnish Forest Research Institute by Jouni Ristioja.

The preparatory cut for regeneration experiment III on dry ErCl-T was carried out 1958. The number of seed trees per hectare was regulated to 15, 25, 35 and 55 stems per hectare respectively of the plots to be treated. The controlled burning destroyed the few seedlings from 1937 and 1949, the dwarfshrubs and the rather compact cover of lichens. A seed year appeared 1961 - 62. A 25 % line survey of the seedling stands using 100 m^2 circular sample plots was carried out 1986. The variables measured were number and height of healthy, damaged and dead plants, number of birch bunches and the dominant height of the healthy pine plants.

During the first visit to the Kaamanen area in early spring 1951 a dense pine seedling regrowth of 1 - 2 years age was observed under a medium dense birchcanopy with a few scattered pines of considerable age. This initial situation invited to ponder upon problems of the following type:

- What to do with the mountain-birch considering the risk of heavy litterfall in the autumn? Or the frost risk?
- Were the seed trees necessary anymore? If left untouched what was the immediate consequence for the existing 1 - 2 yr. old regrowth? After 25 years?
- What to do with the plantless patches under the canopy of the birch-bunches?

A four hectare large demonstration area (experiment II) was established in summer 1951 with the following treatments:

a) clear cut
b) pines removed, birch thinned to 1 - 2 stems per bunch
c) pines removed, birch left untouched
d) no measures, control

During 1957 - 67 an ecological station was in function in area II. Vertical temperature variation, precipitation, evaporation, wind velocity and growth of seedlings were measured on all plots (size 1.0 ha). Inventories of the stands were carried out 1957, 1967 and 1986. At the last inventory the variables of interest were stem number, stemdiameter at 1.3 m, height of trees, bark thickness, radial growth taper of pine, the projection area of the birch bunches as well as the mensuration variables of the birch. Basal area, mean and dominant height, volume, annual growth etc. were calculated using the standard programmes of the Finnish Forestry Research Institute.

The artificial regeneration experiments, including some large regular field experiments on the influence of the altitude will not be subjected to any deep-sounding discussion. The main results will be given in general terms only.




Figure 1. Lay-out of pilot expt-area I Hylocomium Myrtillus (Sieidevaare).

RESULTS

Regeneration of a birch-pine stand

Area I (Sieidevaare) HMT

On the pilot experimental-area I, natural regeneration was compared to patch sowing. The soil cover and stand treatments were respectively:

- prescribed burning of soil and control,
- clearing of mountain birch alternatively no clearing at all,
- natural seeding from seed trees versus artificial seeding.

The lay-out is shown in Figure 1. The plot size is 20 x 500 m^2 exposed to NE. The altitude increased from 225 to 285 m.a.s.l. The main results of the inventory can be seen in Figures 2 and 3.

The conclusions of the reforestation pilot experiment in area I on fresh HMT are in short:

- Compared with the untreated control plots prescribed burning has improved the ecological conditions of the soil surface in a most positive way for natural as well as artificial regeneration.
- Plant number after natural seeding is significantly higher than after artificial seeding, although number of 0-patches is surprisingly low on burned surface (10 % only).

- In unburned plots, clearing of the mountain-birch has improved the conditions of establishment of the germinating seeds very little when compared with the totally untreated control plots.
- The height-growth of the plants has been best on burned plots and poorest on control plots (Figure 3).
- The height difference between plants originating from sown seeds of N. Lapland provenance and plants of local origin despite the age difference is small (except on the control, where it is still significant).
- The effect of altitude appears from the function y = a + bx, where y = number of plants per 100 m^2 (=circular plot) x=altitude, meter a.s.l. l=a constant b=angle of inclination

The data available gave the function the form of y = 60.5 - 0.20x. If the plots of lowest part of the slope are excluded because of their badly burned humus layer the equation gets the form y = 107 - 0.357x. At an altitude of 300 m.a.s.l. the plant number is 0.

In addition to this it can be reported that the mean height of plants is significantly higher in the altitude 225 - 260 than above 260 m. Under the canopy of bunches of birch the number of pine plants is extremely low, whereas the number under pine seed trees is rather high, but the plant height low.

Because, of the geography of the excursion-route the other part of this pilot experiment (Area III) illustrating the effect of prescribed burning will be demonstrated at the third stop.




Figure 2. Plant number dependence of regeneration method and soil treatment.




Figure 3. Influence of regeneration method on the dominant height (H_{100}).

Care-taking of pine re-growth
Area II (Jäkälämorosto) ErClT

The lay-out of the demonstration expt. is shown in Figure 4. The main purpose was to obtain empirical experience of this cheap type of natural regeneration of pine. In the region there are tens of thousands hectares of mountain-birch stands with a few interpersed pines of seed tree character.




Figure 4. Alternate regeneration measures in the demonstration area II (Jäkälämorosto).

The 25 % line-survey using circular sample plots concentrated on measuring the standing stock, the current growth and the influence of the birch bunches upon the development of the pine stand. The inventory was carried out in early June 1986, which means that the present standing stock refers to the situation 1985. The main result is shown in Figure 5.

The figure reveals the present (1985) distribution of species and diameter at 1.3 m. In fact the distribution also depicts the age class distribution of pine quite well too. Almost all of the birches are suckers from 1951 or from later dates. The main part of the pine stand is from the seed year 1949 (<19 cm) while a considerable part of the standing stock of sample plot 3 originates from seed year (>19 cm). The remaining trees (>19 cm) are from about 1860.




Figure 5. Present standing stock.

According to the definition of low productive forest land, the limit has been set at a mean growth of 1.0 m^3 solid volume per hectare and year. At present the 36 year old part of the standing stock of pine has reached a level of 32 - 33 m^3 solid volume in the sample plots 1 - 3. Including the volume of both the mountain birch and a correctly reduced share of the older pine stand constituents the question arises whether the site of the experiment II still is representative for low-productive land. The current annual growth volume (about 2.5 m^3 s.v. ha^{-1} $yr.^{-1}$) indicates that an upward adjustment of the land use class may be justified soon — if the climate does not deteriorate rapidly too much (cf. Fig. 6).

The fourth sample plot has a stem number about 40 % lower than that of the other three plots 1 - 3. Mainly therefore, the annual growth is as low as 1.7 m^3 solid volume per hectare only.

Assuming an annual macroclimate more or less similar to that of the 1980's, the standing stock would increase to some 46 m^3/ha at an age of 40 - 41 years. Even considering the present variation between the plots it seems obvious that the mean annual increment will most probably exceed the upper limit of wood productivity for lowproductive land already at 1990.




Figure 6. Current growth of the demonstration stands.

In best case this upward adjustment of the land use class would theoretically imply the possibility of an increase of the productive forest land with a total of some 0.4 million hectares. However the corresponding annual addition to the total annual growth of the forests of Finland would be of the magnitude of less than 1 %.

It must be recognized in this context that the northward pushed timberline forests will still be managed according to the law of the protection forests.

Prescribed burning for natural regeneration
Area III (Roavvetsobma) ErCl-T

The pilot experiment I at Sieidevaare revealed from the very beginning the superiority of wisely used fire as an efficient tool in the efforts for obtaining successful reforestation results on a fresh site type. However, there are many considerations to be observed for avoiding mishaps - especially when burning for improved germination and seedling stabilization conditions for natural regeneration under a canopy of pine seed trees on dry sites. According to special studies (Sirén 1973) an acceptable outcome of slash burning under seed trees depends besides the weather of weeks passed mainly upon the height of canopy above the ground, the calorific value or amount of the slash under the trees, the groundcover and the humus to be burned as well as upon the undergrowth canopy of tall shrubs, suppressed trees and plants which usually have a damping down effect on the fire and finally on the solar radiation as well as wind conditions the afternoon, when the fire is set (cf. Table 1 and Figure 7).

Table 1. Regression functions for needle damage percentage pending upon x_1 = tree height, x_2 = slash amount and x_3 = standing brush under different conditions and at different hours of the day.

Time	T°C	R%	W m/sek	Functions
17–20	16	29	0–2	$\bar{x}_a = 18{,}48 - 1{,}50^{**}\ x_1 + 2{,}94^{**}\ x_2 - 0{,}50^{**}\ x_3$
15–17	18	27	2–6	$\bar{x}_a = 49{,}40 - 2{,}88^{***} x_1 + 2{,}80^{**}\ x_2 - 2{,}93^{***} x_3$
14–15	21.5	27	5–8	$\bar{x}_a = 75{,}70 - 3{,}30^{***} x_1 + 6{,}38^{***} x_2 - 1{,}38^{**}\ x_3$
13–14	21.0	29	3–5	$\bar{x}_a = 99{,}22 - 3{,}36^{***} x_1 + 4{,}76^{***} x_2 - 0{,}92^{*}\ x_3$

The clearing of slash around the seed trees is a categoric imperative for saving the cambium from damages. In this case the cleared area had a radius of 5 m.

The use of fire on dry as well as dryish sites has often been subjected to critical debate

among biologists, foresters etc. (Uggla 1967). The finding of the antagonistic influence of lichen on the germination process of pine-seed (Oinonen pers comm 1955, Brown and Mikola 1974) finally persuaded about the advantages, provided that the thin humus layer of dry sites was not too heavily burned. To this end a simple practical method was developed.

Time	Functions	Lower limit of crown, m (damage = 0%)
17-20	$x_0 = 22{,}1 - 2{,}09^{**} x_1$	10,6 m
15-17	$x_0 = 43{,}2 - 4{,}14^{***} x_1$	10,4
14-15	$x_0 = 94{,}3 - 7{,}03^{***} x_1$	13,5
13-14	$x_0 = 99{,}0 - 3{,}28^{**} x_1$	30,4




Figure 7. Regression functions for lower limit of undamaged needles of seed trees subjected to prescribed burning under conditions given in table 1 (Sirén 1973).

In order to demonstrate the differences between natural regeneration in an undisturbed cover of lichens and a carefully planned prescribed burning a light surface fire was applied on 50 % of the seed tree area. In addition to this — for elucidating the problem of the sufficient number of seed trees per hectare, the efficient coverage of the pine trees left on the experimental plots was arranged as appears from Figure 8. No regulations regarding seed tree number were carried out in the control plots.

The prescribed burning was carried out in summer 1959. The summers of 1959, 1960, 1961 were warm enough to produce an excellent cone year 1961. The present-day plants are from the seed year 1961 - 62, although some seedlings from 1972 - 73 do exist. One seedling only from the year 1984 was detected just outside the area III.




Figure 8. Lay-out of demonstration experiment area III.




Figure 9. Plant number as function of number of seed trees on dry heathland (ERCLT) at the timberline in Northernmost Finland.

The seedlings and plants from 1937 and 1949 were removed as well as possible from the control plots in 1959 in order to obtain a good comparability regarding the regeneration process in all parts of the experiment. The results of this experiment are given in Figures 9-11 and Table 2.




Figure 10. Mean height of plants as a function of seed tree number per hectare. The bar at the top indicates the standard deviation.

According to observations made on empty cones and number of seedlings in 1966 the seeding capacity of the seed trees has been quite extraordinary in the expt-area III. However, 11 - 12 years (1977 - 78) snow blight was observed especially in the seedling stand of the sample plot 35 seed trees/ha. Still visible signs of camping fires and ski-tracks explain additional losses after 1980 in the same plot (closest to the gate in the snowfence).

The most important results have reference to the differences between the treatments in the number, vitality, height and homogeneity of the seedling stands. The answer to the problem on effect of treatment has been obtained as a result of a test according to Tukey based on an analysis of variance.

The differences proved a good confidence at a level of 99 %.

Treatments	No treatment	Prescribed burning
Mean number of plants, $N.Ha^{-1}$	3008	6694
Number of observations	150	196

The prescribed burning of the slash and ground cover has resulted in more than twice as many plants than leaving the lichen-dominated ground cover untreated. A closer look on the variation between the four different seed tree plots reveals two interrelated results. With the exception of the 35 seed tree plot the variation of the number of plants (cf. Figure 9) seems logical and in good agreement with results obtained from pine forests to south of the timberline (Sirén 1966). This applies to the mean height of living plants too (Figure 10). Due to the growth reducing effect of the seed trees upon the nearest seedlings (cf. Figure 11) the great number of suppressed seedlings still alive on the 55 seed tree plot has its bearing on the mean height. At present the optimum number of seed trees seems to be about 25 individuals per hectare. Considering the low risk of wild fires in seedling stands established after prescribed burning, it seems possible to remove the seed trees at an early date promoting the structure of the future stand.

The homogeneity of the stand is of great importance considering the volume production. The longer the seed trees are overheld the greater the variation in height will develop. Close to the experiment area II openings with a radius exceeding 12 m are frequent around the oldest seed trees.




Figure 11. Plant height dependence of distance to nearest seed tree.

The comparison of mean and dominant height of the two treatments reveals that the difference between mean heights is far less than between dominant heights i.e. the 2 000 highest trees per hectare. The averages of the above differences are 14.4 cm and 40.5 cm respectively in favour of the plants of the burned area. A closer view of the test result of the dominant height differences is shown in Table 2. The difference between the compared treatments is highly significant. However, Tukey's test indicates that comparison between the individual plots has resulted in a slightly more complicated picture.

Table 2. Analysis of variance of dominant height of plants indicating the effect of prescribed burning.

Source of variation	Sum	Degrees of freedom	Square sum	F-value	Probability
Between treatments	71603.63	6	11933.938	4.91 ***	99.963 %
Within treatments	148288.63	61	2430.96		
Total	219892.25	67	3281.97		

Significant differences (Tykeys test)

Plots compared		Mean values		SD	W	Diff.	Signif.
1	2	143.200	206.000	15.59	60.950	62.800	o
2	3	206.000	134.900	15.59	67.181	71.100	*
2	5	206.000	96.000	15.59	79.953	110.000	**
2	6	206.000	115.556	16.02	82.144	90.444	**

OTHER EXPERIENCES OF REFORESTATION

In total ten rather large experiments were laid out between 1951 and 1964. In addition to the results reported above, some interesting experiences have been gained from the rest of the field experiments. The conclusions today are in many cases different from those presented at the UNESCO excursion in 1965. From practical point of view the most useful experiences are as follows:

- natural regeneration is — in addition to use of fire — promoted by a light 2 - 5 cm deep scarification of the soil surface of dry and dryish sites. This method will save the lichens, important for the reindeer-husbandry. The reindeer-pasture in wintertime will on the other hand reduce the chance of survival of the seedlings. — Fire used correctly from the ecological point of view has promoted the germination of seeds and stabilization of the seedlings everywhere on firm land (see Figure 12). Slopes with instable surface should not be sown.




Figure 12. Performance of pine seedling stands established during the period of 1948-59 in Southern and Central Lapland on burned and unburned clear cut areas. The material consists of some 80 sowing areas.

- sowing as well as planting with small to tall rooted plants or bare-root plants has failed where standard patches have been prepared on fresh sites with a thick humus cover
- on dry sites sowing has proved safer than planting, provided that leaf fall of birch has not covered the seedfurrows. Deep ploughing on sandy soil is expensive and totally useless. Above 280 m.a.s.l. all artificial afforestation efforts failed, above 260 m the result was unsatisfactory.
- of the planting methods and choices of plant materials, the tall pine plant (1+1 yr.) in a large pot (>6 cm) planted on dryish sites with modern hand planting tools gave the highest survival. Expensive.
- in the humid conditions of the far North the planting depth of potted plants may vary — for survival — from two thirds of the pot height to a deep burial up to the first whirl of lateral shoots. Carelessly planted rooted plants will frequently survive but will later on succumb by instability. Planting in springtime has resulted in the highest survival.
- provenance tests have confirmed the superiority of the local pine provenances
- the use of the mountain birch as a frost shelter seems justifiable in frost-hallows only. On slopes where sowing of pine will be used the birch storey must be removed before sowing for saving the seed from lethal burial. Experiments on reduction of sprouting have failed because of clearings for construction of electric lines just over and along the row of exptal. plots. The mountain birch is an excellent fuel.

THE SEED YEAR PROBLEM

A well known fact is that the temperature is the most important ecological growth regulating factor at the northern timberline. From pine tree ring series it has been possible to track the variation of ring width. A few years of wide rings often coincide with the time of regeneration of pine (Sirén 1961). Since 1937 there has been good cone-years in 1947 - 49, 1961 - 62, 1972 - 73 and 1983 - 84. Usually these years have been preceded by 2 - 3 years with favourable temperature conditions. This phenomenon coincides more of less clearly with the solar activities, which varies with the same intervals of time (in average 11 - 12 years) as the cone years of pine. The efficient seed years do not vary with the same regularity. According to the available information on the volcanic activity the solar radiation has now and then been intercepted by volcanic dust, cloudiness etc. just a year or two before the maximum period of solar activity. The consequence of this interception has so far been a temporary summer cool spell lasting for a couple of years. Thus energy requiring processes such as the development of the primordials of flowers, the flowering itself, the conception, cone and seed de-

velopment, and finally the ripening of the seed have been prevented.

The connection between the solar activity cycle and the recurrence of the cone years at the northern timberline seems evident nowadays - as well as the disturbances of the seed years caused by the eruptions of the volcanos. Of the vast literature in the matter the works of Budyko 1974, Pohtila 1980, Lindblad 1980, Swedish Society of Physics 1980 and Bolin et al. 1986 are of great interest.

SUMMARY

The practical consequences of the experiments carried out and of the above solar activity phenomenons are in short as follows:

- the ongoing improvement of the temperature climate in the far North has resulted in rather regular recurrence of cone years of pine since 1937 coinciding well with the maximum activity of the solar cycle. The warm spells create also conditions for application of prescribed burning as a successful soil treatment method.
- natural regeneration of pine has been good in the years of 1937 and 1973 and excellent in the years 1947 - 49 and 1961 - 62 provided that soil surface conditions have been favourable enough. Prescribed burning under seed tree stands have resulted in vital pine seedling stands. Seed trees have been removed from 2-year old seedling stand without fatal consequences for the young plants on dry site types.
- sowing has been a more reliable regeneration method than planting. For avoiding losses of developing 1 - 2 year seedlings the litter of birch leaves must be reduced to a necessary extent.
- planting of pine is seldom recommendable even on rather open birch-covered dryish or fresh sites; only after prescribed burning of the humus to a reduced thickness acceptable results have been obtained with tall potted plants of local origin.
- because of the long seed year interval natural regeneration should be promoted by applying prescribed burning over areas corresponding to the planned reforestation activities of at least 3 - 4 years. Local seed should be collected when abundantly available and used for sowing dry and/or dryish sites where soil preparation is unnecessary or sufficiently cheap during the seedless years.

LITERATURE USED

Bolin, B. et al. 1986. The greenhouse effect, climatic change and ecosystems. SCOPE J. Wiley & Sons.

Brown, R.T. & Mikola, P. 1974. The influence of fruticose soil lichens upon the ,mycorrhiza and seedling growth of forest trees. Acta For. Fenn. 141.

Budyko, M. 1974. Climate and life. Acad. Press London.

Hustich, J. 1940. Tallstudier sommaren 1939 i Enare och Utsjoki. Acta Soc. pro F. Fl. Fenn. 62(6): 1-76.

— 1948. The Scotch pine in northernmost Finland and its dependence on the climate in the last decades. Acta Bot. Fenn. 42: 1-76.

— 1958. On the recent expansion of the Scotch pine in Northern Europe. Fennia 82(3): 1-25.

— 1978. The growth of Scots pine in Northern Lapland, 1928-77. Ann. Bot. Fennici 15: 241-252.

Kuusela, K. 1975. Suoja- ja lakimetsien puusto ja kasvu. Metsä ja Puu 2: 8-9.

Lindblad, B.A. 1980. Solära terrestra relationer. Solen. Kosmos 1980 bd. 57. Svenska Fysikersamfundet.

Mikola, P. 1952. Havumetsien viimeaikaisesta kehityksestä metsänrajaseudulla. Summary: On the recent development of coniferous forests in the timberline region of Northern Finland. Commun. Inst. For. Fenn. 40(2): 1-35.

— 1959. Metsänviljelyn mahdollisuuksista pohjoisella metsänrajalla. Summary: Afforestation trials at the polar timberline. Metsätal. Aikak. 1. 76(11): 374-379.

— 1971. Reflexion of climatic fluctuation in the forestry practices of Northern Finland. Rep. Kevo Subarctic Res. Stat. 8: 116-121.

Nuorteva, M. 1948. Metsänviljelyä männyn metsänrajan pohjoispuolella. Metsätal. Aikak. 1. 65(1-2): 14-16.

Oinonen, E., Sarvas, R. & Sirén, G. 1958. Lapin suojametsien käsittelyohjeet. Moniste.

Pohtila, E. 1980. Climatic fluctuations and forestry in Lapland. Holarct. Ecol. 3: 91-98.

Renvall, A. 1912. Die periodischen Erscheinungen der Reproduktion der Kiefer an der polaren Waldgrenze. Acta For. Fenn. 1: 1-154.

— 1919. Mäntymetsän elinehdot sen pohjoisrajalla sekä tämän rajan alenemisen syyt. Suojametsäkysymyksestä 1. Acta For. Fenn. 11: 1-143.

Sarvas, R. 1970. Temperature sum as a restricting factor in the development of forest in the Subartic. Ecology and conservation 1. Ecology of the subartic regions. Proc. Helsinki Symp. 1966: 79-82.

Sirén, G. 1955. The development of spruce forest on raw humus sites in Northern Finland and its ecology. Lyhennelmä. Acta For. Fenn. 62: 41-355.

— 1958a. Hajapoimintoja Lapin metsien tulevaisuudesta. Terra 2: 57-69.

— 1958b. Lapin suojametsäkysymyksestä. Moniste. (Stencil in Finnish only 1-70).

— 1960. Suojametsätutkimuksen nykyvaiheita ja sen tulevia suuntaviivoja. Metsätal. Aikak. 1. 77(3): 83-90.

— 1961a. Skogsgränstallen som indikator för klimatfluktuationerna i norra Fennoskandien under historisk tid. Summary in English. Commun. Inst. For. Fenn. 54(2): 1-66.

— 1961b. Taka-Lapin metsien historiasta ja ilmastosta historiallisena aikana. Synopsis: On the history and climate of forest in Northern Lapland during the historical time. Lapin tutkimusseuran vuosikirja 2: 29-47.

— 1973. Some remarks on fire ecology in Finnish forestry. Proc. Ann. Tall timbers fire ecology conference. Tallahassee. Florida.

— & Hari, P. 1971. Coinciding periodicity in recent tree rings and glacial clay sediments. Rep. Kevo Subarct. Res. Stat. 8: 155-157.

— & Hari, P. 1972. Influence of some ecological factors and the seasonal stage of development upon the annual ring width and radial growth index. Rapp o Upps nr 40: Inst of reforestation. Royal Coll. Forestry.

Uggla, E. 1967. En studie över bränningseffekten på ett tunnt råhumustäcke. Summary: Effects of the fire on a thin layer of raw humus. Svenska Skogsvårdsförb. Tidskrift nr 9.

POSTERS

COMPETITION CONTROL WITH PRONONE (GRANULAR HEXAZINONE) APPLIED IN WINTER

F.W. von Althen, J.E. Wood and
R.A, Campbell

Competition from herbaceous weeds and grasses is a serious problem in the reforestation of boreal mixedwood cutovers. The virgin stands of this forest type consist mainly of white spruce (*Picea glauca* (Moench) Voss, black spruce (*Picea. mariana* (Mill.) B.S,P.), trembling aspen (*Populus tremuloides* Michx.) and white birch (*Betula papyrifera* Marsh.). The soils are characterized by an organic layer, less than 30 cm deep, over well drained to moderately well drained, stone-free, fine loamy clays or silt loams. The most common method of site preparation is shearblading in winter. It consists of the removal of slash and stumps by bulldozer blade in corridors 4 m wide alternating with windrows of debris of the same width.

To determine the feasibility of winter application of herbicide, its effectiveness in competition control, and its effect on crop tree survival and growth, Pronone 5G and 10G (5 % and 10 % a.i.) was applied at 2 and 4 kg a.i./ha in February 1985 in shearbladed corridors. Black spruce 1½ + 1½ transplants and seedlings in FH508 Japanese paperpots were planted in June 1985 and 1½ + 1½ transplants and seedlings in FH408 paperpots were planted in July 1985.

Application of Pronone at both rates greatly reduced the density and vigor of the herbacous competition and had no phytotoxic effects on the planted spruce. After two growing seasons survival was 96 % or better for all planting stock except the FH408 paperpot seedlings planted in July in plots treated with 4 kg a.i./ha of Pronone 10G.

Second-year height increment of both stock types was significantly higher in the Pronone-treated plots than in the controls. The highest increment always occurred in the plots treated with 4 kg a.i./ha of Pronone. Season of planting had no effect on the height increment of the seedlings planted in paperpots, but summer planting greatly reduced the height increment of the transplants.

FIELD GUIDE TO FOREST ECOSYSTEMS OF WEST-CENTRAL ALBERTA

I.G.W. Corns

A forest-ecosystem classification for a west-central Alberta study area was designed using vegetation, soil, and forest productivity information to describe 30 ecosystem associations. Management interpretations were made for harvest season and method; site preparation intensity; soil compaction, puddling, and erosion; reforestation species, method and limitations: frost heave; type and severity of vegetational competition; windthrow; snowshoe hare damage; and potential site productivity in site index and mean annual increment. Colour photos and drawings are presented for 80 common forest plants.

THE LARCH AND THE OTHERS — A COMPARISON

Max. Hagman

Larch has been suggested as an alternative to native tree species in hard northern conditions.

Here are given some results from comparative species trials where larch has been compared to Scots pine and Norway spruce as well as to other exotics such as Lodgepole pine, White and Black spruce.

Survival is reported from 3 experimental series (373, 555 and 558) up to an age of 11 years.

In the oldest experiment 373 the survival of the Siberian larch, 40.8 %, is slightly better than that of Scots pine, 37.6 %. The best larch provenance has a survival value of 49.6 % and the best pine 52.7 %. The survival of the best origin of Lodgepole pine is 52.2 %.

In the younger trial 558 the survival percentages for Siberian larch and for Scots pine are 52.9 % and 56.1 % respectively. Lodgepole pine from Yukon has survived 74.0 % and Black spruce 73.0 %. Local Norway spruce has a survival of 73.5 %.

In the trial 555 there is only one origin of Tamarack with a survival of 39.0 % to be compared with Scots pine 33.1 %, Norway spruce 67.5 %, White spruce 41.8 % and Lodgepole pine 48.3 %.

Mean heights are reported from the same experiments.

In the trial 373 the mean for Siberian larch is 3.0 m, for Scots pine 3.1 m and for Lodgepole pine 3.4 m.

In the trial 558 the mean height of the best larch is 1.4 m and the best Scots pine 1.6 m. The best Lodgepole pine is 1.9 m and the best Norway spruce is 0.9 m. A black spruce origin from Yukon has the good height of 1.2 m.

In the trial 555 the Tamarack has reached 1.6 m, the best pine 1.5 m and the best Lodgepole pine 1.8 m. Norway spruce and White spruce have both reached 0.9 m.

CONCLUSIONS

The promised superiority of larch is not obvious in these experiments. Great care should be taken to match species and site conditions. The importance of the right origin and provenance must be stressed. It is too early to make prognoses about total yield. Further trials are needed with northern origins of Siberian and Dahurian larch, Tamarack, Black spruce and Alpine fir.

THE INFLUENCE FROM SCARIFICATION UPON THE INWINTERING PROCESS IN PINE

Mats Hagner

In Northern Sweden ten year old pine, planted in plowed tilts and in furrows after disc trenching, were studied. Tree heights were 1.4 m, 1.1 m respectively. The degree of inwintering was estimated using the bark colour of the terminal (August) and the colour and shape of the needle base (August).

In both scarification methods the smaller trees showed a higher degree of inwintering than the taller. In a multiple regression analysis the result showed that the genotype and the environment seemed to have an equally great impact upon the inwintering process. This indicates that the increased growth obtained by plowing delays the hardening off. This may be one reason to the large mortality among trees in the plowed plots.

The results are somewhat uncertain and the investigation should be repeated.

ESTABLISHMENT OF PINUS CONTORTA WITH FOUR SITE PREPARATION TREATMENTS ON FOUR SITES IN JÄMTLAND

James Hunt

Swedish University of Agricultural Sciences, Department of Silviculture, M. Sc. Thesis.

Establishment of *Pinus contorta* with 4 site preparation treatments on 4 sites in Jämtland.

INTRODUCTION

This work summarizes inventory results of the establishment phase of the project, "the future productivity of site preparation". The project aims to investigate the influence of site preparation methods on sites' long term productive capacity. Joint short term studies by a number of departments at the Swedish University of Agricultural Sciences and Umeå University (*) include seedling survival, growth and damage in relation to soil temperature, moisture and morphology as well as the breakdown of organic material and the availability of stored nutrients within the seedligs' root zone. Inventory results of survival, height and damage for the initial 5 years are presented here.

METHODS

Plots were laid out in north central Sweden on four sites within a 6 km radius. Four principally different site preparation methods as illustrated in Figure. 2 were used at each site. Four different site types, a dry poor heath type (Bole): a fresh normal blueberry type (Rätan): a moist blueberry type (Nästelsildret), and a rich wet herb type (Östbodarna) were chosen. Site characteristics are described. The plots are 50 m^2 including a 10 m buffer strip with 180 to 225 seedlings per net plot depending on the site type. The experimental design 18 a randomized block except at Östbodarna which has a systematic layout as shown.

The sites were harvested in early 1981 and site prepared in the autumn of 1981. 1-0 Koppparfors containerized seedlings of *Pinus contorta*, provenance Wonowon (lat. 56, long. 121, elev. 900 - 920 m.) were planted. *Pinus sylvestris* and *Picea abies* were included at Östbodarna, the rich, wet herb site. The untreated plots were planted in the summer of 1981 with Hagner's PUM (planting without site preparation) casings. The site prepared plots were planted the following year to reduce the risk of weevil (*Hylobius abietis*) attack and to allow the plowed berms and mounds to settle. Damage by weevils, frost and voles necessitated supplementary planting over the 4 years following establishment. The untreated plots were inventoried in 1983 and 1985 and the site prepared plots in 1982, 1983, 1984 and 1985.

RESULTS

At Bole, the site prepared plots were heavily attacked by Hylobius abietis in the initial years. Severe damage occurred on 64 to 93 % of the site prepared plots with plowed plots sustaining the least damage. No other major damage causes were recorded in 1982. The PUM casings of the untreated plots provided effective protection against weevils, however, Hagner reported about 50 % mortality due to frost in the first season. Weather continued to strongly impair seedling development such that only 14 % of the untreated seedlings were undamaged in 1985.

At Rätan, there was some severe weevil damage in 1983 and moderate vole damage in 1984 and 1985. Pinus contorta had shown a strong capability to recover from injury and

(*) Joint studies include the Departments of Silviculture, Forest Soils and Forest Site at the Swedish University of Agricultural Sciences and the Department of Forest Production at Umeå University.

plant development was not greatly impaired unless the damage was very severe.

Likewise at Nästelsildret, there was a heavy weevil attack (ca. 80 % site prepared seedlings severely damaged) in 1983 followed by moderate vole damage. The site prepared plots showed good recovery though the untreated plots were further impaired by weather damage leg. frost, desiccation).

Damage at Östbodarna was initially small though in 1983, 51 % of the untreated seedlings and up to 84 % of the plowed seedlings were severely damaged, mostly by weevils or competing vegetation. Vole damage was moderate in all treatments. Later the most damage occurred in the plowed and untreated plots with heavy competing vegetation. There is a gradient in site qualities at the Östbodarna site such that the untreated plots are drier with relatively thin humus while the plowed plots are wetter and have thicker humus. This site gradient combines with the systematic layout to confound the treatment effects and limit comparisons of treatments. Pairwise treatment comparisons at Östbodarna indicated that plowing and mounding had meaningfully better survival than disc trenching.

DISCUSSION

At Bole, the dry poor heath type site, plowing gave superior survival and height growth: nontreatment gave clearly inferior results while mounding and disc trenching gave similar medium results. Plowing provided a good selection of favourable planting spots with increases in soil temperature, and some retention of moisture and liberation of nutrients in the overturned humus. The high degree of bare ground exposure in the plowed plots on the poor site type may have hindered weevil attack as well. However, it is questionable if the positive effect of plowing will persist on the poor site type.

At Rätan, the site representative of the most common Swedish site type, there was little difference between treatments though survival was a little better with mounding, and height increment was poorest with non-treatment.

At Nästelsildret, the moist blueberry type site, there was almost no difference between site preparation treatments though performance of the untreated seedlings was unsatisfactory.

At Östbodarna, the richest site, with heavy competing vegetation, the best survival, height and growth were obtained with mounding and the worst results with disc trenching. The untreated plots gave relatively good results but it should be noted that these plots are one year older and are situated on the driest part of the site with less intensive vegetative competition as other plots.

CONCLUSIONS

The short term results from this experiment suggest that differences between site preparation methods (mounding, plowing and disc trenching) are fairly small on medium or good site types. Planting without site preparation gave inferiour results, except on the rich site. Differences between treatments were greatest on the poor site type. The best results were obtained in site preparation treatments with elevated planting positions. A longer time period should elapse before firm trends in treatment effects are considered.

PROPERTIES OF LARIX IN FINNISH SAWMILLING INDUSTRY

R. Juvonen

The preliminary results are included in the research "The production and use properties of larch in the mechanical wood industry". The research deals with the sawing, seasoning, planing, gluing and strength properties of larch timber, the problems in them and their reasons. The results to be presented concern the seasoning and planing properties of sawn timber of *Larix sibirica* and *Larix desidua* felled from planted stand from Southwest-Finland.

Three seasoning experiments were done, preliminary seasoning tests for larch and spruce boards and warm-air and hot-air seasoning for centre goods of larch. The planing property examined was the surface smoothness, when the variables in planing were the feed speed, working depth and moisture content.

According to the preliminary seasoning tests the drying time for larch is clearly longer than for spruce.

The most important seasoning defects of larch were the twist and other deformation defects of sawn timber. The twist was greatest in centre goods sawn from the pith. The main reason for twist is the great spiral grain of larch.

The cracking of larch was in seasoning a smaller problem than expected. The cracking was about equal in larch and spruce boards. In seasoning of centre goods especially the cracking of pith was great and in hot-air seasoning appeared inner shakes, which were long and deep.

The resinousness of larch causes most of the problems in sawing. The resin fastened on saw blades and feed rollers. In seasoning the boiling of resin, especially around dry knots was typical for larch. In hot-air seasoning the resin also got dark.

In warm-air seasoning changes in colour of larch timber were small, but in hot-air seasoning sawn timber got dark and variegated.

The surface smoothness of larch boards after planing does not differ much from the surface smoothness of spruce. The greatest problem in planing larch was the loosening of dry dark-edged knots, to which the feed speed and the working depth had no effect.

The research continues and a specially attention will be paid to the developing of a suitable drying schedule for larch timber.

INTRODUCTION TO KOREAN PINE FOREST IN THE NORTHEAST CHINA

Li Jing-wen

The mature Korean pine forests hold a vital base in timber production and other benefits in China, They have made and will continue to hold a special place in the affections of Chinese people.

1. Habitat conditions

Korean pine (*Pinus koraiensis*) occurs usually with several hardwoods forming mixed stands, so generally to refer it as Hardwood-Korean pine forests. Their total range is limited with a narrow belt of Northeast Asia along west coast of Japan Sea with latitude 40° - 52° and longitude 126° - 140°. In Northeast China, hardwood-pine forests distribute from Changbai Mts. in south to Lesser Xing'an Mts. in north, respectly ranging between 500 - 1 000 m and 300 - 700 m in elevation, close to the subalpine coniferous forest upwards. The annual average temperature from 0° - 8° C, annual precipitation range from 600 - 1 000 mm, of which 70 - 80 % in June to August. The frost-free period average from 100 - 180 days, but usually between 100 - 130 days. Hardwood-pine forests are confined largely to dark brown forest soil. They can maintain themselves on gravelly soil where other species scarcely can survive, but they grow best on well drained loam soil.

2. Forest types and principal species

The hardwood-pine forests of China are divided into two sub-regions: Changbai Mts. mainly located at Jilin province and Lesser Xing'an Mts. at Heilongjiang province. In the latter sub-region, there are four major climax forest types, i.e. *Pinus-Quercus*, *Pinus-Tilia*, *Pinus-Betula*, *Pinus-Picea-Abies* and others. In these forests, all the principal tree species of north forest are found: *Pinus koraiensis*, *Picea koraiensis*, *Picea jezoensis*, *Abies nephrolepsis*, *Larix gmelini*, *Quercus mongolica*, *Tilia amurensis*, *Acer mono*, *Fraxinus mandshurica*, *Ulmus propinqua*, *Phellodendron amurense*, *Betula platyphylla*, *Betula costata* and *Populus davidiana* etc. Shrubs usually include following genus: *Corylus*, *Lonicera,-Ribes*, *Rubus*, *Grossularia*, *Rosa*, *Deutzia*, *Philadelphus*, *Elutherococcus*, *Sorbaria*, *Viburnum* etc. Herbaceous plants are luxuriant. Hardwood-Korean Pine Forests have many similarities with those in the Eastern United States.

3. Succession

The hardwood-pine forests have been considered as the climax communities limited by regional climate. Although climax forest are not easily displaced by other vegetation, logging and fire have played an important part in the successional status and composition of them. Complete removal of these stands by logging or fire resulted in such drastic environmental change that Korean pine and its associates were replaced by birch, aspen or shrub and grass communities. The kind of vegetation initially occupying the site will pass through different length of time to end to the corresponding climax types.

4. Reproduction

Since the early century, the hardwood-pine forests have suffered severely from overcutting and fire. The effect of which has been to substitute birch-aspen and other undesirable species for conifers on the open areas. Existing volume of mixed forests is largely in hardwood trees and many stands lightly stocked on the partial cuts. The virgin mixed forests undisturbed mainly remain in the nature reserves. Several approaches to reproduce Korean pine have been used: (1) planting method for establishing pine on open land; (2) introducing pine in areas occupied by birch-aspen stand with seeding and planting beneath; (3) adopting improvement cuttings to rehabilitate the degraded forest with natural and artificial regeneration.

FIELD EXPERIMENTS ON SITE PREPARATION AT THE DEPARTMENT OF SOIL SCIENCE, FINNISH FOREST RESEARCH INSTITUTE

Kaarina Niska

An extensive series of soil tilling and fertilisation experiments was started in 1975 in co-operation with the National Board of Forestry. The field experiments were established on areas with different climatic conditions, first in Northern Finland on areas difficult to reforest. The aim was to study long-term effects of tilling with treatments representing different intensity levels of timber production.

A split-plot experimental design was employed in which the main treatments are the three tilling methods, and the subtreatments fertilization at four different levels. The size of each sample plot is 50 x 50 m. There are four replications in each experiment. One experimental area is about 12 hectares.

The prescribed burning and tilling experiments which started in 1977 in southern part of Finland uses the same split-plot method. The main treatments are burned and unburned sites and the subtreatments are three soil tilling methods.

The research reports concerning seedling performance in these experiments in the following:

Levula, T. & Heikkilä, R. 1979. Rovaniemen tutk.as. tied. 18: 1-12.

— 1982. Metsäntutk.lait. tied. 11: 1-12.

Starr, M., Levula, T. & Heikkilä, R. 1982. Metsäntutk.lait. tied. 51: 1-ll.

Mälkönen, E., Niska, K. & Levula, T. 1987. IUFRO Working Party S 1.05-12, Grand Praire and Dawson Creek, Canada. 1986 (in prep.)

Niska, K. & Levula. T. 1987. Metsäntutk. lait. tied. 253: 99-108.

SITE PREPARATION, FERTILIZATION AND DRAINING OF FOREST LAND IN FINLAND

Aulis Ritari

SITE PREPARATION

Before the 1950's site preparation, in connection with the reforestation was manual exposing of mineral soil with a hoe. This was first replaced by horse-drawn scarifiers and later by tractor-drawn versions. Prescribed burning which was taken into extensive use already in the 1920 - 30's was based on the positive experiences of the era of swaling. A new rise in the use of prescribed burning was seen in the 1950's after the second world war.

During the 1960's burning gave way to mechanical site preparation. Ever since there has been a continuous development of the tilling methods and tools. In recent years the main methods have been ploughing and disc tilling. During this decade prescribed burning has been favoured again especially in northern Finland.

FOREST FERTILIZATION

Forest fertilization started in Finland in the mid 1960's. On mineral soil sites fertilizers have mainly been given to forests approaching the stage of end cutting in the form of nitrogen and phosphorus. On peatland sites fertilization is normally done in connection with drainage using potassium and phosphorus fertilizers. The state supports forest fertilization according to an accepted plan up to the limit set by the temperature sum 800 d.d. -units.

Until recently, manual spreading was the most widely used method. In addition to operating methods using aircraft, mobile machines operating on the ground have been used to a greater extent in recent years.

FOREST DRAINAGE

Forest drainage was first started in the 1910's on state land; on private land it began to get state support in 1929 when the first Forest Improvement Act was passed. Nowadays forest drainage is given support up to the temperature sum of 750 d.d. depending, however, on the peatland type.

Until the 1950's the forest ditches were dug manually. In the mid 1950's large ditch plows drawn by heavy tractors were taken into use. Since the mid 1960's hydraulic tractor diggers have been the main machines.

It is estimated that the first drainage will be finished in the 1990's; thereafter the emphasis in drainage work will be on maintenance.

LONG-TERM EFFECTS OF PRESCRIBED BURNING ON SOIL CHEMISTRY

A review of the results in P.J. Viro (1969)*

Aulis Ritari

During prescribed burning the surface vegetation, slash and part of the humus layer are burned up. This causes changes in a number of the physical and chemical properties of the soil, some lasting for decades. The present study examines the fire-induced variations in soil chemical properties in respect to time and profile depth. The material was collected from 92 burned and 92 unburned plots in southern end central Finland. The forest sites included *Vaccinum-Myrtillus*-type (54), *Myrtillus*-type (29) and *Oxalis-Myrtillus*-type (9). For details of the methods and material the reader is invited to see the original text.

RESULTS AND DISCUSSION

Acidity (humus layer)
The decrease in acidity was on the order of 2 pH-units, i.e. 100 times H^+ -ion concentration (pH 4 -> pH 61. The change was still noticeable after 30 years.

Organic matter (humus layer)
Burning caused a decrease of 7 tons/ha (24 % of the total amount) in organic matter of the humus layer. The burned material was mostly slash and surface vegetation, The humus layer started to increase in thickness again after 10-20 years.

Nitrogen, (humus layer)
Total nitrogen in the humus layer decreased by approximately 100 kg/ha (25 %) during burning. The recovery was very similar to that of the organic matter. In the mineral soil there was no detectable change.

Ammonium nitrogen content of the incubated samples started to decline one year after burning and the quantity was lower than on the unburned plots for 12 years. The nitrate content, however, was clearly greater on recently burned sites. This condition lasted for about 10 years.

Total nutrients (humus layer)
After burning the total quantities in the humus layer were higher for calcium and magnesium and lower for potassium, natrium and phosphorus. This indicates that the alkali metals and phosphorus are poorly fixed to humus material and a definite loss may result.

Exchangeable and easily soluble nutrients (soil profile)
With the exception of potassium and sodium the exchangeable nutrients in the humus layer in the year of burning were greater in quantity on the burned sites than on the unburned ones. Leaching attained its maximum in about 10 years. The higher concentrations in the uppermost mineral soil at the same time for potassium and phosphorus indicated that most of these elements were retained within the solum. Burning caused a redistribution of the nutrients in the soil profile without any great losses of exchangeable potassium or easily soluble phosphorus in the long run.

*Source: Viro, P.J. 1969. Prescribed burning in forestry. Comm. Inst. For. Fenn. 57(7): 1-49.

RAIVOLA LARCH STAND

Aili Tuimala

Poster 1.

The larch stands in Raivola originate from a policy initiated by Peter the Great, the creator of the Russian navy. Forest officer Fockel, a German, was invited to establish the plantations in Tsarina Anna's time. The oldest block in Raivola, close to Kronstadt and its dockyard, was established by broadcast sowing in May, 1738. The seed was originated from Archangel. Other fields were planted in 1773 and 1821. Spacings were 3.96 x 3.96 and 4.27 x 4.27 or 625 and 549 plants per ha. The stands have never been thinned, but over the years a many severe storms have felled and damaged stems. The stands are nowadays protected as a natural monument and only a very few visitors are allowed.

Poster 2.

The first systematic forest mensuration survey in these larch stands was carried out by D. Tovstoljes in 1903 and the second one by L. Ilvessalo in 1921, when the area belonged to Finland. The area of pure stands totals 18 ha and of mixed 3 ha. Distribution of forest site types in pure larch stands: FT 2.4 %, OT 83.9 %, OMT 6.2 %, MT 7.5 %. The larch stems were very straight and clear up to a height of 60 - 80 feet.

Poster 3.

A small amount of pruned *Larix europaea* and *Larix sibirica* butlogs as well as unpruned *Larix sibirica* butlogs have been sliced into veneer. Veneers have been classified all clear after kiln dryer. The pruning of larch seemed to be very useful.

EFFECT OF SIZE OF CLEAR-CUTTING AREA ON THE DEVELOPMENT OF SCOTS PINE CULTIVATION

Jukka Valtanen

The sample plots were established 1962 - 65 in Northern Finland (Savukoski lat.67°25', height 200 m, Pudasjärvi 65°50', 225 - 280 m, Valtimo 63°45', 185 - 235 m).

CONCLUSIONS

1. The result is very poor.
2. The result does not depend on the size of the cut-over area.
3. The burning has been useful in Savukoski (thick humus layer) and harmful in Pudasjärvi (thin humus).
4. Early spring just after snow melting before June is the best time for planting and for sowing, too. The autumn is unreliable time.
5. The materials are almost of equal value.

The result at the age of 20 years:

	Survival % - Height M		
	Savukoski	Pudasjärvi	Valtimo
Area			
> 5 ha	19 - 3.0	12 - 2.9	17 - 5.2
> 100 ha	20 - 3.2	25 - 3.2	18 - 5.0
Burning			
No	16- 2.8	29- 3.8	18- 5.0
Yes	23- 3.3	21 - 2.6	17 - 5.2
Month			
V	26 - 3.3	31 - 3.3	27 - 5.5
VI	25 - 3.1	26 - 3.2	25 - 5.4
IX + X	18 - 2.9	24 - 2.9	15 - 4.8
Material			
Sowing	36 - 2.9	21 - 2.5	12 - 4.4
2 + 0	16 - 3.1	27 - 3.4	17 - 5.1
2 + 1	14 - 3.2	30 - 3.7	31 - 5.8
X	22 - 3.1	26 - 3.2	20 - 5.1

HEIGHT GROWTH OF LARIX LARICINA ((DU ROI) K. KOCH) ON A VARIETY OF SITES IN INTERIOR ALASKA

Trudy T. Heffernan

Tamarack (*Larix laricina*) growth was compared on a variety of sites in interior Alaska. An early growth study compared years-to-breast-height of tamarack on different site classes and compared its growth with that of its associated tree species. In a second study, height of tamarack at 25 years was compared on different site classes. In both cases, site class groupings were based primarily on soil moisture, permafrost. and landform.

The site classes demonstrated a significant effect on years-to-breast-height, but there was even more variation among sites. Growth rate of tamarack was similar to that of its broadleaf tree associates and generally faster then that of associated conifers within site classes. Site effect on height-at-25-years was significant: however, site class was not.

Multiple linear regression analysis using environmental and vegetation variables demonstrated that the latter explained more height growth variance.

SUMMARY OF RESULTS

1. Differences in tamarack early growth between site classes

Best growth was found in the site class with:
- no permafrost and a thin organic horizon
- tamarack, birch, willows, horse tails, grasses and *Tomenhypnum nitans*

Slowest growth in site class with:
- permafrost and a thick organic horizon
- tamarack, black spruce, and white spruce, high shrub layer (*Ledum groenlandicum*, *Betula glandulosa*) and many grasses, sedges and mosses

2. Differences in height at 25 years between site classes

Original site classes may have been too narrow, but a regrouping into more broad classes might be more appropriate.

Best growth was in site class with sites that were:
- drier, with thin organic horizon
- high in broadleaf trees, willows, *Alnus* sp., *Shepherdia canadensis, Hylocomium splendens, Stereocaulon paschale* and low in herbaceous plants

Slowest growth was in site class with:
- peraquic to subaquic soils with permafrost and thick organic horizon
- tamarack and black spruce, some birch, *Ledum groenlandicum, Potentilla fruticosa,* and many other shrubs

3. Comparison of early growth of tamarack with other tree species

Generally, tamarack growth rate was similar to broadleaf species and often faster than the other conifers. In the class where tamarack growth rate was slowest it was intermediate to the broadleaf species and the conifers.

4. Factors Influencing Growth

In both studies the plant species accounted for more variance in growth rate than did the environmental variables.

(Y=)	Regression Coefficients Years to BH	Height at 25 Years
Soil moisture	-1.3 (+)	-0.3 (-)
Silt	-1.1 (+)	-2.6 (-)
Clay		3.8 (+)
Organic	-1.3 (+)	
Sand	2.2 (-)	-0.4 (-)
Organic horizon depth	0.7 (-)	
Permafrost	0.8 (-)	
Elevation	0.8 (-)	
Larix laricina (tree)	1.1 (-)	
Betula papyrifera (tree)		1.9 (+)
Picea glauca (tree)		3.1 (+)
Picea mariana (tree)		5.8 (+)
Populus tremuloides (sapling)	-0.9 (+)	
Alnus crispa	1.6 (-)	
Alnus tenuifolia		-6.4 (-)
Ledum groenlandicum		-5.1 (-)
Linnaea borealis		-9.6 (-)
Myrica gale	-0.7 (+)	12.0 (+)
Equisetum pratense	0.4 (+)	
Geocaulon lividum		-19.7 (-)
Hedysarum machenzii		-12.5 (-)
Mertensia paniculata	4.4 (-)	
Pyrola secunda		38.2 (+)
Solidago sp.	-2.2 (+)	
Sphagnum sp.	0.4 (-)	-7.1 (-)

RECOMMENDATIONS FOR FURTHER STUDY

1. Improvement of classification of sites by

- obtaining more information on the history of the site (esp. regarding fire, succession, and geologic history)
- identification of indicator species on sites

2. The sampling of more sites (to increase the sample size) locating sites with older trees to compare growth curve shape on different types of sites and to allow the use of an older index age for comparison.

3. Controlled experiments to test effects on growth of:
- soil temperature
- shading
- nutrient availability

EXCURSION ABSTRACTS

The Finnish Forest Research Institute
ROVANIEMI RESEARCH STATION
Eteläranta 55, 96300 Rovaniemi
Tel. (960) 15721

Founded in 1970, the Rovaniemi Research station is the largest of the eight regional research stations of the Forest Research Institute. The quarters for the station were completed in 1973. Floor space amounts to 2 000 square meters, which in terms of volume represents 6 400 cubimeters. Two subsidiaries are located in town, Personnel at the station consists of 21 researches, district forestry officer and other staff totalling about 100. During the summer, this figure rises to about 140. The annual budget totals about 10 million FIM.

Researchers and their research topics:

Airaksinen, Kirsti, M.Sc. (biochem.),
Forest pathology (external funding)
- biochemistry of disease and cold resistance

Helle, Timo, D.Sc. (Zool.),
National economics of forestry
- economics of multiple-use forestry
- reindeer and moose in forestry

Hokka, Paavo, B.Sc . (For.), North Finland Management District of the Experimental forest office, district forest officer

Jalkanen, Risto, D.F. (For.),
Forest pathology
- fungal diseases
- damages caused by fertilization

Kaila, Erkki, M.Sc. (ADP), ADP development
- database applications in forestry and forest research

Kaila, Pirjo, M.Sc. (ADP), system manager
- maintenance and development of computer systems (VAX/VMS, LAN)
- consultation and training in computer use

Kinnunen, Hilkka, M.Sc. (Math.)
Development of forestry information base (external funding)
- information service
- information systems development

Mattila, Eero, D.F. (For.), Forest inventory
- national forest inventory
- forest inventory methods
- inventory of reindeer pastures

Mäkitalo, Kari, B.Sc. (For.), Silviculture
- regeneration of forests

Naskali, Arto, M.Sc. (Econ.),
Business economics of forestry
- roundwood markets

Niska, Kaarina, M.Sc. (Agr. and For.),
Forest soil science
- soil chemistry

Norokorpi, Yrjö, D.F., Research specialist,
Silviculture (and forest pathology)
- methods of forest regeneration and ecology of seedlings
- treatment of sapling stands
- treatment of high land forests

Penttilä, Timo, B.Sc. (For.),
Peatland forestry
- fertilisation and regeneration of the northern peatland forests
- silvicultural and ecological aspects on peatlands

Ritari, Aulis, L.Sc. (For., Soil Sci), Forest soil science
- site preparation
- site classification
- micrometeorology

Saarenmaa, Hannu, D.F., docent,
Station head
- forest entomology
- knowledge engineering

Salminen, Hannu, M.Sc. (Agr. and For.),
Growth and yield studies

Sepponen, Pentti, Ph.D. (Bot.),
Silviculture
- forest site classification in Northern Finland
- biological aspects of multiple use of forestry

Sippola, Anna-Liisa, M.Sc. National park research (external funding)

Sutinen, Marja-Liisa, L.Sc. (Bot.),
Plant Physiology. (Academy of Finland)
- cold resistance of pine seedlings

Tikkanen, Eero, M.Sc. (Bot.),
Silviculture
- ecophysiology of trees
- root systems

Timonen, Mauri, B.Sc. (For.),
Growth and yield studies
- structure, production and treatment of the protection forests
- modeling of growth indexes and climate effects
- data processing methods

Varmola, Martti, M.Sc. (For.),
Growth and yield studies
- thinning and growth modeling of sapling stands
- quality in planted stands

KIVALO EXPERIMENTAL FOREST

Aulis Ritari

The Kivalo Experimental Forest is located on the timber-covered hills of the Kemijoki-river (66°23'N, 26°37'E) 40 km south of the Arctic Circle. The land area of 14 200 ha. became part of the Finnish Forest Research Institute's experimental area in 1924. The mean annual temperature in the region is about +0.5° C and annual precipitation 475 mm (the average for the period 1921 - 81). The most common soil materials are glacial till and peat which is reflected in the quality of forest sites: moist mineral soil sites occupy about 61 % and peatlands about 19 % of the area.


The permanent staff consists of a local forest technician, 8 other permanent workers and 12 temporarily employed. The research is conducted from both the Rovaniemi Research Station and the main office in Helsinki. They include studies on natural and artificial regeneration, ecological conditions, tree species and provenances, thinning and harvesting methods, growth and yield, peatland forestry, forest damages and multiple use. The research findings are mainly reported in the publications of the Research Institute.

TREE SPECIES TRIAL IN HÖPÖTTÄJÄ

Martti Varmola

Forest site type: *Hylocomium-Myrtillus* -type, partly stony or paludified
Previous forest: *Picea abies*, admixed tree species *Pinus sylvestris*, *Betula pubescens*
Soil type: Sandy moraine (stony)
Clearcutting: 1947 - 48
Prescribed burning: 1950
Spacing: 2.5 • 2.5 m (1 600 trees/ha.)

Tree species.	Larix decidua	Larix gmelini	Pinus sylvestris	Picea abies
Origin	unknown	unknown	Finland	Lapland
Planting time	4.6.1952	23.6.1955	13.6.1952	29.6.1955
Age of plants	3 years	4 years	3 years	4 years
Length of plants	25 cm	12 cm	10 cm	20 cm
Quality of plants	dwarfed	dwarfed	strong	strong
Summer	rainy	dry	rainy	dry
Dominant height in 1976	9.0 m	6.8 m	5-6 m	snow limit



STAND ESTABLISHMENT PLOTS IN KEMIJÄRVI COMMON FOREST

E. Pohtila, L. Saarenmaa, H. Saarenmaa, Junttila & T. Mattila

Kemijärvi common forest is a co-operative of over 2 000 private landowners. Its land property comprises 41 000 ha., growth of the forests is 51 000 m^3/year, and the yearly cutting plan 44 000 m^3. Yearly budget is 6.2 million FIM, and a typical yearly profit for a member farm is 10 000 FIM.

Point 1. Nuolivaaran Rakkavaara

200 m.a.s.l. Previous forest mixed spruce-pine
Clear-cut in 1964
Seeding of Scots Pine in 1965
Thinning in 1976
Height now 6 m

Point 2. Nälkämä pine

220 m.a.s.l. Previous forest spruce
A part of a clear-cut of 3 000 ha.
Prescribed burning in 1973
Ploughing in 1973
Seeding of Scots pine in 1974
Herbicide treatment in 1980
Thinning in 1983

Point 3. Nälkämä larch

As point 2 except
Planting of Siberian larch (Kuusamo-Raivola origin) in l974
No thinning
Severe Adelges laricis woolly aphid attack in 1987
Ash treatment 3 000 kg/ha. planned for cure

Point 4. Erkkusenselkä

240 m.a.s.l. Previous forest spruce
One of the first mechanical scalpings in 1963
Seeding Of Scots pine in 1964
Thinning in 1974
Height now 5 m

Point 5. Pikku Nuolivaara

230 m.a.s.l. Seed trees on 64 ha. in early 50's without success — Ploughing in 1966
Planting with "poor quality" Scots pine in 1969 Herbicide treatment in 1974
Thinning in 1984

Point 6. Veitsiluoto Oy

210 m.a.s.l. Clear-cut in 1975
Ploughing in 1975 on 47 ha.
Planting of Scots pine in 1977 on 23 ha.
Seeding of Scots pine in 1977 on 24 ha
Herbicide and mechanical treatment in 1984

Point 7. Tunturipalo slope

240 m.a.s.l. Previous forest spruce, 80 ma/ha.
Now a part of a clear-cut of l 000 ha.
Clear-cut in 1976 - 79
Prescribed burning in 1980
Scalping in 1980
Seeding of Scots pine in 1981
Density now 1 600 - 2 500 seedling patches/ha.


Point 8. Tunturipalo top

260 m.a.s.l. As point 7
Clear-cut in 1972 - 75
Prescribed burning in 1976
Ploughing and scalping in 1976
Seeding of Scots pine in 1977
Density now 3 700 patches /ha.

FORESTRY BOARD OF LAPLAND

Jukka Ylimartimo

Administrative Organization of Private Forestry in Finland



——— subordinate to
..... guidance and supervision, no binding orders

Ministry of Agriculture and Forestry
- forestry policy-making
- preparation of statutes and supervision of their execution
- appoints the members and deputy members of the executive committees of the forestry boards as well as the chairmen of the inspection committees
- approves the plans of central and local forestry boards

National Board of Forestry
- board of appeal
- supervision of use of state funds
- approves budgets of central and local forestry boards
- appoints auditors of central and local forestry boards

Central Forestry Boards
- highest decision-making body is an 11-member executive committee comprising the director and the following:
  5 representatives of forest owners
  2 representatives of the wood industry
  2 representatives of forest workers
  1 representative of the state
- guidance and development of the activities of the local forestry boards

Forestry Boards
- highest decision-making body is the executive committee, which consists of
  4 representatives of forest owners
  2 representatives of the state
  1 representative of the wood industry
  1 representative of forest workers
- principal activities:
  1. maintenance and development of wood production
  2. development of planned forestry
  3. distribution of information on forestry
  4. forest improvement work

Forest Management Societies
- power of decision rests with forest owners
- principal activities:
  1. training and advice for forest owners
  2. provision of services needed by forest owners for improvement and use of forests

MANAGEMENT OF PRIVATE FORESTS

Mikko Hyppönen

At present 63 % (12.7 mill. ha.) of the total forested area in Finland (20.1 mill. ha.) is privately-owned. The state owns 24 %, companies 9 % and other owners 4 %. there are some 400 000 private forest holdings, of which 100 000 are smaller than 5 ha. Forestry boards and forest management societies provide guidance and advice to owners in management and offer professional assistance in the planning and carrying out of work.

Management of private forests resulted from the "Act Concerning Private Forests" passed in 1967. The Act forbids destruction of forests but it carries no obligation to manage forests nor does it require so-called sustained yield management.

The Central Forestry Board, Tapio, has drawn up guidelines for forest management which local forestry boards generally modify to suit the particular demands of their locality. The guidelines contain the principles for managing young of middle-aged stands as well as mature ones. Separate guidelines exist for mineral soils and peatland forests. In addition, the protection forest area of Lapland and high-elevation forests have their own set of guidelines.

In the "Act Concerning Private Forests", growing and regenerating are clearly distinguished, which means that Finland uses a system of forest management by stands. The management unit is an even-aged stand, not a tree or group of trees. The smallest stand compartment is approximately half a hectare.

Although no stand management obligation exists, regeneration of a stand does require certain follow-up measures. In the case of natural regeneration, the regeneration area is always cleared at least, but generally the soil surface is also broken slightly using a disc plow. After clear cutting the regeneration area is always cleared, and soil preparation, seeding or planting are carried out. An effort is made to use natural regeneration wherever the soil and growing stock permit.

At present, felling and management in private forests is based for the most part on forest management plans made for individual holdings. The plans cover 50 - 80 % of the holdings depending on the forestry board. The plans are drawn up mainly by forestry boards. The planning method is survey by stands. An attempt is also made to take into account conservation requirements.

During the period 1981 - 1986 an average of 303 000 ha. of private forest were marked annually. Of this 60 % represented intermediate felling and 40 % regeneration felling. Of the regeneration markings, approximately 70 % were for clear felling and 30 % for natural regeneration (Fig. 1, page 278).

At the beginning of the 1980's, 102 000 ha. of forest were under cultivation yearly, of which' planting comprised 85 % and seeding 15 %. Thinning and cleaning of seedling stands involved 157 000 ha., fertilization 52 000 ha. and swamp drainage 65 000 ha. per year (Fig. 2, page 278). Approximately 2 600 km of forest roads were constructed annually.

STATE SUPPORT FOR OWNERS OF PRIVATE FORESTS

Mikko Hyppönen

The significance of private forests in the national economy of Finland is great. For this reason, it is looked upon as being in society's interest to undertake various measures to promote the management of private forests. The most important of these are education of forest owners and forest management plans which give the forest owners knowledge about how to produce money by forestry. In addition under certain conditions direct loans, financial assistance and forms of tax relief is provided.

The most significant state support 15 based on the Forest Improvement Act. The present act, the ninth such to be passed, came into force just this past spring. According to the Act, the state supports forest improvement work, which include regeneration, prescribed burning, seedling stand management, pruning of standing trees, fertilization, drainage, maintenance of drainage systems and construction of a forest road. Support is provided in the form of tree professional assistance in the planning and directing of work, free herbicides and supplies for cultivation and partial or total financing of work and other expenses through state assistance and loans.

Financial assistance is allotted geographically, with the largest appropriation being granted in Northern Finland and the smallest in the southern part of the country. There are eight assistance zones in all. In granting assistance regional development policy as well as economic, employment and environmental considerations are taken into account.

The Act of regeneration of stands in insufficient production in Lapland, the so-called Lapland Act, is as significant for the owners of private forest in the northernmost part of the country as the Forest Improvement Act is. The former guarantees 100-percent state aid for the regeneration of particularly underproductive stands and for local planning of private forests. The Act is temporary and will expire at the end of 1995.

The Act aimed at reducing unemployment provides a possibility of employing jobless persons partially using state funds. The funds are available to forest management societies, forestry boards, communes, parishes and companies. In addition, an unemployed person may get funds for work carried out in his own forest without an employment contrAct. The assistance is intended to be used for fuelwood, pruning and various forest management measures.

A variety of tax exemptions and forms of tax relief also constitute an important form of aid. For instance, a forest regeneration area, a forest damage area, an afforested field and a drained swamp may be declared tax-exempt for a certain time. The period varies from 5 to 35 years depending upon geographical location and the basis for granting the tax-exempt status and is longer in the north than in the south.

Forests owners may deduct the following from their taxable income from forestry: forestry fee, costs of forest management plan, fertilizer, maintenance of drainage systems and partial costs of building a forest road.

Figure 1.





Figure 2.



REFORESTATION EXPERIMENTS IN POKSASELKÄ

Aulis Ritari

The reforestation experiments in Poksaselkä (67°12'N, 26°12'E) 130 km north from the Arctic Circle were started in 1972 as a joint effort by the Forest Research Institute and the National Board of Forestry. The idea was to experiment with strip cutting and various site preparation and cultivation techniques in a high-elevation (340 m asl.) *Hylocomium myrtillus* -type spruce forest usually difficult to regenerate.

The clearfelled strips are divided into 60 x 180 m blocks for which the treatments were randomized. The mechanical site preparation methods include: 1) scalping, 2) shoulder ploughing, 3) tilt ploughing, 4) rotary tilling and 5) mounding. One half of the clearfelled area is provided with additional drainage.

Cultivation experiments include sowing and planting trials with several tree species provenances and seedling types. The natural regeneration is the subject of a detailed follow-up. The ecological conditions of the site are being studied as well.

Research findings have been published in the following reports:

Ritari, A. & Lähde, E. 1978. Effect of site preparation on physical properties of the soil in a thick-humus spruce stand. Seloste: Muokkauksen vaikutus paksusammalkuusikon maan fysikaalisiin ominaisuuksiin. Commun. Inst. For. Fenn. 92(7): 1-37.

— 1985. Muokkauksen vaikutus paksusammalkuusikon maan ominaisuuksiin. Lic. thesis, Dept. of Silvic. Univ. of Helsinki. 104 p.

Pernu, T. & Ritari, A. 1978. Vastusluotauksia Sodankylän Poksaselässä pohjaveden esiintymisen selvittämiseksi. Groundwater prospecting in North-Finland by means of resistivity soundings. Univ. of Oulu, Dept. of Geophysics, Contrib. 96: 1-15.

Norokorpi, Y. 1979. Old Norway spruce stands, amount of decay and decaying microbes in Northern Finland. Seloste: Peräpohjolan vanhat kuusikot, niiden lahoisuus ja lahottajat. Comm. Inst. For. Fenn. 97(6): 1-77.

— 1973. Kuusipuuston kasvusta ja lahoamisesta Pomokairan alueella. Metsäntutkimuslaitos, Rovaniemen tutkimusaseman tiedonant. 3: 16-22.

Mäkitalo, K. 1983. Koetuloksia männynviljelyn onnistumisesta eri tavoin käsitellyllä paksusammaltyypin maalla Lapissa. Metsäntutkimuslaitoksen tiedonant. 105: 98-110.

GEOLOGICAL FEATURES AND INTERGLACIAL LARCH SUBFOSSILS IN FINNISH LAPLAND

Peter Johansson

During the Quaternary period, ice sheets covered Scandinavia several times. The Precambrian bedrock in Finland was mantled with a sheet of glacial drift. The most striking present-day features are the different kinds of moraines and eskers left by the final retreat of the latest glaciation, the Weichselian glacial stage. In central Lapland, glacial erosion and deposition activity was weaker than in other parts of Finland. A cover of preglacial weathered bedrock is often found between glacial till and bedrock. Organogenic gyttja, peat, and diatomite layers have also been found intercalated between two till beds in about 80 locations. On the basis of microfossil content and radiocarbon age determinations, 49 organogenic deposits studied by various researchers can be classified as either interstadial or interglacial. The former means a short, temperate period between two cold periods with Betula-predominated pollen composition. The latter means a longer and warmer period between two glaciations with Pinus predominated pollen composition. In 1979, a Larix trunk about 8 long and 40 cm thick was found by R. Mäkinen (1) during the excavation of the Vuotso canal. The trunk lay in the sand layer at a depth of 4.5 meters below the till layer. The pollen composition of the organogenic deposit below the trunk (*Pinus* 49 %, *Betula* 24 %, *Picea* 20 %, *Alnus* 4 %, *Corylus* 1.7 %, and some *Carpinus*, *Larix* and *Abies*) Indicates that the Larix trunk grew during the interglacial period. Larix pollen has also been found in the interglacial deposits at Tepsankumpu, Härkätunturi, and Paloseljänoja in central Lapland. Correlating the stratigraphies and the pollen composition of the interglacial deposits, it is assumed that they originate from the same interglacial period, the Lapponian interglacial period, named and studied by H. Hirvas (2). During this period, the climate was as warm as at present or even a little warmer, The age of the Lapponian Interglacial Period is invariably greater than what can be reliably determined by the radiocarbon method. This period is certainly over 50 000 years old and is possibly over 120 000 years old.

Mäkinen, K., 1982. Tiedonanto Vuotson interglasiaalisesta lehtikuusen rungosta. Summary: Report on interglacial Larix trunk at Vuotso, Northern Finland. Geologi 34: 9-10, 183-185 .

Hirvas, H., 1983, Correlation problems of interglacial deposits in Finnish Lapland. IGCP, Project 73/I/24, Glaciations quaternaires dans l'hemisphere, nord. Rapport 9: 129-139, Paris.

REFORESTATION IN THE PALKISOJA FOREST FIRE AREA

Kari Pelkonen

Location 68°30'

Height above mean sea level:
road 200 m
top 320 m

Temperature sum about 690 dd° C.

The area was burnt in a forest fire in July, 1960.

The burnt area is approximately 280 hectares, the majority of which comprises the jointly-owned forest of Inari. About 20 hectares are administered by the Inari Forest District of the National Board of Forestry.

The area of jointly-owned forest was reforested in 1961 - 1963. About 220 hectares was sowed and about 40 hectares planted.

Total amount of the seed sown was 69 kg, which originated as follows:

Pello	24.5 kg
Sodankylä	29.0 "
Inari	10.0 "
Rovaniemi	6.5 "

Supplementary planting was made in an area of 40 hectares in 1974.

In an inventory in 1984 about 8 800 plants/hectares were counted, the average height of which was 3.3 m.

In autumn 1986 a thinning was carried out in an area at 19 hectares along the road side. About 4 000 trees/hectares were cut town.

The State-owned section was planted by using pine seedlings during the summer of 1961.

The plants were two-year-old bare-root seedlings. The seed was of Kemijärvi origin, some 200 kilometres south.

The planting density was 1 600 seedlings per hectare.

Supplementary planting was carried out in 1972 with bare-root seedlings of most likely Kittilä origin. The density was 1 100 seedlings per hectare.

THE GOAL OF FOREST REGENERATION OF A YOUNG FOREST STAND IN KAITAVAARA

Arno Uusvaara

The systematic regeneration of State Forests in Inari began in the early 1960's when markets for pulpwood opened. However, before this date occasional logging operations had been accomplished since the 1930's. They were mostly selective because these operations mainly covered only sawlogs. Another part of these forests recovered and the other part has been regenerated later.

As the overaged forests covered at the beginning of the 1960's about 75 % of the area of the state forests at Inari, the main emphasis of logging operations in Inari Forest District has been on regeneration cuttings. Since this date the total area of regenerated forests rises up to 52 000 hectares. At the same time the area of seedling and sapling areas as well as young forests has increased rapidly as the following numbers show:

Year	Forests less than 80 years
1960	20 000 hectares
1982	77 000 "
2000	110 000 "

By the year 2 000 forests younger than 80 years will consist 40 % of the area of productive forest land in Inari Forest District. The situation is similar in the State Forests all over Lapland.

Because in the future the young forests will form an essential part of the State Forests, a special emphasis is put in the Forest Service of Finland to improve the results of regeneration and the quality of the young stands obtained in this process. The purpose is, naturally, to produce as good forests as, possible. In the instructions of the treatment of state forests in the North Finland Region, given by the Forest Service of Finland 1985, the goal of forest regeneration is determined according to the following criteria:

- Suitable and valuable tree species for each site type.
- Full density of growing stock.
- Genetic value: fast growth and good quality.
- Vitality of new forest.
- Short period of reproduction.
- Good financial result.

The young stand in Kaitavaara is an example of forests we are aiming at. It meets, to a great extent, the demands described above as the data collected from the stand show.

History of the stand:

- Forest fire 1945
- Sowing on snow, pine 2 kg/ha. April 1954
- Thinning 1977

Data of the stand:

- Area of the stand 61 ha.
- Topographical height 140-200 m.a.s.l.
- Temperature sum 700 dd c°
- Site type KVK (Dryish mineral soil)

- Age 33 years
- Dominant height 10 m
- Basal area 13 m^2
- Volume 60 m^3 /ha.
- Tree species pine 90 %
  birch 10 %
- Increment 3 m^3 /ha./year
- Density 750 stems/ha.

EPIRRITA AUTUMNATA DEFOLIATION OF MOUNTAIN BIRCH

Hannu Saarenmaa

The abundance of the geometrid moth *Epirrita autumnata* fluctuates periodically in Northern Scandinavia. Most of the time the species is not at epidemic levels, but at about 20 year intervals, it breaks out over large areas. After a one or two year peak the population collapses again. A peak does not always translate into complete defoliation and trees dying. However, the last large outbreak in 1964 - 66 resulted in total devastation on birch over an area of a half million hectares in the northern timberline. Some of this area has recovered from root saplings, but large areas became treeless tundra.

In river valleys, however, the birches were saved from extensive damage. This is accounted for by deep winter frosts that kill the overwintering eggs in such places while the eggs in high mountains survived. Probably the nutritional reserves of birches were also higher in the climatically more favourable valleys than in the mountains. Just before the outbreak, the birches had been starving after two very cold summers and did not have enough reserves to replace the eaten leaves.

What is the mechanism behind the collapse and long time lag before the next outbreak of *Epirrita* populations? The research made by the research group of professor Erkki Haukioja at the Kevo Subarctic Research Station has shown that the quality of birch leaves as the food for *Epirrita* larvae gets poorer when the leaves are eaten or torn off artificially. The quality changes lightly already in a few days (short-term response), but a more severe long-term induced resistance does not show until the next and the following years. This long-term defence decreases the reproductive capacity of Epirrita, at least by 70 - 80 %. Obviously this can call off an outbreak, but also parasites and predator play a major role.

Similar fluctuations are common in many other herbivores in the Arctic. e.g. lemmings and voles occur in four-year cycles in Scandinavia. These cycles become stronger and more regular towards north. Also the well known pest of pine. *Neodiprion sertifer*, has a two-year epidemic cycle at the alpine timberline in Saariselkä. The common denominators of these phenomena are 1) the poor resistance of plants against herbivores under stressful conditions and 2) very simple food webs where only a few predator species regulate herbivore populations.

THE GREEN GOLD OF THE NORTHERN COUNTRIES

Markus Lassheikki

Dear friends,

On behalf of the Finnish Forestry Association I wish you all welcome to this internordic forest and forestry exhibition.

The exhibition is entitled "the Green Gold of the Northern Countries", and it is the first internordic exhibition of it's kind. All five Nordic countries: Sweden, Norway, Denmark, Iceland, and Finland have built this exhibition together. It will circulate in the Nordic countries for 3 to 4 years, telling the general public. both young and old alike, about our "Green Gold": the forest. The exhibition is a unique proof of what the forestry peoples in different countries can bring about when they work together.

Today, when a big and growing part of the population lives in cities and suburbs, the connection with the original environment is lost, and the forest is often seen as a place only for recreation. The aim of the exhibition is to inform the public of the great importance that forests and forestry have had through the times for the Nordic peoples. The forest has meant, and still means welfare today, but it also means much more. Forest products are used in our everyday life, and the forest is the place where we northerners prefer to rest after the hard and often stressing daily work of today's modern life. The forest has always had a special place in our traditions and religions, and even today it gives us a sense of security. As peoples of the Nordic countries we had, and still have the great majority of the land around us covered with forest, and this we have been, and always will be proud of.

Most of all, however, the forest is a source of raw material for our most important export industry. Though the Nordic countries comprise of only a small percentage of the forested area of the world, the forest products, exported from these countries stand for approximately 20 % of the world forest exports. Forestry, therefore, is an extremely important employer in the Northern countries.

Nordic forestry is said to be a successful battle against a cold and severe climate. When the growing age of a stand varies between 80 and 160 years, the forestry people have to work objectively.

The fruits of our work obtained from the processes of seeding, planting, protecting and caring of young stands will not be ours to harvest, but that of our grandchildren. The growing time may seem to be an insuperable length of time but we still rely upon the forests to guarantee our well-being even after a hundred years, and it is hoped that the quality of Nordic timber will remain high, and still be greatly sought after as it is today.

The evergreen Nordic woods are a world full of beauty and possibilities, a world with space enough for everybody. Dear friends, it is a great honour to have you here, I hope you will enjoy the exhibit, and this part of the Nordic woods.

PROGRAM

Final version of August 16th.

Symposium themes: Larix in northern boreal forests. Site preparation in northern boreal forests. Forest management in protection forests close to timberline.

Organizer: The Finnish Forest Research Institute, Rovaniemi Research Station, Eteläranta 55, 96300 Rovaniemi, Finland, attn: Dr. Hannu Saarenmaa, head. tel: +358-60-15721, telex: 37004 RVNMI SF FFRIROI

Accommodations:
16 - 18.8. Hotel Ounasvaara in Rovaniemi tel: +358-60-23371
18 - 19.8. Hotel Kultakero in Pyhätunturi tel: +358-692-12081
19 - 22.8. Hotel Riekonlinna in Saariselkä tel: +358-679-81601

Sunday 16.8.

12:00	Registration begins at hotel Ounasvaara in Rovaniemi, setup of posters
18:00	*Welcoming address*: chair DR. H. SAARENMAA Introductions, a word from the organizer
18:10	Dinner
19:40	Opening: NP CHAIRMAN DR. E.C. PACKEE
20:00	Opening remarks from The Finnish Forest Research Institute: PROF. A. NYYSSÖNEN
20:20	Northern boreal forest resources, their utilization and ecology: PROF. K. KUUSELA
21:00	Nine thousand years of forests in Finland: DR S.-E. APPELROTH

Monday 17.8.

	Breakfast at hotel Ounasvaara in Rovaniemi
8:00	Poster session begins
8:00	Session *Site preparation in northern boreal forests*
12:00	Lunch
13:00	Photography, interviews
13:05	Poster session showtime
13:40	Session *Larix in northern boreal forests*
15:45	Visit to The Finnish Forest Research Institute, Rovaniemi Research Station: DR. H. SAARENMAA
16:30	Sightseeing in Rovaniemi. Visit at the Arctic Circle
18:00	Exhibition "The Green Gold Of The North" and reception of the city of Rovaniemi at the City Library Building: LORD MAYOR M. PELTTARI
19:00	Evening free
19:00	Poster session ends – removing of posters

Tuesday 18.8.

	Breakfast at hotel Ounasvaara in Rovaniemi
8:00	Bus to Kivalo, presentation of the experimental forest: LIC. A. RITARI
9:30	Full-grown larch stand in Siperia: DR. E. POHTILA – coffee
10:15	Young larch stands in Höpöttäjä: M. VARMOLA
11:00	Moose and forest management in Höpöttäjä: DR. T. HELLE
11:30	Lunch (moose stew) at Sieväkari cabin
12:20	Bus to Kemijärvi
13:30	Visit at the Veitsiluoto pulp-mill in Kemijärvi: A. EERONHEIMO
14:00	Continue
14:30	Coffee at Kummunjärvi cabin
15:00	Forest regeneration results and site preparation plots at Kemijärvi common forest (Nälkämä-Nuolivaara-Tunturipalo): DR. H. SAARENMAA, DR. E. POHTILA
17:30	Bus to Pyhätunturi
19:00	Dinner at hotel Kultakero in Pyhätunturi

Wednesday 19.8.

	Breakfast at hotel Kultakero in Pyhätunturi
8:00	Bus to Sodankylä Siurunmaa
9:00	Private forestry: the farm of P. ONNELA – coffee Administration: J. YLIMARTIMO Rules & regulations of forest management: M. HYPPÖNEN Government support on forest improvement: M. HYPPÖNEN
11:00	Bus to Sodankylä
11:15	Lunch at restaurant Kantakievari
12:30	Bus to Poksaselkä, soil preparation, narrator PROF. G. SIRÉN
13:30	Site preparation field experiment: LIC. A. RITARI – coffee
15:00	Bus to Tankavaara
16:00	Geological features of Lapland and interglacial larch subfossils: DR. P. JOHANSSON
16:30	Gold panning museum: manager I. SYRJÄNEN
17:00	Bus to hotel Riekonlinna in Saariselkä
18:00	Dinner
19:00	Business meeting at hotel Riekonlinna: Chair DR. E.C. PACKEE

Thursday 20.8.

	Breakfast at hotel Riekonlinna
8:00	Session *Forest management in protection forests close to timberline*
12:00	Lunch at hotel Riekonlinna
13:00	Bus to Forest Service Inari District:
13:20	Reforestation of burned area in Palkisoja: K. PELKONEN
13:50	Continue
14:30	The goal of forest regeneration close to protection forests in Kaitavaara – a young pine stand: A. UUSVAARA
15:00	Continue
15:30	Principles of forest management when expanding into wilderness areas – logging activities in the Kessi area: P. VEIJOLA – coffee
16:30	Bus to hotel Riekonlinna in Saariselkä
20:00	Lapland barbecue by Ohjelmapalvelu Matti Saastamoinen in Saariselkä

Friday 21.8.

	Breakfast at hotel Riekonlinna
7:30	Bus to Inari
8:30	Sami museum in Inari
9:20	Bus to Kiellajoki
10:00	Three plantations at the timberline in Kiellajoki: PROF. G. SIRÉN – coffee
11:30	Lunch at Kiellatupa
12:30	On the bus in Kaamasmukka *Epirrita autumnata* defoliation of birch DR. H. SAARENMAA
13:00	Reindeer husbandry in Karigasniemi Ailigas: DR. T. HELLE
13:20	Bus to Teno valley, sightseeing, 70th latitude
15:00	The northernmost plantation of Finland in Kaava: DR. E. POHTILA – coffee
15:30	Bus to Kevo
16:00	Kevo Subarctic Research Station and the timberline arboretum: PROF. P. KALLIO
16:45	Bus to Saariselkä – etc.
21:00	Farewell party at hotel Riekonlinna in Saariselkä

Saturday 22.8.

	Breakfast at hotel Riekonlinna
8:30	Departure to Ivalo
9:00	Shopping in Ivalo
9:40	Departure to Ivalo airport
10:30	Departure by flight to Helsinki (AY 453)
10:30	Departure by bus to Rovaniemi
12:30	Arrival by flight in Helsinki
14:00	Arrival by bus in Rovaniemi
19:00	Departure by train from Rovaniemi
21:05	Departure by train from Rovaniemi!

PARTICIPANTS

Alm, Alvin A., Professor
Cloquet Forestry Center
University of Minnesota
175 University Road
Cloquet, MN 55720, USA

von Althen, F.W., Research scientist
Canadian Forestry Service
Great Lakes Forestry Centre
P O. Box 490
Sault Ste. Marie, Ontario
P6A 5M7 Canada

Andersson, Eje, District forest officer
Domänverket
Hedebergavägen 14
972 00 Gällivare, Sweden

Appelroth, Sven-Eric, Dr.
The Finnish Forest Research Institute
Department of Wood Technology
Unioninkatu 40 A
00170 Helsinki, Finland

Chou, Yi-liang, Professor
Northeast University of Forestry
Forest Botanical Laboratory
Harbin, P.R. China

Corns, Ian, Research scientist
Canadian Forestry Service
Northern Forestry Centre
5320 122th Street
Edmonton, Alberta, T6H 3F5 Canada

Degerlund, Ture
Domänverket, Umeå region
P.O. Box 5036
900 05 Umeå, Sweden

Hagman, Max., Professor
The Finnish Forest Research Institute
Department of Forest Genetics
P.O. Box 18
01301 Vantaa, Finland

Hagner, Mats, Professor
University of Umeå
Department of Forest Production
901 87 Umeå, Sweden

Hall, J.P., Research scientist
Canadian Forestry Service
Newfoundland Forestry Centre
P.O. Box 6028
St. John's, Newfoundland
A1C 5X8, Canada

Haveraaen, Oddvar, Professor
Agricultural University of Norway
Department of Silviculture
P.O. Box 42
1432 Ås-NLH, Norway

Helle, Timo, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O. Box 16
96301 Rovaniemi, Finland

Hunt, James, Research assistant
Swedish University of Agr. Sciences
901 83 Umeå, Sweden

Iroshnikov, A.I.
Central Research Institute of Forest
Genetics and Breeding
105 Lomonosava Str.
Voronezh, USSR

Jalkanen, Risto, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O. Box 16
96301 Rovaniemi, Finland

Jeansson, Evert, Research forester
Swedish University of Agr. Sciences
Department of Silviculture
901 83 Umeå, Sweden

Juvonen, Risto, Professor
Helsinki University of Technology
Department of Forest Products
Puumiehenkuja 2 B
02150 Espoo, Finland

Kaartinen, Viljo, Chief forester
National Board of Forestry
Pohjanmaan pkk, P.O. Box 81
90101 Oulu, Finland

Kallio, Paavo, Professor
University of Turku
Kevo Subarctic Research Institute
20500 Turku, Finland

Kaurinkoski, Samuel, Head of department
Central Association of Finnish Forest Industries
Eteläesplanadi 2
00130 Helsinki, Finland

Kubin, Eero, Research scientist
The Finnish Forest Research Institute
Muhos Research Station
91500 Muhos, Finland

Kuusela, Kullervo, Professor
The Finnish Forest Research Institute
Department of Forest Inventory
P.O. Box 37
00381 Helsinki, Finland

Leikola, Matti, Professor
University of Helsinki
Department of Silviculture
Unioninkatu 40 B
00170 Helsinki, Finland

Lennartsson, Olle
Domänverket, Umeå region
Storgatan 16
831 30 Östersund, Sweden

Li Jingwen, Professor of forest ecology
Northeast Forestry University
Harbin, Heilongjiang Province
P.R. China

Listov, A.A.
Arkhangelsk Forest and Forest Chemistry Institute
13 Lyotchuka Nikitova Str.
Arkhangelsk, USSR

Lundberg, Stig, Skogvårdschef
Domänverket
P.O, Box 810
951 28 Luleå, Sweden

Malcolm, Douglas, C., Dr.
University of Edinburgh
Department of Forestry and Natural Resources Darwin Building, The King's Buildlngs Mayfield Road
Edinburgh, EH9 3 JU, U.K.

Martinsson, Owe, Tf professor
Swedish University of Agr. Sciences
Department of Silviculture
901 83 Umeå, Sweden

McMinn, Robert
Millstream Lake Road, RR 6
Victoria, B.C., V8X 3X2, Canada

Murray, Tom
Agriculture Canada
Canadian Forestry Service-Maritimes
P O. Box 4000
Fredericton, New Brunswick
Canada E3B 5P7

Nilsson, Bo, Forest officer
Domänverket
791 31 Falun, Sweden

Niska, Kaarina, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O. Box 16
96301 Rovaniemi, Finland

Numminen, Erkki, Manager
The Finnish Forest Research Institute
Kolari Research Station
95900 Kolari, Finland

Nyyssönen, Aarne, Director
The Finnish Forest Research Institute
Unioninkatu 40 A
00170 Helsinki, Finland

Ogievsky, D.V.
Leningrad Forestry Research Institute
21 Institutskaya Str.
Leningrad, USSR

Packee, Edmond C., Assistant professor
Agr. For. Experiment Station
University of Alaska
Fairbanks, Alaska 99775, USA

Paloniemi, Jouko, Chief forester
National Board of Forestry
P.O. Box 233
00121 Helsinki, Finland

Pelkonen, Kari, Chief inspector
National Board of Forestry
P.O, Box 233
00121 Helsinki, Finland

Pohtila, Eljas, Director
The Finnish Forest Research Institute
Fabianinkatu 40 A
00170 Helsinki, Finland

Ritari, Aulis, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O, Box 16
96301 Rovaniemi, Finland

Roiko-Jokela, Pentti, Head of department
National Board of Forestry
P.O. Box 233
00121 Helsinki, Finland

Ruotsalainen, Seppo, Research scientist
The Finnish Forest Research Institute
Kolari Research Station
95900 Kolari, Finland

Rutsström, Björn
Domänverket, Jokkmokk district
Storgatan 62
960 40 Jokkmokk, Sweden

Röjfors, B.
Domänverket, Jokkmokk district
Lappstavägen 18
960 40 Jokkmokk, Sweden

Saarenmaa, Hannu, Manager
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O. Box 16
96301 Rovaniemi, Finland

Salminen, Hannu, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.O. Box 16
96301 Rovaniemi, Finland

Schmidt-Vogt, Helmut, Prof., Dr., Dr.h.c.
Albert-Ludwig University
Waldbau-Institut
Bertoldstrasse 17
7800 Freiburg, Fed. Rep. Germany

Sirén, Gustaf, Professor
Svitiodsvägen 10
l8262 Djursholm, Stockholm
Sweden

Svensson, Lars, Forest officer
Domänverket
791 81 Falun, Sweden

Timonen, Mauri, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.0. Box 16
96301 Rovaniemi, Finland

Titus, B.D., Research scientist
NEFC, CFS
P.0. Box 6028
St. Johns's, New Foundland
Canada A1C 5X8


Tuimala, Aili, Research scientist
The Finnish Forest Research Institute
Department of Wood Technology
Unioninkatu 40 A
00170 Helsinki, Finland


Uusvaara, Arno, Chief forester
National Board of Forestry
Puolapolku 4
96500 Rovaniemi, Finland

Varmola, Martti, Research scientist
The Finnish Forest Research Institute
Rovaniemi Research Station
P.0. Box 16
96301 Rovaniemi, Finland

Waatainen, Bernie, Divisional Forester
MacMillan Bloedel, Cameron Division
Port Alberni, B.C.
V9Y 7N4, Canada

Örlander, Göran, Tf professor
Swedish University of Agr. Science
Department of Silviculture
901 83 Umeå
Sweden


Participants by country
USA
China
USSR
Canada
U.K.
W-Germany
Norway
Finland
Sweden


Participants by field
Administration
Field forester
Research
Teaching

Finnish
Forest
Research
Institute
METLA

Unioninkatu 40 A
FIN-00170 HELSINKI
Finland
Ph: +358-0-857051
Fax: +358-0-625308
Internet: info@metla.fi



ISBN 951-40-1466-9
ISSN 0358-4283